

# PIC18F6525/6621/8525/8621 Data Sheet

64/80-Pin High-Performance, 64-Kbyte Enhanced Flash Microcontrollers with A/D

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our
  knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data
  Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not
  mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WAR-RANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED. WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, microID, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart, rfPIC, and SmartShunt are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AmpLab, FilterLab, Migratable Memory, MXDEV, MXLAB, PICMASTER, SEEVAL, SmartSensor and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, MPASM, MPLIB, MPLINK, MPSIM, PICkit, PICDEM, PICDEM.net, PICLAB, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, rfLAB, rfPICDEM, Select Mode, Smart Serial, SmartTel and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2005, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2002

Microchip received ISO/TS-16949:2002 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona and Mountain View, California in October 2003. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



# 64/80-Pin High-Performance, 64-Kbyte Enhanced Flash Microcontrollers with A/D

#### **High Performance RISC CPU:**

- · Linear program memory addressing to 64 Kbytes
- · Linear data memory addressing to 4 Kbytes
- 1 Kbyte of data EEPROM
- Up to 10 MIPs operation:
  - DC 40 MHz osc./clock input
  - 4 MHz 10 MHz osc./clock input with PLL active
- 16-bit wide instructions, 8-bit wide data path
- · Priority levels for interrupts
- · 31-level, software accessible hardware stack
- 8 x 8 Single-cycle Hardware Multiplier

#### **Peripheral Features:**

- High current sink/source 25 mA/25 mA
- Four external interrupt pins
- Timer0 module: 8-bit/16-bit timer/counter
- · Timer1 module: 16-bit timer/counter
- Timer2 module: 8-bit timer/counter
- Timer3 module: 16-bit timer/counter
- Timer4 module: 8-bit timer/counter
- Secondary oscillator clock option Timer1/Timer3
- Two Capture/Compare/PWM (CCP) modules:
- Capture is 16-bit, max. resolution 6.25 ns (Tcy/16)
- Compare is 16-bit, max. resolution 100 ns (Tcy)
- PWM output: 1 to 10-bit PWM resolution
- Three Enhanced Capture/Compare/PWM (ECCP) modules:
  - Same Capture/Compare features as CCP
  - One, two or four PWM outputs
  - Selectable polarity
  - Programmable dead time
  - Auto-Shutdown on external event
  - Auto-Restart
- Master Synchronous Serial Port (MSSP) module with two modes of operation:
  - 2/3/4-wire SPI™ (supports all 4 SPI modes)
  - I<sup>2</sup>C<sup>™</sup> Master and Slave mode
- · Two Enhanced USART modules:
  - Supports RS-485, RS-232 and LIN 1.2
  - Auto-Wake-up on Start bit
  - Auto-Baud Rate Detect
- · Parallel Slave Port (PSP) module

## External Memory Interface (PIC18F8525/8621 Devices Only):

- · Address capability of up to 2 Mbytes
- 16-bit interface

#### **Analog Features:**

- 10-bit, up to 16-channel Analog-to-Digital Converter (A/D):
  - Auto-Acquisition
  - Conversion available during Sleep
- Programmable 16-level Low-Voltage Detection (LVD) module:
  - Supports interrupt on Low-Voltage Detection
- Programmable Brown-out Reset (BOR)
- Dual analog comparators:
  - Programmable input/output configuration


#### **Special Microcontroller Features:**


- 100,000 erase/write cycle Enhanced Flash program memory typical
- 1,000,000 erase/write cycle Data EEPROM memory typical
- 1 second programming time
- Flash/Data EEPROM Retention: > 100 years
- Self-reprogrammable under software control
- Power-on Reset (POR), Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Watchdog Timer (WDT) with its own On-Chip RC Oscillator for reliable operation
- · Programmable code protection
- Power-saving Sleep mode
- · Selectable oscillator options including:
  - 4x Phase Lock Loop (PLL) of primary oscillator
  - Secondary Oscillator (32 kHz) clock input
- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via two pins
- MPLAB® In-Circuit Debug (ICD 2) via two pins

#### **CMOS Technology:**

- Low power, high-speed Flash technology
- · Fully static design
- Wide operating voltage range (2.0V to 5.5V)
- Industrial and Extended temperature ranges

|            | Prog  | ram Memory                | Data I          | Memory            |     | 10-bit      | CCP/ |     | MSSP/SPI™/               |        | Timers       |     |
|------------|-------|---------------------------|-----------------|-------------------|-----|-------------|------|-----|--------------------------|--------|--------------|-----|
| Device     | Bytes | #Single-Word Instructions | SRAM<br>(bytes) | EEPROM<br>(bytes) | 1/0 | A/D<br>(ch) | ECCP | PWM | Master I <sup>2</sup> C™ | EUSART | 8-bit/16-bit | EMI |
| PIC18F6525 | 48K   | 24576                     | 3840            | 1024              | 53  | 12          | 2/3  | 14  | Υ                        | 2      | 2/3          | N   |
| PIC18F6621 | 64K   | 32768                     | 3840            | 1024              | 53  | 12          | 2/3  | 14  | Y                        | 2      | 2/3          | N   |
| PIC18F8525 | 48K   | 24576                     | 3840            | 1024              | 70  | 16          | 2/3  | 14  | Y                        | 2      | 2/3          | Υ   |
| PIC18F8621 | 64K   | 32768                     | 3840            | 1024              | 70  | 16          | 2/3  | 14  | Y                        | 2      | 2/3          | Υ   |





## **Table of Contents**

| 1.0    | Device Overview   | 7   |
|--------|---|-----|
| 2.0    | Oscillator Configurations   | 21  |
| 3.0    | Reset   | 29  |
| 4.0    | Memory Organization   | 39  |
| 5.0    | Flash Program Memory  | 61  |
| 6.0    | External Memory Interface   | 71  |
| 7.0    | Data EEPROM Memory  | 79  |
| 8.0    | 8 x 8 Hardware Multiplier   | 85  |
| 9.0    | Interrupts  | 87  |
| 10.0   | I/O Ports   | 103 |
| 11.0   | Timer0 Module   | 131 |
| 12.0   | Timer1 Module   | 135 |
| 13.0   | Timer2 Module   | 141 |
| 14.0   | Timer3 Module   | 143 |
|        | Timer4 Module   |     |
|        | Capture/Compare/PWM (CCP) Modules   |     |
| 17.0   | Enhanced Capture/Compare/PWM (ECCP) Module                                | 157 |
| 18.0   | Master Synchronous Serial Port (MSSP) Module                              | 173 |
| 19.0   | Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) | 213 |
| 20.0   | 10-Bit Analog-to-Digital Converter (A/D) Module                           | 233 |
| 21.0   | Comparator Module   | 243 |
| 22.0   | Comparator Voltage Reference Module                                       | 249 |
|        | Low-Voltage Detect  |     |
| 24.0   | Special Features of the CPU   | 259 |
| 25.0   | Instruction Set Summary   | 275 |
| 26.0   | Development Support   | 317 |
| 27.0   | Electrical Characteristics  | 323 |
| 28.0   | DC and AC Characteristics Graphs And Tables                               | 357 |
|        | Packaging Information   |     |
|        | ndix A: Revision History  |     |
|        | ndix B: Device Differences  |     |
|        | ndix C: Conversion Considerations   |     |
|        | ndix D: Migration From Mid-Range to Enhanced Devices                      |     |
|        | ndix E: Migration From High-End to Enhanced Devices                       |     |
|        |   |     |
|        | ne Support  |     |
|        | ms Information and Upgrade Hot Line                                       |     |
|        | er Response   |     |
| DIC 19 | RE6525/6621/8525/8621 Product Identification System                       | 303 |

## TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@mail.microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)
- The Microchip Corporate Literature Center; U.S. FAX: (480) 792-7277

When contacting a sales office or the literature center, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our Web site at www.microchip.com/cn to receive the most current information on all of our products.

NOTES:

#### 1.0 DEVICE OVERVIEW

This document contains device specific information for the following devices:

- PIC18F6525
- PIC18F6621
- PIC18F8525
- PIC18F8621

This family offers the advantages of all PIC18 microcontrollers — namely, high computational performance at an economical price — with the addition of high-endurance Enhanced Flash program memory. The PIC18F6525/6621/8525/8621 family also provides an enhanced range of program memory options and versatile analog features that make it ideal for complex, high performance applications.

## 1.1 Key Features

#### 1.1.1 EXPANDED MEMORY

The PIC18F6525/6621/8525/8621 family provides ample room for application code and includes members with 48 Kbytes or 64 Kbytes of code space.

Other memory features are:

- Data RAM and Data EEPROM: The PIC18F6525/ 6621/8525/8621 family also provides plenty of room for application data. The devices have 3840 bytes of data RAM, as well as 1024 bytes of data EEPROM for long term retention of nonvolatile data.
- Memory Endurance: The Enhanced Flash cells for both program memory and data EEPROM are rated to last for many thousands of erase/write cycles – up to 100,000 for program memory and 1,000,000 for EEPROM. Data retention without refresh is conservatively estimated to be greater than 40 years.

#### 1.1.2 EXTERNAL MEMORY INTERFACE

In the unlikely event that 64 Kbytes of program memory is inadequate for an application, the PIC18F8525/8621 members of the family also implement an external memory interface. This allows the controller's internal program counter to address a memory space of up to 2 MBytes, permitting a level of data access that few 8-bit devices can claim.

With the addition of new operating modes, the external memory interface offers many new options, including:

- Operating the microcontroller entirely from external memory
- Using combinations of on-chip and external memory, up to the 2-Mbyte limit
- Using external Flash memory for reprogrammable application code or large data tables
- Using external RAM devices for storing large amounts of variable data

#### 1.1.3 EASY MIGRATION

Regardless of the memory size, all devices share the same rich set of peripherals, allowing for a smooth migration path as applications grow and evolve.

The consistent pinout scheme used throughout the entire family also aids in migrating to the next larger device. This is true when moving between the 64-pin members, between the 80-pin members, or even Jumping From 64-pin To 80-pin Devices.

#### 1.1.4 OTHER SPECIAL FEATURES

- Communications: The PIC18F6525/6621/8525/8621 family incorporates a range of serial communication peripherals, including 2 independent Enhanced USARTs and a Master SSP module capable of both SPI and I<sup>2</sup>C (Master and Slave) modes of operation. Also, for PIC18F6525/6621/8525/8621 devices, one of the general purpose I/O ports can be reconfigured as an 8-bit Parallel Slave Port for direct processor to processor communications.
- CCP Modules: All devices in the family incorporate two Capture/Compare/PWM (CCP) modules and three Enhanced CCP (ECCP) modules to maximize flexibility in control applications. Up to four different time bases may be used to perform several different operations at once. Each of the three ECCPs offer up to four PWM outputs, allowing for a total of 12 PWMs. The ECCPs also offer many beneficial features, including polarity selection, Programmable Dead Time, Auto-Shutdown and Restart and Half-Bridge and Full-Bridge Output modes.
- Analog Features: All devices in the family feature 10-bit A/D converters with up to 16 input channels, as well as the ability to perform conversions during Sleep mode and auto-acquisition conversions. Also included are dual analog comparators with programmable input and output configuration, a programmable Low-Voltage Detect module and a Programmable Brown-out Reset module.
- Self-programmability: These devices can write to their own program memory spaces under internal software control. By using a bootloader routine located in the protected boot block at the top of program memory, it becomes possible to create an application that can update itself in the field.

## 1.2 Details on Individual Family Members

The PIC18F6525/6621/8525/8621 devices are available in 64-pin (PIC18F6525/6621) and 80-pin (PIC18F8525/8621) packages. They are differentiated from each other in four ways:

- Flash program memory (48 Kbytes for PIC18F6525/8525 devices; 64 Kbytes for PIC18F6621/8621 devices).
- 2. A/D channels (12 for PIC18F6525/6621 devices; 16 for PIC18F8525/8621 devices).


- 3. I/O ports (7 on PIC18F6525/6621 devices; 9 on PIC18F8525/8621 devices).
- 4. External program memory interface (present only on PIC18F8525/8621 devices)

All other features for devices in the PIC18F6525/6621/8525/8621 family are identical. These are summarized in Table 1-1.

Block diagrams of the PIC18F6525/6621 and PIC18F8525/8621 devices are provided in Figure 1-1 and Figure 1-2, respectively. The pinouts for these device families are listed in Table 1-2.

TABLE 1-1: PIC18F6525/6621/8525/8621 DEVICE FEATURES

| Features                                | PIC18F6525   | PIC18F6621   | PIC18F8525   | PIC18F8621   |
|---|--|--|--|--|
| Operating Frequency                     | DC – 40 MHz  |
| Program Memory (Bytes)                  | 48K  | 64K  | 48K  | 64K  |
| Program Memory (Instructions)           | 24576  | 32768  | 24576  | 32768  |
| Data Memory (Bytes)                     | 3840   | 3840   | 3840   | 3840   |
| Data EEPROM Memory (Bytes)              | 1024   | 1024   | 1024   | 1024   |
| External Memory Interface               | No   | No   | Yes  | Yes  |
| Interrupt Sources                       | 17   | 17   | 17   | 17   |
| I/O Ports                               | Ports A, B, C, D,<br>E, F, G   | Ports A, B, C, D,<br>E, F, G   | Ports A, B, C, D, E, F, G, H, J  | Ports A, B, C, D, E, F, G, H, J  |
| Timers                                  | 5  | 5  | 5  | 5  |
| Capture/Compare/PWM Modules             | 2  | 2  | 2  | 2  |
| Enhanced Capture/Compare/<br>PWM Module | 3  | 3  | 3  | 3  |
| Serial Communications                   | MSSP,<br>Addressable<br>EUSART (2)   | MSSP,<br>Addressable<br>EUSART (2)   | MSSP,<br>Addressable<br>EUSART (2)   | MSSP,<br>Addressable<br>EUSART (2)   |
| Parallel Communications                 | PSP  | PSP  | PSP  | PSP  |
| 10-bit Analog-to-Digital Module         | 12 input channels  | 12 input channels  | 16 input channels  | 16 input channels  |
| Resets (and Delays)                     | POR, BOR,<br>RESET Instruction,<br>Stack Full,<br>Stack Underflow<br>(PWRT, OST) |
| Programmable Low-Voltage Detect         | Yes  | Yes  | Yes  | Yes  |
| Programmable Brown-out Reset            | Yes  | Yes  | Yes  | Yes  |
| Instruction Set                         | 77 Instructions  | 77 Instructions  | 77 Instructions  | 77 Instructions  |
| Package                                 | 64-pin TQFP  | 64-pin TQFP  | 80-pin TQFP  | 80-pin TQFP  |



© 2005 Microchip Technology Inc.




TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS

| Din Name                    | Pin N      | umber      | mber Pin Buffer |         | Pin Buffer  | Buffer | December 1 |
|-----------------------------|------------|------------|-----------------|---------|---|--------|------------|
| Pin Name                    | PIC18F6X2X | PIC18F8X2X | Туре            | Туре    | Description   |        |            |
| MCLR/VPP/RG5 <sup>(9)</sup> | 7          | 9          |                 |         | Master Clear (input) or programming   |        |            |
| MCLR                        |            |            | I               | ST      | voltage (output).  Master Clear (Reset) input. This pin is an active-low Reset to the device.   |        |            |
| VPP                         |            |            | Р               |         | Programming voltage input.  |        |            |
| RG5                         |            |            | - 1             | ST      | Digital input.  |        |            |
| OSC1/CLKI<br>OSC1<br>CLKI   | 39         | 49         | I               | CMOS/ST | Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; otherwise CMOS. External clock source input. Always associated with pin function OSC1 (see OSC1/CLKI, OSC2/CLKO pins). |        |            |
| OSC2/CLKO/RA6<br>OSC2       | 40         | 50         | 0               | _       | Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal oscillator   |        |            |
| CLKO                        |            |            | 0               | _       | mode. In RC mode, OSC2 pin outputs CLKO which has 1/4 the frequency of OSC1   |        |            |
| RA6                         |            |            | I/O             | TTL     | and denotes the instruction cycle rate.  General purpose I/O pin.   |        |            |

**Legend:** TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

OD = Open-Drain (no P diode to VDD)

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP<sup>TM</sup> modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name      | Pin N      | umber      | Pin  | Buffer | Description                              |
|---------------|------------|------------|------|--------|--|
| riii Naiile   | PIC18F6X2X | PIC18F8X2X | Туре | Туре   | Description                              |
|               |            |            |      |        | PORTA is a bidirectional I/O port.       |
| RA0/AN0       | 24         | 30         |      |        |  |
| RA0           |            |            | I/O  | TTL    | Digital I/O.                             |
| AN0           |            |            | I    | Analog | Analog input 0.                          |
| RA1/AN1       | 23         | 29         |      |        |  |
| RA1           |            |            | I/O  | TTL    | Digital I/O.                             |
| AN1           |            |            | I    | Analog | Analog input 1.                          |
| RA2/AN2/VREF- | 22         | 28         |      |        |  |
| RA2           |            |            | I/O  | TTL    | Digital I/O.                             |
| AN2           |            |            |      | Analog | Analog input 2.                          |
| VREF-         |            |            | l I  | Analog | A/D reference voltage (low) input.       |
| RA3/AN3/VREF+ | 21         | 27         |      |        |  |
| RA3           |            |            | I/O  | TTL    | Digital I/O.                             |
| AN3           |            |            | !    | Analog | Analog input 3.                          |
| VREF+         |            |            | l I  | Analog | A/D reference voltage (high) input.      |
| RA4/T0CKI     | 28         | 34         |      |        |  |
| RA4           |            |            | I/O  | ST/OD  | Digital I/O – Open-drain when configured |
| T00//         |            |            | ١.   | 0.     | as output.                               |
| T0CKI         |            |            | '    | ST     | Timer0 external clock input.             |
| RA5/AN4/LVDIN | 27         | 33         |      |        |  |
| RA5           |            |            | I/O  | TTL    | Digital I/O.                             |
| AN4           |            |            | !    | Analog | Analog input 4.                          |
| LVDIN         |            |            | '    | Analog | Low-Voltage Detect input.                |
| RA6           |            |            |      |        | See the OSC2/CLKO/RA6 pin.               |

**Legend:** TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

S levels Analog = Analog input

I = Input

O = Output

P = Power

OD = Open-Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with  $\overline{MCLR}$  and is only available when the  $\overline{MCLR}$  Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Din Name  | Pin N      | umber      | Pin               | Buffer          | Decariation   |
|---|------------|------------|-------------------|-----------------|---|
| Pin Name  | PIC18F6X2X | PIC18F8X2X | Туре              | Туре            | Description   |
|   |            |            |                   |                 | PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs. |
| RB0/INT0/FLT0   | 48         | 58         |                   |                 |   |
| RB0<br>INT0<br>FLT0                                       |            |            | I/O<br>I<br>I     | TTL<br>ST<br>ST | Digital I/O. External interrupt 0. PWM Fault input for ECCP1.   |
| RB1/INT1  | 47         | 57         |                   |                 | ·   |
| RB1<br>INT1   |            |            | I/O<br>I          | TTL<br>ST       | Digital I/O. External interrupt 1.  |
| RB2/INT2  | 46         | 56         |                   |                 |   |
| RB2<br>INT2   |            |            | I/O<br>I          | TTL<br>ST       | Digital I/O. External interrupt 2.  |
| RB3/INT3/ECCP2/P2A<br>RB3<br>INT3<br>ECCP2 <sup>(1)</sup> | 45         | 55         | I/O<br>I/O<br>I/O | TTL<br>ST<br>ST | Digital I/O. External interrupt 3. Enhanced Capture 2 input, Compare 2 output, PWM2 output.                   |
| P2A <sup>(1)</sup>  |            |            | 0                 | _               | ECCP2 output P2A.   |
| RB4/KBI0<br>RB4<br>KBI0                                   | 44         | 54         | I/O<br>I          | TTL<br>ST       | Digital I/O. Interrupt-on-change pin.   |
| RB5/KBI1/PGM  | 43         | 53         |                   |                 |   |
| RB5<br>KBI1<br>PGM  |            |            | I/O<br>I<br>I/O   | TTL<br>ST<br>ST | Digital I/O.<br>Interrupt-on-change pin.<br>Low-Voltage ICSP™ programming<br>enable pin.                      |
| RB6/KBI2/PGC  | 42         | 52         |                   |                 |   |
| RB6<br>KBI2<br>PGC  |            |            | I/O<br>I<br>I/O   | TTL<br>ST<br>ST | Digital I/O. Interrupt-on-change pin. In-Circuit Debugger and ICSP programming clock.                         |
| RB7/KBI3/PGD<br>RB7<br>KBI3<br>PGD                        | 37         | 47         | I/O<br>I<br>I/O   | TTL<br>ST<br>ST | Digital I/O. Interrupt-on-change pin. In-Circuit Debugger and ICSP programming data.                          |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels
I = Input

Analog = Analog input
O = Output

P = Power

OD = Open-Drain (no P diode to VDD)

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Din Nama             | Pin N      | umber      | Pin  | Buffer | Description                               |  |
|----------------------|------------|------------|------|--------|---|--|
| Pin Name             | PIC18F6X2X | PIC18F8X2X | Туре | Туре   | Description                               |  |
|                      |            |            |      |        | PORTC is a bidirectional I/O port.        |  |
| RC0/T1OSO/T13CKI     | 30         | 36         |      |        |   |  |
| RC0                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| T1OSO                |            |            | 0    | _      | Timer1 oscillator output.                 |  |
| T13CKI               |            |            | I    | ST     | Timer1/Timer3 external clock input.       |  |
| RC1/T1OSI/ECCP2/P2A  | 29         | 35         |      |        |   |  |
| RC1                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| T1OSI                |            |            | I    | CMOS   | Timer1 oscillator input.                  |  |
| ECCP2 <sup>(2)</sup> |            |            | I/O  | ST     | Enhanced Capture 2 input, Compare 2       |  |
| (4)                  |            |            |      |        | output, PWM 2 output.                     |  |
| P2A <sup>(2)</sup>   |            |            | 0    | _      | ECCP2 output P2A.                         |  |
| RC2/ECCP1/P1A        | 33         | 43         |      |        |   |  |
| RC2                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| ECCP1                |            |            | I/O  | ST     | Enhanced Capture 1 input, Compare 1       |  |
|                      |            |            |      |        | output, PWM 1 output.                     |  |
| P1A                  |            |            | 0    | _      | ECCP1 output P1A.                         |  |
| RC3/SCK/SCL          | 34         | 44         |      |        |   |  |
| RC3                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| SCK                  |            |            | I/O  | ST     | Synchronous serial clock input/output for |  |
|                      |            |            |      |        | SPI™ mode.                                |  |
| SCL                  |            |            | I/O  | ST     | Synchronous serial clock input/output for |  |
|                      |            |            |      |        | I <sup>2</sup> C™ mode.                   |  |
| RC4/SDI/SDA          | 35         | 45         |      |        |   |  |
| RC4                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| SDI                  |            |            | I    | ST     | SPI data in.                              |  |
| SDA                  |            |            | I/O  | ST     | I <sup>2</sup> C data I/O.                |  |
| RC5/SDO              | 36         | 46         |      |        |   |  |
| RC5                  |            |            | I/O  | ST     | Digital I/O.                              |  |
| SDO                  |            |            | 0    | _      | SPI data out.                             |  |
| RC6/TX1/CK1          | 31         | 37         |      |        |   |  |
| RC6                  | -          | -          | I/O  | ST     | Digital I/O.                              |  |
| TX1                  |            |            | 0    | _      | USART1 asynchronous transmit.             |  |
| CK1                  |            |            | I/O  | ST     | USART1 synchronous clock                  |  |
|                      |            |            |      |        | (see RX1/DT1).                            |  |
| RC7/RX1/DT1          | 32         | 38         |      |        |   |  |
| RC7                  | -          |            | I/O  | ST     | Digital I/O.                              |  |
| RX1                  |            |            | I    | ST     | USART1 asynchronous receive.              |  |
| DT1                  |            |            | I/O  | ST     | USART1 synchronous data                   |  |
|                      |            |            |      |        | (see TX1/CK1).                            |  |

Legend: TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

Analog = Analog input

I = Input

O = Output

P = Power

OD = Open-Drain (no P diode to VDD)

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

**TABLE 1-2:** PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name  | Pin N      | umber      | Pin               | Buffer           | Description   |
|---|------------|------------|-------------------|------------------|---|
| riii Naiile                                       | PIC18F6X2X | PIC18F8X2X | Туре              | Туре             | Description   |
|   |            |            |                   |                  | PORTD is a bidirectional I/O port. These pins have TTL input buffers when external memory is enabled. |
| RD0/AD0/PSP0<br>RD0<br>AD0 <sup>(3)</sup><br>PSP0 | 58         | 72         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 0.<br>Parallel Slave Port data.                          |
| RD1/AD1/PSP1<br>RD1<br>AD1 <sup>(3)</sup><br>PSP1 | 55         | 69         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 1.<br>Parallel Slave Port data.                          |
| RD2/AD2/PSP2<br>RD2<br>AD2 <sup>(3)</sup><br>PSP2 | 54         | 68         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 2.<br>Parallel Slave Port data.                          |
| RD3/AD3/PSP3<br>RD3<br>AD3 <sup>(3)</sup><br>PSP3 | 53         | 67         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O. External memory address/data 3. Parallel Slave Port data.                                |
| RD4/AD4/PSP4<br>RD4<br>AD4 <sup>(3)</sup><br>PSP4 | 52         | 66         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 4.<br>Parallel Slave Port data.                          |
| RD5/AD5/PSP5<br>RD5<br>AD5 <sup>(3)</sup><br>PSP5 | 51         | 65         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 5.<br>Parallel Slave Port data.                          |
| RD6/AD6/PSP6<br>RD6<br>AD6 <sup>(3)</sup><br>PSP6 | 50         | 64         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 6.<br>Parallel Slave Port data.                          |
| RD7/AD7/PSP7<br>RD7<br>AD7 <sup>(3)</sup><br>PSP7 | 49         | 63         | I/O<br>I/O<br>I/O | ST<br>TTL<br>TTL | Digital I/O.<br>External memory address/data 7.<br>Parallel Slave Port data.                          |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

= Output

ST = Schmitt Trigger input with CMOS levels Analog = Analog input = Input

Ρ = Power OD = Open-Drain (no P diode to VDD)

- Note 1: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX (CONFIG3H<0>) is not set (all Program Memory modes except Microcontroller).
  - 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
  - 3: External memory interface functions are only available on PIC18F8525/8621 devices.
  - 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
  - 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
  - 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
  - 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
  - 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
  - 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Din Nama   | Pin N      | umber      | Pin                  | Buffer                 | Description  |  |
|--|------------|------------|----------------------|------------------------|--|--|
| Pin Name   | PIC18F6X2X | PIC18F8X2X | Туре                 | Туре                   | Description  |  |
| RE0/AD8/RD/P2D   | 2          | 4          |                      |                        | PORTE is a bidirectional I/O port.   |  |
| RE0<br><u>AD8<sup>(3)</sup></u><br>RD<br>P2D                             |            |            | I/O<br>I/O<br>I<br>O | ST<br>TTL<br>TTL       | Digital I/O. External memory address/data 8. Read control for Parallel Slave Port. ECCP2 output P2D.         |  |
| RE1/AD9/WR/P2C<br>RE1<br>AD9 <sup>(3)</sup><br>WR<br>P2C                 | 1          | 3          | I/O<br>I/O<br>I<br>O | ST<br>TTL<br>TTL<br>ST | Digital I/O. External memory address/data 9. Write control for Parallel Slave Port. ECCP2 output P2C.        |  |
| RE2/AD10/ <del>CS</del> /P2B<br>RE2<br>AD10 <sup>(3)</sup><br>CS<br>P2B  | 64         | 78         | I/O<br>I/O<br>I      | ST<br>TTL<br>TTL       | Digital I/O. External memory address/data 10. Chip select control for Parallel Slave Port. ECCP2 output P2B. |  |
| RE3/AD11/P3C<br>RE3<br>AD11 <sup>(3)</sup><br>P3C <sup>(4)</sup>         | 63         | 77         | I/O<br>I/O<br>O      | ST<br>TTL<br>—         | Digital I/O. External memory address/data 11. ECCP3 output P3C.  |  |
| RE4/AD12/P3B<br>RE4<br>AD12 <sup>(3)</sup><br>P3B <sup>(4)</sup>         | 62         | 76         | I/O<br>I/O<br>O      | ST<br>TTL<br>—         | Digital I/O. External memory address/data 12. ECCP3 output P3B.  |  |
| RE5/AD13/P1C<br>RE5<br>AD13 <sup>(3)</sup><br>P1C <sup>(4)</sup>         | 61         | 75         | I/O<br>I/O<br>O      | ST<br>TTL<br>—         | Digital I/O. External memory address/data 13. ECCP1 output P1C.  |  |
| RE6/AD14/P1B<br>RE6<br>AD14 <sup>(3)</sup><br>P1B <sup>(4)</sup>         | 60         | 74         | I/O<br>I/O<br>O      | ST<br>TTL<br>—         | Digital I/O. External memory address/data 14. ECCP1 output P1B.  |  |
| RE7/AD15/ECCP2/P2A<br>RE7<br>AD15 <sup>(3)</sup><br>ECCP2 <sup>(5)</sup> | 59         | 73         | I/O<br>I/O<br>I/O    | ST<br>TTL<br>ST        | Digital I/O. External memory address/data 15. Enhanced Capture 2 input, Compare 2                            |  |
| P2A <sup>(5)</sup>   |            |            | 0                    | _                      | output, PWM 2 output. ECCP2 output P2A.  |  |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

Analog = Analog input

I = Input P = Power O = Output

OD = Open-Drain (no P diode to VDD)

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name                               | Pin Number |            | Pin           | Buffer                 | Description   |
|--|------------|------------|---------------|------------------------|---|
| Pin Name                               | PIC18F6X2X | PIC18F8X2X | Туре          | Type                   | Description   |
|  |            |            |               |                        | PORTF is a bidirectional I/O port.                      |
| RF0/AN5<br>RF0<br>AN5                  | 18         | 24         | I/O<br>I      | ST<br>Analog           | Digital I/O.<br>Analog input 5.                         |
| RF1/AN6/C2OUT                          | 17         | 23         |               |                        |   |
| RF1<br>AN6<br>C2OUT                    |            |            | I/O<br>I<br>O | ST<br>Analog<br>ST     | Digital I/O.<br>Analog input 6.<br>Comparator 2 output. |
| RF2/AN7/C1OUT<br>RF2<br>AN7<br>C1OUT   | 16         | 18         | I/O<br>I<br>O | ST<br>Analog<br>ST     | Digital I/O.<br>Analog input 7.<br>Comparator 1 output. |
| RF3/AN8<br>RF1<br>AN8                  | 15         | 17         | I/O<br>I      | ST<br>Analog           | Digital I/O.<br>Analog input 8.                         |
| RF4/AN9<br>RF1<br>AN9                  | 14         | 16         | I/O<br>I      | ST<br>Analog           | Digital I/O. Analog input 9.                            |
| RF5/AN10/CVREF<br>RF1<br>AN10<br>CVREF | 13         | 15         | I/O<br>I<br>O | ST<br>Analog<br>Analog | Digital I/O. Analog input 10. Comparator VREF output.   |
| RF6/AN11<br>RF6<br>AN11                | 12         | 14         | I/O<br>I      | ST<br>Analog           | Digital I/O. Analog input 11.                           |
| RF7/SS<br>RF7<br>SS                    | 11         | 13         | I/O<br>I      | ST<br>TTL              | Digital I/O.<br>SPI™ slave select input.                |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels Analog = Analog input
I = Input O = Output

P = Power OD = Open-Drain (no P diode to VDD)

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

**TABLE 1-2:** PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name      | Pin N      | umber      | Pin  | Buffer   | Description  |
|---------------|------------|------------|------|----------|--|
| Pin Name      | PIC18F6X2X | PIC18F8X2X | Туре | Туре     | Description  |
|               |            |            |      |          | PORTG is a bidirectional I/O port.                   |
| RG0/ECCP3/P3A | 3          | 5          |      |          |  |
| RG0           |            |            | I/O  | ST       | Digital I/O.   |
| ECCP3         |            |            | I/O  | ST       | Enhanced Capture 3 input, Compare 3                  |
|               |            |            | _    |          | output, PWM 3 output.                                |
| P3A           |            |            | 0    | _        | ECCP3 output P3A.                                    |
| RG1/TX2/CK2   | 4          | 6          |      |          |  |
| RG1           |            |            | I/O  | ST       | Digital I/O.   |
| TX2           |            |            | 0    | _        | USART2 asynchronous transmit.                        |
| CK2           |            |            | I/O  | ST       | USART2 synchronous clock                             |
|               | _          | _          |      |          | (see RX2/DT2).                                       |
| RG2/RX2/DT2   | 5          | 7          |      | 0.       | D: :::11/0   |
| RG2<br>RX2    |            |            | I/O  | ST<br>ST | Digital I/O. USART2 asynchronous receive.            |
| DT2           |            |            | 1/0  | ST       | USART2 asynchronous feceive. USART2 synchronous data |
| D12           |            |            | "    | 01       | (see TX2/CK2).                                       |
| RG3/CCP4/P3D  | 6          | 8          |      |          |  |
| RG3           |            |            | I/O  | ST       | Digital I/O.   |
| CCP4          |            |            | I/O  | ST       | Capture 4 input, Compare 4 output,                   |
|               |            |            |      |          | PWM 4 output.  |
| P3D           |            |            | 0    | _        | ECCP3 output P3D.                                    |
| RG4/CCP5/P1D  | 8          | 10         |      |          |  |
| RG4           |            |            | I/O  | ST       | Digital I/O.   |
| CCP5          |            |            | I/O  | ST       | Capture 5 input, Compare 5 output,                   |
| D4D           |            |            |      |          | PWM 5 output.  |
| P1D           |            |            | 0    | _        | ECCP1 output P1D.                                    |
| RG5           | 7          | 9          | -    | _        | See MCLR/VPP/RG5 pin.                                |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output ST = Schmitt Trigger input with CMOS levels Analog = Analog input = Input 0 = Output

= Open-Drain (no P diode to VDD) = Power OD

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

TABLE 1-2: PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name  | Pin N      | Pin Number |               | Buffer            | Descriptio   |
|---|------------|------------|---------------|-------------------|--|
| FIII Naille                                       | PIC18F6X2X | PIC18F8X2X | Туре          | Туре              | Description  |
|   |            |            |               |                   | PORTH is a bidirectional I/O port <sup>(6)</sup> . |
| RH0/A16<br>RH0                                    | _          | 79         | I/O           | ST                | Digital I/O.                                       |
| A16   |            |            | 0             | TTL               | External memory address 16.                        |
| RH1/A17<br>RH1                                    | _          | 80         | I/O           | ST                | Digital I/O.                                       |
| A17   |            |            | 0             | TTL               | External memory address 17.                        |
| RH2/A18<br>RH2<br>A18                             | _          | 1          | I/O<br>O      | ST<br>TTL         | Digital I/O. External memory address 18.           |
| RH3/A19<br>RH3<br>A19                             | _          | 2          | I/O<br>O      | ST<br>TTL         | Digital I/O. External memory address 19.           |
| RH4/AN12/P3C<br>RH4<br>AN12<br>P3C <sup>(7)</sup> | _          | 22         | I/O<br>I<br>O | ST<br>Analog<br>— | Digital I/O. Analog input 12. ECCP3 output P3C.    |
| RH5/AN13/P3B<br>RH5<br>AN13<br>P3B <sup>(7)</sup> | _          | 21         | I/O<br>I<br>O | ST<br>Analog<br>— | Digital I/O. Analog input 13. ECCP3 output P3B.    |
| RH6/AN14/P1C<br>RH6<br>AN14<br>P1C <sup>(7)</sup> | _          | 20         | I/O<br>I<br>O | ST<br>Analog<br>— | Digital I/O. Analog input 14. ECCP1 output P1C.    |
| RH7/AN15/P1B<br>RH7<br>AN15<br>P1B <sup>(7)</sup> | _          | 19         | I/O<br>I<br>O | ST<br>Analog<br>— | Digital I/O. Analog input 15. ECCP1 output P1B.    |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

Analog = Analog input

I = Input

O = Output

P = Power

OD = Open-Drain (no P diode to VDD)

- Note 1: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX (CONFIG3H<0>) is not set (all Program Memory modes except Microcontroller).
  - 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
  - 3: External memory interface functions are only available on PIC18F8525/8621 devices.
  - 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.
  - 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
  - 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
  - 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
  - 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP<sup>TM</sup> modes. See parameter D001 for details.
  - 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

**TABLE 1-2:** PIC18F6525/6621/8525/8621 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name            | Pin Number |            | Pin  | Buffer | Description  |
|---------------------|------------|------------|------|--------|--|
| Pili Name           | PIC18F6X2X | PIC18F8X2X | Туре | Type   | Description  |
|                     |            |            |      |        | PORTJ is a bidirectional I/O port <sup>(6)</sup> . |
| RJ0/ALE             | _          | 62         |      |        |  |
| RJ0                 |            |            | I/O  | ST     | Digital I/O.                                       |
| ALE_                |            |            | 0    | TTL    | External memory address latch enable.              |
| RJ1/OE              | _          | 61         |      |        | 5  |
| RJ1<br>OE           |            |            | 1/0  | ST     | Digital I/O.                                       |
| -                   |            |            | 0    | TTL    | External memory output enable.                     |
| RJ2/WRL<br>RJ2      | _          | 60         | I/O  | ST     | Digital I/O.                                       |
| WRL                 |            |            | 0    | TTL    | External memory write low control.                 |
| RJ3/WRH             | _          | 59         |      |        |  |
| RJ3                 |            | 33         | I/O  | ST     | Digital I/O.                                       |
| WRH                 |            |            | 0    | TTL    | External memory write high control.                |
| RJ4/BA0             | _          | 39         |      |        |  |
| RJ4                 |            |            | I/O  | ST     | Digital I/O.                                       |
| BA0                 |            |            | 0    | TTL    | System bus byte address 0 control.                 |
| RJ5/CE              | _          | 40         |      |        |  |
| RJ5<br>CE           |            |            | 1/0  | ST     | Digital I/O  |
|                     |            |            | 0    | TTL    | External memory access indicator.                  |
| RJ6/LB<br>RJ6       | _          | 41         | I/O  | ST     | Digital I/O.                                       |
| LB                  |            |            | 0    | TTL    | External memory low byte select.                   |
| RJ7/UB              | _          | 42         |      |        |  |
| RJ7                 |            | 72         | I/O  | ST     | Digital I/O.                                       |
| <del>UB</del>       |            |            | 0    | TTL    | External memory high byte select.                  |
| Vss                 | 9, 25,     | 11, 31,    | Р    | _      | Ground reference for logic and I/O pins.           |
|                     | 41, 56     | 51, 70     |      |        |  |
| Vdd                 | 10, 26,    | 12, 32,    | Р    |        | Positive supply for logic and I/O pins.            |
|                     | 38, 57     | 48, 71     |      |        |  |
| AVss <sup>(8)</sup> | 20         | 26         | Р    | _      | Ground reference for analog modules.               |
| AVDD <sup>(8)</sup> | 19         | 25         | Р    | _      | Positive supply for analog modules.                |

**Legend:** TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

Analog = Analog input = Output = Input О

OD = Open-Drain (no P diode to VDD) = Power

Note 1: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX (CONFIG3H<0>) is not set (all Program Memory modes except Microcontroller).

- 2: Default assignment for ECCP2/P2A when CCP2MX is set (all devices).
- 3: External memory interface functions are only available on PIC18F8525/8621 devices.
- 4: Default assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is set and for all PIC18F6525/6621 devices.

CMOS = CMOS compatible input or output

- 5: Alternate assignment for ECCP2/P2A in PIC18F8525/8621 devices when CCP2MX is not set (Microcontroller mode).
- 6: PORTH and PORTJ (and their multiplexed functions) are only available on PIC18F8525/8621 devices.
- 7: Alternate assignment for P1B/P1C/P3B/P3C for PIC18F8525/8621 devices when ECCPMX (CONFIG3H<1>) is not set.
- 8: AVDD must be connected to a positive supply and AVSS must be connected to a ground reference for proper operation of the part in user or ICSP™ modes. See parameter D001 for details.
- 9: RG5 is multiplexed with MCLR and is only available when the MCLR Resets are disabled.

# 2.0 OSCILLATOR CONFIGURATIONS

## 2.1 Oscillator Types

The PIC18F6525/6621/8525/8621 devices can be operated in twelve different oscillator modes. The user can program four configuration bits (FOSC3, FOSC2, FOSC1 and FOSC0) to select one of these eight modes:

| 1.  | LP        | Low-Power Crystal                                  |
|-----|-----------|--|
| 2.  | XT        | Crystal/Resonator                                  |
| 3.  | HS        | High-Speed Crystal/Resonator                       |
| 4.  | RC        | External Resistor/Capacitor                        |
| 5.  | EC        | External Clock                                     |
| 6.  | ECIO      | External Clock with I/O pin enabled                |
| 7.  | HS+PLL    | High-Speed Crystal/Resonator with PLL enabled      |
| 8.  | RCIO      | External Resistor/Capacitor with I/O pin enabled   |
| 9.  | ECIO+SPLL | External Clock with software controlled PLL        |
| 10. | ECIO+PLL  | External Clock with PLL and I/O pin enabled        |
| 11. | HS+SPLL   | High-Speed Crystal/Resonator with software control |
| 12. | RCIO      | External Resistor/Capacitor with I/O pin enabled   |


## 2.2 Crystal Oscillator/Ceramic Resonators

In XT, LP, HS, HS+PLL or HS+SPLL Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-1 shows the pin connections.

The PIC18F6525/6621/8525/8621 oscillator design requires the use of a parallel cut crystal.

**Note:** Use of a series cut crystal may give a frequency out of the crystal manufacturers specifications.

# FIGURE 2-1: CRYSTAL/CERAMIC RESONATOR OPERATION (HS, XT OR LP CONFIGURATION)



- Note 1: See Table 2-1 and Table 2-2 for recommended values of C1 and C2.
  - **2:** A series resistor (Rs) may be required for AT strip cut crystals.
  - 3: RF varies with the oscillator mode chosen.

## TABLE 2-1: CAPACITOR SELECTION FOR CERAMIC RESONATORS

|      | Ranges Tested: |           |           |  |  |  |  |  |
|------|----------------|-----------|-----------|--|--|--|--|--|
| Mode | Mode Freq C1   |           |           |  |  |  |  |  |
| XT   | 455 kHz        | 68-100 pF | 68-100 pF |  |  |  |  |  |
|      | 2.0 MHz        | 15-68 pF  | 15-68 pF  |  |  |  |  |  |
|      | 4.0 MHz        | 15-68 pF  | 15-68 pF  |  |  |  |  |  |
| HS   | 8.0 MHz        | 10-68 pF  | 10-68 pF  |  |  |  |  |  |
|      | 16.0 MHz       | 10-22 pF  | 10-22 pF  |  |  |  |  |  |

These values are for design guidance only. See notes following this table.

| Resonators Used: |        |  |  |
|------------------|--------|--|--|
| 2 kHz            | 8 MHz  |  |  |
| 4 MHz            | 16 MHz |  |  |

- **Note 1:** Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 2: When operating below 3V VDD, or when using certain ceramic resonators at any voltage, it may be necessary to use high gain HS mode, try a lower frequency resonator or switch to a crystal oscillator.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components or verify oscillator performance.

TABLE 2-2: CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR

|            | Ranges Tested: |                |          |  |  |  |  |  |
|------------|----------------|----------------|----------|--|--|--|--|--|
| Mode       | Freq           | C1             | C2       |  |  |  |  |  |
| LP         | 32.0 kHz       | 33 pF          | 33 pF    |  |  |  |  |  |
| XT         | 200 kHz        | 47-68 pF       | 47-68 pF |  |  |  |  |  |
|            | 1.0 MHz        | 15 pF          | 15 pF    |  |  |  |  |  |
|            | 4.0 MHz        | 15 pF          | 15 pF    |  |  |  |  |  |
| HS         | 4.0 MHz        | 15 pF          | 15 pF    |  |  |  |  |  |
|            | 8.0 MHz        | 15-33 pF       | 15-33 pF |  |  |  |  |  |
|            | 20.0 MHz       | 15-33 pF       | 15-33 pF |  |  |  |  |  |
|            | 25.0 MHz       | 15-33 pF       | 15-33 pF |  |  |  |  |  |
| These valu | es are for de  | esign guidance | only.    |  |  |  |  |  |


These values are for design guidance only. See notes following this table.

| Crystals Used |        |  |  |  |
|---------------|--------|--|--|--|
| 32 kHz        | 4 MHz  |  |  |  |
| 200 kHz       | 8 MHz  |  |  |  |
| 1 MHz         | 20 MHz |  |  |  |

- **Note 1:** Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 2: Rs (see Figure 2-1) may be required in HS mode, as well as XT mode, to avoid overdriving crystals with low drive level specification.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components or verify oscillator performance.

An external clock source may also be connected to the OSC1 pin in the HS, XT and LP modes as shown in Figure 2-2.

FIGURE 2-2: EXTERNAL CLOCK INPUT OPERATION (HS, XT OR LP OSCILLATOR CONFIGURATION)




#### 2.3 RC Oscillator

For timing insensitive applications, the "RC" and "RCIO" device options offer additional cost savings. The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values and the operating temperature. In addition to this, the oscillator frequency will vary from unit to unit due to normal process parameter variation. Furthermore, the difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to take into account variation due to tolerance of external R and C components used. Figure 2-3 shows how the R/C combination is connected.

In the RC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic.

FIGURE 2-3: RC OSCILLATOR MODE




The RCIO Oscillator mode functions like the RC mode except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6).

## 2.4 External Clock Input

The EC, ECIO, EC+PLL and EC+SPLL Oscillator modes require an external clock source to be connected to the OSC1 pin. The feedback device between OSC1 and OSC2 is turned off in these modes to save current. There is a maximum 1.5  $\mu$ s start-up required after a Power-on Reset or wake-up from Sleep mode.


In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-4 shows the pin connections for the EC Oscillator mode.

FIGURE 2-4: EXTERNAL CLOCK INPUT OPERATION (EC CONFIGURATION)



The ECIO Oscillator mode functions like the EC mode except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6). Figure 2-5 shows the pin connections for the ECIO Oscillator mode.

FIGURE 2-5: EXTERNAL CLOCK INPUT OPERATION (ECIO CONFIGURATION)



## 2.5 Phase Locked Loop (PLL)


A Phase Locked Loop circuit is provided as a programmable option for users that want to multiply the frequency of the incoming oscillator signal by 4. For an input clock frequency of 10 MHz, the internal clock frequency will be multiplied to 40 MHz. This is useful for customers who are concerned with EMI due to high-frequency crystals.

The PLL can only be enabled when the oscillator configuration bits are programmed for High-Speed Oscillator or External Clock mode. If they are programmed for any other mode, the PLL is not enabled and the system clock will come directly from OSC1. There are two types of PLL modes: Software Controlled PLL and Configuration Bits Controlled PLL. In Software Controlled PLL mode, PIC18F6525/6621/ 8525/8621 executes at regular clock frequency after all Reset conditions. During execution, the application can enable PLL and switch to 4x clock frequency operation by setting the PLLEN bit in the OSCCON register. In Configuration Bits Controlled PLL, the PLL operation cannot be changed "on-the-fly". To enable or disable it, the controller must either cycle through a Power-on Reset, or switch the clock source from the main oscillator to the Timer1 oscillator and back again (see Section 2.6 "Oscillator Switching Feature" for details).

The type of PLL is selected by programming FOSC<3:0> configuration bits in the CONFIG1H Configuration register. The oscillator mode is specified during device programming.

A PLL lock timer is used to ensure that the PLL has locked before device execution starts. The PLL lock timer has a time-out that is called TPLL.

FIGURE 2-6: PLL BLOCK DIAGRAM




## 2.6 Oscillator Switching Feature

The PIC18F6525/6621/8525/8621 devices include a feature that allows the system clock source to be switched from the main oscillator to an alternate low frequency clock source. For the PIC18F6525/6621/8525/8621 devices, this alternate clock source is the Timer1 oscillator. If a low-frequency crystal (32 kHz, for example) has been attached to the Timer1 oscillator pins and the Timer1 oscillator has been enabled, the device can switch to a low-power execution mode.

Figure 2-7 shows a block diagram of the system clock sources. The clock switching feature is enabled by programming the Oscillator Switching Enable (OSCSEN) bit in the CONFIG1H Configuration register to a '0'. Clock switching is disabled in an erased device. See Section 12.0 "Timer1 Module" for further details of the Timer1 oscillator. See Section 24.0 "Special Features of the CPU" for Configuration register details.

FIGURE 2-7: DEVICE CLOCK SOURCES



#### 2.6.1 SYSTEM CLOCK SWITCH BIT

The system clock source switching is performed under software control. The system clock switch bits, SCS1:SCS0 (OSCCON<1:0>), control the clock switching. When the SCS0 bit is '0', the system clock source comes from the main oscillator that is selected by the FOSC configuration bits in the CONFIG1H Configuration register. When the SCS0 bit is set, the system clock source will come from the Timer1 oscillator. The SCS0 bit is cleared on all forms of Reset.

When the FOSC bits are programmed for Software PLL mode, the SCS1 bit can be used to select between primary oscillator/clock and PLL output. The SCS1 bit will only have an effect on the system clock if the PLL is enabled (PLLEN = 1) and locked (LOCK = 1), else it will be forced cleared. When programmed with Configuration Controlled PLL, the SCS1 bit will be forced clear.

Note: The Timer1 oscillator must be enabled and operating to switch the system clock source. The Timer1 oscillator is enabled by setting the T1OSCEN bit in the Timer1 Control register (T1CON). If the Timer1 oscillator is not enabled, then any write to the SCS0 bit will be ignored (SCS0 bit forced cleared) and the main oscillator will continue to be the system clock source.

#### REGISTER 2-1: OSCCON: OSCILLATOR CONTROL REGISTER

| U-0   | U-0 | U-0 | U-0 | R/W-0 | R/W-0                | R/W-0 | R/W-0               |
|-------|-----|-----|-----|-------|----------------------|-------|---------------------|
| _     | _   | _   | _   | LOCK  | PLLEN <sup>(1)</sup> | SCS1  | SCS0 <sup>(2)</sup> |
| bit 7 |     |     |     |       |                      |       | bit 0               |

bit 7-4 Unimplemented: Read as '0'

bit 3 LOCK: Phase Lock Loop Lock Status bit

1 = Phase Lock Loop output is stable as system clock

0 = Phase Lock Loop output is not stable and output cannot be used as system clock

bit 2 PLLEN: Phase Lock Loop Enable bit(1)

1 = Enable Phase Lock Loop output as system clock

0 = Disable Phase Lock Loop

bit 1 SCS1: System Clock Switch bit 1

When PLLEN and LOCK bits are set:

1 = Use PLL output

0 = Use primary oscillator/clock input pin

When PLLEN or LOCK bit is cleared:

Bit is forced clear.

bit 0 SCS0: System Clock Switch bit 0<sup>(2)</sup>

When  $\overline{OSCSEN}$  configuration bit =  $\underline{0}$  and T1OSCEN bit =  $\underline{1}$ :

1 = Switch to Timer1 oscillator/clock pin

0 = Use primary oscillator/clock input pin

When OSCSEN and T1OSCEN are in other states:

Bit is forced clear.

**Note 1:** PLLEN bit is forced set when configured for ECIO+PLL and HS+PLL modes. This bit is writable for ECIO+SPLL and HS+SPLL modes only; forced cleared for all other oscillator modes.

2: The setting of SCS0 = 1 supersedes SCS1 = 1.


| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

#### 2.6.2 OSCILLATOR TRANSITIONS

PIC18F6525/6621/8525/8621 devices contain circuitry to prevent "glitches" when switching between oscillator sources. Essentially, the circuitry waits for eight rising edges of the clock source that the processor is switching to. This ensures that the new clock source is stable and that its pulse width will not be less than the shortest pulse width of the two clock sources.

A timing diagram indicating the transition from the main oscillator to the Timer1 oscillator is shown in Figure 2-8. The Timer1 oscillator is assumed to be running all the time. After the SCS0 bit is set, the processor is frozen at the next occurring Q1 cycle. After eight synchronization cycles are counted from the Timer1 oscillator, operation resumes. No additional delays are required after the synchronization cycles.






The sequence of events that takes place when switching from the Timer1 oscillator to the main oscillator will depend on the mode of the main oscillator. In addition to eight clock cycles of the main oscillator, additional delays may take place.


If the main oscillator is configured for an external crystal (HS, XT, LP), then the transition will take place after an oscillator start-up time (Tost) has occurred. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for HS, XT and LP modes, is shown in Figure 2-9.

FIGURE 2-9: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS, XT, LP)




If the main oscillator is configured for HS mode with PLL active, an oscillator start-up time (Tost) plus an additional PLL time-out (TPLL) will occur. The PLL time-out is typically 2 ms and allows the PLL to lock to the main oscillator frequency. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for HS+PLL mode, is shown in Figure 2-10.

FIGURE 2-10: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS WITH PLL ACTIVE, SCS1 = 1)




If the main oscillator is configured for EC mode with PLL active, only PLL time-out (TPLL) will occur. The PLL time-out is typically 2 ms and allows the PLL to lock to the main oscillator frequency. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for EC with PLL active, is shown in Figure 2-11.

FIGURE 2-11: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (EC WITH PLL ACTIVE. SCS1 = 1)



If the main oscillator is configured in the RC, RCIO, EC or ECIO modes, there is no oscillator start-up time-out. Operation will resume after eight cycles of the main oscillator have been counted. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for RC, RCIO, EC and ECIO modes, is shown in Figure 2-12.

FIGURE 2-12: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (RC, EC)



## 2.7 Effects of Sleep Mode on the On-Chip Oscillator

When the device executes a SLEEP instruction, the onchip clocks and oscillator are turned off and the device is held at the beginning of an instruction cycle (Q1 state). With the oscillator off, the OSC1 and OSC2 signals will stop oscillating. Since all the transistor switching currents have been removed, Sleep mode achieves the lowest current consumption of the device (only leakage currents). Enabling any on-chip feature that will operate during Sleep will increase the current consumed during Sleep. The user can wake from Sleep through external Reset, Watchdog Timer Reset, or through an interrupt.

TABLE 2-3: OSC1 AND OSC2 PIN STATES IN SLEEP MODE

| Oscillator Mode | OSC1 Pin  | OSC2 Pin  |
|-----------------|---|---|
| RC              | Floating, external resistor should pull high          | At logic low  |
| RCIO            | Floating, external resistor should pull high          | Configured as PORTA, bit 6                            |
| ECIO            | Floating  | Configured as PORTA, bit 6                            |
| EC              | Floating  | At logic low  |
| LP, XT and HS   | Feedback inverter disabled at quiescent voltage level | Feedback inverter disabled at quiescent voltage level |

Note: See Table 3-1 in Section 3.0 "Reset" for time-outs due to Sleep and MCLR Reset.

## 2.8 Power-up Delays

Power-up delays are controlled by two timers so that no external Reset circuitry is required for most applications. The delays ensure that the device is kept in Reset until the device power supply and clock are stable. For additional information on Reset operation, see **Section 3.0** "**Reset**".

The first timer is the Power-up Timer (PWRT) which optionally provides a fixed delay of 72 ms (nominal) on power-up only (POR and BOR). The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable.

With the PLL enabled (HS+PLL and EC+PLL oscillator mode), the time-out sequence following a Power-on Reset is different from other oscillator modes. The time-out sequence is as follows: First, the PWRT time-out is invoked after a POR time delay has expired. Then, the Oscillator Start-up Timer (OST) is invoked. However, this is still not a sufficient amount of time to allow the PLL to lock at high frequencies. The PWRT timer is used to provide an additional fixed 2 ms (nominal) time-out to allow the PLL ample time to lock to the incoming clock frequency.

## 3.0 RESET

The PIC18F6525/6621/8525/8621 devices differentiate between various kinds of Reset:

- a) Power-on Reset (POR)
- b) MCLR Reset during normal operation
- c) MCLR Reset during Sleep
- d) Watchdog Timer (WDT) Reset (during normal operation)
- e) Programmable Brown-out Reset (BOR)
- f) RESET Instruction
- g) Stack Full Reset
- h) Stack Underflow Reset


Most registers are unaffected by a Reset. Their status is unknown on POR and unchanged by all other Resets. The other registers are forced to a "Reset state" on Power-on Reset, MCLR, WDT Reset, Brownout Reset, MCLR Reset during Sleep and by the RESET instruction.

Most registers are not affected by a WDT wake-up since this is viewed as the resumption of normal operation. Status bits from the RCON register, RI, TO, PD, POR and BOR, are set or cleared differently in different Reset situations as indicated in Table 3-2. These bits are used in software to determine the nature of the Reset. See Table 3-3 for a full description of the Reset states of all registers.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 3-1.

The Enhanced MCU devices have a MCLR noise filter in the MCLR Reset path. The filter will detect and ignore small pulses. The MCLR pin is not driven low by any internal Resets, including the WDT.

FIGURE 3-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT




## 3.1 Power-on Reset (POR)

A Power-on Reset pulse is generated on-chip when VDD rise is detected. To take advantage of the POR circuitry, tie the  $\overline{MCLR}$  pin through a 1 k $\Omega$  to 10 k $\Omega$  resistor to VDD. This will eliminate external RC components usually needed to create a Power-on Reset delay. A minimum rise rate for VDD is specified (parameter D004). For a slow rise time, see Figure 3-2.

When the device starts normal operation (i.e., exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met.

FIGURE 3-2: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



- Note 1: External Power-on Reset circuit is required only if the VDD power-up slope is too slow.

  The diode D helps discharge the capacitor quickly when VDD powers down.
  - 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that the voltage drop across R does not violate the device's electrical specification.
  - 3: R1 = 1 k $\Omega$  to 10 k $\Omega$  will limit any current flowing into  $\overline{\text{MCLR}}$  from external capacitor C in the event of  $\overline{\text{MCLR}}/\text{VPP}$  pin breakdown, due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

## 3.2 Power-up Timer (PWRT)

The Power-up Timer provides a fixed nominal time-out (parameter 33) only on power-up from the POR. The Power-up Timer operates on an internal RC oscillator. The chip is kept in Reset as long as the PWRT is active. The PWRT's time delay allows VDD to rise to an acceptable level. A configuration bit is provided to enable/disable the PWRT.

The power-up time delay will vary from chip-to-chip due to VDD, temperature and process variation. See DC parameter 33 for details.

## 3.3 Oscillator Start-up Timer (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delays after the PWRT delay is over (parameter 32). This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP and HS modes and only on Power-on Reset, or wake-up from Sleep.

#### 3.4 PLL Lock Time-out

With the PLL enabled, the time-out sequence following a Power-on Reset is different from other oscillator modes. A portion of the Power-up Timer is used to provide a fixed time-out that is sufficient for the PLL to lock to the main oscillator frequency. This PLL lock time-out (TPLL) is typically 2 ms and follows the oscillator start-up time-out.

## 3.5 Brown-out Reset (BOR)

A configuration bit, BOR, can disable (if clear/programmed) or enable (if set) the Brown-out Reset circuitry. If VDD falls below parameter D005 for greater than parameter 35, the brown-out situation will reset the chip. A Reset may not occur if VDD falls below parameter D005 for less than parameter 35. The chip will remain in Brown-out Reset until VDD rises above BVDD. If the Power-up Timer is enabled, it will be invoked after VDD rises above BVDD; it then will keep the chip in Reset for an additional time delay (parameter 33). If VDD drops below BVDD while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be initialized. Once VDD rises above BVDD, the Power-up Timer will execute the additional time delay.

#### 3.6 Time-out Sequence

On power-up, the time-out sequence is as follows: First, PWRT time-out is invoked after the POR time delay has expired. Then, OST is activated. The total time-out will vary based on oscillator configuration and the status of the PWRT. For example, in RC mode with the PWRT disabled, there will be no time-out at all. Figure 3-3, Figure 3-4, Figure 3-5, Figure 3-6 and Figure 3-7 depict time-out sequences on power-up.

Since the time-outs occur from the POR pulse, the time-outs will expire if MCLR is kept low long enough. Bringing MCLR high will begin execution immediately (Figure 3-5). This is useful for testing purposes or to synchronize more than one PIC18F6525/6621/8525/8621 device operating in parallel.

Table 3-2 shows the Reset conditions for some Special Function Registers, while Table 3-3 shows the Reset conditions for all of the registers.

TABLE 3-1: TIME-OUT IN VARIOUS SITUATIONS

| Oscillator                         | Power-up                 | (2)              |   | Wake-up from<br>Sleep or<br>Oscillator Switch |  |
|------------------------------------|--------------------------|------------------|---|---|--|
| Configuration                      | PWRTE = 0                | PWRTE = 1        | Brown-out                               |   |  |
| HS with PLL enabled <sup>(1)</sup> | 72 ms + 1024 Tosc + 2 ms | 1024 Tosc + 2 ms | 72 ms <sup>(2)</sup> + 1024 Tosc + 2 ms | 1024 Tosc + 2 ms                              |  |
| HS, XT, LP                         | 72 ms + 1024 Tosc        | 1024 Tosc        | 72 ms <sup>(2)</sup> + 1024 Tosc        | 1024 Tosc                                     |  |
| EC                                 | 72 ms                    | 1.5 μs           | 72 ms <sup>(2)</sup>                    | 1.5 μs <sup>(3)</sup>                         |  |
| External RC                        | 72 ms                    | _                | 72 ms <sup>(2)</sup>                    | _   |  |

Note 1: 2 ms is the nominal time required for the 4x PLL to lock.

2: 72 ms is the nominal power-up timer delay, if implemented.

3:  $1.5 \mu s$  is the recovery time from Sleep. There is no recovery time from oscillator switch.

## REGISTER 3-1: RCON REGISTER BITS AND POSITIONS<sup>(1)</sup>

| R/W-0 | U-0 | U-0 | R/W-1 | R/W-1 | R/W-1 | R/W-0 | R/W-0 |
|-------|-----|-----|-------|-------|-------|-------|-------|
| IPEN  | _   | _   | RI    | TO    | PD    | POR   | BOR   |
| bit 7 |     |     |       |       |       |       | bit 0 |

Note 1: Refer to Section 4.14 "RCON Register" for bit definitions.

TABLE 3-2: STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR RCON REGISTER

| Condition                                     | Program<br>Counter    | RI | то | PD | POR | BOR | STKFUL | STKUNF |
|---|-----------------------|----|----|----|-----|-----|--------|--------|
| Power-on Reset                                | 0000h                 | 1  | 1  | 1  | 0   | 0   | u      | u      |
| MCLR Reset during normal operation            | 0000h                 | u  | u  | u  | u   | u   | u      | u      |
| Software Reset during normal operation        | 0000h                 | 0  | u  | u  | u   | u   | u      | u      |
| Stack Full Reset during normal operation      | 0000h                 | u  | u  | u  | u   | u   | u      | 1      |
| Stack Underflow Reset during normal operation | 0000h                 | u  | u  | u  | u   | u   | 1      | u      |
| MCLR Reset during Sleep                       | 0000h                 | u  | 1  | 0  | u   | u   | u      | u      |
| WDT Reset                                     | 0000h                 | 1  | 0  | 1  | u   | u   | u      | u      |
| WDT Wake-up                                   | PC + 2                | u  | 0  | 0  | u   | u   | u      | u      |
| Brown-out Reset                               | 0000h                 | 1  | 1  | 1  | 1   | 0   | u      | u      |
| Interrupt Wake-up from Sleep                  | PC + 2 <sup>(1)</sup> | u  | 1  | 0  | u   | u   | u      | u      |

**Legend:** u = unchanged, x = unknown

**Note 1:** When the wake-up is due to an interrupt and the GIEH or GIEL bits are set, the PC is loaded with the interrupt vector (0008h or 0018h).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS

| Register | Applicable Devices |            | Power-on Reset,<br>Brown-out Reset | MCLR Resets WDT Reset RESET Instruction Stack Resets | Wake-up via WDT<br>or Interrupt |
|----------|--------------------|------------|------------------------------------|--|---------------------------------|
| TOSU     | PIC18F6X2X         | PIC18F8X2X | 0 0000                             | 0 0000   | 0 uuuu <b>(3)</b>               |
| TOSH     | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu <sup>(3)</sup>        |
| TOSL     | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu <b>(3)</b>            |
| STKPTR   | PIC18F6X2X         | PIC18F8X2X | 00-0 0000                          | uu-0 0000  | uu-u uuuu <sup>(3)</sup>        |
| PCLATU   | PIC18F6X2X         | PIC18F8X2X | 0 0000                             | 0 0000   | u uuuu                          |
| PCLATH   | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| PCL      | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | PC + 2 <sup>(2)</sup>           |
| TBLPTRU  | PIC18F6X2X         | PIC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| TBLPTRH  | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| TBLPTRL  | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| TABLAT   | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| PRODH    | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| PRODL    | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| INTCON   | PIC18F6X2X         | PIC18F8X2X | 0000 000x                          | 0000 000u  | uuuu uuuu <b>(1)</b>            |
| INTCON2  | PIC18F6X2X         | PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu(1)                    |
| INTCON3  | PIC18F6X2X         | PIC18F8X2X | 1100 0000                          | 1100 0000  | uuuu uuuu(1)                    |
| INDF0    | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTINC0 | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTDEC0 | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PREINC0  | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PLUSW0   | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| FSR0H    | PIC18F6X2X         | PIC18F8X2X | 0000                               | 0000   | uuuu                            |
| FSR0L    | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| WREG     | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| INDF1    | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTINC1 | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTDEC1 | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PREINC1  | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PLUSW1   | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| FSR1H    | PIC18F6X2X         | PIC18F8X2X | 0000                               | 0000   | uuuu                            |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.
  - 7: If MCLR function is disabled, PORTG<5> is a read-only bit.
  - 8: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
  - 9: The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register            | Applicable Devices |            | Power-on Reset,<br>Brown-out Reset | MCLR Resets WDT Reset RESET Instruction Stack Resets | Wake-up via WDT<br>or Interrupt |
|---------------------|--------------------|------------|------------------------------------|--|---------------------------------|
| FSR1L               | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| BSR                 | PIC18F6X2X         | PIC18F8X2X | 0000                               | 0000   | uuuu                            |
| INDF2               | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTINC2            | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| POSTDEC2            | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PREINC2             | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| PLUSW2              | PIC18F6X2X         | PIC18F8X2X | N/A                                | N/A  | N/A                             |
| FSR2H               | PIC18F6X2X         | PIC18F8X2X | 0000                               | 0000   | uuuu                            |
| FSR2L               | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| STATUS              | PIC18F6X2X         | PIC18F8X2X | x xxxx                             | u uuuu   | u uuuu                          |
| TMR0H               | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | uuuu uuuu  | uuuu uuuu                       |
| TMR0L               | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| T0CON               | PIC18F6X2X         | PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| OSCCON              | PIC18F6X2X         | PIC18F8X2X | 0000                               | 0000   | uuuu                            |
| LVDCON              | PIC18F6X2X         | PIC18F8X2X | 00 0101                            | 00 0101  | uu uuuu                         |
| WDTCON              | PIC18F6X2X         | PIC18F8X2X | 0                                  | 0  | u                               |
| RCON <sup>(4)</sup> | PIC18F6X2X         | PIC18F8X2X | 01 11qq                            | 01 qquu  | u1 qquu                         |
| TMR1H               | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| TMR1L               | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| T1CON               | PIC18F6X2X         | PIC18F8X2X | 0-00 0000                          | u-uu uuuu  | u-uu uuuu                       |
| TMR2                | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| PR2                 | PIC18F6X2X         | PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| T2CON               | PIC18F6X2X         | PIC18F8X2X | -000 0000                          | -000 0000  | -uuu uuuu                       |
| SSPBUF              | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| SSPADD              | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| SSPSTAT             | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| SSPCON1             | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| SSPCON2             | PIC18F6X2X         | PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| ADRESH              | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| ADRESL              | PIC18F6X2X         | PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.
  - 7: If MCLR function is disabled, PORTG<5> is a read-only bit.
  - 8: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
  - 9: The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register              | Applicable Devices |           | Power-on Reset,<br>Brown-out Reset | MCLR Resets WDT Reset RESET Instruction Stack Resets | Wake-up via WDT<br>or Interrupt |
|-----------------------|--------------------|-----------|------------------------------------|--|---------------------------------|
| ADCON0                | PIC18F6X2X P       | IC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| ADCON1                | PIC18F6X2X P       | IC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| ADCON2                | PIC18F6X2X P       | IC18F8X2X | 0-00 0000                          | 0-00 0000  | u-uu uuuu                       |
| CCPR1H                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCPR1L                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCP1CON               | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| CCPR2H                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCPR2L                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCP2CON               | PIC18F6X2X P       | IC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| CCPR3H                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCPR3L                | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| CCP3CON               | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| ECCP1AS               | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| CVRCON                | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| CMCON                 | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| TMR3H                 | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| TMR3L                 | PIC18F6X2X P       | IC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| T3CON                 | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | uuuu uuuu  | uuuu uuuu                       |
| PSPCON <sup>(8)</sup> | PIC18F6X2X P       | IC18F8X2X | 0000                               | 0000   | uuuu                            |
| SPBRG1                | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| RCREG1                | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| TXREG1                | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| TXSTA1                | PIC18F6X2X P       | IC18F8X2X | 0000 0010                          | 0000 0010  | uuuu uuuu                       |
| RCSTA1                | PIC18F6X2X P       | IC18F8X2X | 0000 000x                          | 0000 000x  | uuuu uuuu                       |
| EEADRH                | PIC18F6X2X P       | IC18F8X2X | 00                                 | 00   | uu                              |
| EEADR                 | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| EEDATA                | PIC18F6X2X P       | IC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| EECON2                | PIC18F6X2X P       | IC18F8X2X |                                    |  |                                 |
| EECON1                | PIC18F6X2X P       | IC18F8X2X | xx-0 x000                          | uu-0 u000  | uu-u u000                       |

 $\label{eq:update} \begin{tabular}{ll} $u$ = unchanged, $x$ = unknown, $-$ = unimplemented bit, read as `0', $q$ = value depends on condition. \\ Shaded cells indicate conditions do not apply for the designated device. \\ \end{tabular}$ 

- **Note 1:** One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.
  - 7: If MCLR function is disabled, PORTG<5> is a read-only bit.
  - 8: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
  - 9: The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register               | Applicable Devices    | Power-on Reset,<br>Brown-out Reset | MCLR Resets WDT Reset RESET Instruction Stack Resets | Wake-up via WDT<br>or Interrupt |
|------------------------|-----------------------|------------------------------------|--|---------------------------------|
| IPR3                   | PIC18F6X2X PIC18F8X2X | 11 1111                            | 11 1111  | uu uuuu                         |
| PIR3                   | PIC18F6X2X PIC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| PIE3                   | PIC18F6X2X PIC18F8X2X | 00 0000                            | 00 0000  | uu uuuu                         |
| IPR2                   | PIC18F6X2X PIC18F8X2X | -1-1 1111                          | -1-1 1111  | -u-u uuuu                       |
| PIR2                   | PIC18F6X2X PIC18F8X2X | -0-0 0000                          | -0-0 0000  | -u-u uuuu <sup>(1)</sup>        |
| PIE2                   | PIC18F6X2X PIC18F8X2X | -0-0 0000                          | -0-0 0000  | -u-u uuuu                       |
| IPR1                   | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| PIR1                   | PIC18F6X2X PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu(1)                    |
| PIE1                   | PIC18F6X2X PIC18F8X2X | 0000 0000                          | 0000 0000  | uuuu uuuu                       |
| MEMCON <sup>(9)</sup>  | PIC18F6X2X PIC18F8X2X | 0-0000                             | 0-0000   | u-uuuu                          |
| TRISJ                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISH                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISG                  | PIC18F6X2X PIC18F8X2X | 1 1111                             | 1 1111   | u uuuu                          |
| TRISF                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISE                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISD                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISC                  | PIC18F6X2X PIC18F8X2X | 1111 1111                          | 1111 1111  | uuuu uuuu                       |
| TRISB                  | PIC18F6X2X PIC18F8X2X |                                    | 1111 1111  | uuuu uuuu                       |
| TRISA <sup>(5,6)</sup> | PIC18F6X2X PIC18F8X2X | -111 1111 <sup>(5)</sup>           | -111 1111 <sup>(5)</sup>                             | -uuu uuuu <sup>(5)</sup>        |
| LATJ                   | PIC18F6X2X PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| LATH                   | PIC18F6X2X PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| LATG                   | PIC18F6X2X PIC18F8X2X | x xxxx                             | u uuuu   | u uuuu                          |
| LATF                   | PIC18F6X2X PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| LATE                   | PIC18F6X2X PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| LATD                   | PIC18F6X2X PIC18F8X2X | xxxx xxxx                          | uuuu uuuu  | uuuu uuuu                       |
| LATC                   | PIC18F6X2X PIC18F8X2X |                                    | uuuu uuuu  | uuuu uuuu                       |
| LATB                   | PIC18F6X2X PIC18F8X2X |                                    | uuuu uuuu  | uuuu uuuu                       |
| LATA <sup>(5,6)</sup>  | PIC18F6X2X PIC18F8X2X | -xxx xxxx(5)                       | -uuu uuuu <b>(5)</b>                                 | -uuu uuuu <b>(5)</b>            |
| PORTJ                  | PIC18F6X2X PIC18F8X2X |                                    | uuuu uuuu  | uuuu uuuu                       |
| PORTH                  | PIC18F6X2X PIC18F8X2X | 0000 xxxx                          | 0000 uuuu  | uuuu uuuu                       |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.


- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.
  - 7: If MCLR function is disabled, PORTG<5> is a read-only bit.
  - 8: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
  - 9: The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.


TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)


| Register               |            |            |                          | MCLR Resets WDT Reset RESET Instruction Stack Resets | Wake-up via WDT<br>or Interrupt |  |
|------------------------|------------|------------|--------------------------|--|---------------------------------|--|
| PORTG <sup>(7)</sup>   | PIC18F6X2X | PIC18F8X2X | xx xxxx                  | uu uuuu  | uu uuuu                         |  |
| PORTF                  | PIC18F6X2X | PIC18F8X2X | x000 0000                | u000 0000  | uuuu uuuu                       |  |
| PORTE                  | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | uuuu uuuu  | uuuu uuuu                       |  |
| PORTD                  | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | uuuu uuuu  | uuuu uuuu                       |  |
| PORTC                  | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | uuuu uuuu  | uuuu uuuu                       |  |
| PORTB                  | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | uuuu uuuu  | uuuu uuuu                       |  |
| PORTA <sup>(5,6)</sup> | PIC18F6X2X | PIC18F8X2X | -x0x 0000 <sup>(5)</sup> | -u0u 0000 <b>(5)</b>                                 | -uuu uuuu <sup>(5)</sup>        |  |
| SPBRGH1                | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| BAUDCON1               | PIC18F6X2X | PIC18F8X2X | -1-0 0-00                | -1-0 0-00  | -u-u u-uu                       |  |
| SPBRGH2                | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| BAUDCON2               | PIC18F6X2X | PIC18F8X2X | -1-0 0-00                | -1-0 0-00  | -u-1 u-uu                       |  |
| ECCP1DEL               | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| TMR4                   | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| PR4                    | PIC18F6X2X | PIC18F8X2X | 1111 1111                | 1111 1111  | uuuu uuuu                       |  |
| T4CON                  | PIC18F6X2X | PIC18F8X2X | -000 0000                | -000 0000  | -uuu uuuu                       |  |
| CCPR4H                 | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | xxxx xxxx  | uuuu uuuu                       |  |
| CCPR4L                 | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | xxxx xxxx  | uuuu uuuu                       |  |
| CCP4CON                | PIC18F6X2X | PIC18F8X2X | 00 0000                  | 00 0000  | uu uuuu                         |  |
| CCPR5H                 | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | xxxx xxxx  | uuuu uuuu                       |  |
| CCPR5L                 | PIC18F6X2X | PIC18F8X2X | xxxx xxxx                | xxxx xxxx  | uuuu uuuu                       |  |
| CCP5CON                | PIC18F6X2X | PIC18F8X2X | 00 0000                  | 00 0000  | uu uuuu                         |  |
| SPBRG2                 | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| RCREG2                 | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| TXREG2                 | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| TXSTA2                 | PIC18F6X2X | PIC18F8X2X | 0000 0010                | 0000 0010  | uuuu uuuu                       |  |
| RCSTA2                 | PIC18F6X2X | PIC18F8X2X | 0000 000x                | 0000 000x  | uuuu uuuu                       |  |
| ECCP3AS                | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| ECCP3DEL               | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| ECCP2AS                | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |
| ECCP2DEL               | PIC18F6X2X | PIC18F8X2X | 0000 0000                | 0000 0000  | uuuu uuuu                       |  |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - **4:** See Table 3-2 for Reset value for specific condition.
  - 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.
  - 7: If MCLR function is disabled, PORTG<5> is a read-only bit.
  - 8: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
  - 9: The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.













FIGURE 3-7: TIME-OUT SEQUENCE ON POR W/PLL ENABLED (MCLR TIED TO VDD VIA 1 kΩ RESISTOR)



### 4.0 MEMORY ORGANIZATION

There are three memory blocks in PIC18F6525/6621/8525/8621 devices. They are:

- · Program Memory
- Data RAM
- Data EEPROM

Data and program memory use separate busses which allow for concurrent access of these blocks. Additional detailed information for Flash program memory and data EEPROM is provided in Section 5.0 "Flash Program Memory" and Section 7.0 "Data EEPROM Memory", respectively.

In addition to on-chip Flash, the PIC18F8525/8621 devices are also capable of accessing external program memory through an external memory bus. Depending on the selected operating mode (discussed in Section 4.1.1 "PIC18F6525/6621/8525/8621 Program Memory Modes"), the controllers may access either internal or external program memory exclusively, or both internal and external memory in selected blocks. Additional information on the external memory interface is provided in Section 6.0 "External Memory Interface".

### 4.1 Program Memory Organization

A 21-bit program counter is capable of addressing the 2-Mbyte program memory space. Accessing a location between the physically implemented memory and the 2-Mbyte address will cause a read of all '0's (a NOP instruction).

The PIC18F6525 and PIC18F8525 each have 48 Kbytes of on-chip Flash memory, while the PIC18F6621 and PIC18F8621 have 64 Kbytes of Flash. This means that PIC18FX525 devices can store internally up to 24,576 single-word instructions and PIC18FX621 devices can store up to 32,768 single-word instructions.

The Reset vector address is at 0000h and the interrupt vector addresses are at 0008h and 0018h.

Figure 4-1 shows the program memory map for PIC18FX525 devices, while Figure 4-2 shows the program memory map for PIC18FX621 devices.

## 4.1.1 PIC18F6525/6621/8525/8621 PROGRAM MEMORY MODES

PIC18F8525/8621 devices differ significantly from their PIC18 predecessors in their utilization of program memory. In addition to available on-chip Flash program memory, these controllers can also address up to 2 Mbytes of external program memory through the external memory interface. There are four distinct operating modes available to the controllers:

- Microprocessor (MP)
- Microprocessor with Boot Block (MPBB)
- Extended Microcontroller (EMC)
- Microcontroller (MC)

The Program Memory mode is determined by setting the two Least Significant bits of the CONFIG3L Configuration Byte register as shown in Register 4-1 (see **Section 24.1 "Configuration Bits"** for additional details on the device configuration bits).

The Program Memory modes operate as follows:

- The Microprocessor Mode permits access only to external program memory; the contents of the on-chip Flash memory are ignored. The 21-bit program counter permits access to a 2-Mbyte linear program memory space.
- The Microprocessor with Boot Block Mode accesses on-chip Flash memory from addresses 000000h to 0007FFh. Above this, external program memory is accessed all the way up to the 2-Mbyte limit. Program execution automatically switches between the two memories as required.
- The Microcontroller Mode accesses only on-chip Flash memory. Attempts to read above the physical limit of the on-chip Flash (BFFFh for the PIC18FX525, FFFFh for the PIC18FX621) causes a read of all '0's (a NOP instruction).
   The Microcontroller mode is also the only operating mode available to PIC18F6525/6621 devices.
- The Extended Microcontroller Mode allows access to both internal and external program memories as a single block. The device can access its entire on-chip Flash memory; above this, the device accesses external program memory up to the 2-Mbyte program space limit. As with Boot Block mode, execution automatically switches between the two memories as required.

In all modes, the microcontroller has complete access to data RAM and EEPROM.

Figure 4-3 compares the memory maps of the different program memory modes. The differences between on-chip and external memory access limitations are more fully explained in Table 4-1.

FIGURE 4-1: INTERNAL PROGRAM
MEMORY MAP AND
STACK FOR PIC18FX525




FIGURE 4-2: INTERNAL PROGRAM
MEMORY MAP AND
STACK FOR PIC18FX621




TABLE 4-1: MEMORY ACCESS FOR PIC18F8525/8621 PROGRAM MEMORY MODES

|                                | Inte                  | rnal Program Mer   | mory           | <b>External Program Memory</b> |                    |                |  |  |
|--------------------------------|-----------------------|--------------------|----------------|--------------------------------|--------------------|----------------|--|--|
| Operating Mode                 | Execution<br>From     | Table Read<br>From | Table Write To | Execution<br>From              | Table Read<br>From | Table Write To |  |  |
| Microprocessor                 | No Access             | No Access          | No Access      | Yes                            | Yes                | Yes            |  |  |
| Microprocessor<br>w/Boot Block | Yes                   | Yes                | Yes            | Yes                            | Yes                | Yes            |  |  |
| Microcontroller                | Microcontroller Yes ` |                    | Yes            | No Access                      | No Access          | No Access      |  |  |
| Extended<br>Microcontroller    | Yes                   | Yes                | Yes            | Yes                            | Yes                | Yes            |  |  |

#### **REGISTER 4-1:** CONFIG3L: CONFIGURATION REGISTER 3 LOW

| R/P-1 | U-0 | U-0 | U-0 | U-0 | U-0 | R/P-1 | R/P-1 |
|-------|-----|-----|-----|-----|-----|-------|-------|
| WAIT  | _   | _   | _   | _   | _   | PM1   | PM0   |
| bit 7 |     |     |     |     |     |       | bit 0 |

bit 0

bit 7 WAIT: External Bus Data Wait Enable bit

1 = Wait selections unavailable, device will not wait

0 = Wait programmed by WAIT1 and WAIT0 bits of MEMCOM register (MEMCOM<5:4>)

bit 6-2 Unimplemented: Read as '0'

bit 1-0 PM1:PM0: Processor Data Memory Mode Select bits

11 = Microcontroller mode

10 = Microprocessor mode<sup>(1)</sup>

01 = Microcontroller with Boot Block mode<sup>(1)</sup>

00 = Extended Microcontroller mode<sup>(1)</sup>


Note 1: This mode is available only on PIC18F8525/8621 devices.

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

-n = Value after erase '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### FIGURE 4-3: MEMORY MAPS FOR PIC18F6525/6621/8525/8621 PROGRAM MEMORY MODES



PIC18F8525 and PIC18F6525. Note 1:

PIC18F8621 and PIC18F6621 2:

This mode is available only on PIC18F8525/8621 devices.

### 4.2 Return Address Stack

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC (Program Counter) is pushed onto the stack when a CALL or RCALL instruction is executed, or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN or CALL instructions.

The stack operates as a 31-word by 21-bit RAM and a 5-bit Stack Pointer, with the Stack Pointer initialized to 00000b after all Resets. There is no RAM associated with Stack Pointer 00000b. This is only a Reset value. During a CALL type instruction causing a push onto the stack, the Stack Pointer is first incremented and the RAM location pointed to by the Stack Pointer is written with the contents of the PC. During a RETURN type instruction causing a pop from the stack, the contents of the RAM location pointed to by the STKPTR register are transferred to the PC and then the Stack Pointer is decremented.

The stack space is not part of either program or data space. The Stack Pointer is readable and writable and the address on the top of the stack is readable and writable through SFR registers. Data can also be pushed to, or popped from the stack using the Top-of-Stack SFRs. Status bits indicate if the Stack Pointer is at or beyond the 31 levels provided.

### 4.2.1 TOP-OF-STACK ACCESS

The top of the stack is readable and writable. Three register locations, TOSU, TOSH and TOSL, hold the contents of the stack location pointed to by the STKPTR register. This allows users to implement a software stack if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU, TOSH and TOSL registers. These values can be placed on a user defined software stack. At return time, the software can replace the TOSU, TOSH and TOSL and do a return.

The user must disable the global interrupt enable bits during this time to prevent inadvertent stack operations.

## 4.2.2 RETURN STACK POINTER (STKPTR)

The STKPTR register contains the Stack Pointer value, the STKFUL (Stack Full) status bit and the STKUNF (Stack Underflow) status bits. Register 4-2 shows the STKPTR register. The value of the Stack Pointer can be 0 through 31. The Stack Pointer increments when values are pushed onto the stack and decrements when values are popped off the stack. At Reset, the Stack Pointer value will be '0'. The user may read and write the Stack Pointer value. This feature can be used by a real-time operating system for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit can only be cleared in software or by a POR.

The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) configuration bit. Refer to **Section 25.0 "Instruction Set Summary"** for a description of the device configuration bits. If STVREN is set (default), the 31st push will push the (PC + 2) value onto the stack, set the STKFUL bit and reset the device. The STKFUL bit will remain set and the Stack Pointer will be set to 'o'.

If STVREN is cleared, the STKFUL bit will be set on the 31st push and the Stack Pointer will increment to 31. Any additional pushes will not overwrite the 31st push and STKPTR will remain at 31.

When the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC and sets the STKUNF bit, while the Stack Pointer remains at '0'. The STKUNF bit will remain set until cleared in software or a POR occurs.

**Note:** Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken.

### REGISTER 4-2: STKPTR: STACK POINTER REGISTER

| R/C-0                 | R/C-0                 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-----------------------|-----------------------|-----|-------|-------|-------|-------|-------|
| STKFUL <sup>(1)</sup> | STKUNF <sup>(1)</sup> | _   | SP4   | SP3   | SP2   | SP1   | SP0   |
| bit 7                 |                       |     |       |       |       |       | bit 0 |

bit 7 **STKFUL:** Stack Full Flag bit<sup>(1)</sup>

1 = Stack became full or overflowed

0 = Stack has not become full or overflowed

bit 6 **STKUNF:** Stack Underflow Flag bit<sup>(1)</sup>

1 = Stack underflow occurred

0 = Stack underflow did not occur


bit 5 **Unimplemented:** Read as '0'

bit 4-0 **SP4:SP0:** Stack Pointer Location bits

Note 1: Bit 7 and bit 6 can only be cleared in user software or by a POR.

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

### FIGURE 4-4: RETURN ADDRESS STACK AND ASSOCIATED REGISTERS



### 4.2.3 PUSH AND POP INSTRUCTIONS

Since the Top-of-Stack (TOS) is readable and writable, the ability to push values onto the stack and pull values off the stack, without disturbing normal program execution, is a desirable option. To push the current PC value onto the stack, a PUSH instruction can be executed. This will increment the Stack Pointer and load the current PC value onto the stack. TOSU, TOSH and TOSL can then be modified to place a return address on the stack.

The ability to pull the TOS value off of the stack and replace it with the value that was previously pushed onto the stack, without disturbing normal execution, is achieved by using the POP instruction. The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

### 4.2.4 STACK FULL/UNDERFLOW RESETS

These Resets are enabled by programming the STVREN configuration bit. When the STVREN bit is disabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit, but not cause a device Reset. When the STVREN bit is enabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit and then cause a device Reset. The STKFUL or STKUNF bits are only cleared by the user software or a Power-on Reset.

### 4.3 Fast Register Stack

A "fast interrupt return" option is available for interrupts. A fast register stack is provided for the STATUS, WREG and BSR registers and is only one in depth. The stack is not readable or writable and is loaded with the current value of the corresponding register when the processor vectors for an interrupt. The values in the registers are then loaded back into the working registers if the FAST RETURN instruction is used to return from the interrupt.


A low or high priority interrupt source will push values into the stack registers. If both low and high priority interrupts are enabled, the stack registers cannot be used reliably for low priority interrupts. If a high priority interrupt occurs while servicing a low priority interrupt, the stack register values stored by the low priority interrupt will be overwritten.

If high priority interrupts are not disabled during low priority interrupts, users must save the key registers in software during a low priority interrupt.

If no interrupts are used, the fast register stack can be used to restore the STATUS, WREG and BSR registers at the end of a subroutine call. To use the fast register stack for a subroutine call, a FAST CALL instruction must be executed.

Example 4-1 shows a source code example that uses the fast register stack.

# EXAMPLE 4-1: FAST REGISTER STACK CODE EXAMPLE



### 4.4 PCL, PCLATH and PCLATU

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide. The low byte is called the PCL register; this register is readable and writable. The high byte is called the PCH register. This register contains the PC<15:8> bits and is not directly readable or writable; updates to the PCH register may be performed through the PCLATH register. The upper byte is called PCU. This register contains the PC<20:16> bits and is not directly readable or writable; updates to the PCU register may be performed through the PCLATU register.

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the LSB of the PCL is fixed to a value of '0'. The PC increments by 2 to address sequential instructions in the program memory.


The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.

The contents of PCLATH and PCLATU will be transferred to the program counter by an operation that writes PCL. Similarly, the upper two bytes of the program counter will be transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see **Section 4.8.1** "**Computed GOTO**").

# 4.5 Clocking Scheme/Instruction Cycle

The clock input (from OSC1) is internally divided by four to generate four non-overlapping quadrature clocks, namely Q1, Q2, Q3 and Q4. Internally, the Program Counter (PC) is incremented every Q1, the instruction is fetched from the program memory and latched into the Instruction Register (IR) in Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow are shown in Figure 4-5.





### 4.6 Instruction Flow/Pipelining

An "Instruction Cycle" consists of four Q cycles (Q1, Q2, Q3 and Q4). The instruction fetch and execute are pipelined such that fetch takes one instruction cycle, while decode and execute take another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO), then two cycles are required to complete the instruction (Example 4-2).

A fetch cycle begins with the Program Counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the "Instruction Register" (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3 and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).

### **EXAMPLE 4-2: INSTRUCTION PIPELINE FLOW**

|                        | TCY0        | TCY1      | Tcy2      | Tcy3        | Tcy4          | TcY5 |
|------------------------|-------------|-----------|-----------|-------------|---------------|------|
| 1. MOVLW 55h           | Fetch 1     | Execute 1 |           |             |               |      |
| 2. MOVWF PORTB         |             | Fetch 2   | Execute 2 |             | _             |      |
| 3. BRA SUB_1           |             |           | Fetch 3   | Execute 3   |               | _    |
| 4. BSF PORTA, BIT3 (   | Forced NOP) |           |           | Fetch 4     | Flush (NOP)   |      |
| 5. Instruction @ addre |             |           |           | Fetch SUB_1 | Execute SUB_1 |      |

All instructions are single-cycle except for any program branches. These take two cycles since the fetch instruction is "flushed" from the pipeline, while the new instruction is being fetched and then executed.

### 4.7 Instructions in Program Memory

The program memory is addressed in bytes. Instructions are stored as two bytes or four bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSB = 0). Figure 4-6 shows an example of how instruction words are stored in the program memory. To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSB will always read '0' (see Section 4.4 "PCL, PCLATH and PCLATU").

The CALL and GOTO instructions have an absolute program memory address embedded into the instruction. Since instructions are always stored on

word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1> which accesses the desired byte address in program memory. Instruction #2 in Figure 4-6 shows how the instruction "GOTO 000006h" is encoded in the program memory. Program branch instructions, which encode a relative address offset, operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions that the PC will be offset by. **Section 25.0** "Instruction Set **Summary"** provides further details of the instruction set.

### FIGURE 4-6: INSTRUCTIONS IN PROGRAM MEMORY

|                |            |                    | LSB = 1 | LSB = 0 | Word Address |
|----------------|------------|--------------------|---------|---------|--------------|
|                | Program N  | •                  |         |         | 000000h      |
|                | Byte Locat | ions $\rightarrow$ |         |         | 000002h      |
|                |            |                    |         |         | 000004h      |
|                |            |                    |         |         | 000006h      |
| Instruction 1: | MOVLW      | 055h               | 0Fh     | 55h     | 000008h      |
| Instruction 2: | GOTO       | 000006h            | EFh     | 03h     | 00000Ah      |
|                |            |                    | F0h     | 00h     | 00000Ch      |
| Instruction 3: | MOVFF      | 123h, 456h         | C1h     | 23h     | 00000Eh      |
|                |            | -                  | F4h     | 56h     | 000010h      |
|                |            |                    |         |         | 000012h      |
|                |            |                    |         |         | 000014h      |

### 4.7.1 TWO-WORD INSTRUCTIONS

The PIC18F6525/6621/8525/8621 devices have four two-word instructions: MOVFF, CALL, GOTO and LFSR. The second word of these instructions has the 4 MSBs set to '1's and is a special kind of NOP instruction. The lower 12 bits of the second word contain data to be used by the instruction. If the first word of the instruction is executed, the data in the second word is accessed.

If the second word of the instruction is executed by itself (first word was skipped), it will execute as a NOP. This action is necessary when the two-word instruction is preceded by a conditional instruction that changes the PC. A program example that demonstrates this concept is shown in Example 4-3. Refer to **Section 25.0** "Instruction Set Summary" for further details of the instruction set.

### **EXAMPLE 4-3: TWO-WORD INSTRUCTIONS**

| CASE 1:             |                  |                                     |
|---------------------|------------------|-------------------------------------|
| Object Code         | Source Code      |                                     |
| 0110 0110 0000 0000 | TSTFSZ REG1      | ; is RAM location 0?                |
| 1100 0001 0010 0011 | MOVFF REG1, REG2 | ; No, execute 2-word instruction    |
| 1111 0100 0101 0110 |                  | ; 2nd operand holds address of REG2 |
| 0010 0100 0000 0000 | ADDWF REG3       | ; continue code                     |
|                     |                  |                                     |
| CASE 2:             |                  |                                     |
| Object Code         | Source Code      |                                     |
| 0110 0110 0000 0000 | TSTFSZ REG1      | ; is RAM location 0?                |
| 1100 0001 0010 0011 | MOVFF REG1, REG2 | ; Yes                               |
| 1111 0100 0101 0110 |                  | ; 2nd operand becomes NOP           |
| 0010 0100 0000 0000 | ADDWF REG3       | ; continue code                     |

### 4.8 Look-up Tables

Look-up tables are implemented two ways. These are:

- Computed GOTO
- Table Reads

### 4.8.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL).

A look-up table can be formed with an ADDWF PCL instruction and a group of RETLW 0xnn instructions. WREG is loaded with an offset into the table before executing a call to that table. The first instruction of the called

routine is the ADDWF PCL instruction. The next instruction executed will be one of the RETLW  $0 \times nn$  instructions that returns the value  $0 \times nn$  to the calling function.

The offset value (value in WREG) specifies the number of bytes that the program counter should advance.

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

Note: The ADDWF PCL instruction does not update PCLATH and PCLATU. A read operation on PCL must be performed to update PCLATH and PCLATU.

### **EXAMPLE 4-4: COMPUTED GOTO USING AN OFFSET VALUE**

```
MAIN:
      ORG
             0x0000
      MOVLW
            0x00
      CALL
             TABLE
      ORG
             0x8000
TABLE MOVF
             PCL, F
                       ; A simple read of PCL will update PCLATH, PCLATU
                      ; Multiply by 2 to get correct offset in table
      RLNCF W, W
      ADDWF PCL
                       ; Add the modified offset to force jump into table
      RETLW 'A'
      RETLW 'B'
      RETLW 'C'
      RETLW 'D'
      RETLW
             `E
      END
```

### 4.8.2 TABLE READS/TABLE WRITES

A better method of storing data in program memory allows 2 bytes of data to be stored in each instruction location.

Look-up table data may be stored 2 bytes per program word by using table reads and writes. The Table Pointer (TBLPTR) specifies the byte address and the Table Latch (TABLAT) contains the data that is read from, or written to program memory. Data is transferred to/from program memory, one byte at a time.

A description of the table read/table write operation is shown in **Section 5.0** "Flash Program Memory".

### 4.9 Data Memory Organization

The data memory is implemented as static RAM. Each register in the data memory has a 12-bit address, allowing up to 4096 bytes of data memory. Figure 4-7 shows the data memory organization for the PIC18F6525/6621/8525/8621 devices.

The data memory map is divided into 16 banks that contain 256 bytes each. The lower 4 bits of the Bank Select Register (BSR<3:0>) select which bank will be accessed. The upper 4 bits for the BSR are not implemented.

The data memory contains Special Function Registers (SFR) and General Purpose Registers (GPR). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratch pad operations in the user's application. The SFRs start at the last location of Bank 15 (0FFFh) and extend downwards. Any remaining space beyond the SFRs in the bank may be implemented as GPRs. GPRs start at the first location of Bank 0 and grow upwards. Any read of an unimplemented location will read as '0's.

The entire data memory may be accessed directly or indirectly. Direct addressing may require the use of the BSR register. Indirect addressing requires the use of a File Select Register (FSRn) and a corresponding Indirect File Operand (INDFn). Each FSR holds a 12-bit address value that can be used to access any location in the data memory map without banking.

The instruction set and architecture allow operations across all banks. This may be accomplished by indirect addressing or by the use of the MOVFF instruction. The MOVFF instruction is a two-word/two-cycle instruction that moves a value from one register to another.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle regardless of the current BSR values, an Access Bank is implemented. A segment of Bank 0 and a segment of Bank 15 comprise the Access RAM. **Section 4.10** "Access Bank" provides a detailed description of the Access RAM.

## 4.9.1 GENERAL PURPOSE REGISTER

The register file can be accessed either directly or indirectly. Indirect addressing operates using a File Select Register and corresponding Indirect File Operand. The operation of indirect addressing is shown in Section 4.12 "Indirect Addressing, INDF and FSR Registers".

Enhanced MCU devices may have banked memory in the GPR area. GPRs are not initialized by a Power-on Reset and are unchanged on all other Resets.

Data RAM is available for use as General Purpose Registers by all instructions. The top section of Bank 15 (F60h to FFFh) contains SFRs. All other banks of data memory contain GPRs, starting with Bank 0.

### 4.9.2 SPECIAL FUNCTION REGISTERS

The Special Function Registers (SFRs) are registers used by the CPU and peripheral modules for controlling the desired operation of the device. These registers are implemented as static RAM. A list of these registers is given in Table 4-2 and Table 4-3.

The SFRs can be classified into two sets: those associated with the "core" function and those related to the peripheral functions. Those registers related to the "core" are described in this section, while those related to the operation of the peripheral features are described in the section of that peripheral feature. The SFRs are typically distributed among the peripherals whose functions they control.

The unused SFR locations are unimplemented and read as '0's. The addresses for the SFRs are listed in Table 4-2.




FIGURE 4-7: DATA MEMORY MAP FOR PIC18F6525/6621/8525/8621 DEVICES

TABLE 4-2: SPECIAL FUNCTION REGISTER MAP

| Address | Name                    | Address | Name                    | Address | Name                  | Address | Name                  |
|---------|-------------------------|---------|-------------------------|---------|-----------------------|---------|-----------------------|
| FFFh    | TOSU                    | FDFh    | INDF2 <sup>(3)</sup>    | FBFh    | CCPR1H                | F9Fh    | IPR1                  |
| FFEh    | TOSH                    | FDEh    | POSTINC2 <sup>(3)</sup> | FBEh    | CCPR1L                | F9Eh    | PIR1                  |
| FFDh    | TOSL                    | FDDh    | POSTDEC2 <sup>(3)</sup> | FBDh    | CCP1CON               | F9Dh    | PIE1                  |
| FFCh    | STKPTR                  | FDCh    | PREINC2 <sup>(3)</sup>  | FBCh    | CCPR2H                | F9Ch    | MEMCON <sup>(2)</sup> |
| FFBh    | PCLATU                  | FDBh    | PLUSW2 <sup>(3)</sup>   | FBBh    | CCPR2L                | F9Bh    | (1)                   |
| FFAh    | PCLATH                  | FDAh    | FSR2H                   | FBAh    | CCP2CON               | F9Ah    | TRISJ <sup>(2)</sup>  |
| FF9h    | PCL                     | FD9h    | FSR2L                   | FB9h    | CCPR3H                | F99h    | TRISH <sup>(2)</sup>  |
| FF8h    | TBLPTRU                 | FD8h    | STATUS                  | FB8h    | CCPR3L                | F98h    | TRISG                 |
| FF7h    | TBLPTRH                 | FD7h    | TMR0H                   | FB7h    | CCP3CON               | F97h    | TRISF                 |
| FF6h    | TBLPTRL                 | FD6h    | TMR0L                   | FB6h    | ECCP1AS               | F96h    | TRISE                 |
| FF5h    | TABLAT                  | FD5h    | T0CON                   | FB5h    | CVRCON                | F95h    | TRISD                 |
| FF4h    | PRODH                   | FD4h    | (1)                     | FB4h    | CMCON                 | F94h    | TRISC                 |
| FF3h    | PRODL                   | FD3h    | OSCCON                  | FB3h    | TMR3H                 | F93h    | TRISB                 |
| FF2h    | INTCON                  | FD2h    | LVDCON                  | FB2h    | TMR3L                 | F92h    | TRISA                 |
| FF1h    | INTCON2                 | FD1h    | WDTCON                  | FB1h    | T3CON                 | F91h    | LATJ <sup>(2)</sup>   |
| FF0h    | INTCON3                 | FD0h    | RCON                    | FB0h    | PSPCON <sup>(4)</sup> | F90h    | LATH <sup>(2)</sup>   |
| FEFh    | INDF0 <sup>(3)</sup>    | FCFh    | TMR1H                   | FAFh    | SPBRG1                | F8Fh    | LATG                  |
| FEEh    | POSTINC0 <sup>(3)</sup> | FCEh    | TMR1L                   | FAEh    | RCREG1                | F8Eh    | LATF                  |
| FEDh    | POSTDEC0 <sup>(3)</sup> | FCDh    | T1CON                   | FADh    | TXREG1                | F8Dh    | LATE                  |
| FECh    | PREINC0 <sup>(3)</sup>  | FCCh    | TMR2                    | FACh    | TXSTA1                | F8Ch    | LATD                  |
| FEBh    | PLUSW0 <sup>(3)</sup>   | FCBh    | PR2                     | FABh    | RCSTA1                | F8Bh    | LATC                  |
| FEAh    | FSR0H                   | FCAh    | T2CON                   | FAAh    | EEADRH                | F8Ah    | LATB                  |
| FE9h    | FSR0L                   | FC9h    | SSPBUF                  | FA9h    | EEADR                 | F89h    | LATA                  |
| FE8h    | WREG                    | FC8h    | SSPADD                  | FA8h    | EEDATA                | F88h    | PORTJ <sup>(2)</sup>  |
| FE7h    | INDF1 <sup>(3)</sup>    | FC7h    | SSPSTAT                 | FA7h    | EECON2                | F87h    | PORTH <sup>(2)</sup>  |
| FE6h    | POSTINC1 <sup>(3)</sup> | FC6h    | SSPCON1                 | FA6h    | EECON1                | F86h    | PORTG                 |
| FE5h    | POSTDEC1 <sup>(3)</sup> | FC5h    | SSPCON2                 | FA5h    | IPR3                  | F85h    | PORTF                 |
| FE4h    | PREINC1 <sup>(3)</sup>  | FC4h    | ADRESH                  | FA4h    | PIR3                  | F84h    | PORTE                 |
| FE3h    | PLUSW1 <sup>(3)</sup>   | FC3h    | ADRESL                  | FA3h    | PIE3                  | F83h    | PORTD                 |
| FE2h    | FSR1H                   | FC2h    | ADCON0                  | FA2h    | IPR2                  | F82h    | PORTC                 |
| FE1h    | FSR1L                   | FC1h    | ADCON1                  | FA1h    | PIR2                  | F81h    | PORTB                 |
| FE0h    | BSR                     | FC0h    | ADCON2                  | FA0h    | PIE2                  | F80h    | PORTA                 |

Note 1: Unimplemented registers are read as '0'.

<sup>2:</sup> This register is not available on PIC18F6525/6621 devices and reads as '0'.

**<sup>3:</sup>** This is not a physical register.

<sup>4:</sup> Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

TABLE 4-2: SPECIAL FUNCTION REGISTER MAP (CONTINUED)

| Address | Name     | Address | Name | Address | Name | Address | Name |
|---------|----------|---------|------|---------|------|---------|------|
| F7Fh    | SPBRGH1  | F5Fh    | (1)  | F3Fh    | (1)  | F1Fh    | (1)  |
| F7Eh    | BAUDCON1 | F5Eh    | (1)  | F3Eh    | (1)  | F1Eh    | (1)  |
| F7Dh    | SPBRGH2  | F5Dh    | (1)  | F3Dh    | (1)  | F1Dh    | (1)  |
| F7Ch    | BAUDCON2 | F5Ch    | (1)  | F3Ch    | (1)  | F1Ch    | (1)  |
| F7Bh    | (1)      | F5Bh    | (1)  | F3Bh    | (1)  | F1Bh    | (1)  |
| F7Ah    | (1)      | F5Ah    | (1)  | F3Ah    | (1)  | F1Ah    | (1)  |
| F79h    | ECCP1DEL | F59h    | (1)  | F39h    | (1)  | F19h    | (1)  |
| F78h    | TMR4     | F58h    | (1)  | F38h    | (1)  | F18h    | (1)  |
| F77h    | PR4      | F57h    | (1)  | F37h    | (1)  | F17h    | (1)  |
| F76h    | T4CON    | F56h    | (1)  | F36h    | (1)  | F16h    | (1)  |
| F75h    | CCPR4H   | F55h    | (1)  | F35h    | (1)  | F15h    | (1)  |
| F74h    | CCPR4L   | F54h    | (1)  | F34h    | (1)  | F14h    | (1)  |
| F73h    | CCP4CON  | F53h    | (1)  | F33h    | (1)  | F13h    | (1)  |
| F72h    | CCPR5H   | F52h    | (1)  | F32h    | (1)  | F12h    | (1)  |
| F71h    | CCPR5L   | F51h    | (1)  | F31h    | (1)  | F11h    | (1)  |
| F70h    | CCP5CON  | F50h    | (1)  | F30h    | (1)  | F10h    | (1)  |
| F6Fh    | SPBRG2   | F4Fh    | (1)  | F2Fh    | (1)  | F0Fh    | (1)  |
| F6Eh    | RCREG2   | F4Eh    | (1)  | F2Eh    | (1)  | F0Eh    | (1)  |
| F6Dh    | TXREG2   | F4Dh    | (1)  | F2Dh    | (1)  | F0Dh    | (1)  |
| F6Ch    | TXSTA2   | F4Ch    | (1)  | F2Ch    | (1)  | F0Ch    | (1)  |
| F6Bh    | RCSTA2   | F4Bh    | (1)  | F2Bh    | (1)  | F0Bh    | (1)  |
| F6Ah    | ECCP3AS  | F4Ah    | (1)  | F2Ah    | (1)  | F0Ah    | (1)  |
| F69h    | ECCP3DEL | F49h    | (1)  | F29h    | (1)  | F09h    | (1)  |
| F68h    | ECCP2AS  | F48h    | (1)  | F28h    | (1)  | F08h    | (1)  |
| F67h    | ECCP2DEL | F47h    | (1)  | F27h    | (1)  | F07h    | (1)  |
| F66h    | _(1)     | F46h    | _(1) | F26h    | (1)  | F06h    | (1)  |
| F65h    | (1)      | F45h    | (1)  | F25h    | (1)  | F05h    | (1)  |
| F64h    | (1)      | F44h    | (1)  | F24h    | (1)  | F04h    | (1)  |
| F63h    | (1)      | F43h    | (1)  | F23h    | (1)  | F03h    | (1)  |
| F62h    | (1)      | F42h    | (1)  | F22h    | (1)  | F02h    | (1)  |
| F61h    | (1)      | F41h    | (1)  | F21h    | (1)  | F01h    | (1)  |
| F60h    | (1)      | F40h    | (1)  | F20h    | (1)  | F00h    | (1)  |

Note 1: Unimplemented registers are read as '0'.

<sup>2:</sup> This register is not available on PIC18F6525/6621 devices and reads as '0'.

<sup>3:</sup> This is not a physical register.

**<sup>4:</sup>** Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

TABLE 4-3: REGISTER FILE SUMMARY

| File Name | Bit 7                        | Bit 6   | Bit 5                 | Bit 4                            | Bit 3          | Bit 2         | Bit 1          | Bit 0          | Value on POR, BOR | Details on page: |
|-----------|------------------------------|---|-----------------------|----------------------------------|----------------|---------------|----------------|----------------|-------------------|------------------|
| TOSU      |                              | _   | _                     | Top-of-Stack                     | Upper Byte (   | ΓOS<20:16>)   |                |                | 0 0000            | 32, 42           |
| TOSH      | Top-of-Stack                 | High Byte (TO   | OS<15:8>)             |                                  |                |               |                |                | 0000 0000         | 32, 42           |
| TOSL      | Top-of-Stack                 | Low Byte (TC  | S<7:0>)               |                                  |                |               |                |                | 0000 0000         | 32, 42           |
| STKPTR    | STKFUL                       | STKUNF  | _                     | Return Stack                     | Pointer        |               |                |                | 00-0 0000         | 32, 43           |
| PCLATU    | _                            | _   | _                     | Holding Regi                     | ster for PC<2  | 0:16>         |                |                | 0 0000            | 32, 44           |
| PCLATH    | Holding Reg                  | ister for PC<1  | 5:8>                  |                                  |                |               |                |                | 0000 0000         | 32, 44           |
| PCL       | PC Low Byte                  | e (PC<7:0>)   |                       |                                  |                |               |                |                | 0000 0000         | 32, 44           |
| TBLPTRU   | -                            | -   | bit 21 <sup>(2)</sup> | Program Men                      | nory Table Po  | inter Upper B | yte (TBLPTR<   | <20:16>)       | 00 0000           | 32, 69           |
| TBLPTRH   | Program Me                   | mory Table Po   | inter High By         | rte (TBLPTR<1                    | 15:8>)         |               |                |                | 0000 0000         | 32, 69           |
| TBLPTRL   | Program Me                   | mory Table Po   | inter Low By          | te (TBLPTR<7                     | :0>)           |               |                |                | 0000 0000         | 32, 69           |
| TABLAT    | Program Me                   | mory Table La   | tch                   |                                  |                |               |                |                | 0000 0000         | 32, 69           |
| PRODH     | Product Reg                  | ister High Byte   | )                     |                                  |                |               |                |                | xxxx xxxx         | 32, 85           |
| PRODL     | Product Reg                  | ister Low Byte  | !                     |                                  | _              |               |                | _              | xxxx xxxx         | 32, 85           |
| INTCON    | GIE/GIEH                     | PEIE/GIEL   | TMR0IE                | INT0IE                           | RBIE           | TMR0IF        | INT0IF         | RBIF           | 0000 000x         | 32, 89           |
| INTCON2   | RBPU                         | INTEDG0   | INTEDG1               | INTEDG2                          | INTEDG3        | TMR0IP        | INT3IP         | RBIP           | 1111 1111         | 32, 90           |
| INTCON3   | INT2IP                       | INT1IP  | INT3IE                | INT2IE                           | INT1IE         | INT3IF        | INT2IF         | INT1IF         | 1100 0000         | 32, 91           |
| INDF0     | Uses content                 | ts of FSR0 to a   | jister)               | N/A                              | 56             |               |                |                |                   |                  |
| POSTINC0  |                              | ses contents of FSR0 to address data memory – value of FSR0 post-incremented not a physical register)   |                       |                                  |                |               |                |                |                   | 56               |
| POSTDEC0  |                              | Uses contents of FSR0 to address data memory – value of FSR0 post-decremented (not a physical register) |                       |                                  |                |               |                |                | N/A               | 56               |
| PREINC0   | Uses content                 | ts of FSR0 to a   | ddress data r         | nemory – value                   | e of FSR0 pre- | incremented   | (not a physica | l register)    | N/A               | 56               |
| PLUSW0    |                              |   |                       | memory – val<br>offset by valu   | •              | re-incremente | ed             |                | N/A               | 56               |
| FSR0H     | 1                            |   | 1                     | _                                | Indirect Data  | Memory Add    | dress Pointer  | 0 High Byte    | 0000              | 32, 56           |
| FSR0L     | Indirect Data                | Memory Add  | ress Pointer (        | Low Byte                         |                |               |                |                | xxxx xxxx         | 32, 56           |
| WREG      | Working Reg                  | gister  |                       |                                  |                |               |                |                | xxxx xxxx         | 32               |
| INDF1     | Uses conten                  | ts of FSR1 to   | address data          | memory – val                     | ue of FSR1 n   | ot changed (r | not a physical | register)      | N/A               | 56               |
| POSTINC1  | Uses conten<br>(not a physic |   | address data          | memory – val                     | ue of FSR1 p   | ost-incremen  | ted            |                | N/A               | 56               |
| POSTDEC1  | Uses conten<br>(not a physic |   | address data          | memory – val                     | ue of FSR1 p   | ost-decremer  | nted           |                | N/A               | 56               |
| PREINC1   | Uses conten                  | ts of FSR1 to a   | address data          | memory – valu                    | ue of FSR1 pr  | e-incremente  | d (not a phys  | ical register) | N/A               | 56               |
| PLUSW1    |                              |   |                       | memory – val<br>I offset by valu |                | re-incremente | ed             |                | N/A               | 56               |
| FSR1H     |                              | _   | _                     | _                                | Indirect Data  | Memory Add    | dress Pointer  | 1 High Byte    | 0000              | 32, 56           |
| FSR1L     | Indirect Data                | Memory Add  | ress Pointer 1        | Low Byte                         |                |               |                |                | xxxx xxxx         | 33, 56           |
| BSR       |                              | _   | _                     |                                  | Bank Select    | Register      |                |                | 0000              | 33, 55           |
| INDF2     | Uses conten                  | ts of FSR2 to   | address data          | memory – val                     | ue of FSR2 n   | ot changed (r | not a physical | register)      | N/A               | 56               |
| POSTINC2  | Uses conten<br>(not a physic |   | address data          | memory – val                     | ue of FSR2 p   | ost-incremen  | ted            |                | N/A               | 56               |
| POSTDEC2  | Uses conten<br>(not a physic |   | address data          | memory – val                     | ue of FSR2 p   | ost-decremer  | nted           |                | N/A               | 56               |

 $\textbf{Legend:} \hspace{0.5cm} x = \text{unknown}, \, u = \text{unchanged}, \, - = \text{unimplemented}, \, q = \text{value depends on condition}$ 

- 2: Bit 21 of the TBLPTRU allows access to the device configuration bits.
- 3: These registers are unused on PIC18F6525/6621 devices and read as '0'.
- 4: RG5 is available only if MCLR function is disabled in configuration.
- **5**: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

TABLE 4-3: REGISTER FILE SUMMARY (CONTINUED)

| TABLE 4-  | 3: KE                        | GISTERF                           | ILE SUMI                  | MART (CC       | NIINUEL       | (י           |                            | 1           | <u> </u>          | 1                |
|-----------|------------------------------|-----------------------------------|---------------------------|----------------|---------------|--------------|----------------------------|-------------|-------------------|------------------|
| File Name | Bit 7                        | Bit 6                             | Bit 5                     | Bit 4          | Bit 3         | Bit 2        | Bit 1                      | Bit 0       | Value on POR, BOR | Details on page: |
| PREINC2   | Uses conten<br>(not a physic | ts of FSR2 to<br>al register)     | address data              | memory – val   | ue of FSR2 pi | re-increment | ed                         |             | N/A               | 56               |
| PLUSW2    |                              | ts of FSR2 to<br>al register) – v |                           | •              |               | re-increment | ed                         |             | N/A               | 56               |
| FSR2H     | _                            | _                                 | _                         | _              | Indirect Data | Memory Ad    | dress Pointer              | 2 High Byte | 0000              | 33, 56           |
| FSR2L     | Indirect Data                | Memory Add                        | ress Pointer 2            | Low Byte       | •             |              |                            |             | xxxx xxxx         | 33, 56           |
| STATUS    | _                            | _                                 | _                         | N              | OV            | Z            | DC                         | С           | x xxxx            | 33, 58           |
| TMR0H     | Timer0 Regis                 | ster High Byte                    |                           |                |               |              |                            |             | 0000 0000         | 33, 133          |
| TMR0L     | Timer0 Regis                 | ster Low Byte                     |                           |                |               |              |                            |             | xxxx xxxx         | 33, 133          |
| T0CON     | TMR0ON                       | T08BIT                            | T0CS                      | T0SE           | PSA           | T0PS2        | T0PS1                      | T0PS0       | 1111 1111         | 33, 131          |
| OSCCON    | _                            | _                                 | _                         | _              | LOCK          | PLLEN        | SCS1                       | SCS0        | 0000              | 25, 33           |
| LVDCON    | _                            | _                                 | IRVST                     | LVDEN          | LVDL3         | LVDL2        | LVDL1                      | LVDL0       | 00 0101           | 33, 255          |
| WDTCON    | _                            | _                                 | _                         | _              | _             | _            | _                          | SWDTEN      | 0                 | 33, 267          |
| RCON      | IPEN                         | _                                 | _                         | RI             | TO            | PD           | POR                        | BOR         | 01 11qq           | 33, 59,<br>101   |
| TMR1H     | Timer1 Regis                 | ster High Byte                    | •                         | •              |               |              |                            | •           | xxxx xxxx         | 33, 139          |
| TMR1L     | Timer1 Regis                 | ner1 Register Low Byte            |                           |                |               |              |                            |             |                   | 33, 139          |
| T1CON     | RD16                         | _                                 | T1CKPS1                   | T1CKPS0        | T10SCEN       | T1SYNC       | TMR1CS                     | TMR10N      | 0-00 0000         | 33, 139          |
| TMR2      | Timer2 Regis                 | ster                              |                           |                |               |              |                            | 1           | 0000 0000         | 33, 142          |
| PR2       | Timer2 Perio                 |                                   |                           |                |               |              |                            |             | 1111 1111         | 33, 142          |
| T2CON     | _                            | T2OUTPS3                          | T2OUTPS2                  | T2OUTPS1       | T2OUTPS0      | TMR2ON       | T2CKPS1                    | T2CKPS0     | -000 0000         | 33, 142          |
| SSPBUF    | MSSP Recei                   | ive Buffer/Trar                   | nsmit Register            |                |               |              |                            | ı           | xxxx xxxx         | 33, 181          |
| SSPADD    | MSSP Addre                   | ess Register in                   | I <sup>2</sup> C Slave mo | ode. MSSP Ba   | aud Rate Relo | ad Register  | in I <sup>2</sup> C Master | mode.       | 0000 0000         | 33, 181          |
| SSPSTAT   | SMP                          | CKE                               | D/A                       | Р              | S             | R/W          | UA                         | BF          | 0000 0000         | 33, 174          |
| SSPCON1   | WCOL                         | SSPOV                             | SSPEN                     | CKP            | SSPM3         | SSPM2        | SSPM1                      | SSPM0       | 0000 0000         | 33, 175          |
| SSPCON2   | GCEN                         | ACKSTAT                           | ACKDT                     | ACKEN          | RCEN          | PEN          | RSEN                       | SEN         | 0000 0000         | 33, 185          |
| ADRESH    | A/D Result R                 | Register High E                   | Byte                      | I              |               |              | I                          | I           | xxxx xxxx         | 33, 241          |
| ADRESL    | A/D Result R                 | Register Low E                    | Byte                      |                |               |              |                            |             | xxxx xxxx         | 33, 241          |
| ADCON0    | _                            | _                                 | CHS3                      | CHS2           | CHS1          | CHS0         | GO/DONE                    | ADON        | 00 0000           | 34, 233          |
| ADCON1    | _                            | _                                 | VCFG1                     | VCFG0          | PCFG3         | PCFG2        | PCFG1                      | PCFG0       | 00 0000           | 34, 234          |
| ADCON2    | ADFM                         | _                                 | ACQT2                     | ACQT1          | ACQT0         | ADCS2        | ADCS1                      | ADCS0       | 0-00 0000         | 34, 235          |
| CCPR1H    | Enhanced C                   | apture/Compa                      | re/PWM Reg                | ister 1 High B | vte           |              |                            | ı           | xxxx xxxx         | 34, 172          |
| CCPR1L    |                              | apture/Compa                      |                           |                |               |              |                            |             | xxxx xxxx         |                  |
| CCP1CON   |                              | P1M0                              |                           |                |               | CCP1M2       | CCP1M1                     | CCP1M0      |                   |                  |
| CCPR2H    |                              | apture/Compa                      |                           |                |               |              | I                          |             | xxxx xxxx         | 34, 172          |
| CCPR2L    | Enhanced C                   | apture/Compa                      | re/PWM Reg                | ister 2 Low By | rte           |              |                            |             | xxxx xxxx         | 34, 172          |
| CCP2CON   | P2M1                         | P2M0                              | DC2B1                     | DC2B0          | CCP2M3        | CCP2M2       | CCP2M1                     | CCP2M0      | 0000 0000         | 34, 157          |
| CCPR3H    |                              | apture/Compa                      |                           |                |               |              | I                          | 1           | xxxx xxxx         | 34, 172          |
| CCPR3L    |                              | apture/Compa                      |                           |                |               |              |                            |             | xxxx xxxx         | 34, 172          |
| CCP3CON   | P3M1                         | P3M0                              | DC3B1                     | DC2B0          | CCP3M3        | CCP3M2       | CCP3M1                     | ССР3М0      | 0000 0000         | 34, 157          |
| ECCP1AS   | ECCP1ASE                     | ECCP1AS2                          | ECCP1AS1                  | ECCP1AS0       | PSS1AC1       | PSS1AC0      | PSS1BD1                    | PSS1BD0     | 0000 0000         | 34, 169          |
| CVRCON    | CVREN                        | CVROE                             | CVRR                      | CVRSS          | CVR3          | CVR2         | CVR1                       | CVR0        | 0000 0000         | 34, 249          |
|           | I                            |                                   | <u> </u>                  |                | ·             |              | <u> </u>                   |             | L                 | 1                |

**Legend:** x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

- 2: Bit 21 of the TBLPTRU allows access to the device configuration bits.
- 3: These registers are unused on PIC18F6525/6621 devices and read as '0'.
- **4:** RG5 is available only if MCLR function is disabled in configuration.
- 5: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

TABLE 4-3: REGISTER FILE SUMMARY (CONTINUED)

| File Name             | Bit 7                | Bit 6                 | Bit 5           | Bit 4                            | Bit 3         | Bit 2                    | Bit 1        | Bit 0       | Value on POR, BOR | Details on page: |
|-----------------------|----------------------|-----------------------|-----------------|----------------------------------|---------------|--------------------------|--------------|-------------|-------------------|------------------|
| CMCON                 | C2OUT                | C1OUT                 | C2INV           | C1INV                            | CIS           | CM2                      | CM1          | CM0         | 0000 0000         | 34, 243          |
| TMR3H                 | Timer3 Regis         | ster High Byte        |                 |                                  |               |                          |              |             | xxxx xxxx         | 34, 145          |
| TMR3L                 | Timer3 Regis         | ster Low Byte         |                 |                                  |               |                          |              |             | xxxx xxxx         | 34, 145          |
| T3CON                 | RD16                 | T3CCP2                | T3CKPS1         | T3CKPS0                          | T3CCP1        | T3SYNC                   | TMR3CS       | TMR3ON      | 0000 0000         | 34, 145          |
| PSPCON <sup>(5)</sup> | IBF                  | OBF                   | IBOV            | PSPMODE                          | _             | _                        | _            | _           | 0000              | 34, 129          |
| SPBRG1                | Enhanced U           | SART1 Baud            | Rate Generat    | or Register Lo                   | w Byte        | •                        | •            | •           | 0000 0000         | 34, 217          |
| RCREG1                | Enhanced U           | SART1 Recei           | ve Register     |                                  |               |                          |              |             | 0000 0000         | 34, 224          |
| TXREG1                | Enhanced U           | SART1 Transi          | mit Register    |                                  |               |                          |              |             | 0000 0000         | 34, 222          |
| TXSTA1                | CSRC                 | TX9                   | TXEN            | TXEN SYNC SENDB BRGH TRMT TX9D 0 |               |                          |              | 0000 0010   | 34, 214           |                  |
| RCSTA1                | SPEN                 | RX9                   | SREN            | CREN                             | ADDEN         | FERR                     | OERR         | RX9D        | 0000 000x         | 34, 215          |
| EEADRH                | _                    | _                     | _               | _                                | _             | _                        | EE Addr Re   | gister High | 00                | 34, 83           |
| EEADR                 | Data EEPRO           | OM Address R          | egister         |                                  |               |                          |              |             | 0000 0000         | 34, 83           |
| EEDATA                | Data EEPRO           | DM Data Regis         | ster            |                                  |               |                          |              |             | 0000 0000         | 34, 83           |
| EECON2                | Data EEPRO           | OM Control Re         | gister 2 (not a | a physical regi                  | ster)         |                          |              |             |                   | 34, 83           |
| EECON1                | EEPGD                | CFGS                  | _               | FREE                             | WRERR         | WREN                     | WR           | RD          | xx-0 x000         | 34, 80           |
| IPR3                  | _                    | _                     | RC2IP           | TX2IP                            | TMR4IP        | CCP5IP                   | CCP4IP       | CCP3IP      | 11 1111           | 35, 100          |
| PIR3                  | _                    | _                     | RC2IF           | TX2IF                            | TMR4IF        | CCP5IF                   | CCP4IF       | CCP3IF      | 00 0000           | 35, 94           |
| PIE3                  | _                    | _                     | RC2IE           | TX2IE                            | TMR4IE        | CCP5IE                   | CCP4IE       | CCP3IE      | 00 0000           | 35, 97           |
| IPR2                  | _                    | CMIP                  | _               | EEIP                             | BCLIP         | LVDIP                    | TMR3IP       | CCP2IP      | -1-1 1111         | 35, 99           |
| PIR2                  | _                    | CMIF                  | _               | EEIF                             | BCLIF         | LVDIF                    | TMR3IF       | CCP2IF      | -0-0 0000         | 35, 93           |
| PIE2                  | _                    | CMIE                  | _               | EEIE                             | BCLIE         | LVDIE                    | TMR3IE       | CCP2IE      | -0-0 0000         | 35, 96           |
| IPR1                  | PSPIP <sup>(5)</sup> | ADIP                  | RC1IP           | TX1IP                            | SSPIP         | CCP1IP                   | TMR2IP       | TMR1IP      | 1111 1111         | 35, 98           |
| PIR1                  | PSPIF <sup>(5)</sup> | ADIF                  | RC1IF           | TX1IF                            | SSPIF         | CCP1IF                   | TMR2IF       | TMR1IF      | 0000 0000         | 35, 92           |
| PIE1                  | PSPIE <sup>(5)</sup> | ADIE                  | RC1IE           | TX1IE                            | SSPIE         | CCP1IE                   | TMR2IE       | TMR1IE      | 0000 0000         | 35, 95           |
| MEMCON <sup>(3)</sup> | EBDIS                | _                     | WAIT1           | WAIT0                            | _             | _                        | WM1          | WM0         | 0-0000            | 35, 71           |
| TRISJ <sup>(3)</sup>  | Data Direction       | on Control Reg        | ister for POR   | TJ                               |               |                          |              |             | 1111 1111         | 35, 127          |
| TRISH <sup>(3)</sup>  | Data Direction       | on Control Reg        | ister for POR   | TH                               |               |                          |              |             | 1111 1111         | 35, 124          |
| TRISG                 | _                    | _                     | _               | Data Directio                    | n Control Re  | gister for POF           | RTG          |             | 1 1111            | 35, 119          |
| TRISF                 | Data Direction       | on Control Reg        | ister for POR   | TF                               |               |                          |              |             | 1111 1111         | 35, 116          |
| TRISE                 |                      | on Control Reg        |                 |                                  |               |                          |              |             | 1111 1111         | 35, 113          |
| TRISD                 | Data Direction       | on Control Rec        | gister for POR  | TD                               |               |                          |              |             | 1111 1111         | 35, 110          |
| TRISC                 | Data Direction       | on Control Reg        | ister for POR   | TC                               |               |                          |              |             | 1111 1111         | 35, 108          |
| TRISB                 |                      | on Control Reg        | ,               |                                  |               |                          |              |             | 1111 1111         | 35, 105          |
| TRISA                 | _                    | TRISA6 <sup>(1)</sup> | Data Direction  | on Control Reg                   | ister for POR | TA                       |              |             | -111 1111         | 35, 121          |
| LATJ <sup>(3)</sup>   | Read PORT            | J Data Latch,         | Write PORTJ     | Data Latch                       |               |                          |              |             | xxxx xxxx         | 35, 127          |
| LATH <sup>(3)</sup>   | Read PORT            | H Data Latch,         | Write PORTH     | l Data Latch                     |               |                          |              |             | xxxx xxxx         | 35, 124          |
| LATG                  | -                    | _                     | _               | Read PORTO                       | 3 Data Latch, | Write PORT               | G Data Latch |             | x xxxx            | 35, 121          |
| LATF                  | Read PORT            | F Data Latch,         | Write PORTF     | Data Latch                       |               |                          |              |             | xxxx xxxx         | 35, 119          |
| LATE                  | Read PORT            | E Data Latch,         | Write PORTE     | Data Latch                       |               |                          |              |             | xxxx xxxx         | 35, 116          |
| LATD                  | Read PORT            | D Data Latch,         | Write PORT      | Data Latch                       |               |                          |              |             | xxxx xxxx         | 35, 113          |
| LATC                  | Read PORT            | C Data Latch,         | Write PORTO     | C Data Latch                     |               |                          |              |             | xxxx xxxx         | 35, 110          |
| LATB                  | Read PORT            | B Data Latch,         |                 |                                  |               |                          |              |             | xxxx xxxx         | 35, 108          |
| LATA                  | -                    | LATA6 <sup>(1)</sup>  | Read PORT       | A Data Latch, '                  | Write PORTA   | Data Latch <sup>(1</sup> | )            |             | -xxx xxxx         | 35, 105          |

**Legend:** x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

- 2: Bit 21 of the TBLPTRU allows access to the device configuration bits.
- 3: These registers are unused on PIC18F6525/6621 devices and read as '0'.
- 4: RG5 is available only if MCLR function is disabled in configuration.
- **5:** Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

TABLE 4-3: REGISTER FILE SUMMARY (CONTINUED)

| File Name            | Bit 7           | Bit 6                                  | Bit 5              | Bit 4           | Bit 3           | Bit 2               | Bit 1   | Bit 0   | Value on POR, BOR | Details on page: |
|----------------------|-----------------|--|--------------------|-----------------|-----------------|---------------------|---------|---------|-------------------|------------------|
| PORTJ <sup>(3)</sup> | Read PORT       | J pins, Write F                        | ORTJ Data L        | atch            |                 |                     |         |         | xxxx xxxx         | 35, 127          |
| PORTH <sup>(3)</sup> | Read PORT       | H pins, Write F                        | PORTH Data         | Latch           |                 |                     |         |         | 0000 xxxx         | 35, 124          |
| PORTG                | _               | _                                      | RG5 <sup>(4)</sup> | Read PORTO      | 3 pins, Write I | PORTG Data          | Latch   |         | xx xxxx           | 36, 121          |
| PORTF                | Read PORT       | F pins, Write F                        | ORTF Data L        | atch            |                 |                     |         |         | x000 0000         | 36, 119          |
| PORTE                | Read PORT       | E pins, Write F                        | PORTE Data I       | _atch           |                 |                     |         |         | xxxx xxxx         | 36, 116          |
| PORTD                | Read PORT       | D pins, Write F                        | PORTD Data         | Latch           |                 |                     |         |         | xxxx xxxx         | 36, 113          |
| PORTC                | Read PORT       | ead PORTC pins, Write PORTC Data Latch |                    |                 |                 |                     |         |         |                   | 36, 110          |
| PORTB                | Read PORT       | B pins, Write F                        |                    |                 |                 |                     |         |         | xxxx xxxx         | 36, 108          |
| PORTA                |                 | RA6 <sup>(1)</sup>                     | Read PORTA         | A pins, Write P | ORTA Data L     | atch <sup>(1)</sup> |         |         | -x0x 0000         | 36, 105          |
| SPBRGH1              | Enhanced U      | SART1 Baud                             | Rate Generat       | or Register Hi  | gh Byte         |                     |         |         | 0000 0000         | 36, 217          |
| BAUDCON1             | _               | RCIDL                                  | _                  | SCKP            | BRG16           | _                   | WUE     | ABDEN   | -1-0 0-00         | 36, 216          |
| SPBRGH2              | Enhanced U      | SART2 Baud                             | Rate Generat       | or Register Hi  | gh Byte         |                     |         |         | 0000 0000         | 36, 217          |
| BAUDCON2             |                 | RCIDL                                  | _                  | SCKP            | BRG16           | -                   | WUE     | ABDEN   | -1-0 0-00         | 36, 216          |
| ECCP1DEL             | P1RSEN          | P1DC6                                  | P1DC5              | P1DC4           | P1DC3           | P1DC2               | P1DC1   | P1DC0   | 0000 0000         | 36, 168          |
| TMR4                 | Timer4 Register |  |                    |                 |                 |                     |         |         | 0000 0000         | 36, 148          |
| PR4                  | Timer4 Perio    | d Register                             |                    |                 |                 |                     |         |         | 1111 1111         | 36, 148          |
| T4CON                |                 | T4OUTPS3                               | T4OUTPS2           | T4OUTPS1        | T4OUTPS0        | TMR4ON              | T4CKPS1 | T4CKPS0 | -000 0000         | 36, 147          |
| CCPR4H               | Capture/Con     | npare/PWM R                            | egister 4 High     | n Byte          |                 |                     |         |         | xxxx xxxx         | 36, 153          |
| CCPR4L               | Capture/Con     | npare/PWM R                            | egister 4 Low      | Byte            |                 |                     |         |         | xxxx xxxx         | 36, 153          |
| CCP4CON              |                 | _                                      | DC4B1              | DC4B0           | CCP4M3          | CCP4M2              | CCP4M1  | CCP4M0  | 00 0000           | 36, 149          |
| CCPR5H               | Capture/Con     | npare/PWM R                            | egister 5 High     | n Byte          |                 |                     |         |         | xxxx xxxx         | 36, 153          |
| CCPR5L               | Capture/Con     | npare/PWM R                            | egister 5 Low      | Byte            |                 |                     |         |         | xxxx xxxx         | 36, 153          |
| CCP5CON              | _               | _                                      | DC5B1              | DC5B0           | CCP5M3          | CCP5M2              | CCP5M1  | CCP5M0  | 00 0000           | 36, 149          |
| SPBRG2               | Enhanced U      | SART2 Baud                             | Rate Generat       | or Register Lo  | w Byte          |                     |         |         | 0000 0000         | 36, 217          |
| RCREG2               | Enhanced U      | SART2 Recei                            | ve Register        |                 |                 |                     |         |         | 0000 0000         | 36, 224          |
| TXREG2               | Enhanced U      | SART2 Transı                           | mit Register       |                 |                 |                     |         |         | 0000 0000         | 36, 222          |
| TXSTA2               | CSRC            | TX9                                    | TXEN               | SYNC            | SENDB           | BRGH                | TRMT    | TX9D    | 0000 0010         | 36, 222          |
| RCSTA2               | SPEN            | RX9                                    | SREN               | CREN            | ADDEN           | FERR                | OERR    | RX9D    | 0000 000x         | 36, 222          |
| ECCP3AS              | ECCP3ASE        | ECCP3AS2                               | ECCP3AS1           | ECCP3AS0        | PSS3AC1         | PSS3AC0             | PSS3BD1 | PSS3BD0 | 0000 0000         | 36, 169          |
| ECCP3DEL             | P3RSEN          | P3DC6                                  | P3DC5              | P3DC4           | P3DC3           | P3DC2               | P3DC1   | P3DC0   | 0000 0000         | 36, 168          |
| ECCP2AS              | ECCP2ASE        | ECCP2AS2                               | ECCP2AS1           | ECCP2AS0        | PSS2AC1         | PSS2AC0             | PSS2BD1 | PSS2BD0 | 0000 0000         | 36, 169          |
| ECCP2DEL             | P2RSEN          | P2DC6                                  | P2DC5              | P2DC4           | P2DC3           | P2DC2               | P2DC1   | P2DC0   | 0000 0000         | 36, 168          |

**Legend:** x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

- 2: Bit 21 of the TBLPTRU allows access to the device configuration bits.
- 3: These registers are unused on PIC18F6525/6621 devices and read as '0'.
- 4: RG5 is available only if MCLR function is disabled in configuration.
- 5: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

### 4.10 Access Bank

The Access Bank is an architectural enhancement, which is very useful for C compiler code optimization. The techniques used by the C compiler may also be useful for programs written in assembly.

This data memory region can be used for:

- · Intermediate computational values
- · Local variables of subroutines
- Faster context saving/switching of variables
- · Common variables
- Faster evaluation/control of SFRs (no banking)

The Access Bank is comprised of the upper 160 bytes in Bank 15 (SFRs) and the lower 96 bytes in Bank 0. These two sections will be referred to as Access RAM High and Access RAM Low, respectively. Figure 4-7 indicates the Access RAM areas.

A bit in the instruction word specifies if the operation is to occur in the bank specified by the BSR register or in the Access Bank. This bit is denoted by the 'a' bit (for access bit).

When forced in the Access Bank (a = 0), the last address in Access RAM Low is followed by the first address in Access RAM High. Access RAM High maps the Special Function Registers so that these registers can be accessed without any software overhead. This is useful for testing status flags and modifying control bits.

### 4.11 Bank Select Register (BSR)

The need for a large general purpose memory space dictates a RAM banking scheme. The data memory is partitioned into sixteen banks. When using direct addressing, the BSR should be configured for the desired bank.

BSR<3:0> holds the upper 4 bits of the 12-bit RAM address. The BSR<7:4> bits will always read '0's and writes will have no effect.

A MOVLB instruction has been provided in the instruction set to assist in selecting banks.


If the currently selected bank is not implemented, any read will return all '0's and all writes are ignored. The STATUS register bits will be set/cleared as appropriate for the instruction performed.

Each Bank extends up to FFh (256 bytes). All data memory is implemented as static RAM.

A MOVFF instruction ignores the BSR since the 12-bit addresses are embedded into the instruction word.

Section 4.12 "Indirect Addressing, INDF and FSR Registers" provides a description of indirect addressing which allows linear addressing of the entire RAM space.

### FIGURE 4-8: DIRECT ADDRESSING



- Note 1: For register file map detail, see Table 4-2.
  - 2: The access bit of the instruction can be used to force an override of the selected bank (BSR<3:0>) to the registers of the Access Bank.
  - 3: The MOVFF instruction embeds the entire 12-bit address in the instruction.

# 4.12 Indirect Addressing, INDF and FSR Registers

Indirect addressing is a mode of addressing data memory, where the data memory address in the instruction is not fixed. An FSR register is used as a pointer to the data memory location that is to be read or written. Since this pointer is in RAM, the contents can be modified by the program. This can be useful for data tables in the data memory and for software stacks. Figure 4-9 shows the operation of indirect addressing. This shows the moving of the value to the data memory address specified by the value of the FSR register.

Indirect addressing is possible by using one of the INDF registers. Any instruction using the INDF register actually accesses the register pointed to by the File Select Register, FSR. Reading the INDF register itself indirectly (FSR = 0), will read 00h. Writing to the INDF register indirectly, results in a no operation (NOP). The FSR register contains a 12-bit address which is shown in Figure 4-10.

The INDFn register is not a physical register. Addressing INDFn actually addresses the register whose address is contained in the FSRn register (FSRn is a pointer). This is indirect addressing.

Example 4-5 shows a simple use of indirect addressing to clear the RAM in Bank 1 (locations 100h-1FFh) in a minimum number of instructions.

# EXAMPLE 4-5: HOW TO CLEAR RAM (BANK 1) USING INDIRECT ADDRESSING

|       | LFSR  | FSR0, 0x100 | ;                |
|-------|-------|-------------|------------------|
| NEXT  | CLRF  | POSTINC0    | ; Clear INDF     |
|       |       |             | ; register and   |
|       |       |             | ; inc pointer    |
|       | BTFSS | FSROH, 1    | ; All done with  |
|       |       |             | ; Bank1?         |
|       | GOTO  | NEXT        | ; NO, clear next |
| CONTI | NUE   |             | ; YES, continue  |
| I     |       |             |                  |

There are three indirect addressing registers. To address the entire data memory space (4096 bytes), these registers are 12 bits wide. To store the 12 bits of addressing information, two 8-bit registers are required. These indirect addressing registers are:

- FSR0: composed of FSR0H:FSR0L
- 2. FSR1: composed of FSR1H:FSR1L
- 3. FSR2: composed of FSR2H:FSR2L

In addition, there are registers INDF0, INDF1 and INDF2, which are not physically implemented. Reading or writing to these registers activates indirect addressing, with the value in the corresponding FSR register being the address of the data. If an instruction writes a value to INDF0, the value will be written to the address pointed to by FSR0H:FSR0L. A read from INDF1 reads

the data from the address pointed to by FSR1H:FSR1L. INDFn can be used in code anywhere an operand can be used.

If INDF0, INDF1 or INDF2 are read indirectly via an FSR, all '0's are read (zero bit is set). Similarly, if INDF0, INDF1 or INDF2 are written to indirectly, the operation will be equivalent to a NOP instruction and the Status bits are not affected.

## 4.12.1 INDIRECT ADDRESSING OPERATION

Each FSR register has an INDF register associated with it, plus four additional register addresses. Performing an operation on one of these five registers determines how the FSR will be modified during indirect addressing.

When data access is done to one of the five INDFn locations, the address selected will configure the FSRn register to:

- Do nothing to FSRn after an indirect access (no change) – INDFn.
- Auto-decrement FSRn after an indirect access (post-decrement) – POSTDECn.
- Auto-increment FSRn after an indirect access (post-increment) – POSTINCn.
- Auto-increment FSRn before an indirect access (pre-increment) – PREINCn.
- Use the value in the WREG register as an offset to FSRn. Do not modify the value of the WREG or the FSRn register after an indirect access (no change) – PLUSWn.

When using the auto-increment or auto-decrement features, the effect on the FSR is not reflected in the STATUS register. For example, if the indirect address causes the FSR to equal '0', the Z bit will not be set.

Incrementing or decrementing an FSR affects all 12 bits. That is, when FSRnL overflows from an increment, FSRnH will be incremented automatically.


Adding these features allows the FSRn to be used as a Stack Pointer in addition to its uses for table operations in data memory.

Each FSR has an address associated with it that performs an indexed indirect access. When a data access to this INDFn location (PLUSWn) occurs, the FSRn is configured to add the signed value in the WREG register and the value in FSR to form the address before an indirect access. The FSR value is not changed.


If an FSR register contains a value that points to one of the INDFn, an indirect read will read 00h (zero bit is set), while an indirect write will be equivalent to a NOP (Status bits are not affected).

If an indirect addressing operation is done where the target address is an FSRnH or FSRnL register, the write operation will dominate over the pre- or post-increment/decrement functions.

FIGURE 4-9: INDIRECT ADDRESSING OPERATION



### FIGURE 4-10: INDIRECT ADDRESSING



### 4.13 STATUS Register

The STATUS register, shown in Register 4-3, contains the arithmetic status of the ALU. As with any other SFR, it can be the operand for any instruction.

If the STATUS register is the destination for an instruction that affects the Z, DC, C, OV or N bits, the results of the instruction are not written; instead, the status is updated according to the instruction performed. Therefore, the result of an instruction with the STATUS register as its destination may be different than intended. As an example, CLRF STATUS will set the Z bit and leave the remaining Status bits unchanged ('000u uluu').

It is recommended that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect the Z, C, DC, OV or N bits in the STATUS register.

For other instructions that do not affect Status bits, see the instruction set summaries in Table 25-2.

| Note: | The   | C and   | DC bits | opera | ite as the borr | ow |
|-------|-------|---------|---------|-------|-----------------|----|
|       | and   | digit   | borrow  | bits  | respectively    | in |
|       | subti | raction |         |       |                 |    |

### **REGISTER 4-3: STATUS REGISTER**

| U-0   | U-0 | U-0 | R/W-x | R/W-x | R/W-x | R/W-x | R/W-x |
|-------|-----|-----|-------|-------|-------|-------|-------|
| _     | _   | N   |       | OV    | OV Z  |       | С     |
| bit 7 |     |     |       |       |       |       | bit 0 |

### bit 7-5 Unimplemented: Read as '0'

bit 4 N: Negative bit

This bit is used for signed arithmetic (2's complement). It indicates whether the result was negative (ALU MSB = 1).

- 1 = Result was negative
- 0 = Result was positive
- bit 3 **OV:** Overflow bit

This bit is used for signed arithmetic (2's complement). It indicates an overflow of the 7-bit magnitude which causes the sign bit (bit 7) to change state.

- 1 = Overflow occurred for signed arithmetic (in this arithmetic operation)
- 0 = No overflow occurred
- bit 2 Z: Zero bit
  - 1 = The result of an arithmetic or logic operation is zero
  - 0 = The result of an arithmetic or logic operation is not zero
- bit 1 **DC:** Digit Carry/Borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the 4th low-order bit of the result occurred
- 0 = No carry-out from the 4th low-order bit of the result

For  $\overline{\text{borrow}}$ , the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either bit 4 or bit 3 of the source register.

### bit 0 C: Carry/Borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the Most Significant bit of the result occurred
- 0 = No carry-out from the Most Significant bit of the result occurred

**Note:** For borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high- or low-order bit of the source register.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

### 4.14 RCON Register

The Reset Control (RCON) register contains flag bits that allow differentiation between the sources of a device Reset. These flags include the TO, PD, POR, BOR and RI bits. This register is readable and writable.

It is recommended that the POR bit be set after a Power-on Reset has been detected, so that subsequent Power-on Resets may be detected.

### REGISTER 4-4: RCON: RESET CONTROL REGISTER

| R/W-0 | U-0 | U-0 | R/W-1 | R/W-1 | R/W-1 | R/W-0 | R/W-0 |
|-------|-----|-----|-------|-------|-------|-------|-------|
| IPEN  | _   | -   | RI    | TO    | PD    | POR   | BOR   |
| bit 7 |     |     |       |       |       |       | bit 0 |

Note:

bit 7 IPEN: Interrupt Priority Enable bit

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (PIC16CXXX Compatibility mode)

bit 6-5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

1 = The RESET instruction was not executed

0 = The RESET instruction was executed causing a device Reset (must be set in software after a Brown-out Reset occurs)

bit 3 TO: Watchdog Time-out Flag bit

1 = After power-up, CLRWDT instruction or SLEEP instruction

0 = A WDT time-out occurred

bit 2 PD: Power-down Detection Flag bit

1 = After power-up or by the CLRWDT instruction

0 = By execution of the SLEEP instruction

bit 1 POR: Power-on Reset Status bit

1 = A Power-on Reset has not occurred

0 = A Power-on Reset occurred

(must be set in software after a Power-on Reset occurs)

bit 0 BOR: Brown-out Reset Status bit

1 = A Brown-out Reset has not occurred

0 = A Brown-out Reset occurred

(must be set in software after a Brown-out Reset occurs)

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

NOTES:

### 5.0 FLASH PROGRAM MEMORY

The Flash program memory is readable, writable and erasable, during normal operation over the entire VDD

A read from program memory is executed on one byte at a time. A write to program memory is executed on blocks of 8 bytes at a time. Program memory is erased in blocks of 64 bytes at a time. A bulk erase operation may not be issued from user code.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, therefore, code cannot execute. An internal programming timer terminates program memory writes

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

### 5.1 Table Reads and Table Writes

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:

- Table Read (TBLRD)
- Table Write (TBLWT)

The program memory space is 16 bits wide, while the data RAM space is 8 bits wide. Table reads and table writes move data between these two memory spaces through an 8-bit register (TABLAT).

Table read operations retrieve data from program memory and place it into the data RAM space. Figure 5-1 shows the operation of a table read with program memory and data RAM.

Table write operations store data from the data memory space into holding registers in program memory. The procedure to write the contents of the holding registers into program memory is detailed in Section 5.5 "Writing to Flash Program Memory". Figure 5-2 shows the operation of a table write with program memory and data RAM.

Table operations work with byte entities. A table block containing data, rather than program instructions, is not required to be word aligned. Therefore, a table block can start and end at any byte address. If a table write is being used to write executable code into program memory, program instructions will need to be word aligned.





FIGURE 5-1: **TABLE READ OPERATION** 

### FIGURE 5-2: TABLE WRITE OPERATION



Note 1: Table pointer actually points to one of eight holding registers, the address of which is determined by TBLPTRL<2:0>. The process for physically writing data to the program memory array is discussed in Section 5.5 "Writing to Flash Program Memory".

### 5.2 Control Registers

Several control registers are used in conjunction with the TBLRD and TBLWT instructions. These include the:

- EECON1 register
- · EECON2 register
- TABLAT register
- · TBLPTR registers

### 5.2.1 EECON1 AND EECON2 REGISTERS

EECON1 is the control register for memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the memory write and erase sequences.

Control bit, EEPGD, determines if the access will be a program or data EEPROM memory access. When clear, any subsequent operations will operate on the data EEPROM memory. When set, any subsequent operations will operate on the program memory.

Control bit, CFGS, determines if the access will be to the Configuration/Calibration registers or to program memory/data EEPROM memory. When set, subsequent operations will operate on Configuration registers regardless of EEPGD (see Section 24.0 "Special Features of the CPU"). When clear, memory selection access is determined by EEPGD.

The FREE bit, when set, will allow a program memory erase operation. When the FREE bit is set, the erase operation is initiated on the next WR command. When FREE is clear, only writes are enabled.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to Reset values of zero.

Note: During normal operation, the WRERR bit is read as '1'. This can indicate that a write operation was prematurely terminated by a Reset, or a write operation was attempted improperly.

The WR control bit initiates write operations. The bit cannot be cleared, only set, in software; it is cleared in hardware at the completion of the write operation. The inability to clear the WR bit in software prevents the accidental or premature termination of a write operation.

**Note:** Interrupt flag bit, EEIF in the PIR2 register, is set when the write is complete. It must be cleared in software.

### REGISTER 5-1: EECON1 REGISTER (ADDRESS FA6h)

| R/W-x | R/W-x | U-0 | R/W-0 | R/W-x | R/W-0 | R/S-0 | R/S-0 |
|-------|-------|-----|-------|-------|-------|-------|-------|
| EEPGD | CFGS  | _   | FREE  | WRERR | WREN  | WR    | RD    |
|       |       |     |       |       |       |       |       |

bit 7 bit 0

bit 7 **EEPGD:** Flash Program or Data EEPROM Memory Select bit

1 = Access Flash program memory

0 = Access data EEPROM memory

bit 6 CFGS: Flash Program/Data EEPROM or Configuration Select bit

1 = Access Configuration registers

0 = Access Flash program or data EEPROM memory

bit 5 Unimplemented: Read as '0'

bit 4 FREE: Flash Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next WR command (cleared by completion of erase operation)

0 = Perform write only

bit 3 WRERR: Flash Program/Data EEPROM Error Flag bit

1 = A write operation is prematurely terminated (any Reset during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD and CFGS bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: Flash Program/Data EEPROM Write Enable bit

1 = Allows write cycles to Flash program/data EEPROM

0 = Inhibits write cycles to Flash program/data EEPROM

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle. (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle to the EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read (Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software. RD bit cannot be set when EEPGD = 1.)

0 = Does not initiate an EEPROM read

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 5.2.2 TABLAT – TABLE LATCH REGISTER

The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch register is used to hold 8-bit data during data transfers between program memory and data RAM.

## 5.2.3 TBLPTR – TABLE POINTER REGISTER

The Table Pointer register (TBLPTR) addresses a byte within the program memory. The TBLPTR is comprised of three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer. The low-order 21 bits allow the device to address up to 2 Mbytes of program memory space. The 22nd bit allows access to the device ID, the user ID and the configuration bits.

The Table Pointer, TBLPTR, is used by the TBLRD and TBLWT instructions. These instructions can update the TBLPTR in one of four ways based on the table operation. These operations are shown in Table 5-1. These operations on the TBLPTR only affect the low-order 21 bits.

### 5.2.4 TABLE POINTER BOUNDARIES

TBLPTR is used in reads, writes and erases of the Flash program memory.

When a TBLRD is executed, all 22 bits of the TBLPTR determine which byte is read from program memory into TABLAT.

When a TBLWT is executed, the three LSbs of the Table Pointer register (TBLPTR<2:0>) determine which of the eight program memory holding registers is written to. When the timed write to program memory (long write) begins, the 19 MSbs of the TBLPTR (TBLPTR<21:3>) will determine which program memory block of 8 bytes is written to. For more detail, see **Section 5.5 "Writing to Flash Program Memory"**.


When an erase of program memory is executed, the 16 MSbs of the Table Pointer register (TBLPTR<21:6>) point to the 64-byte block that will be erased. The Least Significant bits (TBLPTR<5:0>) are ignored.

Figure 5-3 describes the relevant boundaries of TBLPTR based on Flash program memory operations.

| TABLE 5-1: | TABLE POINTER OPERATIONS WITH TBLRD AND TBLWT INSTRUCTIONS |
|------------|--|
|            |  |

| Example            | Operation on Table Pointer                  |
|--------------------|---|
| TBLRD* TBLWT*      | TBLPTR is not modified                      |
| TBLRD*+<br>TBLWT*+ | TBLPTR is incremented after the read/write  |
| TBLRD*-<br>TBLWT*- | TBLPTR is decremented after the read/write  |
| TBLRD+* TBLWT+*    | TBLPTR is incremented before the read/write |

FIGURE 5-3: TABLE POINTER BOUNDARIES BASED ON OPERATION




# 5.3 Reading the Flash Program Memory

The TBLRD instruction is used to retrieve data from program memory and places it into data RAM. Table reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next table read operation.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. Figure 5-4 shows the interface between the internal program memory and the TABLAT.

FIGURE 5-4: READS FROM FLASH PROGRAM MEMORY



### **EXAMPLE 5-1: READING A FLASH PROGRAM MEMORY WORD**

|           | •       |                 |                                  |
|-----------|---------|-----------------|----------------------------------|
|           | MOVLW   | CODE_ADDR_UPPER | ; Load TBLPTR with the base      |
|           | MOVWF   | TBLPTRU         | ; address of the word            |
|           | MOVLW   | CODE_ADDR_HIGH  |                                  |
|           | MOVWF   | TBLPTRH         |                                  |
|           | MOVLW   | CODE_ADDR_LOW   |                                  |
|           | MOVWF   | TBLPTRL         |                                  |
| READ WORD |         |                 |                                  |
|           | TBLRD*+ |                 | ; read into TABLAT and increment |
|           | MOVF    | TABLAT, W       | ; get data                       |
|           | MOVWF   | WORD EVEN       |                                  |
|           | TBLRD*+ |                 | ; read into TABLAT and increment |
|           | MOVFW   | TABLAT, W       | ; get data                       |
|           | MOVWF   | WORD ODD        |                                  |
|           |         | _               |                                  |

### 5.4 Erasing Flash Program Memory

The minimum erase block is 32 words or 64 bytes. Only through the use of an external programmer, or through ICSP control, can larger blocks of program memory be bulk erased. Word erase in the Flash array is not supported.

When initiating an erase sequence from the micro-controller itself, a block of 64 bytes of program memory is erased. The Most Significant 16 bits of the TBLPTR<21:6> point to the block being erased. TBLPTR<5:0> are ignored.

The EECON1 register commands the erase operation. The EEPGD bit must be set to point to the Flash program memory. The WREN bit must be set to enable write operations. The FREE bit is set to select an erase operation.

For protection, the write initiate sequence for EECON2 must be used.

A long write is necessary for erasing the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

### 5.4.1 FLASH PROGRAM MEMORY ERASE SEQUENCE

The sequence of events for erasing a block of internal program memory location is:

- Load Table Pointer register with address of row being erased.
- 2. Set the EECON1 register for the erase operation:
  - · set EEPGD bit to point to program memory;
  - clear the CFGS bit to access program memory;
  - · set WREN bit to enable writes;
  - · set FREE bit to enable the erase.
- 3. Disable interrupts.
- 4. Write 55h to EECON2.
- 5. Write AAh to EECON2.
- Set the WR bit. This will begin the row erase cycle.
- 7. The CPU will stall for duration of the erase (about 2 ms using internal timer).
- 8. Re-enable interrupts.

### **EXAMPLE 5-2: ERASING A FLASH PROGRAM MEMORY ROW**

```
MOVLW
                      CODE ADDR UPPER
                                             ; load TBLPTR with the base
              MOVWF
                                             ; address of the memory block
                      TBLPTRU
              MOVLW
                     CODE ADDR HIGH
              MOVWF TBLPTRH
              MOVLW CODE ADDR LOW
              MOVWF
                      TBLPTRL
   ERASE ROW
              BSF
                      EECON1, EEPGD
                                            ; point to Flash program memory
               BCF
                      EECON1, CFGS
                                            ; access Flash program memory
              BSF
                      EECON1, WREN
                                            ; enable write to memory
                      EECON1, FREE
              BSF
                                             ; enable Row Erase operation
              BCF
                      INTCON, GIE
                                             ; disable interrupts
              MOVLW
                      55h
               MOVWF
                      EECON2
                                             ; write 55h
Required
Sequence
              MOVLW
                     AAh
              MOVWE EECON2
                                             ; write AAh
              BSF
                      EECON1, WR
                                             ; start erase (CPU stall)
               BSF
                      INTCON, GIE
                                             ; re-enable interrupts
```

### 5.5 Writing to Flash Program Memory

The minimum programming block is 4 words or 8 bytes. Word or byte programming is not supported.

Table writes are used internally to load the holding registers needed to program the Flash memory. There are 8 holding registers used by the table writes for programming.


Since the Table Latch (TABLAT) is only a single byte, the TBLWT instruction has to be executed 8 times for each programming operation. All of the table write operations will essentially be short writes because only

the holding registers are written. At the end of updating 8 registers, the EECON1 register must be written to, to start the programming operation with a long write.

The long write is necessary for programming the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

The EEPROM on-chip timer controls the write time. The write/erase voltages are generated by an on-chip charge pump, rated to operate over the voltage range of the device for byte or word operations.

FIGURE 5-5: TABLE WRITES TO FLASH PROGRAM MEMORY



## 5.5.1 FLASH PROGRAM MEMORY WRITE SEQUENCE

The sequence of events for programming an internal program memory location should be:

- Read 64 bytes into RAM.
- Update data values in RAM as necessary.
- Load Table Pointer register with address being erased.
- 4. Do the row erase procedure.
- Load Table Pointer register with address of first byte being written.
- 6. Write the first 8 bytes into the holding registers with auto-increment.
- 7. Set the EECON1 register for the write operation:
  - set EEPGD bit to point to program memory;
  - clear the CFGS bit to access program memory;
  - · set WREN to enable byte writes.

- 8. Disable interrupts.
- 9. Write 55h to EECON2.
- 10. Write AAh to EECON2.
- 11. Set the WR bit. This will begin the write cycle.
- 12. The CPU will stall for duration of the write (about 2 ms using internal timer).
- 13. Re-enable interrupts.
- 14. Repeat steps 6-14 seven times to write 64 bytes.
- 15. Verify the memory (table read).

This procedure will require about 18 ms to update one row of 64 bytes of memory. An example of the required code is given in Example 5-3.

**Note:** Before setting the WR bit, the Table Pointer address needs to be within the intended address range of the eight bytes in the holding register.

### **EXAMPLE 5-3: WRITING TO FLASH PROGRAM MEMORY**

```
MOVLW D'64
                                             ; number of bytes in erase block
             MOVWE COUNTER
             MOVLW BUFFER_ADDR_HIGH
                                             ; point to buffer
             MOVWF FSR0H
             MOVLW BUFFER_ADDR_LOW
             MOVWF FSR0L
             MOVLW CODE ADDR UPPER
                                            ; Load TBLPTR with the base
             MOVWF TBLPTRU
                                             ; address of the memory block
              MOVLW CODE ADDR HIGH
              MOVWF
                    TBLPTRH
              MOVLW CODE ADDR LOW
             MOVWF TBLPTRL
READ BLOCK
             TBLRD*+
                                            ; read into TABLAT, and inc
                                            ; get data
             MOVF TABLAT, W
             MOVWF POSTINCO
                                            ; store data
             DECFSZ COUNTER
                                            ; done?
              BRA READ BLOCK
                                             ; repeat
MODIFY WORD
             MOVLW DATA_ADDR_HIGH
                                             ; point to buffer
             MOVWF FSR0H
             MOVLW DATA_ADDR_LOW
             MOVWF FSR0L
             MOVLW NEW DATA LOW
                                           ; update buffer word
             MOVWF POSTINCO
             MOVLW NEW_DATA_HIGH
             MOVWF INDF0
ERASE BLOCK
             MOVLW CODE ADDR UPPER
                                           ; load TBLPTR with the base
             MOVWF
                    TBLPTRU
                                             ; address of the memory block
             MOVLW CODE ADDR_HIGH
             MOVWF TBLPTRH
             MOVLW CODE ADDR LOW
              MOVWF TBLPTRL
              BSF EECON1, EEPGD
                                           ; point to Flash program memory
                                           ; access Flash program memory
             BCF EECON1, CFGS
                    EECON1, WREN
                                           ; enable write to memory
             BSF
                    EECON1, FREE
INTCON, GIE
                                            ; enable Row Erase operation
              BSF
                                             ; disable interrupts
              BCF
             MOVLW 55h
             MOVWF EECON2
Required
                                             ; write 55h
             MOVLW AAh
Sequence
              MOVWF EECON2
                                            ; write AAh
              BSF EECON1, WR ; start erase (CPU stall)
                                          ; re-enable interrupts
              BSF INTCON, GIE
              TBLRD*-
                                             ; dummy read decrement
WRITE BUFFER BACK
                                             ; number of write buffer groups of 8 bytes
             MOVLW
                    8
              MOVWF
                    COUNTER HI
              MOVLW BUFFER_ADDR_HIGH
                                             ; point to buffer
             MOVWF FSR0H
             MOVLW BUFFER ADDR LOW
              MOVWF FSR0L
PROGRAM LOOP
             MOVLW 8
                                             ; number of bytes in holding register
              MOVWF COUNTER
WRITE WORD TO HREGS
             MOVFF POSTINCO, WREG
                                             ; get low byte of buffer data
                                             ; present data to table latch
              TBLWT+*
                                             ; write data, perform a short write
                                             ; to internal TBLWT holding register.
              DECFSZ COUNTER
                                             ; loop until buffers are full
                    WRITE WORD TO HREGS
```

### **EXAMPLE 5-3: WRITING TO FLASH PROGRAM MEMORY (CONTINUED)**

```
PROGRAM MEMORY
                                           ; point to Flash program memory
              BSF
                     EECON1, EEPGD
              BCF
                     EECON1, CFGS
                                           ; access Flash program memory
              BSF
                     EECON1, WREN
                                           ; enable write to memory
              BCF
                     INTCON, GIE
                                           ; disable interrupts
              MOVLW 55h
              MOVWF
                     EECON2
   Required
                                           ; write 55h
   Sequence
              MOVLW
                     AAh
              MOVWF
                     EECON2
                                           ; write AAh
              BSF
                     EECON1, WR
                                           ; start program (CPU stall)
                                           ; re-enable interrupts
              BSF
                     INTCON, GIE
              DECFSZ COUNTER HI
                                           ; loop until done
              BRA PROGRAM LOOP
                     EECON1, WREN
              BCF
                                           ; disable write to memory
```

### 5.5.2 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

## 5.5.3 UNEXPECTED TERMINATION OF WRITE OPERATION

If a write is terminated by an unplanned event, such as loss of power or an unexpected Reset, the memory location just programmed should be verified and reprogrammed if needed. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, users can check the WRERR bit and rewrite the location.

# 5.5.4 PROTECTION AGAINST SPURIOUS WRITES

To protect against spurious writes to Flash program memory, the write initiate sequence must also be followed. See Section 24.0 "Special Features of the CPU" for more detail.

# 5.6 Flash Program Operation During Code Protection

See Section 24.0 "Special Features of the CPU" for details on code protection of Flash program memory.

TABLE 5-2: REGISTERS ASSOCIATED WITH PROGRAM FLASH MEMORY

| Name    | Bit 7   | Bit 6        | Bit 5       | Bit 4      | Bit 3       | Bit 2  | Bit 1   | Bit 0   | Value on:<br>POR, BOR | Value on<br>all other<br>Resets |
|---------|---|--------------|-------------|------------|-------------|--------|---------|---------|-----------------------|---------------------------------|
| TBLPTRU | — bit 21 <sup>(1)</sup> Program Memory Table Pointer Upper Byte (TBLPTR<20:16>) |              |             |            |             |        | 00 0000 | 00 0000 |                       |                                 |
| TBLPTRH | Program M   | lemory Table | Pointer H   | igh Byte ( | TBLPTR<1    | 5:8>)  |         |         | 0000 0000             | 0000 0000                       |
| TBLPTRL | Program Memory Table Pointer High Byte (TBLPTR<7:0>)                            |              |             |            |             |        |         |         | 0000 0000             | 0000 0000                       |
| TABLAT  | Program M   | lemory Table | Latch       |            |             |        |         |         | 0000 0000             | 0000 0000                       |
| INTCON  | GIE/GIEH  | PEIE/GIEL    | TMR0IE      | INT0IE     | RBIE        | TMR0IF | INT0IF  | RBIF    | 0000 000x             | 0000 000u                       |
| EECON2  | EEPROM (  | Control Regi | ster 2 (not | a physica  | l register) |        |         |         | _                     | _                               |
| EECON1  | EEPGD   | CFGS         | _           | FREE       | WRERR       | WREN   | WR      | RD      | xx-0 x000             | uu-0 u000                       |
| IPR2    | _   | CMIP         | _           | EEIP       | BCLIP       | LVDIP  | TMR3IP  | CCP2IP  | -1-1 1111             | -1-1 1111                       |
| PIR2    | _   | CMIF         | _           | EEIF       | BCLIF       | LVDIF  | TMR3IF  | CCP2IF  | -0-0 0000             | -0-0 0000                       |
| PIE2    | _   | CMIE         | _           | EEIE       | BCLIE       | LVDIE  | TMR3IE  | CCP2IE  | -0-0 0000             | -0-0 0000                       |

**Legend:** x = unknown, u = unchanged, r = reserved, — = unimplemented, read as '0'.

Shaded cells are not used during Flash/EEPROM access.

Note 1: Bit 21 of the TBLPTRU allows access to device configuration bits.

NOTES:

# 6.0 EXTERNAL MEMORY INTERFACE

Note: The external memory interface is not implemented on PIC18F6525/6621 (64-pin) devices.

The external memory interface is a feature of the PIC18F8525/8621 devices that allows the controller to access external memory devices (such as Flash, EPROM, SRAM, etc.) as program or data memory.

The physical implementation of the interface uses 27 pins. These pins are reserved for external address/data bus functions; they are multiplexed with I/O port pins on four ports. Three I/O ports are multiplexed with the address/data bus, while the fourth port is multiplexed with the bus control signals. The I/O port functions are enabled when the EBDIS bit in the MEMCON register is set (see Register 6-1). A list of the multiplexed pins and their functions is provided in Table 6-1.

As implemented in the PIC18F8525/8621 devices, the interface operates in a similar manner to the external memory interface introduced on PIC18C601/801 microcontrollers. The most notable difference is that the interface on PIC18F8525/8621 devices only operates in 16-bit modes. The 8-bit mode is not supported.

For a more complete discussion of the operating modes that use the external memory interface, refer to Section 4.1.1 "PIC18F6525/6621/8525/8621 Program Memory Modes".

# 6.1 Program Memory Modes and the External Memory Interface

As previously noted, PIC18F8525/8621 controllers are capable of operating in any one of four program memory modes using combinations of on-chip and external program memory. The functions of the multiplexed port pins depends on the program memory mode selected, as well as the setting of the EBDIS bit.

In **Microprocessor Mode**, the external bus is always active and the port pins have only the external bus function.

In **Microcontroller Mode**, the bus is not active and the pins have their port functions only. Writes to the MEMCOM register are not permitted.

In Microprocessor with Boot Block or Extended Microcontroller Mode, the external program memory bus shares I/O port functions on the pins. When the device is fetching or doing table read/table write operations on the external program memory space, the pins will have the external bus function. If the device is fetching and accessing internal program memory locations only, the EBDIS control bit will change the pins from external memory to I/O port functions. When EBDIS = 0, the pins function as the external bus. When EBDIS = 1, the pins function as I/O ports.

#### REGISTER 6-1: MEMCON: MEMORY CONTROL REGISTER

| R/W-0 | U-0 | R/W-0 | R/W-0 | U-0 | U-0 | R/W-0 | R/W-0 |
|-------|-----|-------|-------|-----|-----|-------|-------|
| EBDIS | _   | WAIT1 | WAIT0 | _   | _   | WM1   | WM0   |
| bit 7 |     |       |       |     |     |       | bit 0 |

bit 7 EBDIS: External Bus Disable bit

1 = External system bus disabled, all external bus drivers are mapped as I/O ports

0 = External system bus enabled and I/O ports are disabled

bit 6 Unimplemented: Read as '0'

bit 5-4 WAIT1:WAIT0: Table Reads and Writes Bus Cycle Wait Count bits

11 = Table reads and writes will wait 0 TcY

10 = Table reads and writes will wait 1 Tcy

01 = Table reads and writes will wait 2 TcY

00 = Table reads and writes will wait 3 TcY

bit 3-2 Unimplemented: Read as '0'

bit 1-0 WM1:WM0: TBLWRT Operation with 16-Bit Bus bits

1x = Word Write mode: TABLAT<0> and TABLAT<1> word output,  $\overline{WRH}$  active when TABLAT<1> written

01 = Byte Select mode: TABLAT data copied on both MSB and LSB, WRH and (UB or LB) will activate

00 = Byte Write mode: TABLAT data copied on both MSB and LSB, WRH or WRL will activate

**Note:** The MEMCON register is unimplemented and reads all '0's when the device is in Microcontroller mode.

| Legend:           |                  |                      |                    |  |
|-------------------|------------------|----------------------|--------------------|--|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | l bit, read as '0' |  |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |  |

If the device fetches or accesses external memory while EBDIS = 1, the pins will switch to external bus. If the EBDIS bit is set by a program executing from external memory, the action of setting the bit will be delayed until the program branches into the internal memory. At that time, the pins will change from external bus to I/O ports.

When the device is executing out of internal memory (EBDIS = 0) in Microprocessor with Boot Block mode or Extended Microcontroller mode, the control signals will NOT be active. They will go to a state where the AD<15:0> and A<19:16> are tri-state; the CE, OE, WRH, WRL, UB and LB signals are '1' and ALE and BAO are '0'.

TABLE 6-1: PIC18F8525/8621 EXTERNAL BUS – I/O PORT FUNCTIONS

| Name               | Port  | Bit   | Function  |  |  |  |
|--------------------|-------|-------|---|--|--|--|
| RD0/AD0            | PORTD | bit 0 | Input/Output or System Bus Address bit 0 or Data bit 0            |  |  |  |
| RD1/AD1            | PORTD | bit 1 | Input/Output or System Bus Address bit 1 or Data bit 1            |  |  |  |
| RD2/AD2            | PORTD | bit 2 | Input/Output or System Bus Address bit 2 or Data bit 2            |  |  |  |
| RD3/AD3            | PORTD | bit 3 | Input/Output or System Bus Address bit 3 or Data bit 3            |  |  |  |
| RD4/AD4            | PORTD | bit 4 | Input/Output or System Bus Address bit 4 or Data bit 4            |  |  |  |
| RD5/AD5            | PORTD | bit 5 | Input/Output or System Bus Address bit 5 or Data bit 5            |  |  |  |
| RD6/AD6            | PORTD | bit 6 | Input/Output or System Bus Address bit 6 or Data bit 6            |  |  |  |
| RD7/AD7            | PORTD | bit 7 | Input/Output or System Bus Address bit 7 or Data bit 7            |  |  |  |
| RE0/AD8            | PORTE | bit 0 | Input/Output or System Bus Address bit 8 or Data bit 8            |  |  |  |
| RE1/AD9            | PORTE | bit 1 | Input/Output or System Bus Address bit 9 or Data bit 9            |  |  |  |
| RE2/AD10           | PORTE | bit 2 | Input/Output or System Bus Address bit 10 or Data bit 10          |  |  |  |
| RE3/AD11           | PORTE | bit 3 | Input/Output or System Bus Address bit 11 or Data bit 11          |  |  |  |
| RE4/AD12           | PORTE | bit 4 | Input/Output or System Bus Address bit 12 or Data bit 12          |  |  |  |
| RE5/AD13           | PORTE | bit 5 | Input/Output or System Bus Address bit 13 or Data bit 13          |  |  |  |
| RE6/AD14           | PORTE | bit 6 | Input/Output or System Bus Address bit 14 or Data bit 14          |  |  |  |
| RE7/AD15           | PORTE | bit 7 | Input/Output or System Bus Address bit 15 or Data bit 15          |  |  |  |
| RH0/A16            | PORTH | bit 0 | Input/Output or System Bus Address bit 16                         |  |  |  |
| RH1/A17            | PORTH | bit 1 | Input/Output or System Bus Address bit 17                         |  |  |  |
| RH2/A18            | PORTH | bit 2 | Input/Output or System Bus Address bit 18                         |  |  |  |
| RH3/A19            | PORTH | bit 3 | Input/Output or System Bus Address bit 19                         |  |  |  |
| RJ0/ALE            | PORTJ | bit 0 | Input/Output or System Bus Address Latch Enable (ALE) Control pin |  |  |  |
| RJ1/OE             | PORTJ | bit 1 | Input/Output or System Bus Output Enable (OE) Control pin         |  |  |  |
| RJ2/WRL            | PORTJ | bit 2 | Input/Output or System Bus Write Low (WRL) Control pin            |  |  |  |
| RJ3/WRH            | PORTJ | bit 3 | Input/Output or System Bus Write High (WRH) Control pin           |  |  |  |
| RJ4/BA0            | PORTJ | bit 4 | Input/Output or System Bus Byte Address bit 0                     |  |  |  |
| RJ5/CE             | PORTJ | bit 5 | Input/Output or System Bus Chip Enable (CE) Control pin           |  |  |  |
| RJ6/LB PORTJ bit 6 |       | bit 6 | Input/Output or System Bus Lower Byte Enable (LB) Control pin     |  |  |  |
| RJ7/UB             | PORTJ | bit 7 | Input/Output or System Bus Upper Byte Enable (UB) Control pin     |  |  |  |

#### 6.2 16-Bit Mode

The external memory interface implemented in PIC18F8525/8621 devices operates only in 16-bit mode. The mode selection is not software configurable but is programmed via the configuration bits.

The WM1:WM0 bits in the MEMCON register determine three types of connections in 16-bit mode. They are referred to as:

- 16-bit Byte Write
- 16-bit Word Write
- · 16-bit Byte Select

These three different configurations allow the designer maximum flexibility in using 8-bit and 16-bit memory devices.

For all 16-bit modes, the Address Latch Enable (ALE) pin indicates that the address bits, A15:A0, are available on the external memory interface bus. Following the address latch, the Output Enable signal  $(\overline{OE})$  will enable both bytes of program memory at once to form <u>a</u> 16-bit instruction word. The Chip Enable signal  $(\overline{CE})$  is active at any time that the microcontroller accesses external memory, whether reading or writing; it is inactive (asserted high) whenever the device is in Sleep mode.


In Byte Select mode, JEDEC standard Flash memories will require BA0 for the byte address line and one I/O line, to select between Byte and Word mode. The other 16-bit modes do not need BA0. JEDEC standard static RAM memories will use the  $\overline{\text{UB}}$  or  $\overline{\text{LB}}$  signals for byte selection.

#### 6.2.1 16-BIT BYTE WRITE MODE

Figure 6-1 shows an example of 16-bit Byte Write mode for PIC18F8525/8621 devices. This mode is used for two separate 8-bit memories connected for 16-bit operation. This generally includes basic EPROM and Flash devices. It allows table writes to byte-wide external memories.

During a TBLWT instruction cycle, the TABLAT data is presented on the upper and lower bytes of the AD15:AD0 bus. The appropriate WRH or WRL control line is strobed on the LSb of the TBLPTR.

FIGURE 6-1: 16-BIT BYTE WRITE MODE EXAMPLE



#### 6.2.2 16-BIT WORD WRITE MODE


Figure 6-2 shows an example of 16-bit Word Write mode for PIC18F8525/8621 devices. This mode is used for word-wide memories which include some of the EPROM and Flash type memories. This mode allows opcode fetches and table reads from all forms of 16-bit memory and table writes to any type of word-wide external memories. This method makes a distinction between TBLWT cycles to even or odd addresses.

During a TBLWT cycle to an even address (TBLPTR<0> = 0), the TABLAT data is transferred to a holding latch and the external address data bus is tristated for the data portion of the bus cycle. No write signals are activated.

During a TBLWT cycle to an odd address (TBLPTR<0> = 1), the TABLAT data is presented on the upper byte of the AD15:AD0 bus. The contents of the holding latch are presented on the lower byte of the AD15:AD0 bus.

The WRH signal is strobed for each write cycle; the WRL pin is unused. The signal on the BA0 pin indicates the LSb of the TBLPTR but it is left unconnected. Instead, the UB and LB signals are active to select both bytes. The obvious limitation to this method is that the table write must be done in pairs on a specific word boundary to correctly write a word location.

#### FIGURE 6-2: 16-BIT WORD WRITE MODE EXAMPLE




#### 6.2.3 16-BIT BYTE SELECT MODE

Figure 6-3 shows an example of 16-bit Byte Select mode for PIC18F8525/8621 devices. This mode allows table write operations to word-wide external memories with byte selection capability. This generally includes both word-wide Flash and SRAM devices.

During a TBLWT cycle, the TABLAT data is presented on the upper and lower byte of the AD15:AD0 bus. The WRH signal is strobed for each write cycle; the WRL pin is not used. The BA0 or UB/LB signals are used to select the byte to be written based on the Least Significant bit of the TBLPTR register.

Flash and SRAM devices use different control signal combinations to implement Byte Select mode. JEDEC standard Flash memories require that a controller I/O port pin be connected to the memory's BYTE/WORD pin to provide the select signal. They also use the BA0 signal from the controller as a byte address. JEDEC standard static RAM memories, on the other hand, use the  $\overline{\text{UB}}$  or  $\overline{\text{LB}}$  signals to select the byte.

FIGURE 6-3: 16-BIT BYTE SELECT MODE EXAMPLE



#### 6.2.4 16-BIT MODE TIMING

The presentation of control signals on the external memory bus is different for the various operating modes. Typical signal timing diagrams are shown in Figure 6-4 through Figure 6-6.

FIGURE 6-4: EXTERNAL MEMORY BUS TIMING FOR TBLRD (MICROPROCESSOR MODE)






FIGURE 6-5: EXTERNAL MEMORY BUS TIMING FOR TBLRD (EXTENDED MICROCONTROLLER MODE)





NOTES:

#### 7.0 DATA EEPROM MEMORY

The data EEPROM is readable and writable during normal operation over the entire VDD range. The data memory is not directly mapped in the register file space. Instead, it is indirectly addressed through the Special Function Registers (SFR).

There are five SFRs used to read and write the program and data EEPROM memory. These registers are:

- EECON1
- EECON2
- EEDATA
- EEADRH
- EEADR

The EEPROM data memory allows byte read and write. When interfacing to the data memory block, EEDATA holds the 8-bit data for read/write. EEADR and EEADRH hold the address of the EEPROM location being accessed. These devices have 1024 bytes of data EEPROM with an address range from 00h to 3FFh.

The EEPROM data memory is rated for high erase/ write cycles. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an on-chip timer. The write time will vary with voltage and temperature, as well as from chip-to-chip. Please refer to parameter D122 (Section 27.0 "Electrical Characteristics") for exact limits.

#### 7.1 EEADR and EEADRH

The address register pair can address up to a maximum of 1024 bytes of data EEPROM. The two Most Significant bits of the address are stored in EEADRH, while the remaining eight Least Significant bits are stored in EEADR. The six Most Significant bits of EEADRH are unused and are read as '0'.

#### 7.2 EECON1 and EECON2 Registers

EECON1 is the control register for EEPROM memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the EEPROM write sequence.

Control bits RD and WR initiate read and write operations, respectively. These bits cannot be cleared, only set in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the WR bit in software prevents the accidental or premature termination of a write operation.

**Note:** During normal operation, the WRERR bit is read as '1'. This can indicate that a write operation was prematurely terminated by a Reset, or a write operation was attempted improperly.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to the Reset condition forcing the contents of the registers to zero.

**Note:** Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be cleared in software.

#### REGISTER 7-1: EECON1 REGISTER (ADDRESS FA6h)

| R/W-x | R/W-x | U-0 | R/W-0 | R/W-x | R/W-0 | R/S-0 | R/S-0 |
|-------|-------|-----|-------|-------|-------|-------|-------|
| EEPGD | CFGS  | _   | FREE  | WRERR | WREN  | WR    | RD    |
| bit 7 |       |     |       |       |       |       | bit 0 |

bit 7 **EEPGD:** Flash Program/Data EEPROM Memory Select bit

1 = Access Flash program memory

0 = Access data EEPROM memory

bit 6 CFGS: Flash Program/Data EEPROM or Configuration Select bit

1 = Access Configuration or Calibration registers

0 = Access Flash program or data EEPROM memory

bit 5 **Unimplemented:** Read as '0'

bit 4 FREE: Flash Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next WR command (cleared by completion of erase operation)

0 = Perform write only

bit 3 WRERR: Flash Program/Data EEPROM Error Flag bit

1 = A write operation is prematurely terminated (any MCLR or any WDT Reset during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD or FREE bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: Flash Program/Data EEPROM Write Enable bit

1 = Allows write cycles to Flash program/data EEPROM

0 = Inhibits write cycles to Flash program/data EEPROM

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle to the EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read (Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software. RD bit cannot be set when EEPGD = 1.)

0 = Does not initiate an EEPROM read

| Legend:           |                  |   |   |  |  |  |
|-------------------|------------------|---|---|--|--|--|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0'        |   |  |  |  |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared $x = Bit$ is unknown | 1 |  |  |  |

# 7.3 Reading the Data EEPROM Memory

To read a data memory location, the user must write the address to the EEADRH:EEADR register pair, clear the EEPGD control bit (EECON1<7>), clear the CFGS

control bit (EECON1<6>) and then set the RD control bit (EECON1<0>). The data is available for the very next instruction cycle; therefore, the EEDATA register can be read by the next instruction. EEDATA will hold this value until another read operation or until it is written to by the user (during a write operation).

#### **EXAMPLE 7-1:** DATA EEPROM READ

```
MOVLW DATA EE ADDRH
MOVWF EEADRH
                             ; Upper bits of Data Memory Address to read
MOVLW DATA EE ADDR
                            ; Lower bits of Data Memory Address to read
MOVWF EEADR
BCF
     EECON1, EEPGD
                            ; Point to DATA memory
BCF
      EECON1, CFGS
                             ; Access EEPROM
      EECON1, RD
                             ; EEPROM Read
BSF
MOVF EEDATA, W
                             ; W = EEDATA
```

# 7.4 Writing to the Data EEPROM Memory

To write an EEPROM data location, the address must first be written to the EEADRH:EEADR register pair and the data written to the EEDATA register. Then the sequence in Example 7-2 must be followed to initiate the write cycle.

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write AAh to EECON2, then set WR bit) for each byte. It is strongly recommended that interrupts be disabled during this code segment.

Additionally, the WREN bit in EECON1 must be set to enable writes. This mechanism prevents accidental writes to data EEPROM due to unexpected code

execution (i.e., runaway programs). The WREN bit should be kept clear at all times except when updating the EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, EECON1, EEADRH, EEADR and EEDATA cannot be modified. The WR bit will be inhibited from being set unless the WREN bit is set. Both WR and WREN cannot be set with the same instruction.

At the completion of the write cycle, the WR bit is cleared in hardware and the EEPROM Write Complete Interrupt Flag bit (EEIF) is set. The user may either enable this interrupt or poll this bit. EEIF must be cleared by software.

#### **EXAMPLE 7-2: DATA EEPROM WRITE**

```
MOVLW
                 DATA EE ADDRH
          MOVWF
                 EEADRH
                                    ; Upper bits of Data Memory Address to write
          MOVLW DATA EE ADDR
          MOVWF EEADR
                                   ; Lower bits of Data Memory Address to write
          MOVLW DATA_EE_DATA
          MOVWF EEDATA
                                   ; Data Memory Value to write
          BCF
                 EECON1, EEPGD
                                   ; Point to DATA memory
          BCF
                 EECON1, CFGS
                                   ; Access EEPROM
          BSF
                  EECON1, WREN
                                    ; Enable writes
                 INTCON, GIE
          BCF
                                    ; Disable Interrupts
          MOVLW 0x55
Required
          MOVWF EECON2
                                   ; Write 55h
Sequence
          MOVLW 0xAA
                                   ; Write AAh
          MOVWF EECON2
          BSF EECON1, WR
                                   ; Set WR bit to begin write
          BSF
                 INTCON, GIE
                                   ; Enable Interrupts
                                    ; User code execution
          BCF
                  EECON1, WREN
                                    ; Disable writes on write complete (EEIF set)
```

#### 7.5 Write Verify

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

#### 7.6 Protection Against Spurious Write

There are conditions when the user may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, the WREN bit is cleared. Also, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together help prevent an accidental write during brown-out, power glitch or software malfunction.

#### 7.7 Operation During Code-Protect

Data EEPROM memory has its own code-protect mechanism. External read and write operations are disabled if either of these mechanisms are enabled. Refer to **Section 24.0** "**Special Features of the CPU**", for additional information.

#### 7.8 Using the Data EEPROM

The data EEPROM is a high endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specification D124. If this is not the case, an array refresh must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory.

A simple data EEPROM refresh routine is shown in Example 7-3.

#### **EXAMPLE 7-3: DATA EEPROM REFRESH ROUTINE**

```
CLRF
              EEADR
                                    ; Start at address 0
       CLRF
              EEADRH
                                   ; Set for memory
       BCF
              EECON1, CFGS
       BCF
              EECON1, EEPGD
                                   ; Set for Data EEPROM
              INTCON, GIE
       BCF
                                   ; Disable interrupts
                                   ; Enable writes
       BSF
              EECON1, WREN
Loop
                                    ; Loop to refresh array
       BSF
              EECON1, RD
                                    ; Read current address
       MOVLW
              55h
              EECON2
                                    ; Write 55h
       MOVWF
       MOVLW
             AAh
       MOVWF
             EECON2
                                   ; Write AAh
       BSF
              EECON1, WR
                                   ; Set WR bit to begin write
       BTFSC EECON1, WR
                                   ; Wait for write to complete
              $-2
       BRA
       INCFSZ EEADR, F
                                   ; Increment address
       BRA
              Loop
                                    ; Not zero, do it again
       INCFSZ EEADRH, F
                                    ; Increment the high address
       BRA
              Loop
                                    ; Not zero, do it again
       BCF
              EECON1, WREN
                                    ; Disable writes
              INTCON, GIE
                                    ; Enable interrupts
       BSF
```

#### TABLE 7-1: REGISTERS ASSOCIATED WITH DATA EEPROM MEMORY

| Name   | Bit 7                           | Bit 6        | Bit 5      | Bit 4      | Bit 3         | Bit 2  | Bit 1  | Bit 0  | Value on:<br>POR, BOR | Value on<br>all other<br>Resets |
|--------|---------------------------------|--------------|------------|------------|---------------|--------|--------|--------|-----------------------|---------------------------------|
| INTCON | GIE/GIEH                        | PEIE/GIEL    | TMR0IE     | INT0IE     | RBIE          | TMR0IF | INT0IF | RBIF   | 0000 000x             | 0000 000u                       |
| EEADRH | H — — — — EE Addr Register High |              |            |            |               |        |        | 00     | 00                    |                                 |
| EEADR  | Data EEPR                       | OM Address   | Register   |            |               |        |        |        | 0000 0000             | 0000 0000                       |
| EEDATA | Data EEPR                       | OM Data Re   | gister     |            |               |        |        |        | 0000 0000             | 0000 0000                       |
| EECON2 | Data EEPR                       | OM Control F | Register 2 | (not a phy | sical registe | er)    |        |        | _                     | _                               |
| EECON1 | EEPGD                           | CFGS         | _          | FREE       | WRERR         | WREN   | WR     | RD     | xx-0 x000             | uu-0 u000                       |
| IPR2   | _                               | CMIP         | _          | EEIP       | BCLIP         | LVDIP  | TMR3IP | CCP2IP | -1-1 1111             | -1-1 1111                       |
| PIR2   | _                               | CMIF         | _          | EEIF       | BCLIF         | LVDIF  | TMR3IF | CCP2IF | -0-0 0000             | 0 0000                          |
| PIE2   | _                               | CMIE         | _          | EEIE       | BCLIE         | LVDIE  | TMR3IE | CCP2IE | -0-0 0000             | 0 0000                          |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used during Flash/EEPROM access.

NOTES:

#### 8.0 8 x 8 HARDWARE MULTIPLIER

#### 8.1 Introduction

An 8 x 8 hardware multiplier is included in the ALU of the PIC18F6525/6621/8525/8621 devices. By making the multiply a hardware operation, it completes in a single instruction cycle. This is an unsigned multiply that gives a 16-bit result. The result is stored in the 16-bit product register pair (PRODH:PRODL). The multiplier does not affect any flags in the ALUSTA register.

Making the 8 x 8 multiplier execute in a single cycle gives the following advantages:

- Higher computational throughput
- Reduces code size requirements for multiply algorithms

The performance increase allows the device to be used in applications previously reserved for Digital Signal Processors.

Table 8-1 shows a performance comparison between Enhanced devices using the single-cycle hardware multiply and performing the same function without the hardware multiply.

#### 8.2 Operation

Example 8-1 shows the sequence to do an 8 x 8 unsigned multiply. Only one instruction is required when one argument of the multiply is already loaded in the WREG register.

Example 8-2 shows the sequence to do an 8  $\times$  8 signed multiply. To account for the signed bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

# EXAMPLE 8-1: 8 x 8 UNSIGNED MULTIPLY ROUTINE

| ĺ | MOVF  | ARG1, | W | ; |      |     |        |    |  |
|---|-------|-------|---|---|------|-----|--------|----|--|
|   | MULWF | ARG2  |   | ; | ARG1 | *   | ARG2   | -> |  |
|   |       |       |   | ; | PRO  | DDI | H:PROI | DL |  |

# EXAMPLE 8-2: 8 x 8 SIGNED MULTIPLY ROUTINE

| MOVF  | ARG1, W  | ;                |
|-------|----------|------------------|
| MULWF | ARG2     | ; ARG1 * ARG2 -> |
|       |          | ; PRODH:PRODL    |
| BTFSC | ARG2, SB | ; Test Sign Bit  |
| SUBWF | PRODH, F | ; PRODH = PRODH  |
|       |          | ; - ARG1         |
| MOVF  | ARG2, W  | ;                |
| BTFSC | ARG1, SB | ; Test Sign Bit  |
| SUBWF | PRODH, F | ; PRODH = PRODH  |
|       |          | ; - ARG2         |

#### TABLE 8-1: PERFORMANCE COMPARISON

|                  | Program Cycles  Routing Multiply Method Memory |                   | Cvcles | Time     |          |         |  |  |
|------------------|--|-------------------|--------|----------|----------|---------|--|--|
| Routine          | Multiply Method                                | Memory<br>(Words) | (Max)  | @ 40 MHz | @ 10 MHz | @ 4 MHz |  |  |
| 0 v 0 uppigned   | Without hardware multiply                      | 13                | 69     | 6.9 μs   | 27.6 μs  | 69 μs   |  |  |
| 8 x 8 unsigned   | Hardware multiply                              | 1                 | 1      | 100 ns   | 400 ns   | 1 μs    |  |  |
| 0 v 0 signed     | Without hardware multiply                      | 33                | 91     | 9.1 μs   | 36.4 μs  | 91 μs   |  |  |
| 8 x 8 signed     | Hardware multiply                              | 6                 | 6      | 600 ns   | 2.4 μs   | 6 μs    |  |  |
| 16 x 16 unsigned | Without hardware multiply                      | 21                | 242    | 24.2 μs  | 96.8 μs  | 242 μs  |  |  |
| To x To unsigned | Hardware multiply                              | 24                | 24     | 2.4 μs   | 9.6 μs   | 24 μs   |  |  |
| 16 v 16 signed   | Without hardware multiply                      | 52                | 254    | 25.4 μs  | 102.6 μs | 254 μs  |  |  |
| 16 x 16 signed   | Hardware multiply                              | 36                | 36     | 3.6 µs   | 14.4 μs  | 36 μs   |  |  |

Example 8-3 shows the sequence to do a 16 x 16 unsigned multiply. Equation 8-1 shows the algorithm that is used. The 32-bit result is stored in four registers, RES3:RES0.

# EQUATION 8-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0 = ARG1H:ARG1L \bullet ARG2H:ARG2L

= (ARG1H \bullet ARG2H \bullet 2<sup>16</sup>) +

(ARG1H \bullet ARG2L \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2H \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2L)
```

# EXAMPLE 8-3: 16 x 16 UNSIGNED MULTIPLY ROUTINE

```
MOVE
       ARG1L, W
                    ; ARG1L * ARG2L ->
MIIIWE
       ARG2T
                    ; PRODH: PRODL
MOVFF
       PRODH, RES1 ;
MOVFF
       PRODL, RESO ;
MOVF
       ARG1H. W
MULWF
       ARG2H
                   ; ARG1H * ARG2H ->
                   ; PRODH: PRODL
MOVFF
       PRODH, RES3
      PRODL, RES2 ;
MOVFF
MOVF
       ARG1L,W
      ARG2H
                  ; ARG1L * ARG2H ->
MULWF
                   ; PRODH: PRODL
MOVF
       PRODL, W
                  ; Add cross
      RES1, F
ADDWF
                  ; products
MOVF
       PRODH, W
ADDWFC RES2, F
CLRF
       WREG
ADDWFC RES3, F
MOVF
       ARG1H, W
                  ; ARG1H * ARG2L ->
MULWF ARG2L
                   ; PRODH: PRODL
       PRODL, W
MOVF
                  ; Add cross
ADDWF
      RES1, F
       PRODH, W
MOVF
                   ; products
ADDWFC RES2, F
CLRF
       WREG
ADDWFC RES3, F
```

Example 8-4 shows the sequence to do a 16 x 16 signed multiply. Equation 8-2 shows the algorithm used. The 32-bit result is stored in four registers, RES3:RES0. To account for the signed bits of the arguments, each argument pairs' Most Significant bit (MSb) is tested and the appropriate subtractions are done.

# EQUATION 8-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0

= ARG1H:ARG1L • ARG2H:ARG2L

= (ARG1H • ARG2H • 2<sup>16</sup>) +
(ARG1H • ARG2L • 2<sup>8</sup>) +
(ARG1L • ARG2H • 2<sup>8</sup>) +
(ARG1L • ARG2L) +
(-1 • ARG2H<7> • ARG1H:ARG1L • 2<sup>16</sup>) +
(-1 • ARG1H<7> • ARG2H:ARG2L • 2<sup>16</sup>)
```

# EXAMPLE 8-4: 16 x 16 SIGNED MULTIPLY ROUTINE

```
ARG1L, W
   MOVF
                       ; ARG1L * ARG2L ->
   MULWF
          ARG2L
                       ; PRODH: PRODL
          PRODH, RES1
   MOVFF
   MOVFF
          PRODL, RESO
   MOVF
          ARG1H, W
   MULWF
          ARG2H
                       ; ARG1H * ARG2H ->
                       ; PRODH: PRODL
   MOVFF
          PRODH, RES3
   MOVFF
          PRODL, RES2
   MOVF
          ARG1L, W
   MULWF
          ARG2H
                       ; ARG1L * ARG2H ->
                       ; PRODH: PRODL
          PRODL, W
   MOVE
                       ; Add cross
          RES1, F
   ADDWF
   MOVF
          PRODH, W
                       ; products
   ADDWFC RES2, F
   CLRF
          WREG
   ADDWFC RES3, F
   MOVF
          ARG1H, W
   MULWF
          ARG2L
                       ; ARG1H * ARG2L ->
                       ; PRODH:PRODL
          PRODL, W
   MOVF
   ADDWF
          RES1, F
                       ; Add cross
          PRODH, W
   MOVF
                       ; products
   ADDWFC RES2, F
   CLRF
          WREG
   ADDWFC RES3, F
   BTFSS
          ARG2H, 7
                       ; ARG2H:ARG2L neg?
          SIGN ARG1 ; no, check ARG1
   BRA
   MOVF
          ARG1L, W
   SUBWF
          RES2
   MOVF
          ARG1H, W
   SUBWFB RES3
SIGN_ARG1
          ARG1H, 7
                       ; ARG1H:ARG1L neq?
   BTFSS
   BRA
          CONT CODE
                       ; no, done
   MOVF
          ARG2L, W ;
   SUBWF
          RES2
   MOVF
          ARG2H, W
   SUBWFB RES3
CONT CODE
    :
```

#### 9.0 INTERRUPTS

The PIC18F6525/6621/8525/8621 devices have multiple interrupt sources and an interrupt priority feature that allows each interrupt source to be assigned a high or a low priority level. The high priority interrupt vector is at 000008h, while the low priority interrupt vector is at 000018h. High priority interrupt events will override any low priority interrupts that may be in progress.

There are thirteen registers which are used to control interrupt operation. They are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2, PIR3
- PIE1, PIE2, PIE3
- IPR1, IPR2, IPR3

It is recommended that the Microchip header files supplied with MPLAB® IDE be used for the symbolic bit names in these registers. This allows the assembler/compiler to automatically take care of the placement of these bits within the specified register.

Each interrupt source has three bits to control its operation. The functions of these bits are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- · Priority bit to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON<7>). When interrupt priority is enabled, there are two bits which enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts that have the priority bit set. Setting the GIEL bit (INTCON<6>) enables all interrupts that have the priority bit cleared. When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 000008h or 000018h, depending on the priority level. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PICmicro® mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. INTCON<6> is the PEIE bit which enables/disables all peripheral interrupt sources. INTCON<7> is the GIE bit which enables/disables all interrupt sources. All interrupts branch to address 000008h in Compatibility mode.


When an interrupt is responded to, the global interrupt enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High priority interrupt sources can interrupt a low priority interrupt.

The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (000008h or 000018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.

The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used) which re-enables interrupts.

For external interrupt events, such as the INT pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set regardless of the status of their corresponding enable bit or the GIE bit.

FIGURE 9-1: INTERRUPT LOGIC



#### 9.1 INTCON Registers

The INTCON registers are readable and writable registers which contain various enable, priority and flag bits.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### REGISTER 9-1: INTCON: INTERRUPT CONTROL REGISTER

| R/W-0    | R/W-0     | R/W-0  | R/W-0  | R/W-0 | R/W-0  | R/W-0  | R/W-x |
|----------|-----------|--------|--------|-------|--------|--------|-------|
| GIE/GIEH | PEIE/GIEL | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF  |
| bit 7    |           |        |        |       |        |        | bit 0 |

Note:

bit 7 GIE/GIEH: Global Interrupt Enable bit

When IPEN (RCON<7>) = 0:

- 1 = Enables all unmasked interrupts
- 0 = Disables all interrupts

When IPEN (RCON<7>) = 1:

- 1 = Enables all high priority interrupts
- 0 = Disables all interrupts
- bit 6 PEIE/GIEL: Peripheral Interrupt Enable bit

When IPEN (RCON<7>) = 0:

- 1 = Enables all unmasked peripheral interrupts
- 0 = Disables all peripheral interrupts

When IPEN (RCON<7>) = 1:

- 1 = Enables all low priority peripheral interrupts
- 0 = Disables all low priority peripheral interrupts
- bit 5 TMR0IE: TMR0 Overflow Interrupt Enable bit
  - 1 = Enables the TMR0 overflow interrupt
  - 0 = Disables the TMR0 overflow interrupt
- bit 4 INT0IE: INT0 External Interrupt Enable bit
  - 1 = Enables the INT0 external interrupt
  - 0 = Disables the INT0 external interrupt
- bit 3 RBIE: RB Port Change Interrupt Enable bit
  - 1 = Enables the RB port change interrupt
  - 0 = Disables the RB port change interrupt
- bit 2 TMR0IF: TMR0 Overflow Interrupt Flag bit
  - 1 = TMR0 register has overflowed (must be cleared in software)
  - 0 = TMR0 register did not overflow
- bit 1 INT0IF: INT0 External Interrupt Flag bit
  - 1 = The INT0 external interrupt occurred (must be cleared in software)
  - 0 = The INT0 external interrupt did not occur
- bit 0 RBIF: RB Port Change Interrupt Flag bit
  - 1 = At least one of the RB7:RB4 pins changed state (must be cleared in software)
  - 0 = None of the RB7:RB4 pins have changed state

**Note:** A mismatch condition will continue to set this bit. Reading PORTB will end the mismatch condition and allow the bit to be cleared.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | l bit, read as '0' |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

#### REGISTER 9-2: INTCON2: INTERRUPT CONTROL REGISTER 2

| R/W-1 | R/W-1   | R/W-1   | R/W-1   | R/W-1   | R/W-1  | R/W-1  | R/W-1 |
|-------|---------|---------|---------|---------|--------|--------|-------|
| RBPU  | INTEDG0 | INTEDG1 | INTEDG2 | INTEDG3 | TMR0IP | INT3IP | RBIP  |
| bit 7 |         |         |         |         |        |        | bit 0 |

bit 7 RBPU: PORTB Pull-up Enable bit

1 = All PORTB pull-ups are disabled

0 = PORTB pull-ups are enabled by individual port latch values

bit 6 INTEDG0: External Interrupt 0 Edge Select bit

1 = Interrupt on rising edge

0 = Interrupt on falling edge

bit 5 INTEDG1: External Interrupt 1 Edge Select bit

1 = Interrupt on rising edge0 = Interrupt on falling edge

bit 4 INTEDG2: External Interrupt 2 Edge Select bit

1 = Interrupt on rising edge0 = Interrupt on falling edge

bit 3 INTEDG3: External Interrupt 3 Edge Select bit

1 = Interrupt on rising edge0 = Interrupt on falling edge

bit 2 TMR0IP: TMR0 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

in a later later to the

bit 1 INT3IP: INT3 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 0 RBIP: RB Port Change Interrupt Priority bit

1 = High priority0 = Low priority

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

**Note:** Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### **REGISTER 9-3:** INTCON3: INTERRUPT CONTROL REGISTER 3

| R/W-1  | R/W-1  | R/W-0  | R/W-0  | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|--------|--------|--------|--------|--------|--------|--------|--------|
| INT2IP | INT1IP | INT3IE | INT2IE | INT1IE | INT3IF | INT2IF | INT1IF |

bit 7 bit 0

bit 7 INT2IP: INT2 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 INT1IP: INT1 External Interrupt Priority bit

1 = High priority

0 = Low priority

INT3IE: INT3 External Interrupt Enable bit bit 5

1 = Enables the INT3 external interrupt

0 = Disables the INT3 external interrupt

bit 4 INT2IE: INT2 External Interrupt Enable bit

> 1 = Enables the INT2 external interrupt 0 = Disables the INT2 external interrupt

bit 3

**INT1IE:** INT1 External Interrupt Enable bit

1 = Enables the INT1 external interrupt

0 = Disables the INT1 external interrupt INT3IF: INT3 External Interrupt Flag bit

1 = The INT3 external interrupt occurred (must be cleared in software)

0 = The INT3 external interrupt did not occur

bit 1 INT2IF: INT2 External Interrupt Flag bit

1 = The INT2 external interrupt occurred (must be cleared in software)

0 = The INT2 external interrupt did not occur

bit 0 INT1IF: INT1 External Interrupt Flag bit

1 = The INT1 external interrupt occurred (must be cleared in software)

0 = The INT1 external interrupt did not occur

Legend:

bit 2

R = Readable bit U = Unimplemented bit, read as '0' W = Writable bit -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### 9.2 PIR Registers

The PIR registers contain the individual flag bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Request Flag registers (PIR1, PIR2 and PIR3).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Interrupt Enable bit, GIE (INTCON<7>).
  - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt and after servicing that interrupt.

#### REGISTER 9-4: PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1

| R/W-0                | R/W-0 | R-0   | R-0   | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|----------------------|-------|-------|-------|-------|--------|--------|--------|
| PSPIF <sup>(1)</sup> | ADIF  | RC1IF | TX1IF | SSPIF | CCP1IF | TMR2IF | TMR1IF |
| bit 7                |       |       |       |       |        |        | bit 0  |

- bit 7 **PSPIF:** Parallel Slave Port Read/Write Interrupt Flag bit<sup>(1)</sup>
  - 1 = A read or a write operation has taken place (must be cleared in software)
  - 0 = No read or write has occurred
    - Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.
- bit 6 ADIF: A/D Converter Interrupt Flag bit
  - 1 = An A/D conversion completed (must be cleared in software)
  - 0 = The A/D conversion is not complete
- bit 5 RC1IF: USART1 Receive Interrupt Flag bit
  - 1 = The USART1 receive buffer, RCREGx, is full (cleared when RCREGx is read)
  - 0 = The USART1 receive buffer is empty
- bit 4 TX1IF: USART1 Transmit Interrupt Flag bit
  - 1 = The USART1 transmit buffer, TXREGx, is empty (cleared when TXREGx is written)
  - 0 = The USART1 transmit buffer is full
- bit 3 SSPIF: Master Synchronous Serial Port Interrupt Flag bit
  - 1 = The transmission/reception is complete (must be cleared in software)
  - 0 = Waiting to transmit/receive
- bit 2 **CCP1IF**: ECCP1 Interrupt Flag bit

#### Capture mode:

- 1 = A TMR1 register capture occurred (must be cleared in software)
- 0 = No TMR1 register capture occurred

#### Compare mode:

- 1 = A TMR1 register compare match occurred (must be cleared in software)
- 0 = No TMR1 register compare match occurred

#### PWM mode:

Unused in this mode.

- bit 1 TMR2IF: TMR2 to PR2 Match Interrupt Flag bit
  - 1 = TMR2 to PR2 match occurred (must be cleared in software)
  - 0 = No TMR2 to PR2 match occurred
- bit 0 TMR1IF: TMR1 Overflow Interrupt Flag bit
  - 1 = TMR1 register overflowed (must be cleared in software)
  - 0 = TMR1 register did not overflow

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### **REGISTER 9-5:** PIR2: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 2

| U-0   | R/W-0 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  |
|-------|-------|-----|-------|-------|-------|--------|--------|
| _     | CMIF  | _   | EEIF  | BCLIF | LVDIF | TMR3IF | CCP2IF |
| bit 7 |       |     |       |       |       |        | bit 0  |

bit 0

bit 7 Unimplemented: Read as '0'

bit 6 CMIF: Comparator Interrupt Flag bit

1 = The comparator input has changed (must be cleared in software)

0 = The comparator input has not changed

bit 5 Unimplemented: Read as '0'

bit 4 EEIF: Data EEPROM/Flash Write Operation Interrupt Flag bit

1 = The write operation is complete (must be cleared in software)

0 = The write operation is not complete, or has not been started

bit 3 **BCLIF**: Bus Collision Interrupt Flag bit

1 = A bus collision occurred while the MSSP module (configured in  $I^2C$  Master mode)

was transmitting (must be cleared in software)

0 = No bus collision occurred

bit 2 LVDIF: Low-Voltage Detect Interrupt Flag bit

1 = A low voltage condition occurred (must be cleared in software)

0 = The device voltage is above the Low-Voltage Detect trip point

bit 1 TMR3IF: TMR3 Overflow Interrupt Flag bit

1 = TMR3 register overflowed (must be cleared in software)

0 = TMR3 register did not overflow

bit 0 CCP2IF: ECCP2 Interrupt Flag bit

Capture mode:

1 = A TMR1 or TMR3 register capture occurred (must be cleared in software)

0 = No TMR1 or TMR3 register capture occurred

1 = A TMR1 or TMR3 register compare match occurred (must be cleared in software)

0 = No TMR1 or TMR3 register compare match occurred

PWM mode:

Unused in this mode.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

'1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown

#### **REGISTER 9-6:** PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3

| U-0   | U-0 | R-0   | R-0   | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-----|-------|-------|--------|--------|--------|--------|
| _     | _   | RC2IF | TX2IF | TMR4IF | CCP5IF | CCP4IF | CCP3IF |
| bit 7 |     |       |       |        |        |        | bit 0  |

bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 RC2IF: USART2 Receive Interrupt Flag bit

1 = The USART2 receive buffer, RCREGx, is full (cleared when RCREGx is read)

0 = The USART2 receive buffer is empty

bit 4 TX2IF: USART2 Transmit Interrupt Flag bit

1 = The USART2 transmit buffer, TXREGx, is empty (cleared when TXREGx is written)

0 = The USART2 transmit buffer is full

bit 3 TMR4IF: TMR3 Overflow Interrupt Flag bit

1 = TMR4 register overflowed (must be cleared in software)

0 = TMR4 register did not overflow

bit 2-0 CCPxIF: CCPx Interrupt Flag bit (ECCP3, CCP4 and CCP5)

Capture mode:

1 = A TMR1 or TMR3 register capture occurred (must be cleared in software)

0 = No TMR1 or TMR3 register capture occurred

Compare mode:

1 = A TMR1 or TMR3 register compare match occurred (must be cleared in software)

0 = No TMR1 or TMR3 register compare match occurred

PWM mode:

Unused in this mode.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 9.3 PIE Registers

The PIE registers contain the individual enable bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Enable registers (PIE1, PIE2 and PIE3). When the IPEN bit (RCON<7>) is '0', the PEIE bit must be set to enable any of these peripheral interrupts.

#### REGISTER 9-7: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

| R/W-0                | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|----------------------|-------|-------|-------|-------|--------|--------|--------|
| PSPIE <sup>(1)</sup> | ADIE  | RC1IE | TX1IE | SSPIE | CCP1IE | TMR2IE | TMR1IE |
| bit 7                |       |       |       |       |        |        | bit 0  |

bit 7 **PSPIE**: Parallel Slave Port Read/Write Interrupt Enable bit<sup>(1)</sup>

1 = Enables the PSP read/write interrupt

0 = Disables the PSP read/write interrupt

**Note:** Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

bit 6 ADIE: A/D Converter Interrupt Enable bit

1 = Enables the A/D interrupt

0 = Disables the A/D interrupt

bit 5 RC1IE: USART1 Receive Interrupt Enable bit

1 = Enables the USART1 receive interrupt

0 = Disables the USART1 receive interrupt

bit 4 TX1IE: USART1 Transmit Interrupt Enable bit

1 = Enables the USART1 transmit interrupt

0 = Disables the USART1 transmit interrupt

bit 3 SSPIE: Master Synchronous Serial Port Interrupt Enable bit

1 = Enables the MSSP interrupt

0 = Disables the MSSP interrupt

bit 2 **CCP1IE**: ECCP1 Interrupt Enable bit

1 = Enables the ECCP1 interrupt

0 = Disables the ECCP1 interrupt

bit 1 TMR2IE: TMR2 to PR2 Match Interrupt Enable bit

1 = Enables the TMR2 to PR2 match interrupt

0 = Disables the TMR2 to PR2 match interrupt

bit 0 TMR1IE: TMR1 Overflow Interrupt Enable bit

1 = Enables the TMR1 overflow interrupt

0 = Disables the TMR1 overflow interrupt

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 9-8: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

| U-0   | R/W-0 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  |
|-------|-------|-----|-------|-------|-------|--------|--------|
| _     | CMIE  | _   | EEIE  | BCLIE | LVDIE | TMR3IE | CCP2IE |
| bit 7 |       |     |       |       |       |        | bit 0  |

bit 7 **Unimplemented:** Read as '0'

bit 6 CMIE: Comparator Interrupt Enable bit

1 = Enables the comparator interrupt

0 = Disables the comparator interrupt

bit 5 **Unimplemented:** Read as '0'

bit 4 **EEIE**: Data EEPROM/Flash Write Operation Interrupt Enable bit

1 = Enables the write operation interrupt

0 = Disables the write operation interrupt

bit 3 BCLIE: Bus Collision Interrupt Enable bit

1 = Enables the bus collision interrupt

0 = Disables the bus collision interrupt

bit 2 LVDIE: Low-Voltage Detect Interrupt Enable bit

1 = Enables the Low-Voltage Detect interrupt

0 = Disables the Low-Voltage Detect interrupt

bit 1 TMR3IE: TMR3 Overflow Interrupt Enable bit

1 = Enables the TMR3 overflow interrupt

0 = Disables the TMR3 overflow interrupt

bit 0 CCP2IE: ECCP2 Interrupt Enable bit

1 = Enables the ECCP2 interrupt

0 = Disables the ECCP2 interrupt

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### **REGISTER 9-9:** PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-----|-------|-------|--------|--------|--------|--------|
| _     | _   | RC2IE | TX2IE | TMR4IE | CCP5IE | CCP4IE | CCP3IE |
| bit 7 |     |       |       |        |        |        | bit 0  |

bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 RC2IE: USART2 Receive Interrupt Enable bit

> 1 = Enables the USART2 receive interrupt 0 = Disables the USART2 receive interrupt

bit 4 TX2IE: USART2 Transmit Interrupt Enable bit

1 = Enables the USART2 transmit interrupt

0 = Disables the USART2 transmit interrupt

bit 3 TMR4IE: TMR4 to PR4 Match Interrupt Enable bit

> 1 = Enables the TMR4 to PR4 match interrupt 0 = Disables the TMR4 to PR4 match interrupt

bit 2-0 CCPxIE: CCPx Interrupt Enable bit (ECCP3, CCP4 and CCP5)

1 = Enables the CCPx interrupt

0 = Disables the CCPx interrupt

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 9.4 IPR Registers

The IPR registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Priority registers (IPR1, IPR2 and IPR3). The operation of the priority bits requires that the Interrupt Priority Enable (IPEN) bit be set.

#### REGISTER 9-10: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1

| R/W-1                | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1  | R/W-1  | R/W-1  |  |
|----------------------|-------|-------|-------|-------|--------|--------|--------|--|
| PSPIP <sup>(1)</sup> | ADIP  | RC1IP | TX1IP | SSPIP | CCP1IP | TMR2IP | TMR1IP |  |
| bit 7                |       |       |       |       |        |        | bit 0  |  |

bit 7 **PSPIP:** Parallel Slave Port Read/Write Interrupt Priority bit<sup>(1)</sup>

1 = High priority

0 = Low priority

**Note:** Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

bit 6 ADIP: A/D Converter Interrupt Priority bit

1 = High priority0 = Low priority

bit 5 RC1IP: USART1 Receive Interrupt Priority bit

1 = High priority0 = Low priority

bit 4 TX1IP: USART1 Transmit Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 SSPIP: Master Synchronous Serial Port Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 CCP1IP: ECCP1 Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 TMR2IP: TMR2 to PR2 Match Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 TMR1IP: TMR1 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 9-11: **IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2**

| U-0   | R/W-1 | U-0 | R/W-1 | R/W-1 | R/W-1 | R/W-1  | R/W-1  |
|-------|-------|-----|-------|-------|-------|--------|--------|
| _     | CMIP  | _   | EEIP  | BCLIP | LVDIP | TMR3IP | CCP2IP |
| bit 7 |       |     |       |       |       |        | bit 0  |

bit 0

bit 7 Unimplemented: Read as '0'

bit 6 **CMIP**: Comparator Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 5 Unimplemented: Read as '0'

**EEIP**: Data EEPROM/Flash Write Operation Interrupt Priority bit bit 4

> 1 = High priority 0 = Low priority

bit 3 **BCLIP**: Bus Collision Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 2 LVDIP: Low-Voltage Detect Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 1 TMR3IP: TMR3 Overflow Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 0 CCP2IP: ECCP2 Interrupt Priority bit

> 1 = High priority 0 = Low priority

Legend:

W = Writable bit U = Unimplemented bit, read as '0' R = Readable bit

-n = Value at POR '0' = Bit is cleared '1' = Bit is set x = Bit is unknown

#### REGISTER 9-12: IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3

| U-0   | U-0 | R/W-1 | R/W-1 | R/W-1  | R/W-1  | R/W-1  | R/W-1  |
|-------|-----|-------|-------|--------|--------|--------|--------|
| _     | _   | RC2IP | TX2IP | TMR4IP | CCP5IP | CCP4IP | CCP3IP |
| bit 7 |     |       |       |        |        |        | bit 0  |

bit 7-6 Unimplemented: Read as '0'

bit 5 RC2IP: USART2 Receive Interrupt Priority bit

1 = High priority0 = Low priority

bit 4 TX2IP: USART2 Transmit Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 TMR4IP: TMR4 to PR4 Match Interrupt Priority bit

1 = High priority0 = Low priority

bit 2-0 **CCPxIP**: CCPx Interrupt Priority bit (ECCP3, CCP4 and CCP5)

1 = High priority0 = Low priority

Legend:

 $R = Readable \ bit$   $W = Writable \ bit$   $U = Unimplemented \ bit$ , read as '0'

-n = Valueat POR 1' = Bitis set 0' = Bitis cleared x = Bitis unknown

#### 9.5 RCON Register

The RCON register contains the IPEN bit which is used to enable prioritized interrupts. The functions of the other bits in this register are discussed in more detail in **Section 4.14** "RCON Register".

#### REGISTER 9-13: RCON: RESET CONTROL REGISTER

| R/W-0 | U-0 | U-0 | R/W-1 | R-1 | R-1 | R/W-0 | R/W-0 |
|-------|-----|-----|-------|-----|-----|-------|-------|
| IPEN  | _   | _   | RI    | TO  | PD  | POR   | BOR   |
| bit 7 |     |     |       |     |     |       | bit 0 |

bit 7 **IPEN:** Interrupt Priority Enable bit

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (PIC16 Compatibility mode)

bit 6-5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

For details of bit operation, see Register 4-4.

bit 3 TO: Watchdog Time-out Flag bit

For details of bit operation, see Register 4-4.

bit 2 PD: Power-down Detection Flag bit

For details of bit operation, see Register 4-4.

bit 1 POR: Power-on Reset Status bit

For details of bit operation, see Register 4-4.

bit 0 BOR: Brown-out Reset Status bit

For details of bit operation, see Register 4-4.

| Lea | e | n  | d | : |
|-----|---|----|---|---|
| -09 | - | •• | · | • |

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 9.6 INT0 Interrupt

External interrupts on the RB0/INT0/FLT0, RB1/INT1, RB2/INT2 and RB3/INT3 pins are edge-triggered; either rising if the corresponding INTEDGx bit is set in the INTCON2 register, or falling if the INTEDGx bit is clear. When a valid edge appears on the RBx/INTx pin, the corresponding flag bit, INTxF, is set. This interrupt can be disabled by clearing the corresponding enable bit, INTxE. Flag bit, INTxF, must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt. All external interrupts (INT0, INT1, INT2 and INT3) can wake-up the processor from Sleep if bit INTxIE was set prior to going into Sleep. If the Global Interrupt Enable bit, GIE, is set, the processor will branch to the interrupt vector following wake-up.

The interrupt priority for INT1, INT2 and INT3 is determined by the value contained in the interrupt priority bits: INT1IP (INTCON3<6>), INT2IP (INTCON3<7>) and INT3IP (INTCON2<1>). There is no priority bit associated with INT0; it is always a high priority interrupt source.

#### 9.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow in the TMR0 register (FFh  $\rightarrow$  00h) will set flag bit TMR0IF. In 16-bit mode, an overflow in the TMR0H:TMR0L registers (FFFFh  $\rightarrow$  0000h) will set flag bit TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit, TMR0IE (INTCON<5>). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit, TMR0IP (INTCON2<2>). See Section 11.0 "Timer0 Module" for further details on the Timer0 module.

#### 9.8 PORTB Interrupt-on-Change

An input change on PORTB<7:4> sets flag bit, RBIF (INTCON<0>). The interrupt can be enabled/disabled by setting/clearing enable bit, RBIE (INTCON<3>). Interrupt priority for PORTB interrupt-on-change is determined by the value contained in the interrupt priority bit, RBIP (INTCON2<0>).

#### 9.9 Context Saving During Interrupts

During an interrupt, the return PC value is saved on the stack. Additionally, the WREG, STATUS and BSR registers are saved on the fast return stack. If a fast return from interrupt is not used (see **Section 4.3 "Fast Register Stack"**), the user may need to save the WREG, STATUS and BSR registers in software. Depending on the user's application, other registers may also need to be saved. Example 9-1 saves and restores the WREG, STATUS and BSR registers during an Interrupt Service Routine.

#### EXAMPLE 9-1: SAVING STATUS, WREG AND BSR REGISTERS IN RAM

```
MOVWF
        W TEMP
                                       ; W TEMP is in virtual bank
MOVFF
        STATUS, STATUS_TEMP
                                       ; STATUS_TEMP located anywhere
MOVFF
       BSR, BSR TEMP
                                       ; BSR located anywhere
; USER ISR CODE
MOVFF
       BSR TEMP, BSR
                                       : Restore BSR
MOVE
        W TEMP, W
                                       ; Restore WREG
MOVFF
       STATUS_TEMP, STATUS
                                       ; Restore STATUS
```

#### 10.0 I/O PORTS

Depending on the device selected, there are either seven or nine I/O ports available on PIC18F6525/6621/8525/8621 devices. Some of their pins are multiplexed with one or more alternate functions from the other peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.


Each port has three registers for its operation. These registers are:

- TRIS register (data direction register)
- PORT register (reads the levels on the pins of the device)
- LAT register (output latch register)

The Data Latch (LAT) register is useful for read-modify-write operations on the value that the I/O pins are driving.

A simplified version of a generic I/O port and its operation is shown in Figure 10-1.

FIGURE 10-1: SIMPLIFIED BLOCK
DIAGRAM OF PORT/LAT/
TRIS OPERATION



# 10.1 PORTA, TRISA and LATA Registers

PORTA is a 7-bit wide, bidirectional port. The corresponding data direction register is TRISA. Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin).

Reading the PORTA register reads the status of the pins, whereas writing to it will write to the port latch.

The Data Latch register (LATA) is also memory mapped. Read-modify-write operations on the LATA register, read and write the latched output value for PORTA.

The RA4 pin is multiplexed with the Timer0 module clock input to become the RA4/T0CKI pin. The RA4/T0CKI pin is a Schmitt Trigger input and an open-drain output. All other RA port pins have TTL input levels and full CMOS output drivers.

The RA6 pin is only enabled as a general I/O pin in ECIO and RCIO Oscillator modes.

The other PORTA pins are multiplexed with analog inputs and the analog VREF+ and VREF- inputs. The operation of each pin is selected by clearing/setting the control bits in the ADCON1 register (A/D Control Register 1).

**Note:** On a Power-on Reset, RA5 and RA3:RA0 are configured as analog inputs and read as '0'. RA6 and RA4 are configured as digital inputs.

The TRISA register controls the direction of the RA pins even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs.

#### **EXAMPLE 10-1: INITIALIZING PORTA**

| CLRF  | PORTA  | ; Initialize PORTA by   |
|-------|--------|-------------------------|
|       |        | ; clearing output       |
|       |        | ; data latches          |
| CLRF  | LATA   | ; Alternate method      |
|       |        | ; to clear output       |
|       |        | ; data latches          |
| MOVLW | 0x0F   | ; Configure A/D         |
| MOVWF | ADCON1 | ; for digital inputs    |
| MOVLW | 0x0F   | ; Value used to         |
|       |        | ; initialize data       |
|       |        | ; direction             |
| MOVWF | TRISA  | ; Set RA<3:0> as inputs |
|       |        | ; RA<6:4> as outputs    |
|       |        |                         |

FIGURE 10-2: BLOCK DIAGRAM OF RA3:RA0 AND RA5 PINS




FIGURE 10-3: BLOCK DIAGRAM OF RA4/T0CKI PIN





FIGURE 10-4: BLOCK DIAGRAM OF RA6 PIN (WHEN ENABLED AS I/O)



**TABLE 10-1: PORTA FUNCTIONS** 

| Name          | Bit#  | Buffer | Function  |
|---------------|-------|--------|---|
| RA0/AN0       | bit 0 | TTL    | Input/output or analog input.   |
| RA1/AN1       | bit 1 | TTL    | Input/output or analog input.   |
| RA2/AN2/VREF- | bit 2 | TTL    | Input/output, analog input or VREF  |
| RA3/AN3/VREF+ | bit 3 | TTL    | Input/output, analog input or VREF+.  |
| RA4/T0CKI     | bit 4 | ST     | Input/output or external clock input for Timer0. Output is open-drain type. |
| RA5/AN4/LVDIN | bit 5 | TTL    | Input/output, analog input or Low-Voltage Detect input.                     |
| OSC2/CLKO/RA6 | bit 6 | TTL    | OSC2, clock output or I/O pin   |

**Legend:** TTL = TTL input, ST = Schmitt Trigger input

TABLE 10-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

| Name   | Bit 7 | Bit 6                 | Bit 5   | Bit 4                         | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|--------|-------|-----------------------|---------|-------------------------------|-------|-------|-------|-------|----------------------|---------------------------------|
| PORTA  | _     | RA6 <sup>(1)</sup>    | RA5     | RA4                           | RA3   | RA2   | RA1   | RA0   | -x0x 0000            | -u0u 0000                       |
| LATA   | _     | LATA6 <sup>(1)</sup>  | LATA Da | ATA Data Output Register      |       |       |       |       | -xxx xxxx            | -uuu uuuu                       |
| TRISA  | _     | TRISA6 <sup>(1)</sup> | PORTA [ | PORTA Data Direction Register |       |       |       |       | -111 1111            | -111 1111                       |
| ADCON1 | _     | _                     | VCFG1   | VCFG0                         | PCFG3 | PCFG2 | PCFG1 | PCFG0 | 00 0000              | 00 0000                         |

**Legend:** x = unknown, u = unchanged, — = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

**Note 1:** RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator modes only and read '0' in all other oscillator modes.

#### 10.2 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATB) is also memory mapped. Read-modify-write operations on the LATB register, read and write the latched output value for PORTB.

#### **EXAMPLE 10-2:** INITIALIZING PORTB

| CLRF PORTB ; Initialize PORTB by ; clearing output : data latches |  |
|---|--|
| : dara larches  |  |
| ,   |  |
| CLRF LATB ; Alternate method                                      |  |
| ; to clear output   |  |
| ; data latches  |  |
| MOVLW 0xCF ; Value used to  |  |
| ; initialize data   |  |
| ; direction   |  |
| MOVWF TRISB ; Set RB<3:0> as inputs                               |  |
| ; RB<5:4> as outputs  |  |
| ; RB<7:6> as inputs   |  |

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit RBPU (INTCON2<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

Note: On a Power-on Reset, these pins are configured as digital inputs.

Four of the PORTB pins (RB3:RB0) are the external interrupt pins, INT3 through INT0. In order to use these pins as external interrupts, the corresponding TRISB bit must be set to '1'.

The other four PORTB pins (RB7:RB4) have an interrupt-on-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB7:RB4 pin configured as an output is excluded from the interrupt-on-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are ORed together to generate the RB Port Change Interrupt with Flag bit, RBIF (INTCON<0>).

This interrupt can wake the device from Sleep. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of PORTB (except with the MOVFF instruction).
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit. RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.


The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.

For PIC18F8525/8621 devices, RB3 can be configured by the configuration bit, CCP2MX, as the alternate peripheral pin for the ECCP2 module. This is only available when the device is configured in Microprocessor, Microprocessor with Boot Block or Extended Microcontroller operating modes.

The RB5 pin is used as the LVP programming pin. When the LVP configuration bit is programmed, this pin loses the I/O function and becomes a programming test function.

When LVP is enabled, the weak pull-up on Note: RB5 is disabled.


#### **BLOCK DIAGRAM OF FIGURE 10-5: RB7:RB4 PINS**




Note 1: I/O pins have diode protection to VDD and Vss.

To enable weak pull-ups, set the appropriate TRIS bit(s) and clear the RBPU bit (INTCON2<7>).

#### FIGURE 10-6: BLOCK DIAGRAM OF RB2:RB0 PINS



#### FIGURE 10-7: BLOCK DIAGRAM OF RB3 PIN



For PIC18F8525/8621 parts, the ECCP2 input/output is multiplexed with RB3 if the CCP2MX bit is enabled (= 0) in the Configuration register and the device is operating in Microprocessor, Microprocessor with Boot Block or

Extended Microcontroller mode.

**TABLE 10-3: PORTB FUNCTIONS** 

| Name  | Bit#  | Buffer                | Function   |
|---|-------|-----------------------|--|
| RB0/INT0/FLT0   | bit 0 | TTL/ST <sup>(1)</sup> | Input/output pin or external interrupt input 0, ECCP1 PWM Fault input. Internal software programmable weak pull-up.  |
| RB1/INT1  | bit 1 | TTL/ST <sup>(1)</sup> | Input/output pin or external interrupt input 1. Internal software programmable weak pull-up.   |
| RB2/INT2  | bit 2 | TTL/ST <sup>(1)</sup> | Input/output pin or external interrupt input 2. Internal software programmable weak pull-up.   |
| RB3/INT3/<br>ECCP2 <sup>(3)</sup> /P2A <sup>(3)</sup> | bit 3 | TTL/ST <sup>(4)</sup> | Input/output pin, external interrupt input 3, Enhanced Capture 2 input/<br>Compare 2 output/PWM 2 output or Enhanced PWM output P2A.<br>Internal software programmable weak pull-up. |
| RB4/KBI0  | bit 4 | TTL                   | Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up.  |
| RB5/KBI1/PGM  | bit 5 | TTL/ST <sup>(2)</sup> | Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Low-Voltage ICSP™ enable pin.  |
| RB6/KBI2/PGC  | bit 6 | TTL/ST <sup>(2)</sup> | Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming clock.  |
| RB7/KBI3/PGD  | bit 7 | TTL/ST <sup>(2)</sup> | Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming data.   |

**Legend:** TTL = TTL input, ST = Schmitt Trigger input

**Note 1:** This buffer is a Schmitt Trigger input when configured as the external interrupt.

2: This buffer is a Schmitt Trigger input when used in Serial Programming mode.

3: Valid for PIC18F8525/8621 devices in all operating modes except Microcontroller mode when CCP2MX is not set. RC1 is the default assignment for ECCP2/PA2 when CCP2MX is set in all devices; RE7 is the alternate assignment for PIC18F8525/8621 devices in Microcontroller mode when CCP2MX is clear.

4: This buffer is a Schmitt Trigger input when configured as the ECCP2 input.

TABLE 10-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

| Name    | Bit 7     | Bit 6                     | Bit 5    | Bit 4   | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Value on POR, BOR | Value on<br>all other<br>Resets |
|---------|-----------|---------------------------|----------|---------|---------|--------|--------|--------|-------------------|---------------------------------|
| PORTB   | RB7       | RB6                       | RB5      | RB4     | RB3     | RB2    | RB1    | RB0    | xxxx xxxx         | uuuu uuuu                       |
| LATB    | LATB Data | LATB Data Output Register |          |         |         |        |        |        |                   | uuuu uuuu                       |
| TRISB   | PORTB Da  | ta Direction F            | Register |         |         |        |        |        | 1111 1111         | 1111 1111                       |
| INTCON  | GIE/GIEH  | PEIE/GIEL                 | TMR0IE   | INT0IE  | RBIE    | TMR0IF | INT0IF | RBIF   | 0000 000x         | 0000 000u                       |
| INTCON2 | RBPU      | INTEDG0                   | INTEDG1  | INTEDG2 | INTEDG3 | TMR0IP | INT3IP | RBIP   | 1111 1111         | 1111 1111                       |
| INTCON3 | INT2IP    | INT1IP                    | INT3IE   | INT2IE  | INT1IE  | INT3IF | INT2IF | INT1IF | 1100 0000         | 1100 0000                       |

**Legend:** x = unknown, u = unchanged. Shaded cells are not used by PORTB.

# 10.3 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATC) is also memory mapped. Read-modify-write operations on the LATC register, read and write the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (Table 10-5). PORTC pins have Schmitt Trigger input buffers.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.


The pin override value is not loaded into the TRIS register. This allows read-modify-write of the TRIS register without concern due to peripheral overrides.

RC1 is normally configured by configuration bit, CCP2MX, as the default peripheral pin of the ECCP2 module (default/erased state, CCP2MX = 1).

#### **EXAMPLE 10-3: INITIALIZING PORTC**

| CLRF  | PORTC | ; Initialize PORTC by   |
|-------|-------|-------------------------|
|       |       | ; clearing output       |
|       |       | ; data latches          |
| CLRF  | LATC  | ; Alternate method      |
|       |       | ; to clear output       |
|       |       | ; data latches          |
| MOVLW | 0xCF  | ; Value used to         |
|       |       | ; initialize data       |
|       |       | ; direction             |
| MOVWF | TRISC | ; Set RC<3:0> as inputs |
|       |       | ; RC<5:4> as outputs    |
|       |       | ; RC<7:6> as inputs     |
|       |       |                         |

#### FIGURE 10-8: PORTC BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



**TABLE 10-5: PORTC FUNCTIONS** 

| Name   | Bit#  | Buffer Type | Function   |
|--|-------|-------------|--|
| RC0/T1OSO/T13CKI                                       | bit 0 | ST          | Input/output port pin, Timer1 oscillator output or Timer1/Timer3 clock input.  |
| RC1/T1OSI/<br>ECCP2 <sup>(1)</sup> /P2A <sup>(1)</sup> | bit 1 | ST          | Input/output port pin, Timer1 oscillator input, Enhanced Capture 2 input/Compare 2 output/PWM 2 output or Enhanced PWM output P2A. |
| RC2/ECCP1/P1A  | bit 2 | ST          | Input/output port pin, Enhanced Capture 1 input/Compare 1 output/PWM 1 output or Enhanced PWM output P1A.                          |
| RC3/SCK/SCL  | bit 3 | ST          | RC3 can also be the synchronous serial clock for both SPI™ and I²C™ modes.   |
| RC4/SDI/SDA  | bit 4 | ST          | RC4 can also be the SPI data in (SPI mode) or data I/O (I <sup>2</sup> C mode).  |
| RC5/SDO  | bit 5 | ST          | Input/output port pin or synchronous serial port data output.  |
| RC6/TX1/CK1  | bit 6 | ST          | Input/output port pin, Addressable USART1 Asynchronous Transmit or Addressable USART1 Synchronous Clock.                           |
| RC7/RX1/DT1  | bit 7 | ST          | Input/output port pin, Addressable USART1 Asynchronous Receive or Addressable USART1 Synchronous Data.                             |

**Legend:** ST = Schmitt Trigger input

Note 1: Valid when CCP2MX is set in all devices and in all operating modes (default). RE7 is the alternate assignment for ECCP2/P2A for all PIC18F6525/6621 devices and PIC18F8525/8621 devices in Microcontroller modes when CCP2MX is not set; RB3 is the alternate assignment for PIC18F8525/8621 devices in all other operating modes.

TABLE 10-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

| Name  | Bit 7   | Bit 6   | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on<br>all other<br>Resets |  |
|-------|---------|---|-------|-------|-------|-------|-------|-------|----------------------|---------------------------------|--|
| PORTC | RC7     | RC6   | RC5   | RC4   | RC3   | RC2   | RC1   | RC0   | xxxx xxxx            | uuuu uuuu                       |  |
| LATC  | LATC Da | ATC Data Output Register xxxx xxxx uuuu uuuu      |       |       |       |       |       |       |                      |                                 |  |
| TRISC | PORTC   | PORTC Data Direction Register 1111 1111 1111 1111 |       |       |       |       |       |       |                      |                                 |  |

**Legend:** x = unknown, u = unchanged

#### 10.4 PORTD, TRISD and LATD Registers

PORTD is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISD. Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATD) is also memory mapped. Read-modify-write operations on the LATD register, read and write the latched output value for PORTD.

PORTD is an 8-bit port with Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.

PORTD is multiplexed with the system bus as the external memory interface. I/O port functions are only available when the system bus is disabled by setting the EBDIS bit in the MEMCOM register (MEMCON<7>). When operating as the external memory interface, PORTD is the low-order byte of the multiplexed address/data bus (AD7:AD0).

PORTD can also be configured as an 8-bit wide microprocessor port (Parallel Slave Port) by setting control bit PSPMODE (TRISE<4>). In this mode, the input buffers are TTL. See **Section 10.10 "Parallel Slave Port"** for additional information on the Parallel Slave Port (PSP).

#### **EXAMPLE 10-4: INITIALIZING PORTD**

|       |       | . INTIALIZATION                             |
|-------|-------|---|
| CLRF  | PORTD | ; Initialize PORTD by                       |
|       |       | <pre>; clearing output ; data latches</pre> |
| CLRF  | LATD  | ; Alternate method                          |
|       |       | ; to clear output                           |
|       |       | ; data latches                              |
| MOVLW | 0xCF  | ; Value used to                             |
|       |       | ; initialize data                           |
|       |       | ; direction                                 |
| MOVWF | TRISD | ; Set RD<3:0> as inputs                     |
|       |       | ; RD<5:4> as outputs                        |
|       |       | ; RD<7:6> as inputs                         |
|       |       |   |

# FIGURE 10-9: PORTD BLOCK DIAGRAM IN I/O PORT MODE





FIGURE 10-10: PORTD BLOCK DIAGRAM IN SYSTEM BUS MODE



**TABLE 10-7: PORTD FUNCTIONS** 

| Name                         | Bit#  | Buffer Type           | Function  |
|------------------------------|-------|-----------------------|---|
| RD0/AD0 <sup>(2)</sup> /PSP0 | bit 0 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 0 or Parallel Slave Port bit 0. |
| RD1/AD1 <sup>(2)</sup> /PSP1 | bit 1 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 1 or Parallel Slave Port bit 1. |
| RD2/AD2 <sup>(2)</sup> /PSP2 | bit 2 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 2 or Parallel Slave Port bit 2. |
| RD3/AD3 <sup>(2)</sup> /PSP3 | bit 3 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 3 or Parallel Slave Port bit 3. |
| RD4/AD4 <sup>(2)</sup> /PSP4 | bit 4 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 4 or Parallel Slave Port bit 4. |
| RD5/AD5 <sup>(2)</sup> /PSP5 | bit 5 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 5 or Parallel Slave Port bit 5. |
| RD6/AD6 <sup>(2)</sup> /PSP6 | bit 6 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 6 or Parallel Slave Port bit 6. |
| RD7/AD7 <sup>(2)</sup> /PSP7 | bit 7 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bus bit 7 or Parallel Slave Port bit 7. |

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

**Note 1:** Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in System Bus or Parallel Slave Port mode.

2: External memory interface functions are only available on PIC18F8525/8621 devices.

TABLE 10-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD

| Name                  | Bit 7   | Bit 6     | Bit 5      | Bit 4   | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|-----------------------|---------|-----------|------------|---------|-------|-------|-------|-------|----------------------|---------------------------------|
| PORTD                 | RD7     | RD6       | RD5        | RD4     | RD3   | RD2   | RD1   | RD0   | xxxx xxxx            | uuuu uuuu                       |
| LATD                  | LATD Da | ata Outpu | ıt Registe | er      |       |       |       |       | xxxx xxxx            | uuuu uuuu                       |
| TRISD                 | PORTD   | Data Dire | ection Re  | gister  |       |       |       |       | 1111 1111            | 1111 1111                       |
| PSPCON <sup>(1)</sup> | IBF     | OBF       | IBOV       | PSPMODE | _     | _     | _     | _     | 0000                 | 0000                            |
| MEMCON <sup>(2)</sup> | EBDIS   |           | WAIT1      | WAIT0   | _     |       | WM1   | WM0   | 0-0000               | 0-0000                          |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by PORTD.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

2: This register is unused on PIC18F6525/6621 devices and reads as '0'.

# 10.5 PORTE, TRISE and LATE Registers

PORTE is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATE register, read and write the latched output value for PORTE.

PORTE is an 8-bit port with Schmitt Trigger input buffers. Each pin is individually configurable as an input or output. PORTE is multiplexed with the ECCP module (Table 10-9).

On PIC18F8525/8621 devices, PORTE is also multiplexed with the system bus as the external memory interface; the I/O bus is available only when the system bus is disabled by setting the EBDIS bit in the MEMCON register (MEMCON<7>). If the device is configured in Microprocessor or Extended Microcontroller mode, then the PORTE<7:0> becomes the high byte of the address/data bus for the external program memory interface. In Microcontroller mode, the PORTE<2:0> pins become the control inputs for the Parallel Slave Port when bit PSPMODE (PSPCON<4>) is set. (Refer to Section 4.1.1 "PIC18F6525/6621/8525/8621 Program Memory Modes" for more information.)

When the Parallel Slave Port is active, three PORTE pins (RE0/AD8/RD/P2D, RE1/AD9/WR/P2C and RE2/AD10/CS/P2B) function as its control inputs. This automatically occurs when the PSPMODE bit (PSPCON<4>) is set. Users must also make certain that bits TRISE<2:0> are set to configure the pins as digital inputs and the ADCON1 register is configured for digital I/O. The PORTE PSP control functions are summarized in Table 10-9.


Pin RE7 can be configured as the alternate peripheral pin for the ECCP2 module when the device is operating in Microcontroller mode. This is done by clearing the configuration bit, CCP2MX, in the CONFIG3H Configuration register (CONFIG3H<0>).

Note: For PIC18F8525/8621 (80-pin) devices operating in Extended Microcontroller mode, PORTE defaults to the system bus on Power-on Reset.

#### **EXAMPLE 10-5: INITIALIZING PORTE**

| CLRF  | PORTE | ; Initialize PORTE by ; clearing output |
|-------|-------|---|
|       |       | ; data latches                          |
| CLRF  | LATE  | ; Alternate method                      |
|       |       | ; to clear output                       |
|       |       | ; data latches                          |
| MOVLW | 0x03  | ; Value used to                         |
|       |       | ; initialize data                       |
|       |       | ; direction                             |
| MOVWF | TRISE | ; Set RE1:RE0 as inputs                 |
|       |       | ; RE7:RE2 as outputs                    |
|       |       |   |

### FIGURE 10-11: PORTE BLOCK DIAGRAM IN I/O MODE



#### FIGURE 10-12: PORTE BLOCK DIAGRAM IN SYSTEM BUS MODE




TABLE 10-9: PORTE FUNCTIONS

| Name  | Bit#  | Buffer Type           | Function   |
|---|-------|-----------------------|--|
| RE0/AD8/RD/P2D  | bit 0 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 8, read control for Parallel Slave Port or Enhanced PWM 2 output P2D For RD (PSP Control mode): 1 = Not a read operation 0 = Read operation, reads PORTD register (if chip selected)     |
| RE1/AD9/WR/P2C  | bit 1 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 9, write control for Parallel Slave Port or Enhanced PWM 2 output P2C For WR (PSP Control mode): 1 = Not a write operation 0 = Write operation, writes PORTD register (if chip selected) |
| RE2/AD10/CS/P2B                                       | bit 2 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 10, chip select control for Parallel Slave Port or Enhanced PWM 2 output P2B For CS (PSP Control mode):  1 = Device is not selected 0 = Device is selected                               |
| RE3/AD11/P3C <sup>(2)</sup>                           | bit 3 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 11 or Enhanced PWM 3 output P3C.   |
| RE4/AD12/P3B <sup>(2)</sup>                           | bit 4 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 12 or Enhanced PWM 3 output P3B.   |
| RE5/AD13/P1C <sup>(2)</sup>                           | bit 5 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 13 or Enhanced PWM 1 output P1C.   |
| RE6/AD14/P1B <sup>(2)</sup>                           | bit 6 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 14 or Enhanced PWM 1 output P1B.   |
| RE7/AD15/<br>ECCP2 <sup>(3)</sup> /P2A <sup>(3)</sup> | bit 7 | ST/TTL <sup>(1)</sup> | Input/output port pin, address/data bit 15, Enhanced Capture 2 input/Compare 2 output/PWM 2 output or Enhanced PWM 2 output P2A.   |

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

- **Note 1:** Input buffers are Schmitt Triggers when in I/O or CCP/ECCP modes and TTL buffers when in System Bus or PSP Control modes.
  - 2: Valid for all PIC18F6525/6621 devices and PIC18F8525/8621 devices when ECCPMX is set. Alternate assignments for P1B/P1C/P3B/P3C are RH7, RH6, RH5 and RH4, respectively.
  - 3: Valid for all PIC18F6525/6621 devices and PIC18F8525/8621 devices in Microcontroller mode when CCP2MX is not set. RC1 is the default assignment for ECCP2/P2A for all devices in Microcontroller mode when CCP2MX is set; RB3 is the alternate assignment for PIC18F8525/8621 devices in operating modes except Microcontroller mode when CCP2MX is not set.

TABLE 10-10: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

| Name                  | Bit 7   | Bit 6  | Bit 5      | Bit 4       | Bit 3    | Bit 2 | Bit 1 | Bit 0 | Value on:<br>POR, BOR | Value on<br>all other<br>Resets |
|-----------------------|---------|--|------------|-------------|----------|-------|-------|-------|-----------------------|---------------------------------|
| TRISE                 | PORTE   | PORTE Data Direction Control Register 1111 1111 1111 1111 1111 1111 1111 1 |            |             |          |       |       |       |                       |                                 |
| PORTE                 | Read PC | ORTE pin   | /Write PC  | RTE Data La | atch     |       |       |       | xxxx xxxx             | uuuu uuuu                       |
| LATE                  | Read PC | ORTE Da  | ta Latch/\ | Vrite PORTE | Data Lat | ch:   |       |       | xxxx xxxx             | uuuu uuuu                       |
| MEMCON <sup>(1)</sup> | EBDIS   | _  | WAIT1      | WAIT0       | _        | _     | WM1   | WM0   | 0-0000                | 000000                          |
| PSPCON <sup>(2)</sup> | IBF     | OBF  | IBOV       | PSPMODE     | _        |       | _     |       | 0000                  | 0000                            |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by PORTE.

Note 1: This register is unused on PIC18F6525/6621 devices and reads as '0'.

2: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

#### 10.6 PORTF, LATF and TRISF Registers

PORTF is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISF. Setting a TRISF bit (= 1) will make the corresponding PORTF pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISF bit (= 0) will make the corresponding PORTF pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATF register, read and write the latched output value for PORTF.

PORTF is multiplexed with several analog peripheral functions, including the A/D converter inputs and comparator inputs, outputs and voltage reference.

- **Note 1:** On a Power-on Reset, the RF6:RF0 pins are configured as inputs and read as '0'.
  - 2: To configure PORTF as digital I/O, turn off comparators and set ADCON1 value.

#### **EXAMPLE 10-6: INITIALIZING PORTF**

| CLRF  | PORTF  | ; Initialize PORTF by<br>; clearing output<br>: data latches |
|-------|--------|--|
| CLRF  | LATF   | ; Alternate method<br>; to clear output                      |
|       |        | ; data latches   |
| MOVLW | 0x07   | ;  |
| MOVWF | CMCON  | ; Turn off comparators                                       |
| MOVLW | 0x0F   | ;  |
| MOVWF | ADCON1 | ; Set PORTF as digital I/O                                   |
| MOVLW | 0xCF   | ; Value used to  |
|       |        | ; initialize data  |
|       |        | ; direction  |
| MOVWF | TRISF  | ; Set RF3:RF0 as inputs                                      |
|       |        | ; RF5:RF4 as outputs   |
|       |        | ; RF7:RF6 as inputs  |
|       |        |  |

#### FIGURE 10-13: PORTF RF1/AN6/C2OUT, RF2/AN7/C1OUT PINS BLOCK DIAGRAM




FIGURE 10-14: RF6:RF3 AND RF0 PINS BLOCK DIAGRAM





FIGURE 10-15: RF7 PIN BLOCK DIAGRAM



**TABLE 10-11: PORTF FUNCTIONS** 

| Name           | Bit#  | Buffer Type | Function   |
|----------------|-------|-------------|--|
| RF0/AN5        | bit 0 | ST          | Input/output port pin or analog input.   |
| RF1/AN6/C2OUT  | bit 1 | ST          | Input/output port pin, analog input or Comparator 2 output.                          |
| RF2/AN7/C1OUT  | bit 2 | ST          | Input/output port pin, analog input or Comparator 1 output.                          |
| RF3/AN8        | bit 3 | ST          | Input/output port pin or analog input/comparator input.                              |
| RF4/AN9        | bit 4 | ST          | Input/output port pin or analog input/comparator input.                              |
| RF5/AN10/CVREF | bit 5 | ST          | Input/output port pin, analog input/comparator input or comparator reference output. |
| RF6/AN11       | bit 6 | ST          | Input/output port pin or analog input/comparator input.                              |
| RF7/SS         | bit 7 | ST/TTL      | Input/output port pin or slave select pin for synchronous serial port.               |

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

TABLE 10-12: SUMMARY OF REGISTERS ASSOCIATED WITH PORTF

| Name   | Bit 7   | Bit 6      | Bit 5     | Bit 4     | Bit 3     | Bit 2     | Bit 1 | Bit 0 | Value on:<br>POR, BOR | Value on<br>all other<br>Resets |
|--------|---------|------------|-----------|-----------|-----------|-----------|-------|-------|-----------------------|---------------------------------|
| TRISF  | PORTF   | Data Dired | ction Con |           | 1111 1111 | 1111 1111 |       |       |                       |                                 |
| PORTF  | Read PC | ORTF pin/  | Write PO  | RTF Data  | Latch     |           |       |       | x000 0000             | u000 0000                       |
| LATF   | Read PC | ORTF Data  | a Latch/W | rite POR  | ΓF Data L | atch      |       |       | xxxx xxxx             | uuuu uuuu                       |
| ADCON1 | _       | _          | VCFG1     | VCFG0     | PCFG3     | PCFG2     | PCFG1 | PCFG0 | 00 0000               | 00 0000                         |
| CMCON  | C2OUT   | C10UT      | CM0       | 0000 0000 | 0000 0000 |           |       |       |                       |                                 |
| CVRCON | CVREN   | CVROE      | CVRR      | CVRSS     | CVR3      | CVR2      | CVR1  | CVR0  | 0000 0000             | 0000 0000                       |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by PORTF.

#### 10.7 PORTG, TRISG and LATG Registers

PORTG is a 6-bit wide port with 5 bidirectional pins (RG0:RG4) and one optional input only pin (RG5). The corresponding data direction register is TRISG. Setting a TRISG bit (= 1) will make the corresponding PORTG pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISG bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATG) is also memory mapped. Read-modify-write operations on the LATG register, read and write the latched output value for PORTG.

PORTG is multiplexed with both CCP/ECCP and EUSART functions (Table 10-13). PORTG pins have Schmitt Trigger input buffers.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTG pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

Note: On a Power-on Reset, these pins are configured as digital inputs.

The pin override value is not loaded into the TRIS register. This allows read-modify-write operations of the TRIS register without concern due to peripheral overrides.

The sixth pin of PORTG (MCLR/VPP/RG5) is a digital input pin. Its operation is controlled by the MCLRE configuration bit in Configuration Register 3H (CONFIG3H<7>). In its default configuration (MCLRE = 1), the pin functions as the device Master Clear input. When selected as a port pin (MCLRE = 0), it functions as an input only pin; as such, it does not have TRISG or LATG bits associated with it.


In either configuration, RG5 also functions as the programming voltage input during device programming.

- Note 1: On a Power-on Reset, RG5 is enabled as a digital input only if Master Clear functionality is disabled (MCLRE = 0).
  - 2: If the device Master Clear is disabled, verify that either of the following is done to ensure proper entry into ICSP mode:
    - a.) disable low-voltage programming (CONFIG4L<2> = 0): or
    - b.) make certain that RB5/KBI1/PGM is held low during entry into ICSP.

#### **EXAMPLE 10-7: INITIALIZING PORTG**

| CLRF  | PORTG | ; Initialize PORTG by ; clearing output                           |
|-------|-------|---|
| CLRF  | LATG  | <pre>; data latches ; Alternate method</pre>                      |
|       |       | ; to clear output   |
|       |       | ; data latches  |
| MOVLW | 0x04  | <pre>; Value used to ; initialize data</pre>                      |
|       |       | ; direction   |
| MOVWF | TRISG | ; Set RG1:RG0 as outputs<br>; RG2 as input<br>; RG4:RG3 as inputs |
|       |       |   |

#### FIGURE 10-16: PORTG BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



Peripheral

ECCP3 I/O


Sync Clock

Sync Data Out

CCP4 I/O

CCP5 I/O

FIGURE 10-17: MCLR/VPP/RG5 PIN BLOCK DIAGRAM



**TABLE 10-13: PORTG FUNCTIONS** 

| Name          | Bit#  | Buffer Type | Function  |
|---------------|-------|-------------|---|
| RG0/ECCP3/P3A | bit 0 | ST          | Input/output port pin, Enhanced Capture 3 input/Compare 3 output/PWM 3 output or Enhanced PWM 3 output P3A.                                   |
| RG1/TX2/CK2   | bit 1 | ST          | Input/output port pin, addressable USART2 asynchronous transmit or addressable USART2 synchronous clock.                                      |
| RG2/RX2/DT2   | bit 2 | ST          | Input/output port pin, addressable USART2 asynchronous receive or addressable USART2 synchronous data.  |
| RG3/CCP4/P3D  | bit 3 | ST          | Input/output port pin, Capture 4 input/Compare 4 output/PWM 4 output or Enhanced PWM 3 output P3D.  |
| RG4/CCP5/P1D  | bit 4 | ST          | Input/output port pin, Capture 5 input/Compare 5 output/PWM 5 output or Enhanced PWM 1 output P1D.  |
| MCLR/VPP/RG5  | bit 5 | ST          | Master Clear input or programming voltage input (if MCLR is enabled). Input only port pin or programming voltage input (if MCLR is disabled). |

**Legend:** ST = Schmitt Trigger input

TABLE 10-14: SUMMARY OF REGISTERS ASSOCIATED WITH PORTG

| Name  | Bit 7 | Bit 6 | Bit 5              | Bit 4     | Bit 3                     | Bit 2      | Bit 1       | Bit 0    | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|-------|-------|-------|--------------------|-----------|---------------------------|------------|-------------|----------|----------------------|---------------------------------|
| PORTG | _     | _     | RG5 <sup>(1)</sup> | Read PC   | ORTG pins                 | s/Write PC | ORTG Dat    | ta Latch | xx xxxx              | uu uuuu                         |
| LATG  | 1     | _     | _                  | LATG Da   | LATG Data Output Register |            |             |          |                      | u uuuu                          |
| TRISG | _     | _     | _                  | Data Dire | ection Co                 | ntrol Regi | ster for Po | ORTG     | 1 1111               | 1 1111                          |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'

**Note 1:** RG5 is available as an input only when  $\overline{MCLR}$  is disabled.

# 10.8 PORTH, LATH and TRISH Registers

**Note:** PORTH is available only on PIC18F8525/8621 devices.

PORTH is an 8-bit wide, bidirectional I/O port. The corresponding data direction register is TRISH. Setting a TRISH bit (= 1) will make the corresponding PORTH pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISH bit (= 0) will make the corresponding PORTH pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATH register, read and write the latched output value for PORTH.

Pins RH7:RH4 are multiplexed with analog inputs AN15:AN12. Pins RH3:RH0 are multiplexed with the system bus as the external memory interface; they are the high-order address bits A19:A16. By default, pins RH7:RH4 are enabled as A/D inputs and pins RH3:RH0 are enabled as the system address bus. Register ADCON1 configures RH7:RH4 as I/O or A/D inputs. Register MEMCON configures RH3:RH0 as I/O or system bus pins.

- Note 1: On Power-on Reset, PORTH pins RH7:RH4 default to A/D inputs and read as '0'.
  - **2:** On Power-on Reset, PORTH pins RH3:RH0 default to system bus signals.

#### **EXAMPLE 10-8: INITIALIZING PORTH**

|       | LL 10-0. |        | INTIALIZING FORTH   |
|-------|----------|--------|---|
| CLRF  | PORTH    | •      | Initialize PORTH by<br>clearing output                                      |
| CLRF  | LATH     | ;      | data latches<br>Alternate method<br>to clear output<br>data latches         |
| MOVLW | 0Fh      | ;      |   |
| MOVWF | ADCON1   | ;      |   |
| MOVLW | 0CFh     | ;      | Value used to   |
| MOVWF | TRISH    | ;<br>; | initialize data<br>direction<br>Set RH3:RH0 as inputs<br>RH5:RH4 as outputs |
|       |          | ;      | RH7:RH6 as inputs   |

# FIGURE 10-18: RH3:RH0 PINS BLOCK DIAGRAM IN I/O MODE




FIGURE 10-19: RH7:RH4 PINS BLOCK DIAGRAM IN I/O MODE





FIGURE 10-20: RH3:RH0 PINS BLOCK DIAGRAM IN SYSTEM BUS MODE



**TABLE 10-15: PORTH FUNCTIONS** 

| Name                        | Bit#  | Buffer Type           | Function  |
|-----------------------------|-------|-----------------------|---|
| RH0/A16                     | bit 0 | ST/TTL <sup>(1)</sup> | Input/output port pin or address bit 16 for external memory interface.      |
| RH1/A17                     | bit 1 | ST/TTL <sup>(1)</sup> | Input/output port pin or address bit 17 for external memory interface.      |
| RH2/A18                     | bit 2 | ST/TTL <sup>(1)</sup> | Input/output port pin or address bit 18 for external memory interface.      |
| RH3/A19                     | bit 3 | ST/TTL <sup>(1)</sup> | Input/output port pin or address bit 19 for external memory interface.      |
| RH4/AN12/P3C <sup>(2)</sup> | bit 4 | ST                    | Input/output port pin, analog input channel 12 or Enhanced PWM output P3C.  |
| RH5/AN13/P3B <sup>(2)</sup> | bit 5 | ST                    | Input/output port pin, analog input channel 13 or Enhanced PWM output P3B.  |
| RH6/AN14/P1C <sup>(2)</sup> | bit 6 | ST                    | Input/output port pin, analog input channel 14 or Enhanced PWM output P1C.  |
| RH7/AN15/P1B <sup>(2)</sup> | bit 7 | ST                    | Input/output port pin, analog input channel 15 or Enhanced PWM3 output P1B. |

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

**Note 1:** Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in System Bus or Parallel Slave Port mode.

2: Valid only for PIC18F8525/8621 devices when ECCPMX is not set. The alternate assignments for P1B/P1C/P3B/P3C in all PIC18F6525/6621 devices and in PIC18F8525/8621 devices when ECCPMX is set are RE6, RE5, RE4 and RE3, respectively.

TABLE 10-16: SUMMARY OF REGISTERS ASSOCIATED WITH PORTH

| Name                  | Bit 7   | Bit 6     | Bit 5     | Bit 4     | Bit 3     | Bit 2 | Bit 1 | Bit 0 | Value on:<br>POR, BOR | Value on<br>all other<br>Resets |
|-----------------------|---------|-----------|-----------|-----------|-----------|-------|-------|-------|-----------------------|---------------------------------|
| TRISH                 | PORTH   | Data Dire |           | 1111 1111 | 1111 1111 |       |       |       |                       |                                 |
| PORTH                 | Read PC | RTH pin/  | Write PO  | RTH Data  | Latch     |       |       |       | 0000 xxxx             | 0000 uuuu                       |
| LATH                  | Read PC | ORTH Dat  | a Latch/W | /rite POR | TH Data I | _atch |       |       | xxxx xxxx             | uuuu uuuu                       |
| ADCON1                | _       | —         |           |           |           |       |       |       |                       | 00 0000                         |
| MEMCON <sup>(1)</sup> | EBDIS   | _         | WAIT1     | WAIT0     | _         | _     | WM1   | WM0   | 0-0000                | 0-0000                          |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by PORTH.

Note 1: This register is unused on PIC18F6525/6621 devices and reads as '0'.

#### 10.9 PORTJ, TRISJ and LATJ Registers

**Note:** PORTJ is available only on PIC18F8525/8621 devices.

PORTJ is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISJ. Setting a TRISJ bit (= 1) will make the corresponding PORTJ pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISJ bit (= 0) will make the corresponding PORTJ pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATJ) is also memory mapped. Read-modify-write operations on the LATJ register, read and write the latched output value for PORTJ.

PORTJ is multiplexed with the system bus as the external memory interface; I/O port functions are only available when the system bus is disabled. When operating as the external memory interface, PORTJ provides the control signal to external memory devices. The RJ5 pin is not multiplexed with any system bus functions.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTJ pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.

The pin override value is not loaded into the TRIS register. This allows read-modify-write of the TRIS register without concern due to peripheral overrides.

#### **EXAMPLE 10-9: INITIALIZING PORTJ**

CLRF PORTJ ; Initialize PORTG by ; clearing output ; data latches CLRF LATJ ; Alternate method ; to clear output ; data latches 0xCF MOVIJW ; Value used to ; initialize data ; direction MOVWF TRISJ ; Set RJ3:RJ0 as inputs ; RJ5:RJ4 as output ; RJ7:RJ6 as inputs

# FIGURE 10-21: PORTJ BLOCK DIAGRAM IN I/O MODE






FIGURE 10-22: RJ4:RJ0 PINS BLOCK DIAGRAM IN SYSTEM BUS MODE



#### FIGURE 10-23: RJ7:RJ6 PINS BLOCK DIAGRAM IN SYSTEM BUS MODE



**TABLE 10-17: PORTJ FUNCTIONS** 

| Name    | Bit#  | Buffer Type | Function   |
|---------|-------|-------------|--|
| RJ0/ALE | bit 0 | ST          | Input/output port pin or address latch enable control for external memory interface. |
| RJ1/OE  | bit 1 | ST          | Input/output port pin or output enable control for external memory interface.        |
| RJ2/WRL | bit 2 | ST          | Input/output port pin or write low byte control for external memory interface.       |
| RJ3/WRH | bit 3 | ST          | Input/output port pin or write high byte control for external memory interface.      |
| RJ4/BA0 | bit 4 | ST          | Input/output port pin or byte address 0 control for external memory interface.       |
| RJ5/CE  | bit 5 | ST          | Input/output port pin or chip enable control for external memory interface.          |
| RJ6/LB  | bit 6 | ST          | Input/output port pin or lower byte select control for external memory interface.    |
| RJ7/UB  | bit 7 | ST          | Input/output port pin or upper byte select control for external memory interface.    |

Legend: ST = Schmitt Trigger input

#### TABLE 10-18: SUMMARY OF REGISTERS ASSOCIATED WITH PORTJ

| Name  | Bit 7     | Bit 6     | Bit 5      | Bit 4       | Bit 3     | Bit 2     | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|-------|-----------|-----------|------------|-------------|-----------|-----------|-------|-------|----------------------|---------------------------------|
| PORTJ | Read PC   | ORTJ pin/ | Write POF  |             | xxxx xxxx | uuuu uuuu |       |       |                      |                                 |
| LATJ  | LATJ Da   | ta Output | Register   |             | xxxx xxxx | uuuu uuuu |       |       |                      |                                 |
| TRISJ | Data Dire | ection Co | ntrol Regi | ster for Po | ORTJ      |           |       |       | 1111 1111            | 1111 1111                       |

**Legend:** x = unknown, u = unchanged

#### 10.10 Parallel Slave Port

PORTD also operates as an 8-bit wide Parallel Slave Port, or microprocessor port, when control bit PSPMODE (PSPCON<4>) is set. It is asynchronously readable and writable by the external world through RD control input pin, RE0/RD and WR control input pin, RE1/WR.


Note: For PIC18F8525/8621 devices, the Parallel Slave Port is available only in Microcontroller mode.

The PSP can directly interface to an 8-bit microprocessor data bus. The external microprocessor can read or write the PORTD latch as an 8-bit latch. Setting bit PSPMODE enables port pin RE0/RD to be the RD input, RE1/WR to be the WR input and RE2/CS to be the  $\overline{\text{CS}}$  (chip select) input. For this functionality, the corresponding data direction bits of the TRISE register (TRISE<2:0>) must be configured as inputs (set). The A/D port configuration bits, PCFG2:PCFG0 (ADCON1<2:0>), must be set, which will configure pins RE2:RE0 as digital I/O.

A write to the PSP occurs when both the  $\overline{CS}$  and  $\overline{WR}$  lines are first detected low. A read from the PSP occurs when both the  $\overline{CS}$  and  $\overline{RD}$  lines are first detected low.

The PORTE I/O pins become control inputs for the microprocessor port when bit PSPMODE (PSPCON<4>) is set. In this mode, the user must make sure that the TRISE<2:0> bits are set (pins are configured as digital inputs) and the ADCON1 is configured for digital I/O. In this mode, the input buffers are TTL.

FIGURE 10-24: PORTD AND PORTE
BLOCK DIAGRAM
(PARALLEL SLAVE PORT)



#### PSPCON: PARALLEL SLAVE PORT CONTROL REGISTER<sup>(1)</sup> REGISTER 10-1:

| R-0   | R-0 | R/W-0 | R/W-0   | U-0 | U-0 | U-0 | U-0   |
|-------|-----|-------|---------|-----|-----|-----|-------|
| IBF   | OBF | IBOV  | PSPMODE | _   | _   | _   | _     |
| bit 7 |     |       |         |     |     |     | bit 0 |

bit 0

bit 7 IBF: Input Buffer Full Status bit

1 = A word has been received and is waiting to be read by the CPU

0 = No word has been received

bit 6 **OBF:** Output Buffer Full Status bit

1 = The output buffer still holds a previously written word

0 = The output buffer has been read

bit 5 **IBOV:** Input Buffer Overflow Detect bit

> 1 = A write occurred when a previously input word has not been read (must be cleared in software)

0 = No overflow occurred

bit 4 PSPMODE: Parallel Slave Port Mode Select bit

> 1 = Parallel Slave Port mode 0 = General Purpose I/O mode

bit 3-0 Unimplemented: Read as '0'

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '0' = Bit is cleared '1' = Bit is set x = Bit is unknown

#### FIGURE 10-25: PARALLEL SLAVE PORT WRITE WAVEFORMS




FIGURE 10-26: PARALLEL SLAVE PORT READ WAVEFORMS




TABLE 10-19: REGISTERS ASSOCIATED WITH PARALLEL SLAVE PORT

| Name                  | Bit 7  | Bit 6                     | Bit 5        | Bit 4        | Bit 3       | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR, BOF | Value on<br>all other<br>Resets |  |  |  |
|-----------------------|--|---------------------------|--------------|--------------|-------------|--------|--------|--------|----------------------|---------------------------------|--|--|--|
| PORTD                 | Port Data L  | atch when w               | ritten; Port | pins when re | ad          |        |        |        | xxxx xxx             | x uuuu uuuu                     |  |  |  |
| LATD                  | LATD Data  | ATD Data Output bits xxxx |              |              |             |        |        |        |                      |                                 |  |  |  |
| TRISD                 | PORTD Da   | ita Direction b           | 1111 111     | 1 1111 1111  |             |        |        |        |                      |                                 |  |  |  |
| PORTE                 | Read POR   | TE pin/Write              |              | xxxx xxx     | x uuuu uuuu |        |        |        |                      |                                 |  |  |  |
| LATE                  | LATE Data  | Output bits               |              |              |             |        |        |        | xxxx xxx             | x uuuu uuuu                     |  |  |  |
| TRISE                 | PORTE Da   | ta Direction b            | oits         |              |             |        |        |        | 1111 111             | 1 1111 1111                     |  |  |  |
| PSPCON <sup>(1)</sup> | IBF  | OBF                       | IBOV         | PSPMODE      | _           | _      | _      | _      | 0000                 | - 0000                          |  |  |  |
| INTCON                | GIE/GIEH   | PEIE/GIEL                 | TMR0IE       | INT0IE       | RBIE        | TMR0IF | INT0IF | RBIF   | 0000 000             | x 0000 000u                     |  |  |  |
| PIR1                  | PSPIF <sup>(1)</sup> ADIF RC1IF TX1IF SSPIF CCP1IF TMR2IF TMR1IF |                           |              |              |             |        |        |        | 0000 000             | 0 0000 0000                     |  |  |  |
| PIE1                  | PSPIE <sup>(1)</sup>   | ADIE                      | RC1IE        | TX1IE        | SSPIE       | CCP1IE | TMR2IE | TMR1IE | 0000 000             | 0 0000 0000                     |  |  |  |
| IPR1                  | PSPIP <sup>(1)</sup>   | ADIP                      | RC1IP        | TX1IP        | SSPIP       | CCP1IP | TMR2IP | TMR1IP | 1111 111             | 1 1111 1111                     |  |  |  |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the Parallel Slave Port.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

#### 11.0 TIMERO MODULE

The Timer0 module has the following features:

- Software selectable as an 8-bit or 16-bit timer/counter
- · Readable and writable
- · Dedicated 8-bit software programmable prescaler
- · Clock source selectable to be external or internal
- Interrupt-on-overflow from FFh to 00h in 8-bit mode and FFFFh to 0000h in 16-bit mode
- · Edge select for external clock

Figure 11-1 shows a simplified block diagram of the Timer0 module in 8-bit mode and Figure 11-2 shows a simplified block diagram of the Timer0 module in 16-bit mode.

The TOCON register (Register 11-1) is a readable and writable register that controls all the aspects of Timer0, including the prescale selection.

#### REGISTER 11-1: TOCON: TIMERO CONTROL REGISTER


| R/W-1  | R/W-1  | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1 |
|--------|--------|-------|-------|-------|-------|-------|-------|
| TMR00N | T08BIT | T0CS  | T0SE  | PSA   | T0PS2 | T0PS1 | T0PS0 |
| bit 7  |        |       |       |       |       |       | bit 0 |

- bit 7 TMR0ON: Timer0 On/Off Control bit
  - 1 = Enables Timer0
  - 0 = Stops Timer0
- bit 6 T08BIT: Timer0 8-bit/16-bit Control bit
  - 1 = Timer0 is configured as an 8-bit timer/counter
  - 0 = Timer0 is configured as a 16-bit timer/counter
- bit 5 TOCS: Timer0 Clock Source Select bit
  - 1 = Transition on T0CKI pin
  - 0 = Internal instruction cycle clock (CLKO)
- bit 4 T0SE: Timer0 Source Edge Select bit
  - 1 = Increment on high-to-low transition on T0CKI pin
  - 0 = Increment on low-to-high transition on T0CKI pin
- bit 3 **PSA**: Timer0 Prescaler Assignment bit
  - 1 = TImer0 prescaler is not assigned. Timer0 clock input bypasses prescaler.
  - 0 = Timer0 prescaler is assigned. Timer0 clock input comes from prescaler output.
- bit 2-0 TOPS2:TOPS0: Timer0 Prescaler Select bits
  - 111 = 1:256 Prescale value
  - 110 = 1:128 Prescale value
  - 101 = 1:64 Prescale value
  - 100 = 1:32 Prescale value
  - 011 = 1:16 Prescale value
  - 010 = 1:8 Prescale value
  - 001 = 1:4 Prescale value
  - 000 = 1:2 Prescale value


#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### FIGURE 11-1: TIMERO BLOCK DIAGRAM IN 8-BIT MODE



#### FIGURE 11-2: TIMERO BLOCK DIAGRAM IN 16-BIT MODE



#### 11.1 Timer0 Operation

Timer0 can operate as a timer or as a counter.

Timer mode is selected by clearing the T0CS bit. In Timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If the TMR0 register is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0 register.

Counter mode is selected by setting the T0CS bit. In Counter mode, Timer0 will increment, either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit (T0SE). Clearing the T0SE bit selects the rising edge. Restrictions on the external clock input are discussed below.

When an external clock input is used for Timer0, it must meet certain requirements. The requirements ensure the external clock can be synchronized with the internal phase clock (Tosc). Also, there is a delay in the actual incrementing of Timer0 after synchronization.

#### 11.2 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not readable or writable.

The PSA and T0PS2:T0PS0 bits determine the prescaler assignment and prescale ratio.

Clearing bit PSA will assign the prescaler to the Timer0 module. When the prescaler is assigned to the Timer0 module, prescale values of 1:2, 1:4, ..., 1:256 are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF  $\,$  TMR0, MOVWF  $\,$  TMR0, BSF  $\,$  TMR0, x and so on) will clear the prescaler count.

Note: Writing to TMR0 when the prescaler is assigned to Timer0 will clear the prescaler count, but will not change the prescaler assignment.

# 11.2.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control, (i.e., it can be changed "on-the-fly" during program execution).

#### 11.3 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode, or FFFFh to 0000h in 16-bit mode. This overflow sets the TMR0IF bit. The interrupt can be masked by clearing the TMR0IE bit. The TMR0IE bit must be cleared in software by the Timer0 module Interrupt Service Routine before re-enabling this interrupt. The TMR0 interrupt cannot awaken the processor from Sleep since the timer is shut off during Sleep.

# 11.4 16-Bit Mode Timer Reads and Writes

TMR0H is not the high byte of the timer/counter in 16-bit mode, but is actually a buffered version of the high byte of Timer0 (refer to Figure 11-2). The high byte of the Timer0 counter/timer is not directly readable nor writable. TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte were valid, due to a rollover between successive reads of the high and low byte.

A write to the high byte of Timer0 must also take place through the TMR0H Buffer register. Timer0 high byte is updated with the contents of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

TABLE 11-1: REGISTERS ASSOCIATED WITH TIMERO

| Name   | Bit 7       | Bit 6                 | Bit 5   | Bit 4                         | Bit 3 | Bit 2  | Bit 1  | Bit 0 | Value on<br>POR, BOR |      | Value on a other Resets |      |
|--------|-------------|-----------------------|---------|-------------------------------|-------|--------|--------|-------|----------------------|------|-------------------------|------|
| TMR0L  | Timer0 Low  | Byte Regist           |         | xxxx                          | xxxx  | uuuu   | uuuu   |       |                      |      |                         |      |
| TMR0H  | Timer0 High | n Byte Regis          | ter     |                               |       |        |        |       | 0000                 | 0000 | uuuu                    | uuuu |
| INTCON | GIE/GIEH    | PEIE/GIEL             | TMR0IE  | INT0IE                        | RBIE  | TMR0IF | INT0IF | RBIF  | 0000                 | 000x | 0000                    | 000u |
| T0CON  | TMR00N      | T08BIT                | T0CS    | T0SE                          | PSA   | T0PS2  | T0PS1  | T0PS0 | 1111                 | 1111 | 1111                    | 1111 |
| TRISA  | _           | TRISA6 <sup>(1)</sup> | PORTA D | PORTA Data Direction Register |       |        |        |       |                      |      | -111                    | 1111 |

**Legend:** x = unknown, u = unchanged, — = unimplemented locations, read as '0'. Shaded cells are not used by Timer0.

Note 1: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator modes only and read '0' in all other oscillator modes.

NOTES:

#### 12.0 TIMER1 MODULE

The Timer1 module timer/counter has the following features:

- 16-bit timer/counter (two 8-bit registers: TMR1H and TMR1L)
- Readable and writable (both registers)
- · Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- · Reset from ECCP module special event trigger

Figure 12-1 is a simplified block diagram of the Timer1 module.

Register 12-1 details the Timer1 Control register. This register controls the operating mode of the Timer1 module and contains the Timer1 oscillator enable bit (T1OSCEN). Timer1 can be enabled or disabled by setting or clearing control bit, TMR1ON (T1CON<0>).

Timer1 can also be used to provide Real-Time Clock (RTC) functionality to applications with only a minimal addition of external components and code overhead.

#### REGISTER 12-1: T1CON: TIMER1 CONTROL REGISTER

| R/W-0 | U-0 | R/W-0   | R/W-0   | R/W-0   | R/W-0  | R/W-0  | R/W-0  |
|-------|-----|---------|---------|---------|--------|--------|--------|
| RD16  | _   | T1CKPS1 | T1CKPS0 | T10SCEN | T1SYNC | TMR1CS | TMR10N |
| bit 7 |     |         |         |         |        |        | bit 0  |

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Timer1 in one 16-bit operation
  - 0 = Enables register read/write of Timer1 in two 8-bit operations
- bit 6 **Unimplemented:** Read as '0'
- bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 3 T10SCEN: Timer1 Oscillator Enable bit
  - 1 = Timer1 oscillator is enabled
  - 0 = Timer1 oscillator is shut off

The oscillator inverter and feedback resistor are turned off to eliminate power drain.

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Select bit

#### When TMR1CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

#### When TMR1CS = 0:

This bit is ignored. Timer1 uses the internal clock when TMR1CS = 0.

- bit 1 TMR1CS: Timer1 Clock Source Select bit
  - 1 = External clock from pin RC0/T10S0/T13CKI (on the rising edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR10N: Timer1 On bit
  - 1 = Enables Timer1
  - 0 = Stops Timer1

| Legend:           |                  |                                    |                    |  |  |  |
|-------------------|------------------|------------------------------------|--------------------|--|--|--|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0' |                    |  |  |  |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared               | x = Bit is unknown |  |  |  |

#### 12.1 Timer1 Operation

Timer1 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The operating mode is determined by the clock select bit, TMR1CS (T1CON<1>).

When TMR1CS = 0, Timer1 increments every instruction cycle. When TMR1CS = 1, Timer1 increments on every rising edge of the external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T13CKI pins become inputs. That is, the TRISC<1:0> value is ignored and the pins are read as '0'.

Timer1 also has an internal "Reset input". This Reset can be generated by the ECCP1 or ECCP2 special event trigger. This is discussed in detail in Section 12.4 "Resetting Timer1 Using an ECCP Special Trigger Output".

#### FIGURE 12-1: TIMER1 BLOCK DIAGRAM



#### FIGURE 12-2: TIMER1 BLOCK DIAGRAM: 16-BIT READ/WRITE MODE



#### 12.2 Timer1 Oscillator

A crystal oscillator circuit is built-in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON<3>). The oscillator is a low-power oscillator rated up to 200 kHz. It will continue to run during Sleep. It is primarily intended for a 32 kHz crystal. The circuit for a typical LP oscillator is shown in Figure 12-3. Table 12-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

# FIGURE 12-3: EXTERNAL COMPONENTS FOR THE TIMER1 LP OSCILLATOR




TABLE 12-1: CAPACITOR SELECTION FOR THE ALTERNATE OSCILLATOR<sup>(2-4)</sup>

| Osc Type   | Freq    | C1                      | C2                      |  |  |  |  |  |
|------------|---------|-------------------------|-------------------------|--|--|--|--|--|
| LP         | 32 kHz  | 15-22 pF <sup>(1)</sup> | 15-22 pF <sup>(1)</sup> |  |  |  |  |  |
|            | Crystal | Tested                  |                         |  |  |  |  |  |
| 32.768 kHz |         |                         |                         |  |  |  |  |  |

- **Note 1:** Microchip suggests 33 pF as a starting point in validating the oscillator circuit.
  - **2:** Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **4:** Capacitor values are for design guidance only.

#### 12.3 Timer1 Interrupt

The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR1 interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit, TMR1IF (PIR1<0>). This interrupt can be enabled/disabled by setting/clearing the TMR1 Interrupt Enable bit, TMR1IE (PIE1<0>).

#### 12.4 Resetting Timer1 Using an ECCP Special Trigger Output

If either the ECCP1 or ECCP2 module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer1. The trigger for ECCP2 will also start an A/D conversion if the A/D module is enabled.

**Note:** The special event triggers from the ECCP1 module will not set interrupt flag bit TMR1IF (PIR1<0>).

Timer1 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from ECCP1, the write will take precedence.

In this mode of operation, the CCPR1H:CCPR1L register pair effectively becomes the period register for Timer1.

#### 12.5 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes (see Figure 12-2). When the RD16 control bit (T1CON<7>) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L will load the contents of the high byte of Timer1 into the Timer1 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, is valid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.

The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

#### 12.6 Using Timer1 as a Real-Time Clock

Adding an external LP oscillator to Timer1 (such as the one described in **Section 12.2 "Timer1 Oscillator"**) gives users the option to include RTC functionality to their applications. This is accomplished with an inexpensive watch crystal to provide an accurate time base and several lines of application code to calculate the time. When operating in Sleep mode and using a battery or supercapacitor as a power source, it can completely eliminate the need for a separate RTC device and battery backup.

The application code routine, RTCisr, shown in Example 12-1, demonstrates a simple method to increment a counter at one-second intervals using an Interrupt Service Routine. Incrementing the TMR1 register pair to overflow, triggers the interrupt and calls

the routine which increments the seconds counter by one; additional counters for minutes and hours are incremented as the previous counter overflow.

Since the register pair is 16 bits wide, counting up to overflow the register directly from a 32.768 kHz clock would take 2 seconds. To force the overflow at the required one-second intervals, it is necessary to preload it. The simplest method is to set the Most Significant bit of TMR1H with a BSF instruction. Note that the TMR1L register is never preloaded or altered; doing so may introduce cumulative error over many cycles.

For this method to be accurate, Timer1 must operate in Asynchronous mode and the Timer1 overflow interrupt must be enabled (PIE1<0> = 1), as shown in the routine, RTCinit. The Timer1 oscillator must also be enabled and running at all times.

#### EXAMPLE 12-1: IMPLEMENTING A REAL-TIME CLOCK USING A TIMER1 INTERRUPT SERVICE

```
RTCinit
          MOVLW
                  0x80
                                 ; Preload TMR1 register pair
                                 ; for 1 second overflow
          MOVWF
                  TMR1H
          CLRF
                  TMR1L
                  b'00001111'
          MOVLW
                                ; Configure for external clock,
                                 ; Asynchronous operation, external oscillator
          MOVWF
                  T1CON
          CLRF
                                ; Initialize timekeeping registers
                  secs
          CLRF
                  mins
          M-TVOM
                  .12
          MOVWE
                  hours
          BSF
                  PIE1, TMR1IE ; Enable Timer1 interrupt
          RETURN
RTCisr
          BSF
                  TMR1H, 7
                                ; Preload for 1 sec overflow
                  PIR1, TMR1IF ; Clear interrupt flag
          BCF
          INCF
                  secs. F
                                ; Increment seconds
          MOVIW 59
                                ; 60 seconds elapsed?
          CPFSGT secs
          RETURN
                                ; No, done
                                ; Clear seconds
          CLRF secs
                                ; Increment minutes
          INCF
                  mins, F
          MOVLW
                  .59
                                ; 60 minutes elapsed?
          CPFSGT mins
          RETURN
                                ; No, done
                  mins
          CLRF
                                 ; clear minutes
          INCF
                                ; Increment hours
                  hours, F
          MOVLW
                  .23
                                 ; 24 hours elapsed?
          CPFSGT hours
          RETURN
                                 ; No, done
                                 ; Reset hours to 1
          MOVLW
                  .01
          MOVWF
                  hours
                                 ; Done
          RETURN
```

#### TABLE 12-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

| Name   | Bit 7   | Bit 6        | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR, BOR |      | Valu<br>all o<br>Res | ther |
|--------|---|--------------|--------|--------|-------|--------|--------|--------|----------------------|------|----------------------|------|
| INTCON | GIE/GIEH  | PEIE/GIEL    | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 0000                 | 000x | 0000                 | 000u |
| PIR1   | PSPIF <sup>(1)</sup>                                | ADIF         | RC1IF  | TX1IF  | SSPIF | CCP1IF | TMR2IF | TMR1IF | 0000                 | 0000 | 0000                 | 0000 |
| PIE1   | PSPIE <sup>(1)</sup>                                | ADIE         | RC1IE  | TX1IE  | SSPIE | CCP1IE | TMR2IE | TMR1IE | 0000                 | 0000 | 0000                 | 0000 |
| IPR1   | PSPIP <sup>(1)</sup>                                | ADIP         | RC1IP  | TX1IP  | SSPIP | CCP1IP | TMR2IP | TMR1IP | 1111                 | 1111 | 1111                 | 1111 |
| TMR1L  | Timer1 Reg  | ister Low By | te     |        |       |        |        |        | xxxx                 | xxxx | uuuu                 | uuuu |
| TMR1H  | Timer1 Register High Byte                           |              |        |        |       |        |        |        |                      | xxxx | uuuu                 | uuuu |
| T1CON  | RD16 — T1CKPS1 T1CKPS0 T1OSCEN T1SYNC TMR1CS TMR1ON |              |        |        |       |        |        | 0-00   | 0000                 | u-uu | uuuu                 |      |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

NOTES:

#### 13.0 TIMER2 MODULE

The Timer2 module timer has the following features:

- 8-bit timer (TMR2 register)
- 8-bit period register (PR2)
- · Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- Interrupt on TMR2 match of PR2
- MSSP module optional use of TMR2 output to generate clock shift

Timer2 has a control register shown in Register 13-1. Timer2 can be shut off by clearing control bit TMR2ON (T2CON<2>) to minimize power consumption. Figure 13-1 is a simplified block diagram of the Timer2 module. Register 13-1 shows the Timer2 Control register. The prescaler and postscaler selection of Timer2 are controlled by this register.

#### 13.1 Timer2 Operation

Timer2 can be used as the PWM time base for the PWM mode of the ECCP module. The TMR2 register is readable and writable and is cleared on any device Reset. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON<1:0>). The match output of TMR2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR2 interrupt, latched in flag bit TMR2IF (PIR1<1>).

The prescaler and postscaler counters are cleared when any of the following occurs:

- · a write to the TMR2 register
- a write to the T2CON register
- any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset, or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

#### REGISTER 13-1: T2CON: TIMER2 CONTROL REGISTER

| U-0   | R/W-0    | R/W-0    | R/W-0    | R/W-0    | R/W-0  | R/W-0   | R/W-0   |
|-------|----------|----------|----------|----------|--------|---------|---------|
| _     | T2OUTPS3 | T2OUTPS2 | T2OUTPS1 | T2OUTPS0 | TMR2ON | T2CKPS1 | T2CKPS0 |
| bit 7 |          |          |          |          |        |         | bit 0   |

bit 7 Unimplemented: Read as '0'

bit 6-3 **T20UTPS3:T20UTPS0**: Timer2 Output Postscale Select bits

0000 = 1:1 Postscale 0001 = 1:2 Postscale

•

1111 = 1:16 Postscale

bit 2 TMR2ON: Timer2 On bit

1 = Timer2 is on

0 = Timer2 is off

bit 1-0 T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits

00 = Prescaler is 1 01 = Prescaler is 4 1x = Prescaler is 16

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 13.2 Timer2 Interrupt

The Timer2 module has an 8-bit period register, PR2. Timer2 increments from 00h until it matches PR2 and then resets to 00h on the next increment cycle. PR2 is a readable and writable register. The PR2 register is initialized to FFh upon Reset.

#### 13.3 Output of TMR2

The output of TMR2 (before the postscaler) is fed to the synchronous serial port module which optionally uses it to generate the shift clock.

FIGURE 13-1: TIMER2 BLOCK DIAGRAM




TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

| Name   | Bit 7                | Bit 6                  | Bit 5    | Bit 4    | Bit 3    | Bit 2  | Bit 1   | Bit 0   | Value on<br>POR, BOR |      | Valu<br>all c<br>Res | ther |
|--------|----------------------|------------------------|----------|----------|----------|--------|---------|---------|----------------------|------|----------------------|------|
| INTCON | GIE/GIEH             | PEIE/GIEL              | TMR0IE   | INT0IE   | RBIE     | TMR0IF | INT0IF  | RBIF    | 0000                 | 000x | 0000                 | 000u |
| PIR1   | PSPIF <sup>(1)</sup> | ADIF                   | RC1IF    | TX1IF    | SSPIF    | CCP1IF | TMR2IF  | TMR1IF  | 0000                 | 0000 | 0000                 | 0000 |
| PIE1   | PSPIE <sup>(1)</sup> | ADIE                   | RC1IE    | TX1IE    | SSPIE    | CCP1IE | TMR2IE  | TMR1IE  | 0000                 | 0000 | 0000                 | 0000 |
| IPR1   | PSPIP <sup>(1)</sup> | ADIP                   | RC1IP    | TX1IP    | SSPIP    | CCP1IP | TMR2IP  | TMR1IP  | 1111                 | 1111 | 1111                 | 1111 |
| TMR2   | Timer2 Mo            | dule Register          | •        |          |          |        |         |         | 0000                 | 0000 | 0000                 | 0000 |
| T2CON  | -                    | T2OUTPS3               | T2OUTPS2 | T2OUTPS1 | T2OUTPS0 | TMR2ON | T2CKPS1 | T2CKPS0 | -000                 | 0000 | -000                 | 0000 |
| PR2    | Timer2 Per           | Timer2 Period Register |          |          |          |        |         |         |                      |      |                      |      |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

### 14.0 TIMER3 MODULE

The Timer3 module timer/counter has the following features:

- 16-bit timer/counter
  - (two 8-bit registers: TMR3H and TMR3L)
- Readable and writable (both registers)
- · Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- · Reset from ECCP module trigger

Figure 14-1 is a simplified block diagram of the Timer3 module.

Register 14-1 shows the Timer3 Control register. This register controls the operating mode of the Timer3 module and sets the CCP/ECCP clock source.

Register 12-1 shows the Timer1 Control register. This register controls the operating mode of the Timer1 module, as well as contains the Timer1 oscillator enable bit (T1OSCEN) which can be a clock source for Timer3.

## REGISTER 14-1: T3CON: TIMER3 CONTROL REGISTER

| R/W-0 | R/W-0  | R/W-0   | R/W-0   | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|--------|---------|---------|--------|--------|--------|--------|
| RD16  | T3CCP2 | T3CKPS1 | T3CKPS0 | T3CCP1 | T3SYNC | TMR3CS | TMR3ON |
| bit 7 |        |         |         |        |        |        | bit 0  |

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Timer3 in one 16-bit operation
  - 0 = Enables register read/write of Timer3 in two 8-bit operations
- bit 6,3 T3CCP2:T3CCP1: Timer3 and Timer1 to CCPx Enable bits
  - 11 = Timer3 and Timer4 are the clock sources for ECCP1 through CCP5
  - 10 = Timer3 and Timer4 are the clock sources for ECCP3 through CCP5;
    - Timer1 and Timer2 are the clock sources for ECCP1 and ECCP2
  - 01 = Timer3 and Timer4 are the clock sources for ECCP2 through CCP5;
    - Timer1 and Timer2 are the clock sources for ECCP1
  - 00 = Timer1 and Timer2 are the clock sources for ECCP1 through CCP5
- bit 5-4 T3CKPS1:T3CKPS0: Timer3 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 2 **T3SYNC:** Timer3 External Clock Input Synchronization Control bit (Not usable if the system clock comes from Timer1/Timer3)

#### When TMR3CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

### When TMR3CS = $\underline{0}$ :

This bit is ignored. Timer3 uses the internal clock when TMR3CS = 0.

- bit 1 TMR3CS: Timer3 Clock Source Select bit
  - 1 = External clock input from Timer1 oscillator or T13CKI (on the rising edge after the first falling edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR3ON: Timer3 On bit
  - 1 = Enables Timer3
  - 0 = Stops Timer3

| Lea |    |
|-----|----|
|     |    |
| LCU | ч. |

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared <math>x = Bit is unknown

## 14.1 Timer3 Operation

Timer3 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The operating mode is determined by the clock select bit, TMR3CS (T3CON<1>).

When TMR3CS = 0, Timer3 increments every instruction cycle. When TMR3CS = 1, Timer3 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T13CKI pins become inputs. That is, the TRISC<1:0> value is ignored and the pins are read as '0'.

Timer3 also has an internal "Reset input". This Reset can be generated by the ECCP module (Section 14.0 "Timer3 Module").

## FIGURE 14-1: TIMER3 BLOCK DIAGRAM



## FIGURE 14-2: TIMER3 BLOCK DIAGRAM CONFIGURED IN 16-BIT READ/WRITE MODE



#### 14.2 Timer1 Oscillator

The Timer1 oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN (T1CON<3>) bit. The oscillator is a low-power oscillator rated up to 200 kHz. See **Section 12.0** "**Timer1 Module**" for further details.

## 14.3 Timer3 Interrupt

The TMR3 register pair (TMR3H:TMR3L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR3 interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit, TMR3IF (PIR2<1>). This interrupt can be enabled/disabled by setting/clearing TMR3 interrupt enable bit, TMR3IE (PIE2<1>).

# 14.4 Resetting Timer3 Using an ECCP Special Trigger Output

If either the ECCP1 or ECCP2 module is configured in Compare mode to generate a special event trigger (CCP1M3:CCP1M0 = 1011), this signal will reset Timer3.

**Note:** The special event triggers from the ECCP module will not set interrupt flag bit, TMR3IF (PIR1<0>).

Timer3 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer3 is running in Asynchronous Counter mode, this Reset operation may not work. In the event that a write to Timer3 coincides with a special event trigger from ECCP1, the write will take precedence. In this mode of operation, the CCPR1H:CCPR1L register pair effectively becomes the period register for Timer3.

TABLE 14-1: REGISTERS ASSOCIATED WITH TIMER3 AS A TIMER/COUNTER

| Name   | Bit 7        | Bit 6         | Bit 5   | Bit 4   | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Value o |     | Valu<br>all o<br>Res |      |
|--------|--------------|---------------|---------|---------|---------|--------|--------|--------|---------|-----|----------------------|------|
| INTCON | GIE/<br>GIEH | PEIE/<br>GIEL | TMR0IE  | INT0IE  | RBIE    | TMR0IF | INT0IF | RBIF   | 0000 0  | 00x | 0000                 | 000u |
| PIR2   | _            | CMIF          | _       | EEIF    | BCLIF   | LVDIF  | TMR3IF | CCP2IF | -0-0 0  | 000 | -0-0                 | 0000 |
| PIE2   |              | CMIE          | 1       | EEIE    | BCLIE   | LVDIE  | TMR3IE | CCP2IE | -0-0 0  | 000 | -0-0                 | 0000 |
| IPR2   |              | CMIP          | _       | EEIP    | BCLIP   | LVDIP  | TMR3IP | CCP2IP | -1-1 1  | 111 | -1-1                 | 1111 |
| TMR3L  | Timer3 Re    | egister Low   | Byte    |         |         |        |        |        | xxxx x  | xxx | uuuu                 | uuuu |
| TMR3H  | Timer3 Re    | egister High  | Byte    |         |         |        |        |        | xxxx x  | xxx | uuuu                 | uuuu |
| T1CON  | RD16         | ı             | T1CKPS1 | T1CKPS0 | T1OSCEN | T1SYNC | TMR1CS | TMR10N | 0-00 0  | 000 | u-uu                 | uuuu |
| T3CON  | RD16         | T3CCP2        | T3CKPS1 | T3CKPS0 | T3CCP1  | T3SYNC | TMR3CS | TMR3ON | 0000 0  | 000 | uuuu                 | uuuu |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the Timer3 module.

NOTES:

## 15.0 TIMER4 MODULE

The Timer4 module timer has the following features:

- 8-bit timer (TMR4 register)
- 8-bit period register (PR4)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- · Interrupt on TMR4 match of PR4

Timer4 has a control register shown in Register 15-1. Timer4 can be shut off by clearing control bit, TMR4ON (T4CON<2>), to minimize power consumption. The prescaler and postscaler selection of Timer4 are also controlled by this register. Figure 15-1 is a simplified block diagram of the Timer4 module.

## 15.1 Timer4 Operation

Timer4 can be used as the PWM time base for the PWM mode of the CCP module. The TMR4 register is readable and writable and is cleared on any device Reset. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T4CKPS1:T4CKPS0 (T4CON<1:0>). The match output of TMR4 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR4 interrupt, latched in flag bit TMR4IF (PIR3<3>).

The prescaler and postscaler counters are cleared when any of the following occurs:

- · a write to the TMR4 register
- a write to the T4CON register
- any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset, or Brown-out Reset)

TMR4 is not cleared when T4CON is written.

#### REGISTER 15-1: T4CON: TIMER4 CONTROL REGISTER

| U-0   | R/W-0    | R/W-0    | R/W-0    | R/W-0    | R/W-0  | R/W-0   | R/W-0   |
|-------|----------|----------|----------|----------|--------|---------|---------|
| _     | T4OUTPS3 | T4OUTPS2 | T4OUTPS1 | T4OUTPS0 | TMR4ON | T4CKPS1 | T4CKPS0 |
| bit 7 |          |          |          |          |        |         | bit 0   |

bit 7 Unimplemented: Read as '0'

bit 6-3 **T40UTPS3:T40UTPS0**: Timer4 Output Postscale Select bits

0000 = 1:1 Postscale 0001 = 1:2 Postscale

•

1111 = 1:16 Postscale

bit 2 TMR4ON: Timer4 On bit

1 = Timer4 is on 0 = Timer4 is off

bit 1-0 T4CKPS1:T4CKPS0: Timer4 Clock Prescale Select bits

00 =Prescaler is 1 01 =Prescaler is 4 1x =Prescaler is 16

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 15.2 Timer4 Interrupt

The Timer4 module has an 8-bit period register, PR4, which is both readable and writable. Timer4 increments from 00h until it matches PR4 and then resets to 00h on the next increment cycle. The PR4 register is initialized to FFh upon Reset.

## 15.3 Output of TMR4

The output of TMR4 (before the postscaler) is used only as a PWM time base for the CCP modules. It is not used as a baud rate clock for the MSSP, as is the Timer2 output.

FIGURE 15-1: TIMER4 BLOCK DIAGRAM




TABLE 15-1: REGISTERS ASSOCIATED WITH TIMER4 AS A TIMER/COUNTER

| Name   | Bit 7      | Bit 6  | Bit 5   | Bit 4   | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Value<br>POR, E |      | Valu<br>all o<br>Res | ther |
|--------|------------|--|---------|---------|--------|--------|--------|--------|-----------------|------|----------------------|------|
| INTCON | GIE/GIEH   | GIEH PEIE/GIEL TMROIE INTOIE RBIE TMROIF INTOIF RE |         |         |        |        |        |        |                 | 000x | 0000                 | 000u |
| IPR3   | _          | - RC2IP TX2IP TMR4IP CCP5IP CCP4IP CC              |         |         |        |        |        |        |                 |      | 00                   | 0000 |
| PIR3   | _          | - RC2IF TX2IF TMR4IF CCP5IF CCP4IF CC              |         |         |        |        |        |        |                 |      | 00                   | 0000 |
| PIE3   | _          | -  | RC2IE   | TX2IE   | TMR4IE | CCP5IE | CCP4IE | CCP3IE | 00 (            | 0000 | 00                   | 0000 |
| TMR4   | Timer4 Reg | mer4 Register                                      |         |         |        |        |        |        | 0000            | 0000 | 0000                 | 0000 |
| T4CON  | _          | T4OUTPS3   | T4CKPS1 | T4CKPS0 | -000 ( | 0000   | -000   | 0000   |                 |      |                      |      |
| PR4    | Timer4 Per | Timer4 Period Register                             |         |         |        |        |        |        | 1111 1          | 1111 | 1111                 | 1111 |

Legend: x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the Timer4 module.

# 16.0 CAPTURE/COMPARE/PWM (CCP) MODULES

PIC18F6525/6621/8525/8621 devices all have a total of five CCP (Capture/Compare/PWM) modules. Two of these (CCP4 and CCP5) implement standard Capture, Compare and Pulse-Width Modulation (PWM) modes and are discussed in this section. The other three modules (ECCP1, ECCP2, ECCP3) implement standard Capture and Compare modes, as well as Enhanced PWM modes. These are discussed in Section 17.0 "Enhanced Capture/Compare/PWM (ECCP) Module".

Each CCP/ECCP module contains a 16-bit register which can operate as a 16-bit Capture register, a 16-bit Compare register or a PWM Master/Slave Duty Cycle register. For the sake of clarity, all CCP module operation in the following sections is described with respect to CCP4, but is equally applicable to CCP5.

Capture and Compare operations described in this chapter apply to all standard and Enhanced CCP modules. The operations of PWM mode described in **Section 16.4 "PWM Mode"** apply to CCP4 and CCP5 only.

Note: Throughout this section and Section 17.0 "Enhanced Capture/Compare/PWM (ECCP) Module", references to register and bit names that may be associated with a specific CCP module are referred to generically by the use of 'x' or 'y' in place of the specific module number. Thus, "CCPxCON" might refer to the control register for CCP4 or CCP5, or ECCP1, ECCP2 or ECCP3. "CCPxCON" is used throughout these sections to refer to the module control register, regardless of whether the CCP module is a standard or Enhanced implementation.

## REGISTER 16-1: CCPxCON REGISTER (CCP4 AND CCP5 MODULES)

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-----|-------|-------|--------|--------|--------|--------|
| _     | _   | DCxB1 | DCxB0 | CCPxM3 | CCPxM2 | CCPxM1 | CCPxM0 |
| bit 7 |     |       |       |        |        |        | bit 0  |

bit 7-6 Unimplemented: Read as '0'

bit 5-4 **DCxB1:DCxB0**: PWM Duty Cycle bit 1 and bit 0 for CCP Module x

Capture mode:

Unused.

Compare mode:

Unused.

PWM mode:

These bits are the two Least Significant bits (bit 1 and bit 0) of the 10-bit PWM duty cycle. The eight Most Significant bits (DCx9:DCx2) of the duty cycle are found in CCPRxL.

bit 3-0 CCPxM3:CCPxM0: CCP Module x Mode Select bits

0000 = Capture/Compare/PWM disabled (resets CCPx module)

0001 = Reserved

0010 = Compare mode, toggle output on match (CCPxIF bit is set)

0011 = Reserved

0100 = Capture mode, every falling edge

0101 = Capture mode, every rising edge

0110 = Capture mode, every 4th rising edge

0111 = Capture mode, every 16th rising edge

1000 = Compare mode; initialize CCP pin low; on compare match, force CCP pin high (CCPIF bit is set)

1001 = Compare mode; initialize CCP pin high; on compare match, force CCP pin low (CCPIF bit is set)

1010 = Compare mode; generate software interrupt on compare match (CCPIF bit is set, CCP pin reflects I/O state)

1011 = Reserved

11xx = PWM mode

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 16.1 CCP Module Configuration

Each Capture/Compare/PWM module is associated with a control register (generically, CCPxCON) and a data register (CCPRx). The data register in turn is comprised of two 8-bit registers: CCPRxL (low byte) and CCPRxH (high byte). All registers are both readable and writable.

# 16.1.1 CCP MODULES AND TIMER RESOURCES


The CCP/ECCP modules utilize Timers 1, 2, 3 or 4, depending on the mode selected. Timer1 and Timer3 are available to modules in Capture or Compare modes, while Timer2 and Timer4 are available for modules in PWM mode.

TABLE 16-1: CCP MODE – TIMER RESOURCE

| CCP Mode | Timer Resource   |
|----------|------------------|
| Capture  | Timer1 or Timer3 |
| Compare  | Timer1 or Timer3 |
| PWM      | Timer2 or Timer4 |


The assignment of a particular timer to a module is determined by the Timer-to-CCP enable bits in the T3CON register (Register 14-1, page 143). Depending on the configuration selected, up to four timers may be active at once, with modules in the same configuration (Capture/Compare or PWM) sharing timer resources. The possible configurations are shown in Figure 16-1.

FIGURE 16-1: CCP AND TIMER INTERCONNECT CONFIGURATIONS




Timer1 is used for all Capture and Compare operations for all CCP modules. Timer2 is used for PWM operations for all CCP modules. Modules may share either timer resource as a common time base.

Timer3 and Timer4 are not available.



Timer1 and Timer2 are used for Capture and Compare or PWM operations for ECCP1 only (depending on selected mode).


All other modules use either Timer3 or Timer4. Modules may share either timer resource as a common time base if they are in Capture/Compare or PWM modes.



T3CCP<2:1> = 10

Timer1 and Timer2 are used for Capture and Compare or PWM operations for ECCP1 and ECCP2 only (depending on the mode selected for each module). Both modules may use a timer as a common time base if they are both in Capture/Compare or PWM modes.

The other modules use either Timer3 or Timer4. Modules may share either timer resource as a common time base if they are in Capture/Compare or PWM modes.



Timer3 is used for all Capture and Compare operations for all CCP modules. Timer4 is used for PWM operations for all CCP modules. Modules may share either timer resource as a common time base.

Timer1 and Timer2 are not available.

## 16.2 Capture Mode

In Capture mode, the CCPR4H:CCPR4L register pair captures the 16-bit value of the TMR1 or TMR3 registers when an event occurs on pin RG3/CCP4/P1D. An event is defined as one of the following:

- · every falling edge
- · every rising edge
- · every 4th rising edge
- · every 16th rising edge

The event is selected by the mode select bits, CCP4M3:CCP4M0 (CCP4CON<3:0>). When a capture is made, the interrupt request flag bit CCP4IF (PIR3<1>) is set; it must be cleared in software. If another capture occurs before the value in register CCPR4 is read, the old captured value is overwritten by the new captured value.

### 16.2.1 CCP PIN CONFIGURATION

In Capture mode, the RG3/CCP4/P1D pin should be configured as an input by setting the TRISG<3> bit.

**Note:** If the RG3/CCP4/P1D is configured as an output, a write to the port can cause a capture condition.

#### 16.2.2 TIMER1/TIMER3 MODE SELECTION

The timers that are to be used with the capture feature (Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation may not work. The timer to be used with each CCP module is selected in the T3CON register (see Section 16.1.1 "CCP Modules and Timer Resources").

#### 16.2.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep bit CCP4IE (PIE3<1>) clear to avoid false interrupts and should clear the flag bit, CCP4IF, following any such change in operating mode.

### 16.2.4 CCP PRESCALER


There are four prescaler settings in Capture mode; they are specified as part of the operating mode selected by the mode select bits (CCP4M3:CCP4M0). Whenever the CCP module is turned off or the CCP module is not in Capture mode, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared; therefore, the first capture may be from a non-zero prescaler. Example 16-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

# EXAMPLE 16-1: CHANGING BETWEEN CAPTURE PRESCALERS

```
CLRF CCP4CON ; Turn CCP module off
MOVLW NEW_CAPT_PS ; Load WREG with the
; new prescaler mode
; value and CCP ON
MOVWF CCP4CON ; Load CCP1CON with
; this value
```

## FIGURE 16-2: CAPTURE MODE OPERATION BLOCK DIAGRAM



## 16.3 Compare Mode

In Compare mode, the 16-bit CCPR1 register value is constantly compared against either the TMR1 or TMR3 register pair value. When a match occurs, the CCP4 pin can be:

- · driven high
- · driven low
- toggled (high-to-low or low-to-high)
- remain unchanged (that is, reflects the state of the I/O latch)

The action on the pin is based on the value of the mode select bits (CCP4M3:CCP4M0). At the same time, the interrupt flag bit CCP4IF is set.

#### 16.3.1 CCP PIN CONFIGURATION

The user must configure the CCPx pin as an output by clearing the appropriate TRIS bit.

Note:

Clearing the CCP4CON register will force the RG3/CCP4/P1D compare output latch to the default low level. This is not the PORTG I/O data latch.

#### 16.3.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode or Synchronized Counter mode, if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

### 16.3.3 SOFTWARE INTERRUPT MODE

When the Generate Software Interrupt mode is chosen (CCP4M3:CCP4M0 = 1010), the CCP4 pin is not affected. Only a CCP interrupt is generated if enabled and the CCP4IE bit is set.

### 16.3.4 SPECIAL EVENT TRIGGER

Although shown in Figure 16-3, the compare on match special event triggers are not implemented on CCP4 or CCP5; they are only available on ECCP1 and ECCP2. Their operation is discussed in detail in **Section 17.2.1** "**Special Event Trigger**".

FIGURE 16-3: COMPARE MODE OPERATION BLOCK DIAGRAM




TABLE 16-2: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, TIMER1 AND TIMER3

| Name    | Bit 7                     | Bit 6         | Bit 5      | Bit 4         | Bit 3         | Bit 2    | Bit 1  | Bit 0     | Value on POR, BOR | Value on<br>all other<br>Resets |
|---------|---------------------------|---------------|------------|---------------|---------------|----------|--------|-----------|-------------------|---------------------------------|
| INTCON  | GIE/GIEH                  | PEIE/GIEL     | TMR0IE     | INT0IE        | RBIE          | TMR0IF   | INT0IF | RBIF      | 0000 000x         | 0000 000u                       |
| RCON    | IPEN                      | _             | _          | RI            | TO            | PD       | POR    | BOR       | 01 11qq           | 0q qquu                         |
| PIR1    | PSPIF <sup>(1)</sup>      | ADIF          | RC1IF      | TX1IF         | SSPIF         | CCP1IF   | TMR2IF | TMR1IF    | 0000 0000         | 0000 0000                       |
| PIE1    | PSPIE <sup>(1)</sup>      | ADIE          | RC1IE      | TX1IE         | SSPIE         | CCP1IE   | TMR2IE | TMR1IE    | 0000 0000         | 0000 0000                       |
| IPR1    | PSPIP <sup>(1)</sup>      | ADIP          | RC1IP      | TX1IP         | SSPIP         | CCP1IP   | TMR2IP | TMR1IP    | 1111 1111         | 1111 1111                       |
| PIR2    | _                         | CMIF          | _          | EEIF          | BCLIF         | LVDIF    | TMR3IF | CCP2IF    | -0-0 0000         | 0 0000                          |
| PIE2    | _                         | CMIE          | _          | EEIE          | BCLIE         | LVDIE    | TMR3IE | CCP2IE    | -0-0 0000         | 0 0000                          |
| IPR2    | _                         | CMIP          | _          | EEIP          | BCLIP         | LVDIP    | TMR3IP | CCP2IP    | -1-1 1111         | 1 1111                          |
| PIR3    | _                         | _             | RC2IF      | TX2IF         | TMR4IF        | CCP5IF   | CCP4IF | CCP3IF    | 00 0000           | 00 0000                         |
| PIE3    | _                         | _             | RC2IE      | TX2IE         | TMR4IE        | CCP5IE   | CCP4IE | CCP3IE    | 00 0000           | 00 0000                         |
| IPR3    | _                         | -             | RC2IP      | TX2IP         | TMR4IP        | CCP5IP   | CCP4IP | CCP3IP    | 11 1111           | 11 1111                         |
| TRISB   | PORTB Da                  | ata Direction | Register   |               |               |          |        |           | 1111 1111         | 1111 1111                       |
| TRISC   | PORTC Da                  | ata Direction | Register   |               |               |          |        |           | 1111 1111         | 1111 1111                       |
| TRISE   | PORTE Da                  | ata Direction | Register   |               |               |          |        |           | 1111 1111         | 1111 1111                       |
| TRISG   | _                         | _             | _          | PORTG Da      | ata Direction | Register |        |           | 1 1111            | 1 1111                          |
| TMR1L   | Timer1 Re                 | gister Low B  | yte        |               |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| TMR1H   | Timer1 Register High Byte |               |            |               |               |          |        | xxxx xxxx | uuuu uuuu         |                                 |
| T1CON   | RD16                      | _             | T1CKPS1    | T1CKPS0       | T10SCEN       | T1SYNC   | TMR1CS | TMR10N    | 0-00 0000         | u-uu uuuu                       |
| TMR3H   | Timer3 Re                 | gister High E | Byte       |               |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| TMR3L   | Timer3 Re                 | gister Low B  | yte        |               |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| T3CON   | RD16                      | T3CCP2        | T3CKPS1    | T3CKPS0       | T3CCP1        | T3SYNC   | TMR3CS | TMR3ON    | 0000 0000         | uuuu uuuu                       |
| CCPR1L  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 1 | Low Byte      |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCPR1H  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 1 | High Byte     |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCP1CON | P1M1                      | P1M0          | DC1B1      | DC1B0         | CCP1M3        | CCP1M2   | CCP1M1 | CCP1M0    | 0000 0000         | 0000 0000                       |
| CCPR2L  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 2 | Low Byte      |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCPR2H  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 2 | High Byte     |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCP2CON | P2M1                      | P2M0          | DC2B1      | DC2B0         | CCP2M3        | CCP2M2   | CCP2M1 | CCP2M0    | 0000 0000         | 0000 0000                       |
| CCPR3L  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 3 | Low Byte      |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCPR3H  | Enhanced                  | Capture/Co    | mpare/PWN  | /I Register 3 | High Byte     |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCP3CON | P3M1                      | P3M0          | DC3B1      | DC3B0         | ССР3М3        | CCP3M2   | CCP3M1 | CCP3M0    | 0000 0000         | 0000 0000                       |
| CCPR4L  | Capture/Co                | ompare/PWI    | M Register | 4 Low Byte    |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCPR4H  | Capture/Co                | ompare/PWI    | M Register | 4 High Byte   |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCP4CON | _                         | _             | DC4B1      | DC4B0         | CCP4M3        | CCP4M2   | CCP4M1 | CCP4M0    | 00 0000           | 00 0000                         |
| CCPR5L  | Capture/Co                | ompare/PWI    | M Register | 5 Low Byte    |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCPR5H  | Capture/Co                | ompare/PWI    | M Register | 5 High Byte   |               |          |        |           | xxxx xxxx         | uuuu uuuu                       |
| CCP5CON | _                         |               | DC5B1      | DC5B0         | CCP5M3        | CCP5M2   | CCP5M1 | CCP5M0    | 00 0000           | 00 0000                         |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'.

Shaded cells are not used by Capture and Compare, Timer1 or Timer3.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

#### 16.4 PWM Mode


In Pulse-Width Modulation (PWM) mode, the CCP4 pin produces up to a 10-bit resolution PWM output. Since the CCP4 pin is multiplexed with the PORTG data latch, the TRISG<3> bit must be cleared to make the CCP4 pin an output.

Note: Clearing the CCP4CON register will force the CCP4 PWM output latch to the default low level. This is not the PORTG I/O data latch.

Figure 16-4 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up the CCP module for PWM operation, see **Section 16.4.3** "**Setup for PWM Operation**".

# FIGURE 16-4: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 16-5) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

### FIGURE 16-5: PWM OUTPUT



#### 16.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 (PR4) register. The PWM period can be calculated using the following formula:

### **EQUATION 16-1:**

PWM Period = [(PR2) + 1] • 4 • Tosc • (TMR2 Prescale Value)

PWM frequency is defined as 1/[PWM period].

When TMR2 (TMR4) is equal to PR2 (PR2), the following three events occur on the next increment cycle:

- TMR2 (TMR4) is cleared
- The CCP4 pin is set (exception: if PWM duty cycle = 0%, the CCP4 pin will not be set)
- The PWM duty cycle is latched from CCPR4L into CCPR4H

Note: The Timer2 and Timer4 postscalers (see Section 13.0 "Timer2 Module") are not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

## 16.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR4L register and to the CCP4CON<5:4> bits. Up to 10-bit resolution is available. The CCPR4L contains the eight MSbs and the CCP4CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR4L:CCP4CON<5:4>. The following equation is used to calculate the PWM duty cycle in time:

## **EQUATION 16-2:**

PWM Duty Cycle = (CCPR4L:CCP4CON<5:4>) • Tosc • (TMR2 Prescale Value)

CCPR4L and CCP4CON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPR4H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR4H is a read-only register.

The CCPR4H register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation.

When the CCPR4H and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP4 pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by the equation:

## **EQUATION 16-3:**

PWM Resolution (max) = 
$$\frac{\log\left(\frac{FOSC}{FPWM}\right)}{\log(2)}$$
 bits

**Note:** If the PWM duty cycle value is longer than the PWM period, the CCP4 pin will not be cleared.

#### 16.4.3 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- Select TMR2 or TMR4 by setting or clearing the T3CCP2:T3CCP1 bits in the T3CON register.
- Set the PWM period by writing to the PR2 or PR4 register
- 3. Set the PWM duty cycle by writing to the CCPR4L register and CCP4CON<5:4> bits.
- 4. Make the CCP4 pin an output by clearing the TRISG<3> bit.
- Set TMR2 or TMR4 prescale value, enable Timer2 or Timer4 by writing to T2CON or T4CON.
- 6. Configure the CCP4 module for PWM operation.

TABLE 16-3: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

| PWM Frequency              | 2.44 kHz | 9.77 kHz | 39.06 kHz | 156.25 kHz | 312.50 kHz | 416.67 kHz |
|----------------------------|----------|----------|-----------|------------|------------|------------|
| Timer Prescaler (1, 4, 16) | 16       | 4        | 1         | 1          | 1          | 1          |
| PR2 Value                  | FFh      | FFh      | FFh       | 3Fh        | 1Fh        | 17h        |
| Maximum Resolution (bits)  | 14       | 12       | 10        | 8          | 7          | 6.58       |

TABLE 16-4: REGISTERS ASSOCIATED WITH PWM, TIMER2 AND TIMER4

| Name    | Bit 7                | Bit 6  | Bit 5        | Bit 4         | Bit 3     | Bit 2     | Bit 1   | Bit 0   | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|---------|----------------------|--|--------------|---------------|-----------|-----------|---------|---------|----------------------|---------------------------------|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                      | TMR0IE       | INT0IE        | RBIE      | TMR0IF    | INT0IF  | RBIF    | 0000 000x            | 0000 000u                       |
| RCON    | IPEN                 |  | _            | RI            | TO        | PD        | POR     | BOR     | 01 11qq              | 0q qquu                         |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF   | RC1IF        | TX1IF         | SSPIF     | CCP1IF    | TMR2IF  | TMR1IF  | 0000 0000            | 0000 0000                       |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE   | RC1IE        | TX1IE         | SSPIE     | CCP1IE    | TMR2IE  | TMR1IE  | 0000 0000            | 0000 0000                       |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP   | RC1IP        | TMR1IP        | 1111 1111 | 1111 1111 |         |         |                      |                                 |
| PIR2    | _                    | CMIF   | _            | CCP2IF        | -0-0 0000 | 0 0000    |         |         |                      |                                 |
| PIE2    | _                    | CMIE   | _            | EEIE          | BCLIE     | LVDIE     | TMR3IE  | CCP2IE  | -0-0 0000            | 0 0000                          |
| IPR2    | _                    | CMIP   | _            | TMR3IP        | CCP2IP    | -1-1 1111 | 1 1111  |         |                      |                                 |
| PIR3    | _                    | - RC2IF TX2IF TMR4IF CCP5IF CCP4IF             |              |               |           |           |         |         | 00 0000              | 00 0000                         |
| PIE3    | _                    | - RC2IE TX2IE TMR4IE CCP5IE CCP4IE CC          |              |               |           |           |         |         | 00 0000              | 00 0000                         |
| IPR3    | _                    | -  | RC2IP        | TX2IP         | TMR4IP    | CCP5IP    | CCP4IP  | CCP3IP  | 11 1111              | 11 1111                         |
| TMR2    | Timer2 Re            | gister   |              |               |           |           |         |         | 0000 0000            | 0000 0000                       |
| PR2     | Timer2 Per           | riod Register                                  |              |               |           |           |         |         | 1111 1111            | 1111 1111                       |
| T2CON   | _                    | T2OUTPS3                                       | T2OUTPS2     | T2OUTPS1      | T2OUTPS0  | TMR2ON    | T2CKPS1 | T2CKPS0 | -000 0000            | -000 0000                       |
| T3CON   | RD16                 | T3CCP2   | T3CKPS1      | T3CKPS0       | T3CCP1    | T3SYNC    | TMR3CS  | TMR3ON  | 0000 0000            | uuuu uuuu                       |
| TMR4    | Timer4 Re            | gister   |              |               |           |           |         | •       | 0000 0000            | uuuu uuuu                       |
| PR4     | Timer4 Per           | riod Register                                  |              |               |           |           |         |         | 1111 1111            | uuuu uuuu                       |
| T4CON   | _                    | T4OUTPS3                                       | T4OUTPS2     | T4OUTPS1      | T4OUTPS0  | TMR4ON    | T4CKPS1 | T4CKPS0 | -000 0000            | uuuu uuuu                       |
| CCPR1L  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 1 Lo | w Byte    |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR1H  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 1 Hi | gh Byte   |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP1CON | P1M1                 | P1M0   | DC1B1        | DC1B0         | CCP1M3    | CCP1M2    | CCP1M1  | CCP1M0  | 0000 0000            | 0000 0000                       |
| CCPR2L  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 2 Lo | w Byte    |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR2H  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 2 Hi | gh Byte   |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP2CON | P2M1                 | P2M0   | DC2B1        | DC2B0         | CCP2M3    | CCP2M2    | CCP2M1  | CCP2M0  | 0000 0000            | 0000 0000                       |
| CCPR3L  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 3 Lo | w Byte    |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR3H  | Enhanced             | Capture/Con                                    | npare/PWM I  | Register 3 Hi | gh Byte   |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP3CON | P3M1                 | P3M0   | DC3B1        | DC3B0         | ССР3М3    | CCP3M2    | CCP3M1  | ССР3М0  | 0000 0000            | 0000 0000                       |
| CCPR4L  | Capture/Co           | ompare/PWN                                     | 1 Register 4 | Low Byte      |           |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR4H  | Capture/Co           | ompare/PWN                                     | 1 Register 4 | High Byte     |           |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP4CON |                      | - DC4B1 DC4B0 CCP4M3 CCP4M2 CCP4M <sup>-</sup> |              |               |           |           |         |         | 00 0000              | 00 0000                         |
| CCPR5L  | Capture/Co           | ompare/PWN                                     | 1 Register 5 | Low Byte      |           |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR5H  | Capture/Co           | ompare/PWN                                     | 1 Register 5 | High Byte     |           |           |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP5CON | _                    | _  | DC5B1        | DC5B0         | CCP5M3    | CCP5M2    | CCP5M1  | CCP5M0  | 00 0000              | 00 0000                         |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by PWM, Timer2 or Timer4.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

## 17.0 ENHANCED CAPTURE/ COMPARE/PWM (ECCP) MODULE

The Enhanced CCP (ECCP) modules differ from the standard CCP modules by the addition of Enhanced PWM capabilities. These allow for 2 or 4 output channels, user selectable polarity, dead-band control and automatic shutdown and restart and are discussed in detail in **Section 17.4** "Enhanced PWM Mode". Except for the addition of the special event trigger,

Capture and Compare functions of the ECCP module are the same as the standard CCP module.

The prototype control register for the Enhanced CCP module is shown in Register 17-1. In addition to the expanded range of modes available through the CCPxCON register, the ECCP modules each have two additional registers associated with Enhanced PWM operation and auto-shutdown features. They are:

- · ECCPxDEL (Dead-Band Delay)
- ECCPxAS (Auto-Shutdown Configuration)

## REGISTER 17-1: CCPxCON REGISTER (ECCP1, ECCP2 AND ECCP3 MODULES)

| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-------|-------|-------|--------|--------|--------|--------|
| PxM1  | PxM0  | DCxB1 | DCxB0 | CCPxM3 | CCPxM2 | CCPxM1 | CCPxM0 |
| bit 7 | -     | -     | -     | -      | -      |        | bit 0  |

### bit 7-6 **PxM1:PxM0:** Enhanced PWM Output Configuration bits

If CCPxM3:CCPxM2 = 00, 01, 10:

xx = PxA assigned as Capture/Compare input/output; PxB, PxC, PxD assigned as port pins If CCPxM3:CCPxM2 = 11:

- 00 = Single output: PxA modulated; PxB, PxC, PxD assigned as port pins
- 01 = Full-bridge output forward: P1D modulated; P1A active; P1B, P1C inactive
- 10 = Half-bridge output: P1A, P1B modulated with dead-band control; P1C, P1D assigned as port pins
- 11 = Full-bridge output reverse: P1B modulated; P1C active; P1A, P1D inactive

#### bit 5-4 **DCxB1:DCxB0**: PWM Duty Cycle bit 1 and bit 0

Capture mode:

Unused.

Compare mode:

Unused.

### PWM mode:

These bits are the two LSbs of the 10-bit PWM duty cycle. The eight MSbs of the duty cycle are found in CCPRxL.

#### bit 3-0 CCPxM3:CCPxM0: Enhanced CCP Mode Select bits

- 0000 = Capture/Compare/PWM off (resets ECCPx module)
- 0001 = Reserved
- 0010 = Compare mode, toggle output on match
- 0011 = Capture mode
- 0100 = Capture mode, every falling edge
- 0101 = Capture mode, every rising edge
- 0110 = Capture mode, every 4th rising edge
- 0111 = Capture mode, every 16th rising edge
- 1000 = Compare mode, initialize ECCP pin low, set output on compare match (set CCPxIF)
- 1001 = Compare mode, initialize ECCP pin high, clear output on compare match (set CCPxIF)
- 1010 = Compare mode, generate software interrupt only, ECCP pin reverts to I/O state
- 1011 = Compare mode, trigger special event (ECCP resets TMR1 or TMR3, sets CCxIF bit, ECCP2 trigger starts A/D conversion if A/D module is enabled)<sup>(1)</sup>
- 1100 = PWM mode; PxA, PxC active-high; PxB, PxD active-high
- 1101 = PWM mode; PxA, PxC active-high; PxB, PxD active-low
- 1110 = PWM mode; PxA, PxC active-low; PxB, PxD active-high
- 1111 = PWM mode; PxA, PxC active-low; PxB, PxD active-low

Note 1: Implemented only for ECCP1 and ECCP2; same as '1010' for ECCP3.

| Legend:           |                  |   |
|-------------------|------------------|---|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0'        |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared $x = Bit$ is unknown |

## 17.1 ECCP Outputs and Configuration

Each of the Enhanced CCP modules may have up to four PWM outputs, depending on the selected operating mode. These outputs, designated PxA through PxD, are multiplexed with various I/O pins. Some ECCP pin assignments are constant, while others change based on device configuration. For those pins that do change, the controlling bits are:

- CCP2MX configuration bit (CONFIG3H<0>)
- ECCPMX configuration bit (CONFIG3H<1>)
- Program Memory mode (set by configuration bits CONFIG3L<1:0>)

The pin assignments for the Enhanced CCP modules are summarized in Table 17-1, Table 17-2 and Table 17-3. To configure the I/O pins as PWM outputs, the proper PWM mode must be selected by setting the PxMx and CCPxMx bits (CCPxCON<7:6> and <3:0>, respectively). The appropriate TRIS direction bits for the corresponding port pins must also be set as outputs.

# 17.1.1 USE OF CCP4 AND CCP5 WITH ECCP1 AND ECCP3

Only the ECCP2 module has four dedicated output pins available for use. Assuming that the I/O ports or other multiplexed functions on those pins are not needed, they may be used whenever needed without interfering with any other CCP module.

ECCP1 and ECCP3, on the other hand, only have three dedicated output pins: ECCPx/PxA, PxB and PxC. Whenever these modules are configured for Quad PWM mode, the pin normally used for CCP4 or CCP5 becomes the D output pins for ECCP3 and ECCP1, respectively. The CCP4 and CCP5 modules remain functional but their outputs are overridden.

# 17.1.2 ECCP MODULE OUTPUTS AND PROGRAM MEMORY MODES

For PIC18F8525/8621 devices, the Program Memory mode of the device (**Section 4.1.1 "PIC18F6525/6621/8525/8621 Program Memory Modes"**) impacts both pin multiplexing and the operation of the module.

The ECCP2 input/output (ECCP2/P2A) can be multiplexed to one of three pins. By default, this is RC1 for all devices. In this case, the default occurs when CCP2MX is set and the device is operating in Microcontroller mode. With PIC18F8525/8621 devices, three other options exist. When CCP2MX is not set (= 0) and the device is in Microcontroller mode, ECCP2/P2A is multiplexed to RE7; in all other program memory modes, it is multiplexed to RB3.

The final option is for CCP2MX to be set while the device is operating in one of the three other program memory modes. In this case, ECCP1 and ECCP3 operate as compatible (i.e., single output) CCP modules. The pins used by their other outputs (PxB through PxD) are available for other multiplexed functions. ECCP2 continues to operate as an Enhanced CCP module regardless of the program memory mode.

TABLE 17-1: PIN CONFIGURATIONS FOR ECCP1

| IADLL II-I.  | BEL 17-1. FIN CONTIGURATIONS FOR ECCET |                |               |               |               |          |          |  |  |  |
|--|--|----------------|---------------|---------------|---------------|----------|----------|--|--|--|
| ECCP Mode  | CCP1CON<br>Configuration               | RC2            | RE6           | RE5           | RG4           | RH7      | RH6      |  |  |  |
|  |  | All P          | PIC18F6525/66 | 321 devices:  |               |          |          |  |  |  |
| Compatible CCP   | 00xx 11xx                              | ECCP1          | RE6           | RE5           | RG4/CCP5      | N/A      | N/A      |  |  |  |
| Dual PWM   | 10xx 11xx                              | P1A            | P1B           | RE5           | RG4/CCP5      | N/A      | N/A      |  |  |  |
| Quad PWM   | x1xx 11xx                              | P1A            | P1B           | P1C           | P1D           | N/A      | N/A      |  |  |  |
| PIC18F8525/8621 devices, ECCPMX = 1, Microcontroller mode: |  |                |               |               |               |          |          |  |  |  |
| Compatible CCP   | 00xx 11xx                              | ECCP1          | RE6/AD14      | RE5/AD13      | RG4/CCP5      | RH7/AN15 | RH6/AN14 |  |  |  |
| Dual PWM   | 10xx 11xx                              | P1A            | P1B           | RE5/AD13      | RG4/CCP5      | RH7/AN15 | RH6/AN14 |  |  |  |
| Quad PWM   | x1xx 11xx                              | P1A            | P1B           | P1C           | P1D           | RH7/AN15 | RH6/AN14 |  |  |  |
|  | PIC18F8                                | 525/8621 dev   | rices, ECCPM  | X = 0, Microc | ontroller mod | de:      |          |  |  |  |
| Compatible CCP   | 00xx 11xx                              | ECCP1          | RE6/AD14      | RE5/AD13      | RG4/CCP5      | RH7/AN15 | RH6/AN14 |  |  |  |
| Dual PWM   | 10xx 11xx                              | P1A            | RE6/AD14      | RE5/AD13      | RG4/CCP5      | P1B      | RH6/AN14 |  |  |  |
| Quad PWM   | x1xx 11xx                              | P1A            | RE6/AD14      | RE5/AD13      | P1D           | P1B      | P1C      |  |  |  |
|  | PIC18F8525/86                          | 321 devices, l | ECCPMX = 1,   | all other Pro | gram Memory   | / modes: |          |  |  |  |
| Compatible CCP   | 00xx 11xx                              | ECCP1          | RE6/AD14      | RE5/AD13      | RG4/CCP5      | RH7/AN15 | RH6/AN14 |  |  |  |

**Legend:** x = Don't care, N/A = Not available. Shaded cells indicate pin assignments not used by ECCP1 in a given mode. **Note 1:** With ECCP1 in Quad PWM mode, CCP5's output is overridden by P1D; otherwise CCP5 is fully operational.

TABLE 17-2: PIN CONFIGURATIONS FOR ECCP2

| ECCP Mode      | CCP2CON<br>Configuration                       | RB3            | RC1          | RE7            | RE2         | RE1    | RE0    |  |  |
|----------------|--|----------------|--------------|----------------|-------------|--------|--------|--|--|
|                | A  | All devices, C | CP2MX = 1, N | licrocontrolle | er mode:    |        |        |  |  |
| Compatible CCP | 00xx 11xx                                      | RB3/INT3       | ECCP2        | RE7            | RE2         | RE1    | RE0    |  |  |
| Dual PWM       | 10xx 11xx                                      | RB3/INT3       | P2A          | RE7            | P2B         | RE1    | RE0    |  |  |
| Quad PWM       | x1xx 11xx                                      | RB3/INT3       | P2A          | RE7            | P2B         | P2C    | P2D    |  |  |
|                | All devices, CCP2MX = 0, Microcontroller mode: |                |              |                |             |        |        |  |  |
| Compatible CCP | 00xx 11xx                                      | RB3/INT3       | RC1/T1OS1    | ECCP2          | RE2         | RE1    | RE0    |  |  |
| Dual PWM       | 10xx 11xx                                      | RB3/INT3       | RC1/T1OS1    | P2A            | P2B         | RE1    | RE0    |  |  |
| Quad PWM       | x1xx 11xx                                      | RB3/INT3       | RC1/T1OS1    | P2A            | P2B         | P2C    | P2D    |  |  |
|                | PIC18F8525/86                                  | 321 devices,   | CCP2MX = 0,  | all other Prog | gram Memory | modes: |        |  |  |
| Compatible CCP | 00xx 11xx                                      | ECCP2          | RC1/T1OS1    | RE7/AD15       | RE2/CS      | RE1/WR | RE0/RD |  |  |
| Dual PWM       | 10xx 11xx                                      | P2A            | RC1/T1OS1    | RE7/AD15       | P2B         | RE1/WR | RE0/RD |  |  |
| Quad PWM       | x1xx 11xx                                      | P2A            | RC1/T1OS1    | RE7/AD15       | P2B         | P2C    | P2D    |  |  |

**Legend:** x = Don't care. Shaded cells indicate pin assignments not used by ECCP2 in a given mode.

**TABLE 17-3: PIN CONFIGURATIONS FOR ECCP3** 

| ECCP Mode  | CCP3CON<br>Configuration | RG0          | RE4           | RE3           | RG3           | RH5      | RH4      |  |  |
|--|--------------------------|--------------|---------------|---------------|---------------|----------|----------|--|--|
|  |                          | All F        | PIC18F6525/66 | 21 devices:   |               |          |          |  |  |
| Compatible CCP   | 00xx 11xx                | ECCP3        | RE4           | RE3           | RG3/CCP4      | N/A      | N/A      |  |  |
| Dual PWM   | 10xx 11xx                | P3A          | P3B           | RE3           | RG3/CCP4      | N/A      | N/A      |  |  |
| Quad PWM   | x1xx 11xx                | P3A          | P3B           | P3C           | P3D           | N/A      | N/A      |  |  |
| PIC18F8525/8621 devices, ECCPMX = 1, Microcontroller mode: |                          |              |               |               |               |          |          |  |  |
| Compatible CCP   | 00xx 11xx                | ECCP3        | RE4/AD12      | RE3/AD11      | RG3/CCP4      | RH5/AN13 | RH4/AN12 |  |  |
| Dual PWM   | 10xx 11xx                | P3A          | P3B           | RE3/AD11      | RG3/CCP4      | RH5/AN13 | RH4/AN12 |  |  |
| Quad PWM   | x1xx 11xx                | P3A          | P3B           | P3C           | P3D           | RH5/AN13 | RH4/AN12 |  |  |
|  | PIC18F8                  | 525/8621 dev | rices, ECCPM  | X = 0, Microc | ontroller mod | de:      |          |  |  |
| Compatible CCP   | 00xx 11xx                | ECCP3        | RE6/AD14      | RE5/AD13      | RG3/CCP4      | RH7/AN15 | RH6/AN14 |  |  |
| Dual PWM   | 10xx 11xx                | P3A          | RE6/AD14      | RE5/AD13      | RG3/CCP4      | P3B      | RH6/AN14 |  |  |
| Quad PWM   | x1xx 11xx                | P3A          | RE6/AD14      | RE5/AD13      | P3D           | P3B      | P3C      |  |  |
|  | PIC18F8525/86            | 21 devices,  | ECCPMX = 1,   | all other Pro | gram Memory   | modes:   |          |  |  |
| Compatible CCP   | 00xx 11xx                | ECCP3        | RE6/AD14      | RE5/AD13      | RG3/CCP4      | RH7/AN15 | RH6/AN14 |  |  |

**Legend:** x = Don't care, N/A = Not available. Shaded cells indicate pin assignments not used by ECCP3 in a given mode. **Note 1:** With ECCP3 in Quad PWM mode, CCP4's output is overridden by P1D; otherwise CCP4 is fully operational.

# 17.1.3 ECCP MODULES AND TIMER RESOURCES

Like the standard CCP modules, the ECCP modules can utilize Timers 1, 2, 3 or 4, depending on the mode selected. Timer1 and Timer3 are available for modules in Capture or Compare modes, while Timer2 and Timer4 are available for modules in PWM mode. Additional details on timer resources are provided in Section 16.1.1 "CCP Modules and Timer Resources".

## 17.2 Capture and Compare Modes

Except for the operation of the special event trigger discussed below, the Capture and Compare modes of the ECCP module are identical in operation to that of CCP4. These are discussed in detail in Section 16.2 "Capture Mode" and Section 16.3 "Compare Mode".

### 17.2.1 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated in Compare mode, on a match between the CCPR register pair and the selected timer. This can be used in turn to initiate an action.

The special event trigger output of either ECCP1 or ECCP2 resets the TMR1 or TMR3 register pair, depending on which timer resource is currently selected. This allows the CCPRx register to effectively be a 16-bit programmable period register for Timer1 or Timer3. In addition, the ECCP2 special event trigger will also start an A/D conversion if the A/D module is enabled.

The triggers are not implemented for ECCP3, CCP4 or CCP5. Selecting the Special Event mode (CCPxM3:CCPxM0 = 1011) for these modules has the same effect as selecting the Compare with Software Interrupt mode (CCPxM3:CCPxM0 = 1010).

Note: The special event trigger from ECCP2 will not set the Timer1 or Timer3 interrupt flag bits.

## 17.3 Standard PWM Mode

When configured in Single Output mode, the ECCP module functions identically to the standard CCP module in PWM mode as described in **Section 16.4** "**PWM Mode**". This is also sometimes referred to as "Compatible CCP" mode as in Tables 17-1 through 17-3.

Note: When setting up single output PWM operations, users are free to use either of the processes described in Section 16.4.3 "Setup for PWM Operation" or Section 17.4.9 "Setup for PWM Operation". The latter is more generic but will work for either single or multi-output PWM.

#### 17.4 Enhanced PWM Mode

The Enhanced PWM mode provides additional PWM output options for a broader range of control applications. The module is a backward compatible version of the standard CCP module and offers up to four outputs, designated PxA through PxD. Users are also able to select the polarity of the signal (either active-high or active-low). The module's output mode and polarity are configured by setting the PxM1:PxM0 and CCPxM3CCPxM0 bits of the CCPxCON register (CCPxCON<7:6> and CCPxCON<3:0>, respectively).

For the sake of clarity, Enhanced PWM mode operation is described generically throughout this section with respect to ECCP1 and TMR2 modules. Control register names are presented in terms of ECCP1. All three Enhanced modules, as well as the two timer resources, can be used interchangeably and function identically. TMR2 or TMR4 can be selected for PWM operation by selecting the proper bits in T3CON.

Figure 17-1 shows a simplified block diagram of PWM operation. All control registers are double-buffered and are loaded at the beginning of a new PWM cycle (the period boundary when Timer2 resets) in order to prevent glitches on any of the outputs. The exception is the PWM Delay register, ECCP1DEL, which is loaded at either the duty cycle boundary or the boundary period (whichever comes first). Because of the buffering, the module waits until the assigned timer resets instead of starting immediately. This means that Enhanced PWM waveforms do not exactly match the standard PWM waveforms, but are instead offset by one full instruction cycle (4 Tosc).

As before, the user must manually configure the appropriate TRIS bits for output.

### 17.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the equation:

#### **EQUATION 17-1:**

PWM Period = [(PR2) + 1] • 4 • Tosc • (TMR2 Prescale Value)

PWM frequency is defined as 1/[PWM period]. When TMR2 is equal to PR2, the following three events occur on the next increment cycle:


· TMR2 is cleared

Note:

- The ECCP1 pin is set (if PWM duty cycle = 0%, the ECCP1 pin will not be set)
- The PWM duty cycle is copied from CCPR1L into CCPR1H

The Timer2 postscaler (see Section 13.0 "Timer2 Module") is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### **FIGURE 17-1:** SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODULE



time base.

#### 17.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. The CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPRxL:CCPxCON<5:4>. The PWM duty cycle is calculated by the equation:

## **EQUATION 17-2:**

CCPR1L and CCP1CON<5:4> can be written to at any time but the duty cycle value is not copied into CCPR1H until a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPRxH register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation. When the CCPR1H and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or two bits of the TMR2 prescaler, the ECCP1 pin is cleared. The maximum PWM resolution (bits) for a given PWM frequency is given by the equation:

#### **EQUATION 17-3:**

PWM Resolution (max) = 
$$\frac{\log\left(\frac{FOSC}{FPWM}\right)}{\log(2)}$$
 bits

Note: If the PWM duty cycle value is longer than the PWM period, the ECCP1 pin will not be cleared.

**TABLE 17-4: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz** 

| PWM Frequency              | 2.44 kHz | 9.77 kHz | 39.06 kHz | 156.25 kHz | 312.50 kHz | 416.67 kHz |
|----------------------------|----------|----------|-----------|------------|------------|------------|
| Timer Prescaler (1, 4, 16) | 16       | 4        | 1         | 1          | 1          | 1          |
| PR2 Value                  | FFh      | FFh      | FFh       | 3Fh        | 1Fh        | 17h        |
| Maximum Resolution (bits)  | 10       | 10       | 10        | 8          | 7          | 6.58       |

#### 17.4.3 PWM OUTPUT CONFIGURATIONS


The P1M1:P1M0 bits in the CCP1CON register allow one of four configurations:


- Single Output
- · Half-Bridge Output
- · Full-Bridge Output, Forward mode
- Full-Bridge Output, Reverse mode

The Single Output mode is the standard PWM mode discussed in **Section 17.4 "Enhanced PWM Mode"**. The Half-Bridge and Full-Bridge Output modes are covered in detail in the sections that follow.

The general relationship of the outputs in all configurations is summarized in Figure 17-2.

FIGURE 17-2: PWM OUTPUT RELATIONSHIPS (ACTIVE-HIGH STATE)





**FIGURE 17-3:** PWM OUTPUT RELATIONSHIPS (ACTIVE-LOW STATE)


#### 17.4.4 HALF-BRIDGE MODE


In the Half-Bridge Output mode, two pins are used as outputs to drive push-pull loads. The PWM output signal is output on the P1A pin, while the complementary PWM output signal is output on the P1B pin (Figure 17-4). This mode can be used for half-bridge applications, as shown in Figure 17-5, or for full-bridge applications, where four power switches are being modulated with two PWM signals.

In Half-Bridge Output mode, the programmable dead-band delay can be used to prevent shoot-through current in half-bridge power devices. The value of bits PDC6:PDC0 sets the number of instruction cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See Section 17.4.6 "Programmable Dead-Band Delay" for more details on dead-band delay operations.

Since the P1A and P1B outputs are multiplexed with the PORTC<2> and PORTE<6> data latches, the TRISC<2> and TRISE<6> bits must be cleared to configure P1A and P1B as outputs.

**FIGURE 17-4: HALF-BRIDGE PWM** OUTPUT






**EXAMPLES OF HALF-BRIDGE OUTPUT MODE APPLICATIONS** 

### 17.4.5 FULL-BRIDGE MODE

In Full-Bridge Output mode, four pins are used as outputs; however, only two outputs are active at a time. In the Forward mode, pin P1A is continuously active and pin P1D is modulated. In the Reverse mode, pin P1C is continuously active and pin P1B is modulated. These are illustrated in Figure 17-6.

P1A, P1B, P1C and P1D outputs are multiplexed with the PORTC<2>, PORTE<6:5> and PORTG<4> data latches. The TRISC<2>, TRISC<6:5> and TRISG<4> bits must be cleared to make the P1A, P1B, P1C and P1D pins outputs.

FIGURE 17-6: FULL-BRIDGE PWM OUTPUT






FIGURE 17-7: EXAMPLE OF FULL-BRIDGE APPLICATION

## 17.4.5.1 Direction Change in Full-Bridge Mode

In the Full-Bridge Output mode, the P1M1 bit in the CCP1CON register allows users to control the forward/reverse direction. When the application firmware changes this direction control bit, the module will assume the new direction on the next PWM cycle.

Just before the end of the current PWM period, the modulated outputs (P1B and P1D) are placed in their inactive state, while the unmodulated outputs (P1A and P1C) are switched to drive in the opposite direction. This occurs in a time interval of (4 Tosc \* (Timer2 Prescale Value) before the next PWM period begins. The Timer2 prescaler will be either 1, 4 or 16, depending on the value of the T2CKPS bit (T2CON<1:0>). During the interval from the switch of the unmodulated outputs to the beginning of the next period, the modulated outputs (P1B and P1D) remain inactive. This relationship is shown in Figure 17-8.

Note that in the Full-Bridge Output mode, the ECCP1 module does not provide any dead-band delay. In general, since only one output is modulated at all times, dead-band delay is not required. However, there is a situation where a dead-band delay might be required. This situation occurs when both of the following conditions are true:

- The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- The turn-off time of the power switch, including the power device and driver circuit, is greater than the turn-on time.


Figure 17-9 shows an example where the PWM direction changes from forward to reverse at a near 100% duty cycle. At time t1, the output P1A and P1D become inactive, while output P1C becomes active. In this example, since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current may flow through power devices QC and QD (see Figure 17-7) for the duration of 't'. The same phenomenon will occur to power devices QA and QB for PWM direction change from reverse to forward.

If changing PWM direction at high duty cycle is required for an application, one of the following requirements must be met:

- 1. Reduce PWM for a PWM period before changing directions.
- Use switch drivers that can drive the switches off faster than they can drive them on.

Other options to prevent shoot-through current may exist.


FIGURE 17-8: PWM DIRECTION CHANGE



Note 1: The direction bit in the ECCP1 Control register (CCP1CON<7>) is written any time during the PWM cycle.

2: When changing directions, the P1A and P1C signals switch before the end of the current PWM cycle at intervals of 4 Tosc, 16 Tosc or 64 Tosc, depending on the Timer2 prescaler value. The modulated P1B and P1D signals are inactive at this time.

FIGURE 17-9: PWM DIRECTION CHANGE AT NEAR 100% DUTY CYCLE



Note 1: All signals are shown as active-high.

2: t<sub>ON</sub> is the turn-on delay of power switch QC and its driver.

3:  $t_{\text{OFF}}$  is the turn-off delay of power switch QD and its driver.

# 17.4.6 PROGRAMMABLE DEAD-BAND DELAY

In half-bridge applications where all power switches are modulated at the PWM frequency at all times, the power switches normally require more time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on and the other turned off), both switches may be on for a short period of time until one switch completely turns off. During this brief interval, a very high current (shoot-through current) may flow through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on either of the power switches is normally delayed to allow the other switch to completely turn off.

In the Half-Bridge Output mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 17-4 for illustration. The lower seven bits of the ECCPxDEL register (Register 17-2) set the delay period in terms of microcontroller instruction cycles (Tcy or 4 Tosc).

## 17.4.7 ENHANCED PWM AUTO-SHUTDOWN

When an ECCP module is programmed for any PWM mode, the active output pin(s) may be configured for auto-shutdown. Auto-shutdown immediately places the PWM output pin(s) into a defined shutdown state when a shutdown event occurs.

A shutdown event can be caused by either of the two comparator modules or the INTO/FLT0 pin (or any combination of these three sources). The comparators may be used to monitor a voltage input proportional to a current being monitored in the bridge circuit. If the voltage exceeds a threshold, the comparator switches state and triggers a shutdown. Alternatively, a digital signal on the INTO/FLTO pin can also trigger a shutdown. The auto-shutdown feature can be disabled by not selecting any auto-shutdown sources. The auto-shutdown sources to be used are selected using ECCP1AS2:ECCP1AS0 bits (bits<6:4> the ECCP1AS register).

When a shutdown occurs, the output pin(s) are asynchronously placed in their shutdown states, specified by the PSS1AC1:PSS1AC0 and PSS1BD1:PSS1BD0 bits (ECCP1AS3:ECCP1AS0). Each pin pair (P1A/P1C and P1B/P1D) may be set to drive high, drive low or be tri-stated (not driving). The ECCP1ASE bit (ECCP1AS<7>) is also set to hold the Enhanced PWM outputs in their shutdown states.

The ECCP1ASE bit is set by hardware when a shutdown event occurs. If automatic restarts are not enabled, the ECCPASE bit is cleared by firmware when the cause of the shutdown clears. If automatic restarts are enabled, the ECCPASE bit is automatically cleared when the cause of the Auto-Shutdown has cleared.

If the ECCPASE bit is set when a PWM period begins, the PWM outputs remain in their shutdown state for that entire PWM period. When the ECCPASE bit is cleared, the PWM outputs will return to normal operation at the beginning of the next PWM period.

**Note:** Writing to the ECCPASE bit is disabled while a shutdown condition is active.

## REGISTER 17-2: ECCPxDEL: PWM CONFIGURATION REGISTER

| R/W-0  | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|--------|-------|-------|-------|-------|-------|-------|-------|
| PxRSEN | PxDC6 | PxDC5 | PxDC4 | PxDC3 | PxDC2 | PxDC1 | PxDC0 |
| bit 7  |       |       |       |       |       |       | bit 0 |

## bit 7 PxRSEN: PWM Restart Enable bit

- 1 = Upon Auto-Shutdown, the ECCPxASE bit clears automatically once the shutdown event goes away; the PWM restarts automatically
- 0 = Upon Auto-Shutdown, ECCPxASE must be cleared in software to restart the PWM

#### bit 6-0 PxDC6:PxDC0: PWM Delay Count bits

Delay time, in number of Fosc/4 (4 \* Tosc) cycles, between the scheduled and actual time for a PWM signal to transition to active.

| Legend:           |                  |   | ٦ |
|-------------------|------------------|---|---|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0'        |   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared $x = Bit$ is unknown |   |

# REGISTER 17-3: ECCPxAS: ENHANCED CAPTURE/COMPARE/PWM AUTO-SHUTDOWN CONTROL REGISTER

| R/W-0    | R/W-0    | R/W-0    | R/W-0    | R/W-0   | R/W-0   | R/W-0   | R/W-0   |
|----------|----------|----------|----------|---------|---------|---------|---------|
| ECCPxASE | ECCPxAS2 | ECCPxAS1 | ECCPxAS0 | PSSxAC1 | PSSxAC0 | PSSxBD1 | PSSxBD0 |
| bit 7    |          |          |          |         |         |         | bit 0   |

bit 7 ECCPxASE: ECCP Auto-Shutdown Event Status bit

0 = ECCP outputs are operating

1 = A shutdown event has occurred; ECCP outputs are in shutdown state

bit 6-4 ECCPxAS2:ECCPxAS0: ECCP Auto-Shutdown Source Select bits

000 = Auto-shutdown is disabled
001 = Comparator 1 output
010 = Comparator 2 output
011 = Either Comparator 1 or 2

100 = INTO/FLT0

101 = INTO/FLT0 or Comparator 1 110 = INTO/FLT0 or Comparator 2

111 = INT0/FLT0 or Comparator 1 or Comparator 2

bit 3-2 PSSxAC1:PSSxAC0: Pins A and C Shutdown State Control bits

00 = Drive Pins A and C to '0' 01 = Drive Pins A and C to '1' 1x = Pins A and C tri-state

bit 1-0 PSSxBD1:PSSxBD0: Pins B and D Shutdown State Control bits

00 = Drive Pins B and D to '0' 01 = Drive Pins B and D to '1' 1x = Pins B and D tri-state

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 17.4.7.1 Auto-Shutdown and Automatic Restart

The auto-shutdown feature can be configured to allow automatic restarts of the module following a shutdown event. This is enabled by setting the P1RSEN bit of the ECCP1DEL register (ECCP1DEL<7>).

In Shutdown mode with PRSEN = 1 (Figure 17-10), the ECCPASE bit will remain set for as long as the cause of the shutdown continues. When the shutdown condition clears, the ECCP1ASE bit is cleared. If PRSEN = 0 (Figure 17-11), once a shutdown condition occurs, the ECCP1ASE bit will remain set until it is cleared by firmware. Once ECCP1ASE is cleared, the Enhanced PWM will resume at the beginning of the next PWM period.

**Note:** Writing to the ECCPASE bit is disabled while a shutdown condition is active.

Independent of the P1RSEN bit setting, if the auto-shutdown source is one of the comparators, the shutdown condition is a level. The ECCP1ASE bit cannot be cleared as long as the cause of the shutdown persists.

The Auto-Shutdown mode can be forced by writing a '1' to the ECCPASE bit.

#### 17.4.8 START-UP CONSIDERATIONS

When the ECCP module is used in the PWM mode, the application hardware must use the proper external pull-up and/or pull-down resistors on the PWM output pins. When the microcontroller is released from Reset, all of the I/O pins are in the high-impedance state. The external circuits must keep the power switch devices in the off state until the microcontroller drives the I/O pins with the proper signal levels, or activates the PWM output(s).

The CCP1M1:CCP1M0 bits (CCP1CON<1:0>) allow the user to choose whether the PWM output signals are active-high or active-low for each pair of PWM output pins (P1A/P1C and P1B/P1D). The PWM output polarities must be selected before the PWM pins are configured as outputs. Changing the polarity configuration while the PWM pins are configured as outputs is not recommended since it may result in damage to the application circuits.

The P1A, P1B, P1C and P1D output latches may not be in the proper states when the PWM module is initialized. Enabling the PWM pins for output at the same time as the ECCP module may cause damage to the application circuit. The ECCP module must be enabled in the proper output mode and complete a full PWM cycle before configuring the PWM pins as outputs. The completion of a full PWM cycle is indicated by the TMR2IF bit being set as the second PWM period begins.





FIGURE 17-10: PWM AUTO-SHUTDOWN (PRSEN = 1, AUTO-RESTART ENABLED)





#### 17.4.9 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the ECCP1 module for PWM operation using Timer2:

- Configure the PWM pins, P1A and P1B (and P1C and P1D, if used), as inputs by setting the corresponding TRIS bits.
- 2. Set the PWM period by loading the PR2 register.
- 3. If auto-shutdown is required do the following:
  - Disable auto-shutdown (ECCP1AS = 0)
  - Configure source (FLT0, Comparator 1 or Comparator 2)
  - · Wait for non-shutdown condition
- Configure the ECCP1 module for the desired PWM mode and configuration by loading the CCP1CON register with the appropriate values:
  - Select one of the available output configurations and direction with the P1M1:P1M0 bits.
  - Select the polarities of the PWM output signals with the CCP1M3:CCP1M0 bits.
- Set the PWM duty cycle by loading the CCPR1L register and CCP1CON<5:4> bits.
- For Half-Bridge Output mode, set the dead-band delay by loading ECCP1DEL<6:0> with the appropriate value.
- If auto-shutdown operation is required, load the ECCP1AS register:
  - Select the auto-shutdown sources using the ECCP1AS2:ECCP1AS0 bits.
  - Select the shutdown states of the PWM output pins using the PSS1AC1:PSS1AC0 and PSS1BD1:PSS1BD0 bits.
  - Set the ECCP1ASE bit (ECCP1AS<7>).
  - Configure the comparators using the CMCON register.
  - Configure the comparator inputs as analog inputs.

- If auto-restart operation is required, set the P1RSEN bit (ECCP1DEL<7>).
- 9. Configure and start TMR2:
  - Clear the TMR2 interrupt flag bit by clearing the TMR2IF bit (PIR1<1>).
  - Set the TMR2 prescale value by loading the T2CKPS bits (T2CON<1:0>).
  - Enable Timer2 by setting the TMR2ON bit (T2CON<2>).
- Enable PWM outputs after a new PWM cycle has started:
  - Wait until TMRn overflows (TMRnIF bit is set).
  - Enable the ECCP1/P1A, P1B, P1C and/or P1D pin outputs by clearing the respective TRIS bits.
  - Clear the ECCP1ASE bit (ECCP1AS<7>).

#### 17.4.10 EFFECTS OF A RESET

Both Power-on Reset and subsequent Resets will force all ports to Input mode and the CCP registers to their Reset states.

This forces the Enhanced CCP module to reset to a state compatible with the standard CCP module.

TABLE 17-5: REGISTERS ASSOCIATED WITH ECCP MODULES AND TIMER1 TO TIMER4

| Name     | Bit 7                | Bit 6          | Bit 5       | Bit 4          | Bit 3          | Bit 2   | Bit 1   | Bit 0   | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|----------------------|----------------|-------------|----------------|----------------|---------|---------|---------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH             | PEIE/GIEL      | TMR0IE      | INT0IE         | RBIE           | TMR0IF  | INT0IF  | RBIF    | 0000 000x            | 0000 000u                       |
| RCON     | IPEN                 | _              | _           | RI             | TO             | PD      | POR     | BOR     | 01 11qq              | 0q qquu                         |
| PIR1     | PSPIF <sup>(1)</sup> | ADIF           | RC1IF       | TX1IF          | SSPIF          | CCP1IF  | TMR2IF  | TMR1IF  | 0000 0000            | 0000 0000                       |
| PIE1     | PSPIE <sup>(1)</sup> | ADIE           | RC1IE       | TX1IE          | SSPIE          | CCP1IE  | TMR2IE  | TMR1IE  | 0000 0000            | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup> | ADIP           | RC1IP       | TX1IP          | SSPIP          | CCP1IP  | TMR2IP  | TMR1IP  | 1111 1111            | 1111 1111                       |
| PIR2     | _                    | CMIF           | _           | EEIF           | BCLIF          | LVDIF   | TMR3IF  | CCP2IF  | -0-0 0000            | 0 0000                          |
| PIE2     | _                    | CMIE           | _           | EEIE           | BCLIE          | LVDIE   | TMR3IE  | CCP2IE  | -0-0 0000            | 0 0000                          |
| IPR2     | _                    | CMIP           | _           | EEIP           | BCLIP          | LVDIP   | TMR3IP  | CCP2IP  | -1-1 1111            | 1 1111                          |
| PIR3     | _                    | _              | RC2IF       | TX2IF          | TMR4IF         | CCP5IF  | CCP4IF  | CCP3IF  | 00 0000              | 00 0000                         |
| PIE3     | _                    | _              | RC2IE       | TX2IE          | TMR4IE         | CCP5IE  | CCP4IE  | CCP3IE  | 00 0000              | 00 0000                         |
| IPR3     | _                    | _              | RC2IP       | TX2IP          | TMR4IP         | CCP5IP  | CCP4IP  | CCP3IP  | 11 1111              | 11 1111                         |
| TRISB    | PORTB Data           | Direction Re   | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TRISC    | PORTC Data           | a Direction Re | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TRISCD   | PORTD Data           | a Direction Re | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TRISE    | PORTE Data           | Direction Re   | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TRISF    | PORTF Data           | Direction Re   | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TRISG    | _                    | _              | _           | PORTG Data     | a Direction Re | gister  |         |         | 1 1111               | 1 1111                          |
| TRISH    | PORTH Data           | a Direction Re | gister      |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TMR1L    | Timer1 Regis         | ster Low Byte  |             |                |                |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| TMR1H    | Timer1 Regi          | ister High By  | te          |                |                |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| T1CON    | RD16                 | _              | T1CKPS1     | T1CKPS0        | T10SCEN        | T1SYNC  | TMR1CS  | TMR10N  | 0-00 0000            | u-uu uuuu                       |
| TMR2     | Timer2 Regis         | ster           |             |                |                |         |         |         | 0000 0000            | 0000 0000                       |
| T2CON    | _                    | T2OUTPS3       | T2OUTPS2    | T2OUTPS1       | T2OUTPS0       | TMR2ON  | T2CKPS1 | T2CKPS0 | -000 0000            | -000 0000                       |
| PR2      | Timer2 Perio         | d Register     |             |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| TMR3L    | Timer3 Regi          | ister Low Byt  | е           |                |                |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| TMR3H    | Timer3 Regi          | ister High By  | te          |                |                |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| T3CON    | RD16                 | T3CCP2         | T3CKPS1     | T3CKPS0        | T3CCP1         | T3SYNC  | TMR3CS  | TMR3ON  | 0000 0000            | uuuu uuuu                       |
| TMR4     | Timer4 Regis         | ster           |             |                |                |         |         |         | 0000 0000            | 0000 0000                       |
| T4CON    | _                    | T4OUTPS3       | T4OUTPS2    | T4OUTPS1       | T4OUTPS0       | TMR4ON  | T4CKPS1 | T4CKPS0 | -000 0000            | -000 0000                       |
| PR4      | Timer4 Perio         | d Register     |             |                |                |         |         |         | 1111 1111            | 1111 1111                       |
| CCPR1L   | Enhanced Ca          | apture/Compa   | are/PWM Reg | ister 1 Low By | yte            |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR1H   | Enhanced Ca          | apture/Compa   |             |                | yte            |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP1CON  | P1M1                 | P1M0           | DC1B1       | DC1B0          | CCP1M3         | CCP1M2  | CCP1M1  | CCP1M0  | 0000 0000            | 0000 0000                       |
| ECCP1AS  | ECCP1ASE             | ECCP1AS2       | ECCP1AS1    | ECCP1AS0       | PSS1AC1        | PSS1AC0 | PSS1BD1 | PSS1BD0 | 0000 0000            | 0000 0000                       |
| ECCP1DEL | P1RSEN               | P1DC6          | P1DC5       | P1DC4          | P1DC3          | P1DC2   | P1DC1   | P1DC0   | 0000 0000            | uuuu uuuu                       |
| CCPR2L   | Enhanced Ca          | apture/Compa   | are/PWM Reg | ister 2 Low By | /te            |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCPR2H   | Enhanced Ca          | apture/Compa   | are/PWM Reg | ister 2 High B | yte            |         |         |         | xxxx xxxx            | uuuu uuuu                       |
| CCP2CON  | P2M1                 | P2M0           | DC2B1       | DC2B0          | CCP2M3         | CCP2M2  | CCP2M1  | CCP2M0  | 0000 0000            | 0000 0000                       |
| ECCP2AS  | ECCP2ASE             | ECCP2AS2       | ECCP2AS1    | ECCP2AS0       | PSS2AC1        | PSS2AC0 | PSS2BD1 | PSS2BD0 | 0000 0000            | 0000 0000                       |
| ECCP2DEL | P2RSEN               | P2DC6          | P2DC5       | P2DC4          | P2DC3          | P2DC2   | P2DC1   | P2DC0   | 0000 0000            | uuuu uuuu                       |
| CCPR3L   | Enhanced Ca          | apture/Compa   |             | xxxx xxxx      | uuuu uuuu      |         |         |         |                      |                                 |
| CCPR3H   | Enhanced Ca          | apture/Compa   |             | xxxx xxxx      | uuuu uuuu      |         |         |         |                      |                                 |
| CCP3CON  | P3M1                 | P3M0           | DC3B1       | DC3B0          | CCP3M3         | CCP3M2  | CCP3M1  | CCP3M0  | 0000 0000            | 0000 0000                       |
| ECCP3AS  | ECCP3ASE             | ECCP3AS2       | ECCP3AS1    | ECCP3AS0       | PSS3AC1        | PSS3AC0 | PSS3BD1 | PSS3BD0 | 0000 0000            | 0000 0000                       |
| ECCP3DEL | Px3RSEN              | P3DC6          | P3DC5       | P3DC4          | P3DC3          | P3DC2   | P3DC1   | P3DC0   | 0000 0000            | uuuu uuuu                       |

 $\textbf{Legend:} \qquad \textbf{x} = \text{unknown}, \textbf{u} = \text{unchanged}, \textbf{--} = \text{unimplemented}, \text{read as `0'}. \text{ Shaded cells are not used during ECCP operation}.$ 

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

## 18.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

## 18.1 Master SSP (MSSP) Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface, useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- · Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)
  - Full Master mode
  - Slave mode (with general address call)

The  $I^2C$  interface supports the following modes in hardware:

- · Master mode
- Multi-Master mode
- Slave mode

## 18.2 Control Registers

The MSSP module has three associated registers. These include a status register (SSPSTAT) and two control registers (SSPCON1 and SSPCON2). The use of these registers and their individual configuration bits differ significantly depending on whether the MSSP module is operated in SPI or I<sup>2</sup>C mode.

Additional details are provided under the individual sections.

#### 18.3 SPI Mode

The SPI mode allows 8 bits of data to be synchronously transmitted and received simultaneously. All four modes of SPI are supported. To accomplish communication, typically three pins are used:


- Serial Data Out (SDO) RC5/SDO
- Serial Data In (SDI) RC4/SDI/SDA
- Serial Clock (SCK) RC3/SCK/SCL

Additionally, a fourth pin may be used when in a Slave mode of operation:

• Slave Select (SS) - RF7/SS

Figure 18-1 shows the block diagram of the MSSP module when operating in SPI mode.

FIGURE 18-1: MSSP BLOCK DIAGRAM (SPI™ MODE)



#### 18.3.1 REGISTERS

The MSSP module has four registers for SPI mode operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer Register (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible

SSPCON1 and SSPSTAT are the control and status registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

## REGISTER 18-1: SSPSTAT: MSSP STATUS REGISTER (SPI MODE)

| R/W-0 | R/W-0 | R-0              | R-0 | R-0 | R-0 | R-0 | R-0   |
|-------|-------|------------------|-----|-----|-----|-----|-------|
| SMP   | CKE   | $D/\overline{A}$ | Р   | S   | R/W | UA  | BF    |
| bit 7 |       |                  |     |     |     |     | bit 0 |

### bit 7 SMP: Sample bit

#### SPI Master mode:

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

#### SPI Slave mode:

SMP must be cleared when SPI is used in Slave mode.

## bit 6 CKE: SPI Clock Edge Select bit

- 1 = Transmit occurs on transition from active to Idle clock state
- 0 = Transmit occurs on transition from Idle to active clock state

**Note:** Polarity of clock state is set by the CKP bit (SSPCON1<4>).

#### bit 5 D/A: Data/Address bit

Used in I<sup>2</sup>C mode only.

#### bit 4 P: Stop bit

Used in I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.

## bit 3 S: Start bit

Used in I<sup>2</sup>C mode only.

## bit 2 R/W: Read/Write bit Information

Used in I<sup>2</sup>C mode only.

## bit 1 UA: Update Address bit

Used in I<sup>2</sup>C mode only.

## bit 0 **BF:** Buffer Full Status bit

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

| Legend |  |
|--------|--|
|--------|--|

| R = Readable bit  | Readable bit W = Writable bit |                      | bit, read as '0'   |
|-------------------|-------------------------------|----------------------|--------------------|
| -n = Value at POR | '1' = Bit is set              | '0' = Bit is cleared | x = Bit is unknown |

## REGISTER 18-2: SSPCON1: MSSP CONTROL REGISTER 1 (SPI MODE)

| bit 7 | •     | •     | •     | •     |       |       | bit 0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |
| R/W-0 |

bit 7 WCOL: Write Collision Detect bit (Transmit mode only)

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision
- bit 6 SSPOV: Receive Overflow Indicator bit

#### SPI Slave mode:

- 1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. The user must read the SSPBUF, even if only transmitting data, to avoid setting overflow (must be cleared in software).
- 0 = No overflow

**Note:** In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

- bit 5 SSPEN: Master Synchronous Serial Port Enable bit
  - 1 = Enables serial port and configures SCK, SDO, SDI and  $\overline{SS}$  as serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, these pins must be properly configured as input or output.

- bit 4 CKP: Clock Polarity Select bit
  - 1 = Idle state for clock is a high level
  - 0 = Idle state for clock is a low level
- bit 3-0 SSPM3:SSPM0: Master Synchronous Serial Port Mode Select bits
  - 0101 = SPI Slave mode, clock = SCK pin, SS pin control disabled, SS can be used as I/O pin
  - 0100 = SPI Slave mode, clock = SCK pin, SS pin control enabled
  - 0011 = SPI Master mode, clock = TMR2 output/2
  - 0010 = SPI Master mode, clock = Fosc/64
  - 0001 = SPI Master mode, clock = Fosc/16
  - 0000 = SPI Master mode, clock = Fosc/4

**Note:** Bit combinations not specifically listed here are either reserved or implemented in I<sup>2</sup>C mode only.

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 18.3.2 OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0>) and SSPSTAT<7:6>. These control bits allow the following to be specified:

- · Master mode (SCK is the clock output)
- Slave mode (SCK is the clock input)
- · Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- Slave Select mode (Slave mode only)

The MSSP consists of a transmit/receive shift register (SSPSR) and a buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then the buffer full detect bit, BF (SSPSTAT<0>) and the interrupt flag bit, SSPIF, are set. This double-buffering of the received data (SSPBUF) allows the next byte to start reception before

reading the data that was just received. Any write to the SSPBUF register during transmission/reception of data will be ignored and the write collision detect bit, WCOL (SSPCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPBUF register completed successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. Buffer full bit, BF (SSPSTAT<0>), indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. The SSPBUF must be read and/or written. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur. Example 18-1 shows the loading of the SSPBUF (SSPSR) for data transmission.

The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPBUF register. Additionally, the MSSP Status register (SSPSTAT) indicates the various status conditions.

## **EXAMPLE 18-1: LOADING THE SSPBUF (SSPSR) REGISTER**

| LOOP | BTFSS<br>BRA<br>MOVF | SSPSTAT, BF<br>LOOP<br>SSPBUF, W | ;Has data been received (transmit complete)? ;No ;WREG reg = contents of SSPBUF |
|------|----------------------|----------------------------------|---|
|      | MOVWF                | RXDATA                           | ;Save in user RAM, if data is meaningful  |
|      | MOVF<br>MOVWF        | TXDATA, W<br>SSPBUF              | ;W reg = contents of TXDATA ;New data to xmit                                   |

#### 18.3.3 ENABLING SPI I/O

To enable the serial port, MSSP Enable bit, SSPEN (SSPCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, re-initialize the SSPCON registers and then set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- · SDI is automatically controlled by the SPI module
- SDO must have TRISC<5> bit cleared
- SCK (Master mode) must have TRISC<3> bit cleared
- SCK (Slave mode) must have TRISC<3> bit set
- SS must have TRISF<7> bit set


Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

#### 18.3.4 TYPICAL CONNECTION

Figure 18-2 shows a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCK signal. Data is shifted out of both shift registers on their programmed clock edge and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends data Slave sends dummy data
- · Master sends data Slave sends data
- · Master sends dummy data Slave sends data

FIGURE 18-2: SPI™ MASTER/SLAVE CONNECTION



#### 18.3.5 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK. The master determines when the slave (Processor 2, Figure 18-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode.


The clock polarity is selected by appropriately programming the CKP bit (SSPCON1<4>). This then, would give waveforms for SPI communication as shown in Figure 18-3, Figure 18-5 and Figure 18-6, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- Timer2 output/2

This allows a maximum data rate (at 40 MHz) of 10.00 Mbps.

Figure 18-3 shows the waveforms for Master mode.

FIGURE 18-3: SPI™ MODE WAVEFORM (MASTER MODE)



#### 18.3.6 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

Before enabling the module in SPI Slave mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit (SSPCON1<4>).

While in Sleep mode, the slave can transmit/receive data. When a byte is received, the device will wake-up from Sleep.

# 18.3.7 SLAVE SELECT SYNCHRONIZATION

The  $\overline{SS}$  pin allows a Synchronous Slave mode. The SPI must be in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON1<3:0> = 04h). The pin must not be driven low for the  $\overline{SS}$  pin to function as an input. The data latch

must be high. When the  $\overline{SS}$  pin is low, transmission and reception are enabled and the SDO pin is driven. When the  $\overline{SS}$  pin goes high, the SDO pin is no longer driven even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.

- Note 1: When the SPI is in Slave mode with SS pin control enabled (SSPCON<3:0> = 0100), the SPI module will reset if the SS pin is set to VDD.
  - 2: If the SPI is used in Slave mode with CKE set, then the SS pin control must be enabled.

When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SS pin to a high level or clearing the SSPEN bit.

To emulate two-wire communication, the SDO pin can be connected to the SDI pin. When the SPI needs to operate as a receiver, the SDO pin can be configured as an input. This disables transmissions from the SDO. The SDI can always be left as an input (SDI function) since it cannot create a bus conflict.




FIGURE 18-5: SPI™ MODE WAVEFORM (SLAVE MODE WITH CKE = 0)





FIGURE 18-6: SPI™ MODE WAVEFORM (SLAVE MODE WITH CKE = 1)



#### 18.3.8 SLEEP OPERATION

In Master mode, all module clocks are halted and the transmission/reception will remain in that state until the device wakes from Sleep. After the device returns to normal mode, the module will continue to transmit/receive data.

In Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device from Sleep.

### 18.3.9 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 18.3.10 BUS MODE COMPATIBILITY

Table 18-1 shows the compatibility between the standard SPI modes and the states of the CKP and CKE control bits.

TABLE 18-1: SPI™ BUS MODES

| Standard SPI Mode | <b>Control Bits State</b> |     |  |  |  |
|-------------------|---------------------------|-----|--|--|--|
| Terminology       | CKP                       | CKE |  |  |  |
| 0, 0              | 0                         | 1   |  |  |  |
| 0, 1              | 0                         | 0   |  |  |  |
| 1, 0              | 1                         | 1   |  |  |  |
| 1, 1              | 1                         | 0   |  |  |  |

There is also a SMP bit which controls when the data is sampled.

TABLE 18-2: REGISTERS ASSOCIATED WITH SPI™ OPERATION

| Name    | Bit 7                                 | Bit 6         | Bit 5            | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR, BOR | Value on all other Resets |
|---------|---------------------------------------|---------------|------------------|--------|--------|--------|--------|--------|----------------------|---------------------------|
| INTCON  | GIE/GIEH                              | PEIE/GIEL     | TMR0IE           | INT0IE | RBIE   | TMR0IF | INT0IF | RBIF   | 0000 000x            | 0000 000u                 |
| PIR1    | PSPIF <sup>(1)</sup>                  | ADIF          | RC1IF            | TX1IF  | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 0000 0000            | 0000 0000                 |
| PIE1    | PSPIE <sup>(1)</sup>                  | ADIE          | RC1IE            | TX1IE  | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 0000 0000            | 0000 0000                 |
| IPR1    | PSPIP <sup>(1)</sup>                  | ADIP          | RC1IP            | TX1IP  | SSPIP  | CCP1IP | TMR2IP | TMR1IP | 1111 1111            | 1111 1111                 |
| TRISC   | PORTC Dat                             | a Direction R | egister          |        |        |        |        |        | 1111 1111            | 1111 1111                 |
| TRISF   | TRISF7                                | TRISF6        | TRISF5           | TRISF4 | TRISF3 | TRISF2 | TRISF1 | TRISF0 | 1111 1111            | 1111 1111                 |
| SSPBUF  | MSSP Receive Buffer/Transmit Register |               |                  |        |        |        |        |        |                      | uuuu uuuu                 |
| SSPCON1 | WCOL                                  | SSPOV         | SSPEN            | CKP    | SSPM3  | SSPM2  | SSPM1  | SSPM0  | 0000 0000            | 0000 0000                 |
| SSPSTAT | SMP                                   | CKE           | $D/\overline{A}$ | Р      | S      | R/W    | UA     | BF     | 0000 0000            | 0000 0000                 |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used by the MSSP in SPI™ mode.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

### 18.4 I<sup>2</sup>C Mode


The MSSP module in I<sup>2</sup>C mode fully implements all master and slave functions (including general call support) and provides interrupts on Start and Stop bits in hardware to determine a free bus (multi-master function). The MSSP module implements the standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- Serial clock (SCL) RC3/SCK/SCL
- Serial data (SDA) RC4/SDI/SDA

The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

FIGURE 18-7: MSSP BLOCK DIAGRAM (I<sup>2</sup>CTM MODE)



#### 18.4.1 REGISTERS

The MSSP module has six registers for I<sup>2</sup>C operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Control Register 2 (SSPCON2)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer Register (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible
- MSSP Address Register (SSPADD)

SSPCON1, SSPCON2 and SSPSTAT are the control and status registers in  $I^2C$  mode operation. The SSPCON1 and SSPCON2 registers are readable and writable. The lower 6 bits of the SSPSTAT are readonly. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

SSPADD register holds the slave device address when the MSSP is configured in I<sup>2</sup>C Slave mode. When the MSSP is configured in Master mode, the lower seven bits of SSPADD act as the Baud Rate Generator reload value.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

### REGISTER 18-3: SSPSTAT: MSSP STATUS REGISTER (I<sup>2</sup>C MODE)

| R/W-0 | R/W-0 | R-0 | R-0 | R-0 | R-0 | R-0 | R-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| SMP   | CKE   | D/A | Р   | S   | R/W | UA  | BF    |
| hit 7 |       |     |     |     |     |     | hit 0 |

bit 7 SMP: Slew Rate Control bit

#### In Master or Slave mode:

- 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz)
- 0 = Slew rate control enabled for High Speed mode (400 kHz)
- bit 6 CKE: SMBus Select bit

### In Master or Slave mode:

- 1 = Enable SMBus specific inputs
- 0 = Disable SMBus specific inputs
- bit 5 D/A: Data/Address bit

### In Master mode:

Reserved

### In Slave mode:

- 1 = Indicates that the last byte received or transmitted was data
- 0 = Indicates that the last byte received or transmitted was address
- bit 4 P: Stop bit
  - 1 = Indicates that a Stop bit has been detected last
  - 0 = Stop bit was not detected last

Note: This bit is cleared on Reset and when SSPEN is cleared.

- bit 3 S: Start bit
  - 1 = Indicates that a Start bit has been detected last
  - 0 = Start bit was not detected last

Note: This bit is cleared on Reset and when SSPEN is cleared.

bit 2 R/W: Read/Write bit Information (I<sup>2</sup>C mode only)

### In Slave mode:

- 1 = Read
- 0 = Write

**Note:** This bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next Start bit, Stop bit or not ACK bit.

### In Master mode:

- 1 = Transmit is in progress
- 0 = Transmit is not in progress

**Note:** ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Idle mode.

- bit 1 **UA:** Update Address bit (10-bit Slave mode only)
  - 1 = Indicates that the user needs to update the address in the SSPADD register
  - 0 = Address does not need to be updated
- bit 0 BF: Buffer Full Status bit

### In Transmit mode:

- 1 = SSPBUF is full
- 0 = SSPBUF is empty

### In Receive mode:

- 1 = SSPBUF is full (does not include the  $\overline{ACK}$  and Stop bits)
- 0 = SSPBUF is empty (does not include the  $\overline{ACK}$  and Stop bits)

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 18-4: SSPCON1: MSSP CONTROL REGISTER 1 (I<sup>2</sup>C MODE)

|   | R/W-0 |
|---|-------|-------|-------|-------|-------|-------|-------|-------|
|   | WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |
| , | bit 7 |       |       |       |       |       |       | bit 0 |

#### bit 7 WCOL: Write Collision Detect bit

#### In Master Transmit mode:

- 1 = A write to the SSPBUF register was attempted while the I<sup>2</sup>C conditions were not valid for a transmission to be started (must be cleared in software)
- 0 = No collision

#### In Slave Transmit mode:

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision

### In Receive mode (Master or Slave modes):

This is a "don't care" bit.

#### bit 6 SSPOV: Receive Overflow Indicator bit

### In Receive mode:

- 1 = A byte is received while the SSPBUF register is still holding the previous byte (must be cleared in software)
- 0 = No overflow

### In Transmit mode:

This is a "don't care" bit in Transmit mode.

- bit 5 SSPEN: Master Synchronous Serial Port Enable bit
  - 1 = Enables the serial port and configures the SDA and SCL pins as the serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, the SDA and SCL pins must be properly configured as input or output.

### bit 4 CKP: SCK Release Control bit

### In Slave mode:

- 1 = Release clock
- 0 = Holds clock low (clock stretch), used to ensure data setup time

### In Master mode:

Unused in this mode.

- bit 3-0 SSPM3:SSPM0: Master Synchronous Serial Port Mode Select bits
  - $1111 = I^2C$  Slave mode, 10-bit address with Start and Stop bit interrupts enabled
  - $1110 = I^2C$  Slave mode, 7-bit address with Start and Stop bit interrupts enabled
  - $1011 = I^2C$  Firmware Controlled Master mode (Slave Idle)
  - 1000 =  $I^2C$  Master mode, clock = Fosc/(4 \* (SSPADD + 1))
  - $0111 = I^2C$  Slave mode, 10-bit address
  - $0110 = I^2C$  Slave mode, 7-bit address

**Note:** Bit combinations not specifically listed here are either reserved or implemented in SPI mode only.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n - Value at POR | '1' - Rit is set | '0' = Rit is cleared | y – Rit is unknown |

### REGISTER 18-5: SSPCON2: MSSP CONTROL REGISTER 2 (1<sup>2</sup>C MODE)

| GCEN  | ACKSTAT | ACKDT | ACKEN | RCEN  | PEN   | RSEN  | SEN   |
|-------|---------|-------|-------|-------|-------|-------|-------|
| R/W-0 | R/W-0   | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |

bit 7 bit 0

- bit 7 GCEN: General Call Enable bit (Slave mode only)
  - 1 = Enable interrupt when a general call address (0000h) is received in the SSPSR
  - 0 = General call address disabled
- bit 6 ACKSTAT: Acknowledge Status bit (Master Transmit mode only)
  - 1 = Acknowledge was not received from slave
  - 0 = Acknowledge was received from slave
- bit 5 ACKDT: Acknowledge Data bit (Master Receive mode only)
  - 1 = Not Acknowledge
  - 0 = Acknowledge

**Note:** Value that will be transmitted when the user initiates an Acknowledge sequence at the end of a receive.

- bit 4 ACKEN: Acknowledge Sequence Enable bit (Master Receive mode only)
  - 1 = Initiate Acknowledge sequence on SDA and SCL pins and transmit ACKDT data bit. Automatically cleared by hardware.
  - 0 = Acknowledge sequence Idle
- bit 3 RCEN: Receive Enable bit (Master mode only)
  - 1 = Enables Receive mode for I<sup>2</sup>C
  - 0 = Receive Idle
- bit 2 **PEN:** Stop Condition Enable bit (Master mode only)
  - 1 = Initiate Stop condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Stop condition Idle
- bit 1 RSEN: Repeated Start Condition Enable bit (Master mode only)
  - 1 = Initiate Repeated Start condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Repeated Start condition Idle
- bit 0 SEN: Start Condition Enable/Stretch Enable bit

### In Master mode:

- 1 = Initiate Start condition on SDA and SCL pins. Automatically cleared by hardware.
- 0 = Start condition Idle

### In Slave mode:

- 1 = Clock stretching is enabled for both slave transmit and slave receive (stretch enabled)
- 0 = Clock stretching is disabled

**Note:** For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the Idle mode, this bit may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 18.4.2 OPERATION

The MSSP module functions are enabled by setting MSSP Enable bit, SSPEN (SSPCON<5>).

The SSPCON1 register allows control of the I<sup>2</sup>C operation. Four mode selection bits (SSPCON<3:0>) allow one of the following I<sup>2</sup>C modes to be selected:

- I<sup>2</sup>C Master mode, clock = (Fosc/4) x (SSPADD + 1)
- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address), with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Slave mode (10-bit address), with Start and Stop bit interrupts enabled
- I<sup>2</sup>C firmware controlled master operation, slave is Idle

Selection of any I<sup>2</sup>C mode with the SSPEN bit set, forces the SCL and SDA pins to be open-drain, provided these pins are programmed to inputs by setting the appropriate TRISC bits. To ensure proper operation of the module, pull-up resistors must be provided externally to the SCL and SDA pins.

#### 18.4.3 SLAVE MODE

In Slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The I<sup>2</sup>C Slave mode hardware will always generate an interrupt on an address match. Through the mode select bits, the user can also choose to interrupt on Start and Stop bits

When an address is matched, or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge (ACK) pulse and load the SSPBUF register with the received value currently in the SSPSR register.

Any combination of the following conditions will cause the MSSP module not to give this ACK pulse:

- The buffer full bit BF (SSPSTAT<0>) was set before the transfer was received.
- The overflow bit SSPOV (SSPCON<6>) was set before the transfer was received.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. The BF bit is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the  $I^2C$  specification, as well as the requirement of the MSSP module, are shown in timing parameter 100 and parameter 101.

### 18.4.3.1 Addressing

Once the MSSP module has been enabled, it waits for a Start condition to occur. Following the Start condition, the 8-bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- The SSPSR register value is loaded into the SSPBUF register.
- 2. The buffer full bit BF is set.
- 3. An ACK pulse is generated.
- MSSP Interrupt Flag bit, SSPIF (PIR1<3>), is set (interrupt is generated, if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit Address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit R/W (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7 through 9 for the slave-transmitter:

- Receive first (high) byte of address (bits SSPIF, BF and UA (SSPSTAT<1>) are set).
- Update the SSPADD register with second (low) byte of address (clears bit UA and releases the SCL line).
- 3. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- Receive second (low) byte of address (bits SSPIF, BF and UA are set).
- Update the SSPADD register with the first (high) byte of address. If match releases SCL line, this will clear bit UA.
- 6. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive Repeated Start condition.
- Receive first (high) byte of address (bits SSPIF and BF are set).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

### 18.4.3.2 Reception

When the R/W bit of the address byte is clear and an address match occurs, the R/W bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and the SDA line is held low (ACK).

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set, or bit SSPOV (SSPCON1<6>) is set.

An MSSP interrupt is generated for each data transfer byte. Flag bit, SSPIF (PIR1<3>), must be cleared in software. The SSPSTAT register is used to determine the status of the byte.


If SEN is enabled (SSPCON1<0> = 1), RC3/SCK/SCL will be held low (clock stretch) following each data transfer. The clock must be released by setting bit CKP (SSPCON<4>). See **Section 18.4.4 "Clock Stretching"** for more detail.


#### 18.4.3.3 Transmission


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and pin RC3/SCK/SCL is held low regardless of SEN (see Section 18.4.4 "Clock Stretching" for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPBUF register which also loads the SSPSR register. Then pin RC3/ SCK/SCL should be enabled by setting bit, CKP (SSPCON1<4>). The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 18-9).


The  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line is high (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave monitors for another occurrence of the Start bit. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPBUF register. Again, pin RC3/SCK/SCL must be enabled by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared in software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.









© 2005 Microchip Technology Inc.

### 18.4.4 CLOCK STRETCHING

Both 7-bit and 10-bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCL pin to be held low at the end of each data receive sequence.

# 18.4.4.1 Clock Stretching for 7-bit Slave Receive Mode (SEN = 1)

In 7-bit Slave Receive mode, on the falling edge of the ninth clock at the end of the ACK sequence if the BF bit is set, the CKP bit in the SSPCON1 register is automatically cleared, forcing the SCL output to be held low. The CKP being cleared to '0' will assert the SCL line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the SSPBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring (see Figure 18-13).

- Note 1: If the user reads the contents of the SSPBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
  - 2: The CKP bit can be set in software regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

# 18.4.4.2 Clock Stretching for 10-bit Slave Receive Mode (SEN = 1)

In 10-bit Slave Receive mode during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address and following the receive of the second byte of the 10-bit address with the  $R/\overline{W}$  bit cleared to 'o'. The release of the clock line occurs upon updating SSPADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

Note: If the user polls the UA bit and clears it by updating the SSPADD register before the falling edge of the ninth clock occurs and if the user hasn't cleared the BF bit by reading the SSPBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

### 18.4.4.3 Clock Stretching for 7-bit Slave Transmit Mode

7-bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock if the BF bit is clear. This occurs regardless of the state of the SEN bit.

The user's ISR must set the CKP bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the SSPBUF before the master device can initiate another transmit sequence (see Figure 18-9).

- Note 1: If the user loads the contents of SSPBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
  - **2:** The CKP bit can be set in software regardless of the state of the BF bit.

# 18.4.4.4 Clock Stretching for 10-bit Slave Transmit Mode


In 10-bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-bit Slave Receive mode. The first two addresses are followed by a third address sequence which contains the high-order bits of the 10-bit address and the R/W bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode and clock stretching is controlled by the BF flag as in 7-bit Slave Transmit mode (see Figure 18-11).


# 18.4.4.5 Clock Synchronization and the CKP bit


When the CKP bit is cleared, the SCL output is forced to '0'. However, clearing the CKP bit will not assert the SCL output low until the SCL output is already sampled low. Therefore, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C master device has

already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have deasserted SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 18-12).









© 2005 Microchip Technology Inc.

# 18.4.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the  $I^2C$  protocol. It consists of all '0's with  $R/\overline{W}=0$ .


The general call address is recognized when the General Call Enable bit (GCEN) is enabled (SSPCON2<7> set). Following a Start bit detect, 8 bits are shifted into the SSPSR and the address is compared against the SSPADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPSR is transferred to the SSPBUF, the BF flag bit is set (eighth bit) and on the falling edge of the ninth bit (ACK bit), the SSPIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPBUF. The value can be used to determine if the address was device specific or a general call address.

In 10-bit mode, the SSPADD is required to be updated for the second half of the address to match and the UA bit is set (SSPSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-bit Address mode, then the second half of the address is not necessary, the UA bit will not be set and the slave will begin receiving data after the Acknowledge (Figure 18-15).

FIGURE 18-15: SLAVE MODE GENERAL CALL ADDRESS SEQUENCE (7-BIT OR 10-BIT ADDRESS MODE)



#### 18.4.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPCON1 and by setting the SSPEN bit. In Master mode, the SCL and SDA lines are manipulated by the MSSP hardware.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set or the bus is Idle, with both the S and P bits clear.

In Firmware Controlled Master mode, user code conducts all  $\rm I^2C$  bus operations based on Start and Stop bit conditions.

Once Master mode is enabled, the user has six options.


- 1. Assert a Start condition on SDA and SCL.
- Assert a Repeated Start condition on SDA and SCL.
- 3. Write to the SSPBUF register initiating transmission of data/address.
- 4. Configure the I<sup>2</sup>C port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a Stop condition on SDA and SCL.

Note: The MSSP module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPBUF register to initiate transmission before the Start condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur.

The following events will cause MSSP Interrupt Flag bit, SSPIF, to be set (MSSP interrupt, if enabled):

- · Start condition
- Stop condition
- Data transfer byte transmitted/received
- · Acknowledge transmit
- · Repeated Start

FIGURE 18-16: MSSP BLOCK DIAGRAM (I<sup>2</sup>C™ MASTER MODE)



### 18.4.6.1 I<sup>2</sup>C Master Mode Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Master Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the slave <u>address</u> of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the  $R/\overline{W}$  bit. In this case, the  $R/\overline{W}$  bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

The Baud Rate Generator used for the SPI mode operation is used to set the SCL clock frequency for either 100 kHz, 400 kHz or 1 MHz I<sup>2</sup>C operation. See **Section 18.4.7** "**Baud Rate Generator**" for more detail.

A typical transmit sequence would go as follows:

- 1. The user generates a Start condition by setting the Start Enable bit, SEN (SSPCON2<0>).
- SSPIF is set. The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPBUF with the slave address to transmit.
- Address is shifted out of the SDA pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- The user loads the SSPBUF with eight bits of data.
- Data is shifted out of the SDA pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF hit
- 11. The user generates a Stop condition by setting the Stop Enable bit, PEN (SSPCON2<2>).
- 12. Interrupt is generated once the Stop condition is complete.

### 18.4.7 BAUD RATE GENERATOR

In I<sup>2</sup>C Master mode, the Baud Rate Generator (BRG) reload value is placed in the lower 7 bits of the SSPADD register (Figure 18-17). When a write occurs to SSPBUF, the Baud Rate Generator will automatically begin counting. The BRG counts down to '0' and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (TCY) on the Q2 and Q4 clocks. In I<sup>2</sup>C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by  $\overline{ACK}$ ), the internal clock will automatically stop counting and the SCL pin will remain in its last state.

Table 18-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

FIGURE 18-17: BAUD RATE GENERATOR BLOCK DIAGRAM




TABLE 18-3: I<sup>2</sup>C™ CLOCK RATE w/BRG

| Fosc   | FcY    | FcY*2  | BRG Value | FSCL<br>(2 Rollovers of BRG) |
|--------|--------|--------|-----------|------------------------------|
| 40 MHz | 10 MHz | 20 MHz | 18h       | 400 kHz <sup>(1)</sup>       |
| 40 MHz | 10 MHz | 20 MHz | 1Fh       | 312.5 kHz                    |
| 40 MHz | 10 MHz | 20 MHz | 63h       | 100 kHz                      |
| 16 MHz | 4 MHz  | 8 MHz  | 09h       | 400 kHz <sup>(1)</sup>       |
| 16 MHz | 4 MHz  | 8 MHz  | 0Ch       | 308 kHz                      |
| 16 MHz | 4 MHz  | 8 MHz  | 27h       | 100 kHz                      |
| 4 MHz  | 1 MHz  | 2 MHz  | 02h       | 333 kHz <sup>(1)</sup>       |
| 4 MHz  | 1 MHz  | 2 MHz  | 09h       | 100 kHz                      |
| 4 MHz  | 1 MHz  | 2 MHz  | 00h       | 1 MHz <sup>(1)</sup>         |


**Note 1:** The I<sup>2</sup>C interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.

#### 18.4.7.1 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, deasserts the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the

SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 18-18).

### FIGURE 18-18: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



Note:

# 18.4.8 I<sup>2</sup>C MASTER MODE START CONDITION TIMING

To initiate a Start condition, the user sets the Start condition enable bit, SEN (SSPCON2<0>). If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low while SCL is high is the Start condition and causes the S bit (SSPSTAT<3>) to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit (SSPCON2<0>) will be automatically cleared by hardware, the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.


If at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.

### 18.4.8.1 WCOL Status Flag

If the user writes the SSPBUF when a Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

**Note:** Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the Start condition is complete.





# 18.4.9 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit (SSPCON2<1>) is programmed high and the I<sup>2</sup>C logic module is in the Idle state. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded with the contents of SSPADD<5:0> and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. Following this, the RSEN bit (SSPCON2<1>) will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit (SSPSTAT<3>) will be set. The SSPIF bit will not be set until the Baud Rate Generator has timed out.

**Note 1:** If RSEN is programmed while any other event is in progress, it will not take effect.

- **2:** A bus collision during the Repeated Start condition occurs if:
  - SDA is sampled low when SCL goes from low-to-high.
  - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data '1'.

Immediately following the SSPIF bit getting set, the user may write the SSPBUF with the 7-bit address in 7-bit mode, or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional eight bits of address (10-bit mode) or eight bits of data (7-bit mode).


### 18.4.9.1 WCOL Status Flag

Note:

If the user writes the SSPBUF when a Repeated Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Because queueing of events is not allowed, writing of the lower 5 bits of SSPCON2 is disabled until the Repeated Start condition is complete.





# 18.4.10 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the buffer full flag bit, BF and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted (see data hold time specification parameter 106). SCL is held low for one Baud Rate Generator rollover count (TBRG). Data should be valid before SCL is released high (see data setup time specification parameter 107). When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred, or if data was received properly. The status of ACK is written into the ACKDT bit on the falling edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 18-21).

After the write to the SSPBUF, each bit of address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will deassert the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPIF is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

### 18.4.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPSTAT<0>) is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

### 18.4.10.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

WCOL must be cleared in software.

### 18.4.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPCON2<6>) is cleared when the slave has sent an Acknowledge  $(\overline{ACK}=0)$  and is set when the slave does not Acknowledge  $(\overline{ACK}=1)$ . A slave sends an Acknowledge when it has recognized its address (including a general call), or when the slave has properly received its data.

### 18.4.11 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the receive enable bit, RCEN (SSPCON2<3>).

**Note:** The MSSP module must be in an Idle state before the RCEN bit is set or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge sequence enable bit, ACKEN (SSPCON2<4>).

#### 18.4.11.1 BF Status Flag


In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.


### 18.4.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

### 18.4.11.3 WCOL Status Flag

If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).





# 18.4.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge sequence enable bit. **ACKEN** (SSPCON2<4>). When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 18-23).

### 18.4.12.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).


#### 18.4.13 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop sequence enable bit, PEN (SSPCON2<2>). At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to 'o'. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit (SSPSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 18-24).


### 18.4.13.1 WCOL Status Flag

If the user writes the SSPBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

### FIGURE 18-23: ACKNOWLEDGE SEQUENCE WAVEFORM



### FIGURE 18-24: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 18.4.14 SLEEP OPERATION

While in Sleep mode, the I<sup>2</sup>C module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

### 18.4.15 EFFECT OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

### 18.4.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit (SSPSTAT<4>) is set, or the bus is Idle with both the S and P bits clear. When the bus is busy, enabling the MSSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed in hardware with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- Data Transfer
- · A Start Condition
- · A Repeated Start Condition
- An Acknowledge Condition

### 18.4.17 MULTI-MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA, by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = 0, then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag, BCLIF and reset the  $I^2C$  port to its Idle state (Figure 18-25).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the  $\rm I^2C$  bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the  $I^2C$  bus is free, the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the P bit is set in the SSPSTAT register, or the bus is Idle and the S and P bits are cleared.





# 18.4.17.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- SDA or SCL are sampled low at the beginning of the Start condition (Figure 18-26).
- SCL is sampled low before SDA is asserted low (Figure 18-27).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the Start condition is aborted,
- · the BCLIF flag is set and
- the MSSP module is reset to its Idle state (Figure 18-26).

The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded from SSPADD<6:0> and counts down to '0'. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 18-28). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to '0' and during this time, if the SCL pin is sampled as '0', a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

Note:

The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.






FIGURE 18-27: BUS COLLISION DURING START CONDITION (SCL = 0)





FIGURE 18-28: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



# 18.4.17.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- A low level is sampled on SDA when SCL goes from low level to high level.
- SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user deasserts SDA and the pin is allowed to float high, the BRG is loaded with SSPADD<6:0> and counts down to '0'. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 18-29). If SDA is sampled high, the BRG is reloaded and begins counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.

If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition, see Figure 18-30.

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.

FIGURE 18-29: BUS COLLISION DURING A REPEATED START CONDITION (CASE 1)





FIGURE 18-30: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)



# 18.4.17.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- b) After the SCL pin is deasserted, SCL is sampled low before SDA goes high.

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPADD<6:0> and counts down to '0'. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 18-31). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 18-32).

FIGURE 18-31: BUS COLLISION DURING A STOP CONDITION (CASE 1)




FIGURE 18-32: BUS COLLISION DURING A STOP CONDITION (CASE 2)




TABLE 18-4: REGISTERS ASSOCIATED WITH I<sup>2</sup>C™ OPERATION

| Name    | Bit 7   | Bit 6                                 | Bit 5   | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|---------|---|---------------------------------------|---------|--------|--------|--------|--------|--------|----------------------|---------------------------------|
| INTCON  | GIE/GIEH  | PEIE/GIEL                             | TMR0IE  | INT0IE | RBIE   | TMR0IF | INT0IF | RBIF   | 0000 000x            | 0000 000u                       |
| PIR1    | PSPIF <sup>(1)</sup>  | ADIF                                  | RC1IF   | TX1IF  | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 0000 0000            | 0000 0000                       |
| PIE1    | PSPIE <sup>(1)</sup>  | ADIE                                  | RC1IE   | TX1IE  | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 0000 0000            | 0000 0000                       |
| IPR1    | PSPIP <sup>(1)</sup>  | ADIP                                  | RC1IP   | TX1IP  | SSPIP  | CCP1IP | TMR2IP | TMR1IP | 1111 1111            | 1111 1111                       |
| TRISC   | PORTC Data  | a Direction Re                        | egister |        |        |        |        |        | 1111 1111            | 1111 1111                       |
| TRISF   | TRISF7  | TRISF6                                | TRISF5  | TRISF4 | TRISF3 | TRISF2 | TRISF1 | TRISF0 | 1111 1111            | 1111 1111                       |
| SSPBUF  | MSSP Rece   | MSSP Receive Buffer/Transmit Register |         |        |        |        |        |        |                      |                                 |
| SSPADD  | MSSP Address Register in I <sup>2</sup> C Slave mode. MSSP Baud Rate Reload Register in I <sup>2</sup> C Master mod |                                       |         |        |        |        |        |        |                      | 0000 0000                       |
| SSPCON1 | WCOL  | SSPOV                                 | SSPEN   | CKP    | SSPM3  | SSPM2  | SSPM1  | SSPM0  | 0000 0000            | 0000 0000                       |
| SSPSTAT | SMP   | CKE                                   | D/A     | Р      | S      | R/W    | UA     | BF     | 0000 0000            | 0000 0000                       |

**Legend:**  $x = \text{unknown}, u = \text{unchanged}, --- = \text{unimplemented}, \text{ read as '0'}. \text{ Shaded cells are not used by the MSSP in } 1^2C^{TM} \text{ mode}.$ 

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

# 19.0 ENHANCED UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (EUSART)

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is one of the two serial I/O modules. (USART is also known as a Serial Communications Interface or SCI.) The EUSART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers. It can also be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs, etc.

The Enhanced USART module implements additional features, including automatic baud rate detection and calibration, automatic wake-up on Sync Break reception and 12-bit Break character transmit. These make it ideally suited for use in Local Interconnect Network bus (LIN bus) systems.

The EUSART can be configured in the following modes:

- Asynchronous (full duplex) with:
  - Auto-Wake-up on character reception
  - Auto-Baud calibration
  - 12-bit Break character transmission
- Synchronous Master (half duplex) with selectable clock polarity
- Synchronous Slave (half duplex) with selectable clock polarity

The pins of USART1 and USART2 are multiplexed with the functions of PORTC (RC6/TX1/CK1 and RC7/RX1/DT1) and PORTG (RG1/TX2/CK2 and RG2/RX2/DT2), respectively. In order to configure these pins as an EUSART:

- For USART1:
  - bit SPEN (RCSTA1<7>) must be set (= 1)
  - bit TRISC<7> must be set (= 1)
  - bit TRISC<6> must be cleared (= 0) for Asynchronous and Synchronous Master modes
  - bit TRISC<6> must be set (= 1) for Synchronous Slave mode
- For USART2:
  - bit SPEN (RCSTA2<7>) must be set (= 1)
  - bit TRISG<2> must be set (= 1)
  - bit TRISG<1> must be cleared (= 0) for Asynchronous and Synchronous Master modes
  - bit TRISC<6> must be set (= 1) for Synchronous Slave mode

**Note:** The EUSART control will automatically reconfigure the pin from input to output as needed.

The operation of each Enhanced USART module is controlled through three registers:

- Transmit Status and Control (TXSTAx)
- Receive Status and Control (RCSTAx)
- Baud Rate Control (BAUDCONx)

These are detailed on the following pages in Register 19-1, Register 19-2 and Register 19-3, respectively.

Note: Throughout this section, references to register and bit names that may be associated with a specific EUSART module are referred to generically by the use of 'x' in place of the specific module number. Thus, "RCSTAx" might refer to the Receive Status register for either USART1 or USART2

#### REGISTER 19-1: TXSTAX: TRANSMIT STATUS AND CONTROL REGISTER

| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R-1  | R/W-0 |
|-------|-------|-------|-------|-------|-------|------|-------|
| CSRC  | TX9   | TXEN  | SYNC  | SENDB | BRGH  | TRMT | TX9D  |
| bit 7 |       | •     |       | •     |       | •    | bit 0 |

bit 0

bit 7 **CSRC:** Clock Source Select bit

Asynchronous mode:

Don't care.

Synchronous mode:

1 = Master mode (clock generated internally from BRG)

0 = Slave mode (clock from external source)

bit 6 TX9: 9-bit Transmit Enable bit

1 = Selects 9-bit transmission

0 = Selects 8-bit transmission

bit 5 TXEN: Transmit Enable bit

1 = Transmit enabled

0 = Transmit disabled

SREN/CREN overrides TXEN in Sync mode.

bit 4 SYNC: EUSART Mode Select bit

1 = Synchronous mode

0 = Asynchronous mode

bit 3 SENDB: Send Break Character bit

Asynchronous mode:

1 = Send sync break on next transmission (cleared by hardware upon completion)

0 = Sync break transmission completed

Synchronous mode:

Don't care.

bit 2 **BRGH:** High Baud Rate Select bit

Asynchronous mode:

1 = High speed

0 = Low speed

Synchronous mode:

Unused in this mode.

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty

0 = TSR full

bit 0 TX9D: 9th bit of Transmit Data

Can be address/data bit or a parity bit.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

'1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-2: RCSTAX: RECEIVE STATUS AND CONTROL REGISTER

| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R-0  | R-0  | R-x   |
|-------|-------|-------|-------|-------|------|------|-------|
| SPEN  | RX9   | SREN  | CREN  | ADDEN | FERR | OERR | RX9D  |
| bit 7 |       |       |       |       |      |      | bit 0 |

bit 0

- bit 7 SPEN: Serial Port Enable bit
  - 1 = Serial port enabled (configures RXx/DTx and TXx/CKx pins as serial port pins)
  - 0 = Serial port disabled (held in Reset)
- bit 6 RX9: 9-bit Receive Enable bit
  - 1 = Selects 9-bit reception
  - 0 = Selects 8-bit reception
- SREN: Single Receive Enable bit bit 5

#### Asynchronous mode:

Don't care.

### Synchronous mode - Master:

- 1 = Enables single receive
- 0 = Disables single receive

This bit is cleared after reception is complete.

#### Synchronous mode - Slave:

Don't care.

#### bit 4 **CREN:** Continuous Receive Enable bit

#### Asynchronous mode:

- 1 = Enables receiver
- 0 = Disables receiver

#### Synchronous mode:

- 1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)
- 0 = Disables continuous receive

#### bit 3 **ADDEN:** Address Detect Enable bit

### Asynchronous mode 9-bit (RX9 = 1):

- 1 = Enables address detection, enables interrupt and loads the receive buffer when RSR<8>
- 0 = Disables address detection, all bytes are received and ninth bit can be used as parity bit Asynchronous mode 9-bit (RX9 = 0):

Don't care.

- bit 2 **FERR:** Framing Error bit
  - 1 = Framing error (can be updated by reading RCREGx register and receive next valid byte)
  - 0 = No framing error
- bit 1 **OERR:** Overrun Error bit
  - 1 = Overrun error (can be cleared by clearing bit CREN)
  - 0 = No overrun error
- bit 0 RX9D: 9th bit of Received Data

This can be address/data bit or a parity bit and must be calculated by user firmware.

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-3: **BAUDCONX: BAUD RATE CONTROL REGISTER**

| U-0   | R-1   | U-0 | R/W-0 | R/W-0 | U-0 | R/W-0 | R/W-0 |
|-------|-------|-----|-------|-------|-----|-------|-------|
| _     | RCIDL | _   | SCKP  | BRG16 | _   | WUE   | ABDEN |
| bit 7 |       |     |       |       |     |       | bit 0 |

bit 0

bit 7 Unimplemented: Read as '0'

bit 6 RCIDL: Receive Operation Idle Status bit

1 = Receive operation is Idle

0 = Receive operation is active

bit 5 Unimplemented: Read as '0'

bit 4 SCKP: Synchronous Clock Polarity Select bit

> Asynchronous mode: Unused in this mode.

Synchronous mode:

1 = Idle state for clock (CKx) is a high level

0 = Idle state for clock (CKx) is a low level

bit 3 BRG16: 16-bit Baud Rate Register Enable bit

1 = 16-bit Baud Rate Generator - SPBRGHx and SPBRGx

0 = 8-bit Baud Rate Generator - SPBRGx only (Compatible mode), SPBRGHx value ignored

bit 2 Unimplemented: Read as '0'

bit 1 WUE: Wake-up Enable bit

Asynchronous mode:

1 = EUSART will continue to sample the RXx pin - interrupt generated on falling edge; bit cleared in hardware on following rising edge

0 = RXx pin not monitored or rising edge detected

Synchronous mode:

Unused in this mode.

bit 0 ABDEN: Auto-Baud Rate Detect Enable bit

#### Asynchronous mode:

- 1 = Enable baud rate measurement on the next character requires reception of a Sync field (55h); cleared in hardware upon completion
- 0 = Baud rate measurement disabled or completed

### Synchronous mode:

Unused in this mode.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 19.1 EUSART Baud Rate Generator (BRG)

The BRG is a dedicated 8-bit or 16-bit generator that supports both the Asynchronous and Synchronous modes of the EUSART. By default, the BRG operates in 8-bit mode; setting the BRG16 bit (BAUDCONx<3>) selects 16-bit mode.

The SPBRGHx:SPBRGx register pair controls the period of a free running timer. In Asynchronous mode, bits BRGH (TXSTAx<2>) and BRG16 also control the baud rate. In Synchronous mode, bit BRGH is ignored. Table 19-1 shows the formula for computation of the baud rate for different EUSART modes which only apply in Master mode (internally generated clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRGHx:SPBRGx registers can be calculated using the formulas in Table 19-1. From

this, the error in baud rate can be determined. An example calculation is shown in Example 19-1. Typical baud rates and error values for the various Asynchronous modes are shown in Table 19-2. It may be advantageous to use the high baud rate (BRGH = 1) or the 16-bit BRG to reduce the baud rate error, or achieve a slow baud rate for a fast oscillator frequency.

Writing a new value to the SPBRGHx:SPBRGx registers causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

### 19.1.1 SAMPLING

The data on the RXx pin (either RC7/RX1/DT1 or RG2/RX2/DT2) is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RXx pin.

TABLE 19-1: BAUD RATE FORMULAS

| Co   | onfiguration B | its  | BRG/EUSART Mode     | Baud Rate Formula |
|------|----------------|------|---------------------|-------------------|
| SYNC | BRG16          | BRGH | BRG/EUSART Mode     | Baud Rate Formula |
| 0    | 0              | 0    | 8-bit/Asynchronous  | Fosc/[64 (n + 1)] |
| 0    | 0              | 1    | 8-bit/Asynchronous  | F000/[46 /n + 4\] |
| 0    | 1              | 0    | 16-bit/Asynchronous | Fosc/[16 (n + 1)] |
| 0    | 1              | 1    | 16-bit/Asynchronous |                   |
| 1    | 0              | х    | 8-bit/Synchronous   | Fosc/[4 (n + 1)]  |
| 1    | 1              | х    | 16-bit/Synchronous  |                   |

**Legend:** x = Don't care, n = value of SPBRGHx:SPBRGx register pair

### **EXAMPLE 19-1: CALCULATING BAUD RATE ERROR**

For a device with FOSC of 16 MHz, desired baud rate of 9600, Asynchronous mode, 8-bit BRG:

Desired Baud Rate = Fosc/(64 ([SPBRGHx:SPBRGx] + 1))

Solving for SPBRGHx:SPBRGx:

X = ((Fosc/Desired Baud Rate)/64) - 1

= ((16000000/9600)/64) - 1

= [25.042] = 25

Calculated Baud Rate = 16000000/(64(25+1))

= 9615

Error = (Calculated Baud Rate – Desired Baud Rate)/Desired Baud Rate

= (9615 - 9600)/9600 = 0.16%

### TABLE 19-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

| Name     | Bit 7    | Bit 6  | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on all other Resets |
|----------|----------|--|-------|-------|-------|-------|-------|-------|----------------------|---------------------------|
| TXSTAx   | CSRC     | TX9  | TXEN  | SYNC  | SENDB | BRGH  | TRMT  | TX9D  | 0000 0010            | 0000 0010                 |
| RCSTAx   | SPEN     | RX9  | SREN  | CREN  | ADDEN | FERR  | OERR  | RX9D  | 0000 000x            | 0000 000x                 |
| BAUDCONx | _        | RCIDL  | _     | SCKP  | BRG16 | _     | WUE   | ABDEN | -1-0 0-00            | -1-0 0-00                 |
| SPBRGHx  | Enhanced | Enhanced USARTx Baud Rate Generator Register High Byte |       |       |       |       |       |       | 0000 0000            | 0000 0000                 |
| SPBRGx   | Enhanced | inhanced USARTx Baud Rate Generator Register Low Byte  |       |       |       |       |       |       | 0000 0000            | 0000 0000                 |

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used by the BRG.

TABLE 19-3: BAUD RATES FOR ASYNCHRONOUS MODES

|              |                       |            |                             |                       | SYNC       | = 0, BRG                    | l = 0, BRG            | <b>316 =</b> 0 |                             |                       |            |                             |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|----------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                  | = 10.000       | ) MHz                       | Fos                   | c = 8.000  | MHz                         |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3          | _                     |            | _                           | _                     |            | _                           | _                     | _              | _                           | _                     | _          | _                           |
| 1.2          | _                     | _          | _                           | 1.221                 | 1.73       | 255                         | 1.202                 | 0.16           | 129                         | 1201                  | -0.16      | 103                         |
| 2.4          | 2.441                 | 1.73       | 255                         | 2.404                 | 0.16       | 129                         | 2.404                 | 0.16           | 64                          | 2403                  | -0.16      | 51                          |
| 9.6          | 9.615                 | 0.16       | 64                          | 9.766                 | 1.73       | 31                          | 9.766                 | 1.73           | 15                          | 9615                  | -0.16      | 12                          |
| 19.2         | 19.531                | 1.73       | 31                          | 19.531                | 1.73       | 15                          | 19.531                | 1.73           | 7                           | _                     | _          | _                           |
| 57.6         | 56.818                | -1.36      | 10                          | 62.500                | 8.51       | 4                           | 52.083                | -9.58          | 2                           | _                     | _          | _                           |
| 115.2        | 125.000               | 8.51       | 4                           | 104.167               | -9.58      | 2                           | 78.125                | -32.18         | 1                           | _                     | _          | _                           |

|             |                       |            | s                           | YNC = 0, BRGH = 0, BRG16 = 0 |            |                             |                       |            |                             |  |  |
|-------------|-----------------------|------------|-----------------------------|------------------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|--|
| BAUD        | Fos                   | c = 4.000  | MHz                         | Fos                          | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |  |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K)        | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |  |
| 0.3         | 0.300                 | 0.16       | 207                         | 300                          | -0.16      | 103                         | 300                   | -0.16      | 51                          |  |  |
| 1.2         | 1.202                 | 0.16       | 51                          | 1201                         | -0.16      | 25                          | 1201                  | -0.16      | 12                          |  |  |
| 2.4         | 2.404                 | 0.16       | 25                          | 2403                         | -0.16      | 12                          | _                     | _          | _                           |  |  |
| 9.6         | 8.929                 | -6.99      | 6                           | _                            | _          | _                           | _                     | _          | _                           |  |  |
| 19.2        | 20.833                | 8.51       | 2                           | _                            | _          | _                           | _                     | _          | _                           |  |  |
| 57.6        | 62.500                | 8.51       | 0                           | _                            | _          | _                           | _                     | _          | _                           |  |  |
| 115.2       | 62.500                | -45.75     | 0                           | _                            | _          | _                           | _                     | _          | _                           |  |  |

|              |                       |            |                             |                       | <b>SYNC</b> = 0, <b>BRGH</b> = 1, <b>BRG16</b> = 0 |                             |                       |            |                             |                       |            |                             |  |  |
|--------------|-----------------------|------------|-----------------------------|-----------------------|--|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|--|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc = 20.000 MHz     |  |                             | Fosc = 10.000 MHz     |            |                             | Fosc = 8.000 MHz      |            |                             |  |  |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error   | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |  |
| 0.3          | _                     |            | _                           | _                     |  | _                           | _                     | _          | _                           | _                     | _          | _                           |  |  |
| 1.2          | _                     | _          | _                           | _                     | _  | _                           | _                     | _          | _                           | _                     | _          |                             |  |  |
| 2.4          | _                     | _          | _                           | _                     | _  | _                           | 2.441                 | 1.73       | 255                         | 2403                  | -0.16      | 207                         |  |  |
| 9.6          | 9.766                 | 1.73       | 255                         | 9.615                 | 0.16   | 129                         | 9.615                 | 0.16       | 64                          | 9615                  | -0.16      | 51                          |  |  |
| 19.2         | 19.231                | 0.16       | 129                         | 19.231                | 0.16   | 64                          | 19.531                | 1.73       | 31                          | 19230                 | -0.16      | 25                          |  |  |
| 57.6         | 58.140                | 0.94       | 42                          | 56.818                | -1.36  | 21                          | 56.818                | -1.36      | 10                          | 55555                 | 3.55       | 8                           |  |  |
| 115.2        | 113.636               | -1.36      | 21                          | 113.636               | -1.36  | 10                          | 125.000               | 8.51       | 4                           | _                     | _          | _                           |  |  |

|              |                       |            | s                           | YNC = 0, E            | BRGH = 1   | , BRG16 =                   | 0                     |            |                             |  |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|
| BAUD<br>RATE | Fosc                  | c = 4.000  | MHz                         | Fos                   | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |  |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |
| 0.3          | _                     | _          | _                           | _                     | _          | _                           | 300                   | -0.16      | 207                         |  |
| 1.2          | 1.202                 | 0.16       | 207                         | 1201                  | -0.16      | 103                         | 1201                  | -0.16      | 51                          |  |
| 2.4          | 2.404                 | 0.16       | 103                         | 2403                  | -0.16      | 51                          | 2403                  | -0.16      | 25                          |  |
| 9.6          | 9.615                 | 0.16       | 25                          | 9615                  | -0.16      | 12                          | _                     | _          | _                           |  |
| 19.2         | 19.231                | 0.16       | 12                          | _                     | _          | _                           | _                     | _          | _                           |  |
| 57.6         | 62.500                | 8.51       | 3                           | _                     | _          | _                           | _                     | _          | _                           |  |
| 115.2        | 125.000               | 8.51       | 1                           | _                     | _          | _                           |                       | _          | _                           |  |

TABLE 19-3: BAUD RATES FOR ASYNCHRONOUS MODES (CONTINUED)

|              |                       |            |                             |                       | SYNC       | = 0, BRGI                   | GH = 0, BRG16 = 1     |            |                             |                       |                  |                             |  |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------------|-----------------------------|--|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                  | = 10.000   | ) MHz                       | Fos                   | Fosc = 8.000 MHz |                             |  |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error       | SPBRG<br>value<br>(decimal) |  |
| 0.3          | 0.300                 | 0.00       | 8332                        | 0.300                 | 0.02       | 4165                        | 0.300                 | 0.02       | 2082                        | 300                   | -0.04            | 1665                        |  |
| 1.2          | 1.200                 | 0.02       | 2082                        | 1.200                 | -0.03      | 1041                        | 1.200                 | -0.03      | 520                         | 1201                  | -0.16            | 415                         |  |
| 2.4          | 2.402                 | 0.06       | 1040                        | 2.399                 | -0.03      | 520                         | 2.404                 | 0.16       | 259                         | 2403                  | -0.16            | 207                         |  |
| 9.6          | 9.615                 | 0.16       | 259                         | 9.615                 | 0.16       | 129                         | 9.615                 | 0.16       | 64                          | 9615                  | -0.16            | 51                          |  |
| 19.2         | 19.231                | 0.16       | 129                         | 19.231                | 0.16       | 64                          | 19.531                | 1.73       | 31                          | 19230                 | -0.16            | 25                          |  |
| 57.6         | 58.140                | 0.94       | 42                          | 56.818                | -1.36      | 21                          | 56.818                | -1.36      | 10                          | 55555                 | 3.55             | 8                           |  |
| 115.2        | 113.636               | -1.36      | 21                          | 113.636               | -1.36      | 10                          | 125.000               | 8.51       | 4                           |                       | _                | _                           |  |

|             |                       |            | S                           | /NC = 0, E            | BRGH = 0   | , BRG16 =                   | 1                     |            |                             |
|-------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD        | Fosc                  | = 4.000    | MHz                         | Fos                   | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3         | 0.300                 | 0.04       | 832                         | 300                   | -0.16      | 415                         | 300                   | -0.16      | 207                         |
| 1.2         | 1.202                 | 0.16       | 207                         | 1201                  | -0.16      | 103                         | 1201                  | -0.16      | 51                          |
| 2.4         | 2.404                 | 0.16       | 103                         | 2403                  | -0.16      | 51                          | 2403                  | -0.16      | 25                          |
| 9.6         | 9.615                 | 0.16       | 25                          | 9615                  | -0.16      | 12                          | _                     | _          | _                           |
| 19.2        | 19.231                | 0.16       | 12                          | _                     | _          | _                           | _                     | _          | _                           |
| 57.6        | 62.500                | 8.51       | 3                           | _                     | _          | _                           | _                     | _          | _                           |
| 115.2       | 125.000               | 8.51       | 1                           | _                     | _          | _                           | _                     | _          | _                           |

|             |                       |            |                             | SYNC = 0              | , BRGH =   | = 1, BRG16                  | 16 = 1 or SYNC = 1, BRG16 = 1 |            |                             |                       |            |                             |  |
|-------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-------------------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|
| BAUD        | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                          | = 10.000   | ) MHz                       | Fosc = 8.000 MHz      |            |                             |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K)         | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |
| 0.3         | 0.300                 | 0.00       | 33332                       | 0.300                 | 0.00       | 16665                       | 0.300                         | 0.00       | 8332                        | 300                   | -0.01      | 6665                        |  |
| 1.2         | 1.200                 | 0.00       | 8332                        | 1.200                 | 0.02       | 4165                        | 1.200                         | 0.02       | 2082                        | 1200                  | -0.04      | 1665                        |  |
| 2.4         | 2.400                 | 0.02       | 4165                        | 2.400                 | 0.02       | 2082                        | 2.402                         | 0.06       | 1040                        | 2400                  | -0.04      | 832                         |  |
| 9.6         | 9.606                 | 0.06       | 1040                        | 9.596                 | -0.03      | 520                         | 9.615                         | 0.16       | 259                         | 9615                  | -0.16      | 207                         |  |
| 19.2        | 19.193                | -0.03      | 520                         | 19.231                | 0.16       | 259                         | 19.231                        | 0.16       | 129                         | 19230                 | -0.16      | 103                         |  |
| 57.6        | 57.803                | 0.35       | 172                         | 57.471                | -0.22      | 86                          | 58.140                        | 0.94       | 42                          | 57142                 | 0.79       | 34                          |  |
| 115.2       | 114.943               | -0.22      | 86                          | 116.279               | 0.94       | 42                          | 113.636                       | -1.36      | 21                          | 117647                | -2.12      | 16                          |  |

|             |                       | SYN        | IC = 0, BR                  | GH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1 |            |                             |                       |            |                             |  |  |
|-------------|-----------------------|------------|-----------------------------|--|------------|-----------------------------|-----------------------|------------|-----------------------------|--|--|
| BAUD        | Fos                   | c = 4.000  | MHz                         | Fos                                      | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |  |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K)                    | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |  |
| 0.3         | 0.300                 | 0.01       | 3332                        | 300                                      | -0.04      | 1665                        | 300                   | -0.04      | 832                         |  |  |
| 1.2         | 1.200                 | 0.04       | 832                         | 1201                                     | -0.16      | 415                         | 1201                  | -0.16      | 207                         |  |  |
| 2.4         | 2.404                 | 0.16       | 415                         | 2403                                     | -0.16      | 207                         | 2403                  | -0.16      | 103                         |  |  |
| 9.6         | 9.615                 | 0.16       | 103                         | 9615                                     | -0.16      | 51                          | 9615                  | -0.16      | 25                          |  |  |
| 19.2        | 19.231                | 0.16       | 51                          | 19230                                    | -0.16      | 25                          | 19230                 | -0.16      | 12                          |  |  |
| 57.6        | 58.824                | 2.12       | 16                          | 55555                                    | 3.55       | 8                           | _                     | _          | _                           |  |  |
| 115.2       | 111.111               | -3.55      | 8                           | _  | _          | _                           | _                     | _          | _                           |  |  |

#### 19.1.2 AUTO-BAUD RATE DETECT

The Enhanced USART module supports the automatic detection and calibration of baud rate. This feature is active only in Asynchronous mode and while the WUE bit is clear.

The automatic baud rate measurement sequence (Figure 19-1) begins whenever a Start bit is received and the ABDEN bit is set. The calculation is self-averaging.

In the Auto-Baud Rate Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RXx signal, the RXx signal is timing the BRG. In ABD mode, the internal Baud Rate Generator is used as a counter to time the bit period of the incoming serial byte stream.

Once the ABDEN bit is set, the state machine will clear the BRG and look for a Start bit. The Auto-Baud Rate Detect must receive a byte with the value 55h (ASCII "U", which is also the LIN bus Sync character), in order to calculate the proper bit rate. The measurement is taken over both a low and a high bit time in order to minimize any effects caused by asymmetry of the incoming signal. After a Start bit, the SPBRGx begins counting up using the preselected clock source on the first rising edge of RXx. After eight bits on the RXx pin or the fifth rising edge, an accumulated value totalling the proper BRG period is left in the SPBRGHx:SPBRGx register pair. Once the 5th edge is seen (this should correspond to the Stop bit), the ABDEN bit is automatically cleared.

While calibrating the baud rate period, the BRG registers are clocked at 1/8th the preconfigured clock rate. Note that the BRG clock will be configured by the BRG16 and BRGH bits. Independent of the BRG16 bit setting, both the SPBRGx and SPBRGHx will be used

as a 16-bit counter. This allows the user to verify that no carry occurred for 8-bit modes by checking for 00h in the SPBRGHx register. Refer to Table 19-4 for counter clock rates to the BRG.

While the ABD sequence takes place, the EUSART state machine is held in Idle. The RCxIF interrupt is set once the fifth rising edge on RXx is detected. The value in the RCREGx needs to be read to clear the RC1IF interrupt. RCREGx content should be discarded.


- **Note 1:** If the WUE bit is set with the ABDEN bit, Auto-Baud Rate Detection will occur on the byte *following* the Break character.
  - 2: It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible due to bit error rates. Overall system timing and communication baud rates must be taken into consideration when using the Auto-Baud Rate Detection feature.

TABLE 19-4: BRG COUNTER CLOCK RATES

| BRG16 | BRGH | BRG Counter Clock |
|-------|------|-------------------|
| 0     | 0    | Fosc/512          |
| 0     | 1    | Fosc/128          |
| 1     | 0    | Fosc/128          |
| 1     | 1    | Fosc/32           |

Note: During the ABD sequence, SPBRGx and SPBRGHx are both used as a 16-bit counter, independent of BRG16 setting.

FIGURE 19-1: AUTOMATIC BAUD RATE CALCULATION



### 19.2 EUSART Asynchronous Mode

The Asynchronous mode of operation is selected by clearing the SYNC bit (TXSTAx<4>). In this mode, the EUSART uses standard non-return-to-zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8 bits. An on-chip dedicated 8-bit/16-bit Baud Rate Generator can be used to derive standard baud rate frequencies from the oscillator.

The EUSART transmits and receives the LSb first. The EUSART module's transmitter and receiver are functionally independent but use the same data format and baud rate. The Baud Rate Generator produces a clock, either x16 or x64 of the bit shift rate depending on the BRGH and BRG16 bits (TXSTAx<2> and BAUDCONx<3>). Parity is not supported by the hardware but can be implemented in software and stored as the 9th data bit.

When operating in Asynchronous mode, the EUSART module consists of the following important elements:

- · Baud Rate Generator
- Sampling Circuit
- · Asynchronous Transmitter
- · Asynchronous Receiver
- Auto-Wake-up on Sync Break Character
- 12-bit Break Character Transmit
- · Auto-Baud Rate Detection

## 19.2.1 EUSART ASYNCHRONOUS TRANSMITTER

The EUSART transmitter block diagram is shown in Figure 19-2. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREGx. The TXREGx register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREGx register (if available).

Once the TXREGx register transfers the data to the TSR register (occurs in one Tcy), the TXREGx register is empty and flag bit TXxIF is set. This interrupt can be enabled/disabled by setting/clearing enable bit TXxIE. Flag bit TXxIF will be set regardless of the state of enable bit TXxIE and cannot be cleared in software. Flag bit TXxIF is not cleared immediately upon loading the Transmit Buffer register, TXREGx. TXxIF becomes valid in the second instruction cycle following the load instruction. Polling TXxIF immediately following a load of TXREGx will return invalid results.

While flag bit TXxIF indicates the status of the TXREGx register, another bit, TRMT (TXSTAx<1>), shows the status of the TSR register. Status bit TRMT is a read-only bit which is set when the TSR register is empty. No interrupt logic is tied to this bit so the user has to poll this bit in order to determine if the TSR register is empty.

- **Note 1:** The TSR register is not mapped in data memory so it is not available to the user.
  - **2:** Flag bit TXxIF is set when enable bit TXEN is set.

To set up an Asynchronous Transmission:

- Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit TXxIE.
- If 9-bit transmission is desired, set transmit bit TX9. Can be used as address/data bit.
- Enable the transmission by setting bit TXEN which will also set bit TXxIF.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Load data to the TXREGx register (starts transmission).

If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.






FIGURE 19-3: ASYNCHRONOUS TRANSMISSION




FIGURE 19-4: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)




TABLE 19-5: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

| Name     | Bit 7  | Bit 6       | Bit 5                    | Bit 4                                    | Bit 3  | Bit 2              | Bit 1  | Bit 0     | Value on POR, BOR | Value on<br>all other<br>Resets |
|----------|--|-------------|--------------------------|--|--------|--------------------|--------|-----------|-------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL   | TMR0IE                   | INT0IE                                   | RBIE   | TMR0IF INT0IF RBIF |        | 0000 000x | 0000 000u         |                                 |
| PIR1     | PSPIF <sup>(1)</sup>   | ADIF        | RC1IF                    | RC1IF TX1IF SSPIF CCP1IF TMR2IF TMR1IF 0 |        |                    |        |           | 0000 0000         | 0000 0000                       |
| PIE1     | PSPIE <sup>(1)</sup> ADIE RC1IE TX1IE SSPIE CCP1IE TMR2IE TMR1IE |             |                          |  |        |                    |        |           | 0000 0000         | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>   | ADIP        | RC1IP                    | TX1IP                                    | SSPIP  | CCP1IP             | TMR2IP | TMR1IP    | 1111 1111         | 1111 1111                       |
| PIR3     | _  | _           | RC2IF                    | TX2IF                                    | TMR4IF | CCP5IF             | CCP4IF | CCP3IF    | 00 0000           | 00 0000                         |
| PIE3     | _  | _           | RC2IE                    | TX2IE                                    | TMR4IE | CCP5IE             | CCP4IE | CCP3IE    | 00 0000           | 00 0000                         |
| IPR3     | -  | _           | RC2IP                    | TX2IP                                    | TMR4IP | CCP5IP             | CCP4IP | CCP3IP    | 11 1111           | 11 1111                         |
| RCSTAx   | SPEN   | RX9         | SREN                     | CREN                                     | ADDEN  | FERR               | OERR   | RX9D      | 0000 000x         | 0000 000x                       |
| TXREGx   | Enhanced U   | SARTx Trans | mit Regist               | er                                       |        |                    |        |           | 0000 0000         | 0000 0000                       |
| TXSTAx   | CSRC TX9 TXEN SYNC SENDB BRGH TRMT TX9D                          |             |                          |  |        |                    |        |           | 0000 0010         | 0000 0010                       |
| BAUDCONx | _  | RCIDL       | - SCKP BRG16 - WUE ABDEN |  |        |                    |        |           | -1-0 0-00         | -1-0 0-00                       |
| SPBRGHx  | GHx Enhanced USARTx Baud Rate Generator Register High Byte       |             |                          |  |        |                    |        |           |                   | 0000 0000                       |
| SPBRGx   | x Enhanced USARTx Baud Rate Generator Register Low Byte          |             |                          |  |        |                    |        |           |                   | 0000 0000                       |

Legend: x = unknown, - = unimplemented locations read as '0'. Shaded cells are not used for asynchronous transmission.

## 19.2.2 EUSART ASYNCHRONOUS RECEIVER

The receiver block diagram is shown in Figure 19-5. The data is received on the RXx pin and drives the data recovery block. The data recovery block is actually a high speed shifter operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

To set up an Asynchronous Reception:

- Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit RCxIE.
- 4. If 9-bit reception is desired, set bit RX9.
- 5. Enable the reception by setting bit CREN.
- Flag bit RCxIF will be set when reception is complete and an interrupt will be generated if enable bit RCxIE was set.
- Read the RCSTAx register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREGx register.
- If any error occurred, clear the error by clearing enable bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

## 19.2.3 SETTING UP 9-BIT MODE WITH ADDRESS DETECT

This mode would typically be used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If interrupts are required, set the RCEN bit and select the desired priority level with the RCxIP bit
- 4. Set the RX9 bit to enable 9-bit reception.
- 5. Set the ADDEN bit to enable address detect.
- 6. Enable reception by setting the CREN bit.
- The RCxIF bit will be set when reception is complete. The interrupt will be Acknowledged if the RCxIE and GIE bits are set.
- 8. Read the RCSTAx register to determine if any error occurred during reception, as well as read bit 9 of data (if applicable).
- Read RCREGx to determine if the device is being addressed.
- 10. If any error occurred, clear the CREN bit.
- 11. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.






FIGURE 19-6: ASYNCHRONOUS RECEPTION




TABLE 19-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

| Name     | Bit 7  | Bit 6                                       | Bit 5      | Bit 4     | Bit 3  | Bit 2  | Bit 1  | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|--|---|------------|-----------|--------|--------|--------|-----------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL                                   | TMR0IE     | INT0IE    | RBIE   | TMR0IF | INT0IF | RBIF      | 0000 000x            | 0000 000u                       |
| PIR1     | PSPIF <sup>(1)</sup>   | ADIF  | RC1IF      | TX1IF     | SSPIF  | CCP1IF | TMR2IF | TMR1IF    | 0000 0000            | 0000 0000                       |
| PIE1     | PSPIE <sup>(1)</sup> ADIE RC1IE TX1IE SSPIE CCP1IE TMR2IE TMR1IE |   |            |           |        |        |        |           | 0000 0000            | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>   | ADIP RC1IP TX1IP SSPIP CCP1IP TMR2IP TMR1IP |            |           |        |        |        | 1111 1111 | 1111 1111            |                                 |
| PIR3     | _  | _   | RC2IF      | TX2IF     | TMR4IF | CCP5IF | CCP4IF | CCP3IF    | 00 0000              | 00 0000                         |
| PIE3     | _  | _   | RC2IE      | TX2IE     | TMR4IE | CCP5IE | CCP4IE | CCP3IE    | 00 0000              | 00 0000                         |
| IPR3     | _  | _   | RC2IP      | TX2IP     | TMR4IP | CCP5IP | CCP4IP | CCP3IP    | 11 1111              | 11 1111                         |
| RCSTAx   | SPEN   | RX9   | SREN       | CREN      | ADDEN  | FERR   | OERR   | RX9D      | 0000 000x            | 0000 000x                       |
| RCREGx   | Enhanced U   | SARTx Recei                                 | ve Registe | er        |        |        |        |           | 0000 0000            | 0000 0000                       |
| TXSTAx   | CSRC   | TX9   | 0000 0010  | 0000 0010 |        |        |        |           |                      |                                 |
| BAUDCONx | - RCIDL - SCKP BRG16 - WUE ABDEN                                 |   |            |           |        |        |        | -1-0 0-00 | -1-0 0-00            |                                 |
| SPBRGHx  | Hx Enhanced USARTx Baud Rate Generator Register High Byte        |   |            |           |        |        |        |           |                      | 0000 0000                       |
| SPBRGx   | Enhanced U   | 0000 0000                                   | 0000 0000  |           |        |        |        |           |                      |                                 |

**Legend:** x = unknown, - = unimplemented locations read as '0'. Shaded cells are not used for asynchronous reception.

## 19.2.4 AUTO-WAKE-UP ON SYNC BREAK CHARACTER

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the Baud Rate Generator is inactive and a proper byte reception cannot be performed. The Auto-Wake-up feature allows the controller to wake-up due to activity on the RXx/DTx line, while the EUSART is operating in Asynchronous mode.

The Auto-Wake-up feature is enabled by setting the WUE bit (BAUDCONx<1>). Once set, the typical receive sequence on RXx/DTx is disabled and the EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RXx/DTx line. (This coincides with the start of a Sync Break or a Wake-up Signal character for the LIN protocol.)

Following a wake-up event, the module generates an RC1IF interrupt. The interrupt is generated synchronously to the Q clocks in normal operating modes (Figure 19-7) and asynchronously, if the device is in Sleep mode (Figure 19-8). The interrupt condition is cleared by reading the RCREGx register.

The WUE bit is automatically cleared once a low-to-high transition is observed on the RXx line following the wake-up event. At this point, the EUSART module is in Idle mode and returns to normal operation. This signals to the user that the Sync Break event is over.

## 19.2.4.1 Special Considerations Using Auto-Wake-up

Since auto-wake-up functions by sensing rising edge transitions on RXx/DTx, information with any state changes before the Stop bit may signal a false end-of-

character and cause data or framing errors. To work properly, therefore, the initial character in the transmission must be all '0's. This can be 00h (8 bytes) for standard RS-232 devices, or 000h (12 bits) for LIN bus.

Oscillator start-up time must also be considered, especially in applications using oscillators with longer start-up intervals (i.e., XT or HS mode). The Sync Break (or Wake-up Signal) character must be of sufficient length and be followed by a sufficient interval to allow enough time for the selected oscillator to start and provide proper initialization of the EUSART.


### 19.2.4.2 Special Considerations Using the WUE Bit

The timing of WUE and RCxIF events may cause some confusion when it comes to determining the validity of received data. As noted, setting the WUE bit places the EUSART in an Idle mode. The wake-up event causes a receive interrupt by setting the RCxIF bit. The WUE bit is cleared after this when a rising edge is seen on RXx/DTx. The interrupt condition is then cleared by reading the RCREGx register. Ordinarily, the data in RCREGx will be dummy data and should be discarded.


The fact that the WUE bit has been cleared (or is still set) and the RCxIF flag is set should not be used as an indicator of the integrity of the data in RCREGx. Users should consider implementing a parallel method in firmware to verify received data integrity.

To assure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

#### FIGURE 19-7: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING NORMAL OPERATION



### FIGURE 19-8: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING SLEEP



2: The EUSART remains in Idle while the WUE bit is set.

#### 19.2.5 BREAK CHARACTER SEQUENCE

The Enhanced USART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. The Break character transmit consists of a Start bit, followed by twelve '0' bits and a Stop bit. The frame Break character is sent whenever the SENDB and TXEN bits (TXSTAx<3> and TXSTAx<5>) are set while the Transmit Shift register is loaded with data. Note that the value of data written to TXREGx will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

Note that the data value written to the TXREGx for the Break character is ignored. The write simply serves the purpose of initiating the proper sequence.

The TRMT bit indicates when the transmit operation is active or Idle, just as it does during normal transmission. See Figure 19-9 for the timing of the Break character sequence.

### 19.2.5.1 Break and Sync Transmit Sequence

The following sequence will send a message frame header made up of a Break, followed by an auto-baud Sync byte. This sequence is typical of a LIN bus master.

- 1. Configure the EUSART for the desired mode.
- Set the TXEN and SENDB bits to set up the Break character.
- Load the TXREGx with a dummy character to initiate transmission (the value is ignored).
- Write '55h' to TXREGx to load the Sync character into the transmit FIFO buffer.
- 5. After the Break has been sent, the SENDB bit is reset by hardware. The Sync character now transmits in the preconfigured mode.

When the TXREGx becomes empty, as indicated by the TXxIF, the next data byte can be written to TXREGx.

#### 19.2.6 RECEIVING A BREAK CHARACTER


The Enhanced USART module can receive a Break character in two ways.

The first method forces configuration of the baud rate at a frequency of 9/13 the typical speed. This allows for the Stop bit transition to be at the correct sampling location (13 bits for Break versus Start bit and 8 data bits for typical data).

The second method uses the Auto-Wake-up feature described in **Section 19.2.4** "**Auto-Wake-up on Sync Break Character**". By enabling this feature, the EUSART will sample the next two transitions on RXx/DTx, cause an RCxIF interrupt and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Rate Detect feature. For both methods, the user can set the ABD bit once the TXxIF interrupt is observed.

FIGURE 19-9: SEND BREAK CHARACTER SEQUENCE



### 19.3 EUSART Synchronous Master Mode

The Synchronous Master mode is entered by setting the CSRC bit (TXSTAx<7>). In this mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTAx<4>). In addition, enable bit SPEN (RCSTAx<7>) is set in order to configure the TXx and RXx pins to CKx (clock) and DTx (data) lines, respectively.

The Master mode indicates that the processor transmits the master clock on the CKx line. Clock polarity is selected with the SCKP bit (BAUDCONx<4>); setting SCKP sets the Idle state on CKx as high, while clearing the bit sets the Idle state as low. This option is provided to support Microwire devices with this module.

### 19.3.1 EUSART SYNCHRONOUS MASTER TRANSMISSION

The EUSART transmitter block diagram is shown in Figure 19-2. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREGx. The TXREGx register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREGx (if available).

Once the TXREGx register transfers the data to the TSR register (occurs in one TCYCLE), the TXREGx is empty and interrupt bit TXxIF is set. The interrupt can be enabled/disabled by setting/clearing enable bit TXxIE. Flag bit TXxIF will be set regardless of the state of enable bit TXxIE and cannot be cleared in software. It will reset only when new data is loaded into the TXREGx register.

While flag bit TXxIF indicates the status of the TXREGx register, another bit, TRMT (TXSTAx<1>), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR is empty. No interrupt logic is tied to this bit so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory so it is not available to the user.

To set up a Synchronous Master Transmission:

- Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the desired baud rate.
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. If interrupts are desired, set enable bit TXxIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- 5. Enable the transmission by setting bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Start transmission by loading data to the TXREGx register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

FIGURE 19-10: SYNCHRONOUS TRANSMISSION




FIGURE 19-11: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)




TABLE 19-7: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

| Name     | Bit 7  | Bit 6                              | Bit 5                                      | Bit 4  | Bit 3     | Bit 2     | Bit 1  | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|--|------------------------------------|--|--------|-----------|-----------|--------|-----------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL                          | TMR0IE                                     | INTOIE | RBIE      | TMR0IF    | INT0IF | RBIF      | 0000 000x            | 0000 000u                       |
| PIR1     | PSPIF <sup>(1)</sup>                                       | ADIF                               | DIF RC1IF TX1IF SSPIF CCP1IF TMR2IF TMR1IF |        | 0000 0000 | 0000 0000 |        |           |                      |                                 |
| PIE1     | PSPIE <sup>(1)</sup>                                       |                                    |  |        |           |           |        |           |                      | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>                                       | ADIP                               | RC1IP                                      | TX1IP  | SSPIP     | CCP1IP    | TMR2IP | TMR1IP    | 1111 1111            | 1111 1111                       |
| PIR3     | _  |                                    | RC2IF                                      | TX2IF  | TMR4IF    | CCP5IF    | CCP4IF | CCP3IF    | 00 0000              | 00 0000                         |
| PIE3     | _  | _                                  | RC2IE                                      | TX2IE  | TMR4IE    | CCP5IE    | CCP4IE | CCP3IE    | 00 0000              | 00 0000                         |
| IPR3     | _  | _                                  | RC2IP                                      | TX2IP  | TMR4IP    | CCP5IP    | CCP4IP | CCP3IP    | 11 1111              | 11 1111                         |
| RCSTAx   | SPEN   | RX9                                | SREN                                       | CREN   | ADDEN     | FERR      | OERR   | RX9D      | 0000 000x            | 0000 000x                       |
| TXREGx   | Enhanced I   | USARTx Tra                         | nsmit Regi                                 | ster   |           |           |        |           | 0000 0000            | 0000 0000                       |
| TXSTAx   | CSRC   | TX9 TXEN SYNC SENDB BRGH TRMT TX9D |  |        |           |           |        |           | 0000 0010            | 0000 0010                       |
| BAUDCONx | - RCIDL - SCKP BRG16 - WUE ABDEN                           |                                    |  |        |           |           |        | -1-0 0-00 | -1-0 0-00            |                                 |
| SPBRGHx  | GHx Enhanced USARTx Baud Rate Generator Register High Byte |                                    |  |        |           |           |        |           |                      | 0000 0000                       |
| SPBRGx   | Gx Enhanced USARTx Baud Rate Generator Register Low Byte   |                                    |  |        |           |           |        |           |                      | 0000 0000                       |

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master transmission.

## 19.3.2 EUSART SYNCHRONOUS MASTER RECEPTION

Once Synchronous mode is selected, reception is enabled by setting either the Single Receive Enable bit, SREN (RCSTAx<5>), or the Continuous Receive Enable bit, CREN (RCSTAx<4>). Data is sampled on the RXx pin on the falling edge of the clock.

If enable bit SREN is set, only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence.

To set up a Synchronous Master Reception:

- Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the desired baud rate.
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.

- Ensure bits CREN and SREN are clear.
- 4. If interrupts are desired, set enable bit RCxIE.
- 5. If 9-bit reception is desired, set bit RX9.
- 6. If a single reception is required, set bit SREN. For continuous reception, set bit CREN.
- Interrupt flag bit RCxIF will be set when reception is complete and an interrupt will be generated if the enable bit RCxIE was set.
- Read the RCSTAx register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREGx register.
- If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

### FIGURE 19-12: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)




TABLE 19-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

| Name     | Bit 7  | Bit 6                              | Bit 5                                       | Bit 4  | Bit 3  | Bit 2              | Bit 1  | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|--|------------------------------------|---|--------|--------|--------------------|--------|-----------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL                          | TMR0IE                                      | INT0IE | RBIE   | TMR0IF INT0IF RBIF |        | 0000 000x | 0000 000u            |                                 |
| PIR1     | PSPIF <sup>(1)</sup>                                       | ADIF                               | ADIF RC1IF TX1IF SSPIF CCP1IF TMR2IF TMR1IF |        |        |                    |        | 0000 0000 | 0000 0000            |                                 |
| PIE1     | PSPIE <sup>(1)</sup>                                       |                                    |   |        |        |                    |        |           |                      | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>                                       | ADIP                               | RC1IP                                       | TX1IP  | SSPIP  | CCP1IP             | TMR2IP | TMR1IP    | 1111 1111            | 1111 1111                       |
| PIR3     | _  | I                                  | RC2IF                                       | TX2IF  | TMR4IF | CCP5IF             | CCP4IF | CCP3IF    | 00 0000              | 00 0000                         |
| PIE3     | _  | 1                                  | RC2IE                                       | TX2IE  | TMR4IE | CCP5IE             | CCP4IE | CCP3IE    | 00 0000              | 00 0000                         |
| IPR3     | _  | I                                  | RC2IP                                       | TX2IP  | TMR4IP | CCP5IP             | CCP4IP | CCP3IP    | 11 1111              | 11 1111                         |
| RCSTAx   | SPEN   | RX9                                | SREN  | CREN   | ADDEN  | FERR               | OERR   | RX9D      | 0000 000x            | 0000 000x                       |
| RCREGx   | Enhanced I   | JSARTx Red                         | eive Regist                                 | er     |        |                    |        |           | 0000 0000            | 0000 0000                       |
| TXSTAx   | CSRC   | TX9 TXEN SYNC SENDB BRGH TRMT TX9D |   |        |        |                    |        |           |                      | 0000 0010                       |
| BAUDCONx | - RCIDL - SCKP BRG16 - WUE ABDEN                           |                                    |   |        |        |                    |        |           | -1-0 0-00            | -1-0 0-00                       |
| SPBRGHx  | GHx Enhanced USARTx Baud Rate Generator Register High Byte |                                    |   |        |        |                    |        |           |                      | 0000 0000                       |
| SPBRGx   | Enhanced USARTx Baud Rate Generator Register Low Byte      |                                    |   |        |        |                    |        |           |                      | 0000 0000                       |

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master reception.

## 19.4 EUSART Synchronous Slave Mode

Synchronous Slave mode is entered by clearing bit CSRC (TXSTAx<7>). This mode differs from the Synchronous Master mode in that the shift clock is supplied externally at the CKx pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in any low-power mode.

### 19.4.1 EUSART SYNCHRONOUS SLAVE TRANSMIT

The operation of the Synchronous Master and Slave modes are identical except in the case of the Sleep mode.

If two words are written to the TXREGx and then the SLEEP instruction is executed, the following will occur:

- The first word will immediately transfer to the TSR register and transmit.
- The second word will remain in the TXREGx register.
- c) Flag bit TXxIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREGx register will transfer the second word to the TSR and flag bit TXxIF will now be set.
- e) If enable bit TXxIE is set, the interrupt will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Transmission:

- Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. Clear bits CREN and SREN.
- If interrupts are desired, set enable bit TXxIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- Enable the transmission by setting enable bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Start transmission by loading data to the TXREGx register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

TABLE 19-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

| Name     | Bit 7  | Bit 6                                       | Bit 5       | Bit 4                                     | Bit 3  | Bit 2              | Bit 1  | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|--|---|-------------|---|--------|--------------------|--------|-----------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL                                   | TMR0IE      | INT0IE                                    | RBIE   | TMR0IF INT0IF RBIF |        | 0000 000x | 0000 000u            |                                 |
| PIR1     | PSPIF <sup>(1)</sup>   | ADIF  | RC1IF       | RC1IF TX1IF SSPIF CCP1IF TMR2IF TMR1IF 00 |        |                    |        |           | 0000 0000            | 0000 0000                       |
| PIE1     | PSPIE <sup>(1)</sup> ADIE RC1IE TX1IE SSPIE CCP1IE TMR2IE TMR1IE |   |             |   |        |                    |        |           |                      | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>   | ADIP RC1IP TX1IP SSPIP CCP1IP TMR2IP TMR1IP |             |   |        |                    |        | 1111 1111 | 1111 1111            |                                 |
| PIR3     | 1  | I   | RC2IF       | TX2IF                                     | TMR4IF | CCP5IF             | CCP4IF | CCP3IF    | 00 0000              | 00 0000                         |
| PIE3     | _  | _   | RC2IE       | TX2IE                                     | TMR4IE | CCP5IE             | CCP4IE | CCP3IE    | 00 0000              | 00 0000                         |
| IPR3     | _  | -   | RC2IP       | TX2IP                                     | TMR4IP | CCP5IP             | CCP4IP | CCP3IP    | 11 1111              | 11 1111                         |
| RCSTAx   | SPEN   | RX9   | SREN        | CREN                                      | ADDEN  | FERR               | OERR   | RX9D      | 0000 000x            | 0000 000x                       |
| TXREGx   | Enhanced U   | SARTx Trans                                 | mit Registe | er  |        |                    |        |           | 0000 0000            | 0000 0000                       |
| TXSTAx   | CSRC   | TX9   | TXEN        | SYNC                                      | SENDB  | BRGH               | TRMT   | TX9D      | 0000 0010            | 0000 0010                       |
| BAUDCONx | _  | - RCIDL - SCKP BRG16 - WUE ABDEN            |             |   |        |                    |        |           | -1-0 0-00            | -1-0 0-00                       |
| SPBRGHx  | Hx Enhanced USARTx Baud Rate Generator Register High Byte        |   |             |   |        |                    |        |           |                      | 0000 0000                       |
| SPBRGx   | Enhanced U   |   | 0000 0000   | 0000 0000                                 |        |                    |        |           |                      |                                 |

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous slave transmission.

## 19.4.2 EUSART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical except in the case of Sleep or any Idle mode and bit SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting the CREN bit prior to entering Sleep or any Idle mode, then a word may be received while in this Low-Power mode. Once the word is received, the RSR register will transfer the data to the RCREGx register; if the RC1IE enable bit is set, the interrupt generated will wake the chip from Low-Power mode. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. If interrupts are desired, set enable bit RCxIE.
- 3. If 9-bit reception is desired, set bit RX9.
- 4. To enable reception, set enable bit CREN.
- Flag bit RCxIF will be set when reception is complete. An interrupt will be generated if enable bit RCxIE was set.
- Read the RCSTAx register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREGx register.
- 8. If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

TABLE 19-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

| Name     | Bit 7  | Bit 6      | Bit 5       | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------|--|------------|-------------|--------|--------|--------|--------|-----------|----------------------|---------------------------------|
| INTCON   | GIE/GIEH   | PEIE/GIEL  | TMR0IE      | INT0IE | RBIE   | TMR0IF | INT0IF | RBIF      | 0000 000x            | 0000 000u                       |
| PIR1     | PSPIF <sup>(1)</sup>   |            |             |        |        |        |        | 0000 0000 | 0000 0000            |                                 |
| PIE1     | PSPIE <sup>(1)</sup> ADIE RC1IE TX1IE SSPIE CCP1IE TMR2IE TMR1IE |            |             |        |        |        |        |           | 0000 0000            | 0000 0000                       |
| IPR1     | PSPIP <sup>(1)</sup>   | ADIP       | RC1IP       | TX1IP  | SSPIP  | CCP1IP | TMR2IP | TMR1IP    | 1111 1111            | 1111 1111                       |
| PIR3     | _  | _          | RC2IF       | TX2IF  | TMR4IF | CCP5IF | CCP4IF | CCP3IF    | 00 0000              | 00 0000                         |
| PIE3     | _  |            | RC2IE       | TX2IE  | TMR4IE | CCP5IE | CCP4IE | CCP3IE    | 00 0000              | 00 0000                         |
| IPR3     | _  | -          | RC2IP       | TX2IP  | TMR4IP | CCP5IP | CCP4IP | CCP3IP    | 11 1111              | 11 1111                         |
| RCSTAx   | SPEN   | RX9        | SREN        | CREN   | ADDEN  | FERR   | OERR   | RX9D      | 0000 000x            | 0000 000x                       |
| RCREGx   | Enhanced U   | SARTx Rece | ive Registe | r      |        |        |        |           | 0000 0000            | 0000 0000                       |
| TXSTAx   | CSRC TX9 TXEN SYNC SENDB BRGH TRMT TX9D                          |            |             |        |        |        |        |           | 0000 0010            | 0000 0010                       |
| BAUDCONx | - RCIDL - SCKP BRG16 - WUE ABDEN                                 |            |             |        |        |        |        | -1-0 0-00 | -1-0 0-00            |                                 |
| SPBRGHx  | SHx Enhanced USARTx Baud Rate Generator Register High Byte       |            |             |        |        |        |        |           |                      | 0000 0000                       |
| SPBRGx   | Enhanced USARTx Baud Rate Generator Register Low Byte            |            |             |        |        |        |        |           |                      | 0000 0000                       |

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous slave reception.

# 20.0 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The analog-to-digital (A/D) converter module has 12 inputs for the PIC18F6525/6621 devices and 16 for the PIC18F8525/8621 devices. This module allows conversion of an analog input signal to a corresponding 10-bit digital number.

A new feature for the A/D converter is the addition of programmable acquisition time. This feature allows the user to select a new channel for conversion and setting the GO/DONE bit immediately. When the GO/DONE bit is set, the selected channel is sampled for the programmed acquisition time before a conversion is actually started. This removes the firmware overhead that may have been required to allow for an acquisition (sampling) period (see Register 20-3 and Section 20.5 "A/D Conversions").

The module has five registers:

- A/D Result High Register (ADRESH)
- A/D Result Low Register (ADRESL)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)
- A/D Control Register 2 (ADCON2)

The ADCON0 register, shown in Register 20-1, controls the operation of the A/D module. The ADCON1 register, shown in Register 20-2, configures the functions of the port pins. The ADCON2 register, shown in Register 20-3, configures the A/D clock source, justification and auto-acquisition time.

### REGISTER 20-1: ADCON0: A/D CONTROL REGISTER 0

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0   | R/W-0 |
|-------|-----|-------|-------|-------|-------|---------|-------|
| _     | _   | CHS3  | CHS2  | CHS1  | CHS0  | GO/DONE | ADON  |
| bit 7 |     |       |       |       |       |         | bit 0 |

#### bit 7-6 Unimplemented: Read as '0'

#### bit 5-2 CHS3:CHS0: Analog Channel Select bits

0000 = Channel 0 (AN0)

0001 = Channel 1 (AN1)

0010 = Channel 2 (AN2)

0011 = Channel 3 (AN3)

0100 = Channel 4 (AN4)

0101 = Channel 5 (AN5)

0110 = Channel 6 (AN6)

0111 = Channel 7 (AN7)

1000 = Channel 8 (AN8)

1001 = Channel 9 (AN9) 1010 = Channel 10 (AN10)

1010 - Chamel 10 (/1110)

1011 = Channel 11 (AN11)

1100 = Channel 12 (AN12)(1)

1101 = Channel 13 (AN13)(1)

1110 = Channel 14 (AN14)(1)

1111 = Channel 15 (AN15)(1)

Note 1: These channels are not available on the PIC18F6525/6621 (64-pin) devices.

### bit 1 GO/DONE: A/D Conversion Status bit

### When ADON = 1:

- 1 = A/D conversion in progress (setting this bit starts the A/D conversion which is automatically cleared by hardware when the A/D conversion is complete)
- 0 = A/D conversion not in progress

### bit 0 ADON: A/D On bit

- 1 = A/D converter module is enabled
- 0 = A/D converter module is disabled

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 20-2: ADCON1: A/D CONTROL REGISTER 1

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-------|-----|-------|-------|-------|-------|-------|-------|
| _     | _   | VCFG1 | VCFG0 | PCFG3 | PCFG2 | PCFG1 | PCFG0 |
| hit 7 |     |       |       |       |       |       | hit 0 |

bit 7-6 Unimplemented: Read as '0'

bit 5-4 VCFG1:VCFG0: Voltage Reference Configuration bits:

| VCFG1<br>VCFG0 | A/D VREF+      | A/D VREF-      |
|----------------|----------------|----------------|
| 00             | AVdd           | AVss           |
| 01             | External VREF+ | AVss           |
| 10             | AVDD           | External VREF- |
| 11             | External VREF+ | External VREF- |

### bit 3-0 **PCFG3:PCFG0:** A/D Port Configuration Control bits:

| PCFG3<br>PCFG0 | AN15 | AN14 | AN13 | AN12 | AN11 | AN10 | AN9 | AN8 | AN7 | AN6 | AN5 | AN4 | AN3 | AN2 | AN1 | ANO |
|----------------|------|------|------|------|------|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 0000           | Α    | Α    | Α    | Α    | Α    | Α    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0001           | D    | D    | Α    | Α    | Α    | Α    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0010           | D    | D    | D    | Α    | Α    | Α    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0011           | D    | D    | D    | D    | Α    | Α    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0100           | D    | D    | D    | D    | D    | Α    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0101           | D    | D    | D    | D    | D    | D    | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0110           | D    | D    | D    | D    | D    | D    | D   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 0111           | D    | D    | D    | D    | D    | D    | D   | D   | Α   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 1000           | D    | D    | D    | D    | D    | D    | D   | D   | D   | Α   | Α   | Α   | Α   | Α   | Α   | Α   |
| 1001           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | Α   | Α   | Α   | Α   | Α   | Α   |
| 1010           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | Α   | Α   | Α   | Α   | Α   |
| 1011           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | D   | Α   | Α   | Α   | Α   |
| 1100           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | D   | D   | Α   | Α   | Α   |
| 1101           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | D   | D   | D   | Α   | Α   |
| 1110           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | D   | D   | D   | D   | Α   |
| 1111           | D    | D    | D    | D    | D    | D    | D   | D   | D   | D   | D   | D   | D   | D   | D   | D   |

A = Analog input D = Digital I/O

**Note:** Shaded cells indicate A/D channels available only on PIC18F8525/8621 devices.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 20-3: ADCON2: A/D CONTROL REGISTER 2

| ADFM — ACQT2 ACQT1 ACQT0 ADCS2 ADCS1 ADCS0 | R/W-0 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|--|-------|-----|-------|-------|-------|-------|-------|-------|
|  | ADFM  | _   | ACQT2 | ACQT1 | ACQT0 | ADCS2 | ADCS1 | ADCS0 |

bit 7 bit 0

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified0 = Left justified

bit 6 Unimplemented: Read as '0'

bit 5-3 ACQT2:ACQT0: A/D Acquisition Time Select bits

000 = 0 TAD<sup>(1)</sup> 001 = 2 TAD 010 = 4 TAD 011 = 6 TAD 100 = 8 TAD 101 = 12 TAD 110 = 16 TAD 111 = 20 TAD

bit 2-0 ADCS2:ADCS0: A/D Conversion Clock Select bits

000 = Fosc/2 001 = Fosc/8 010 = Fosc/32

011 = FRC (clock derived from A/D RC oscillator)<sup>(1)</sup>

100 = FOSC/4 101 = FOSC/16 110 = FOSC/64

111 = FRC (clock derived from A/D RC oscillator)(1)

**Note 1:** If the A/D FRC clock source is selected, a delay of one TcY (instruction cycle) is added before the A/D clock starts. This allows the SLEEP instruction to be executed before starting a conversion.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (VDD and Vss), or the voltage level on the RA3/AN3/ VREF+ pin and RA2/AN2/VREF- pin.


The A/D converter has a unique feature of being able to operate while the device is in Sleep mode. To operate in Sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.

The output of the sample and hold is the input into the converter which generates the result via successive approximation.

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off and any conversion is aborted.

Each port pin associated with the A/D converter can be configured as an analog input (RA3 can also be a voltage reference), or as a digital I/O. The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH/ADRESL registers, the GO/DONE bit (ADCON0 register) is cleared and A/D interrupt flag bit, ADIF, is set. The block diagram of the A/D module is shown in Figure 20-1.

FIGURE 20-1: A/D BLOCK DIAGRAM



The value in the ADRESH/ADRESL registers is not modified for a Power-on Reset. The ADRESH/ADRESL registers will contain unknown data after a Power-on Reset.


After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see **Section 20.1** "A/D Acquisition Requirements". After this acquisition time has elapsed, the A/D conversion can be started.

The following steps should be followed to do an A/D conversion:

- 1. Configure the A/D module:
  - Configure analog pins, voltage reference and digital I/O (ADCON1)
  - Select A/D input channel (ADCON0)
  - Select A/D conversion clock (ADCON2)
  - Turn on A/D module (ADCON0)

- 2. Configure A/D interrupt (if desired):
  - · Clear ADIF bit
  - Set ADIE bit
  - · Set GIE bit
- 3. Wait the required acquisition time (not required in case of auto-acquisition time).
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0 register)
- 5. Wait for A/D conversion to complete, by either:
  - Polling for the GO/DONE bit to be cleared OR
  - · Waiting for the A/D interrupt
- Read A/D Result registers (ADRESH:ADRESL); clear bit ADIF, if required.
- For next conversion, go to step 1 or step 2, as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before the next acquisition starts.

### FIGURE 20-2: ANALOG INPUT MODEL



### 20.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 20-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 2.5 k $\Omega$ . After the analog input channel is selected (changed), this acquisition must be done before the conversion can be started.

**Note:** When the conversion is started, the holding capacitor is disconnected from the input pin.

To calculate the minimum acquisition time, Equation 20-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

Example 20-3 shows the calculation of the minimum required acquisition time, TACQ. This calculation is based on the following application system assumptions:

 $\begin{array}{lll} \text{CHOLD} & = & 120 \text{ pF} \\ \text{Rs} & = & 2.5 \text{ k}\Omega \\ \text{Conversion Error} & \leq & 1/2 \text{ LSb} \end{array}$ 

VDD =  $5V \rightarrow Rss = 7 \text{ k}\Omega$ Temperature =  $50^{\circ}\text{C}$  (system max.) VHOLD = 0V @ time = 0

#### **EQUATION 20-1: ACQUISITION TIME**

TACQ = Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient

= TAMP + TC + TCOFF

#### **EQUATION 20-2: A/D MINIMUM CHARGING TIME**

 $V \text{HOLD} \quad = \quad \left( V \text{REF} - \left( V \text{REF} / 2048 \right) \right) \bullet \left( 1 - e^{\left( - \text{Tc/C} + \text{CHOLD} \left( Ric + Rss + Rs \right) \right)} \right)$ 

or

Tc =  $-(120 \text{ pF})(1 \text{ k}\Omega + \text{Rss} + \text{Rs}) \ln(1/2047)$ 

#### EQUATION 20-3: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME

TACQ = TAMP + TC + TCOFF

Temperature coefficient is only required for temperatures > 25°C.

TACQ =  $2 \mu s + TC + [(Temp - 25^{\circ}C)(0.05 \mu s/^{\circ}C)]$ 

TC =  $-\text{CHOLD} (\text{RIC} + \text{RSS} + \text{RS}) \ln(1/2047)$ 

 $-120 \text{ pF} (1 \text{ k}\Omega + 7 \text{ k}\Omega + 2.5 \text{ k}\Omega) \ln(0.0004885)$ 

-120 pF (10.5 k $\Omega$ ) ln(0.0004885)

-1.26  $\mu s$  (-7.6241)

9.61 µs

TACQ =  $2 \mu s + 9.61 \mu s + [(50^{\circ}C - 25^{\circ}C)(0.05 \mu s/^{\circ}C)]$ 

 $11.61 \, \mu s + 1.25 \, \mu s$ 

12.86 µs

# 20.2 Selecting and Configuring Acquisition Time

The ADCON2 register allows the user to select an acquisition time that occurs each time the GO/DONE bit is set. It also gives users the option to use an automatically determined acquisition time.

Acquisition time may be set with the ACQT2:ACQT0 bits (ADCON2<5:3>), which provides a range of 2 to 20 TAD. When the GO/DONE bit is set, the A/D module continues to sample the input for the selected acquisition time, then automatically begins a conversion. Since the acquisition time is programmed, there may be no need to wait for an acquisition time between selecting a channel and setting the GO/DONE bit.

Automatic acquisition is selected when the ACQT2:ACQT0 = 000. When the GO/DONE bit is set, sampling is stopped and a conversion begins. The user is responsible for ensuring the required acquisition time has passed between selecting the desired input channel and setting the GO/DONE bit. This option is also the default Reset state of the ACQT2:ACQT0 bits and is compatible with devices that do not offer programmable acquisition times.

In either case, when the conversion is completed, the GO/DONE bit is cleared, the ADIF flag is set and the A/D begins sampling the currently selected channel again. If an acquisition time is programmed, there is nothing to indicate if the acquisition time has ended or if the conversion has begun.

## 20.3 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 12 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable. There are seven possible options for TAD:

- 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- · Internal RC oscillator

For correct A/D conversions, the A/D conversion clock (TAD) must be selected to ensure a minimum TAD time of 1.6  $\mu$ s.

Table 20-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

TABLE 20-1: TAD vs. DEVICE OPERATING FREQUENCIES

| AD Clock So | Maximum Device Frequency |                           |  |
|-------------|--------------------------|---------------------------|--|
| Operation   | ADCS2:ADCS0              | PIC18F6525/6621/8525/8621 |  |
| 2 Tosc      | 000                      | 1.25 MHz                  |  |
| 4 Tosc      | 100                      | 2.50 MHz                  |  |
| 8 Tosc      | 001                      | 5.00 MHz                  |  |
| 16 Tosc     | 101                      | 10.0 MHz                  |  |
| 32 Tosc     | 010                      | 20.0 MHz                  |  |
| 64 Tosc     | 110                      | 40.0 MHz                  |  |
| RC          | x11                      | _                         |  |

### 20.4 Configuring Analog Port Pins

The ADCON1, TRISA, TRISF and TRISH registers control the operation of the A/D port pins. The port pins needed as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS3:CHS0 bits and the TRIS bits.


- Note 1: When reading the port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as a digital input will convert as an analog input. Analog levels on a digitally configured input will not affect the conversion accuracy.
  - 2: Analog levels on any pin defined as a digital input may cause the input buffer to consume current out of the device's specification limits.

### 20.5 A/D Conversions

Figure 20-3 shows the operation of the A/D converter after the GODONE bit has been set. Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D Result register pair will NOT be updated with the partially completed A/D conversion sample. That is, the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion (or the last value written to the ADRESH:ADRESL registers). After the A/D conversion is aborted, a 2 TAD wait is required before the next acquisition is started. After this 2 TAD wait, acquisition on the selected channel is automatically started.

Note: The GO/DONE bit should NOT be set in the same instruction that turns on the A/D.

### FIGURE 20-3: A/D CONVERSION TAD CYCLES



### 20.6 Use of the ECCP2 Trigger

An A/D conversion can be started by the special event trigger of the ECCP2 module. This requires that the CCP2M3:CCP2M0 bits (CCP2CON<3:0>) be programmed as '1011' and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/DONE bit will be set, starting the A/D conversion and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the

A/D acquisition period with minimal software overhead (moving ADRESH/ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition done before the special event trigger sets the GO/DONE bit and starts a conversion.

If the A/D module is not enabled (ADON is cleared), the special event trigger will be ignored by the A/D module but will still reset the Timer1 (or Timer3) counter.

TABLE 20-2: SUMMARY OF REGISTERS ASSOCIATED WITH A/D

| Name                 | Bit 7                                 | Bit 6                                 | Bit 5    | Bit 4         | Bit 3      | Bit 2  | Bit 1     | Bit 0     | Value on<br>POR, BOR | Value on<br>all other<br>Resets |
|----------------------|---------------------------------------|---------------------------------------|----------|---------------|------------|--------|-----------|-----------|----------------------|---------------------------------|
| INTCON               | GIE/<br>GIEH                          | PEIE/<br>GIEL                         | TMR0IE   | INT0IE        | RBIE       | TMR0IF | INT0IF    | RBIF      | 0000 000x            | 0000 000u                       |
| PIR1                 | PSPIF <sup>(1)</sup>                  | ADIF                                  | RC1IF    | TX1IF         | SSPIF      | CCP1IF | TMR2IF    | TMR1IF    | 0000 0000            | 0000 0000                       |
| PIE1                 | PSPIE <sup>(1)</sup>                  | ADIE                                  | RC1IE    | TX1IE         | SSPIE      | CCP1IE | TMR2IE    | TMR1IE    | 0000 0000            | 0000 0000                       |
| IPR1                 | PSPIP <sup>(1)</sup>                  | ADIP                                  | RC1IP    | TX1IP         | SSPIP      | CCP1IP | TMR2IP    | TMR1IP    | 1111 1111            | 1111 1111                       |
| PIR2                 | _                                     | CMIF                                  | _        | EEIF          | BCLIF      | LVDIF  | TMR3IF    | CCP2IF    | -0-0 0000            | -0-0 0000                       |
| PIE2                 | _                                     | CMIE                                  | _        | EEIE          | BCLIE      | LVDIE  | TMR3IE    | CCP2IE    | -0-0 0000            | -0-0 0000                       |
| IPR2                 | _                                     | CMIP                                  | _        | EEIP          | BCLIP      | LVDIP  | TMR3IP    | CCP2IP    | -1-1 1111            | -1-1 1111                       |
| ADRESH               | A/D Resul                             | t Register H                          | igh Byte |               |            |        |           |           | xxxx xxxx            | uuuu uuuu                       |
| ADRESL               | A/D Resul                             | t Register L                          | ow Byte  |               |            |        |           |           | xxxx xxxx            | uuuu uuuu                       |
| ADCON0               | _                                     | _                                     | CHS3     | CHS3          | CHS1       | CHS0   | GO/DONE   | ADON      | 00 0000              | 00 0000                         |
| ADCON1               | _                                     | _                                     | VCFG1    | VCFG0         | PCFG3      | PCFG2  | PCFG1     | PCFG0     | 00 0000              | 00 0000                         |
| ADCON2               | ADFM                                  | _                                     | ACQT2    | ACQT1         | ACQT0      | ADCS2  | ADCS1     | ADCS0     | 0-00 0000            | 0-00 0000                       |
| PORTA                | _                                     | RA6 <sup>(2)</sup>                    | RA5      | RA4           | RA3        | RA2    | RA1       | RA0       | -x0x 0000            | -u0u 0000                       |
| TRISA                | _                                     | TRISA6 <sup>(2)</sup>                 | PORTA Da | ata Direction | on Registe |        | -111 1111 | -111 1111 |                      |                                 |
| PORTF                | RF7                                   | RF6                                   | RF5      | RF4           | RF3        | RF2    | RF1       | RF0       | x000 0000            | u000 0000                       |
| TRISF                | PORTF Data Direction Control Register |                                       |          |               |            |        |           | 1111 1111 | 1111 1111            |                                 |
| PORTH <sup>(3)</sup> | RH7 RH6 RH5 RH4 RH3 RH2 RH1 RH0       |                                       |          |               |            |        |           | RH0       | 0000 xxxx            | 0000 uuuu                       |
| TRISH(3)             | PORTH Da                              | PORTH Data Direction Control Register |          |               |            |        |           |           |                      | 1111 1111                       |

**Legend:** x = unknown, u = unchanged, — = unimplemented, read as '0'. Shaded cells are not used for A/D conversion.

Note 1: Enabled only in Microcontroller mode for PIC18F8525/8621 devices.

<sup>2:</sup> RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator modes only and read '0' in all other oscillator modes.

<sup>3:</sup> Implemented on PIC18F8525/8621 devices only, otherwise read as '0'.

NOTES:

### 21.0 COMPARATOR MODULE

The comparator module contains two analog comparators. The inputs to the comparators are multiplexed with the RF1 through RF6 pins. The on-chip Voltage Reference (Section 22.0 "Comparator Voltage Reference Module") can also be an input to the comparators.

The CMCON register, shown as Register 21-1, controls the comparator input and output multiplexers. A block diagram of the various comparator configurations is shown in Figure 21-1.

### REGISTER 21-1: CMCON: COMPARATOR CONTROL REGISTER

| R-0   | R-0   | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| C2OUT | C1OUT | C2INV | C1INV | CIS   | CM2   | CM1   | CM0   |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7 **C2OUT**: Comparator 2 Output bit

When C2INV = 0:

1 = C2 VIN+ > C2 VIN-

0 = C2 VIN+ < C2 VIN-

When C2INV = 1:

1 = C2 VIN+ < C2 VIN-

0 = C2 Vin+ > C2 Vin-

bit 6 C10UT: Comparator 1 Output bit

When C1INV = 0:

1 = C1 VIN+ > C1 VIN-

0 = C1 VIN+ < C1 VIN-

When C1INV = 1:

1 = C1 VIN+ < C1 VIN-

0 = C1 Vin+ > C1 Vin-

bit 5 **C2INV**: Comparator 2 Output Inversion bit

1 = C2 output inverted

0 = C2 output not inverted

bit 4 C1INV: Comparator 1 Output Inversion bit

1 = C1 output inverted

0 = C1 output not inverted

bit 3 CIS: Comparator Input Switch bit

When CM2:CM0 = 110:

1 = C1 Vin- connects to RF5/AN10

C2 VIN- connects to RF3/AN8

0 = C1 VIN- connects to RF6/AN11

C2 VIN- connects to RF4/AN9

bit 2-0 CM2:CM0: Comparator Mode bits

Figure 21-1 shows the Comparator modes and the CM2:CM0 bit settings.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'


-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 21.1 Comparator Configuration

There are eight modes of operation for the comparators. The CMCON register is used to select these modes. Figure 21-1 shows the eight possible modes. The TRISF register controls the data direction of the comparator pins for each mode. If the Comparator mode is changed, the comparator output level may not be valid for the specified mode change delay shown in **Section 27.0 "Electrical Characteristics"**.

**Note:** Comparator interrupts should be disabled during a Comparator mode change; otherwise, a false interrupt may occur.

#### FIGURE 21-1: COMPARATOR I/O OPERATING MODES




### 21.2 Comparator Operation

A single comparator is shown in Figure 21-2, along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 21-2 represent the uncertainty due to input offsets and response time.

### 21.3 Comparator Reference

An external or internal reference signal may be used depending on the comparator operating mode. The analog signal present at VIN- is compared to the signal at VIN+ and the digital output of the comparator is adjusted accordingly (Figure 21-2).

FIGURE 21-2: SINGLE COMPARATOR



### 21.3.1 EXTERNAL REFERENCE SIGNAL

When external voltage references are used, the comparator module can be configured to have the comparators operate from the same, or different reference sources. However, threshold detector applications may require the same reference. The reference signal must be between VSS and VDD and can be applied to either pin of the comparator(s).

#### 21.3.2 INTERNAL REFERENCE SIGNAL

The comparator module also allows the selection of an internally generated voltage reference for the comparators. **Section 22.0 "Comparator Voltage Reference Module"** contains a detailed description of the comparator voltage reference module that provides this signal. The internal reference signal is used when comparators are in mode CM<2:0> = 110 (Figure 21-1). In this mode, the internal voltage reference is applied to the VIN+ pin of both comparators.

### 21.4 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output has a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (Section 27.0 "Electrical Characteristics").

### 21.5 Comparator Outputs

The comparator outputs are read through the CMCON register. These bits are read-only. The comparator outputs may also be directly output to the RF1 and RF2 I/O pins. When enabled, multiplexors in the output path of the RF1 and RF2 pins will switch and the output of each pin will be the unsynchronized output of the comparator. The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications. Figure 21-3 shows the comparator output block diagram.

The TRISA bits will still function as an output enable/ disable for the RF1 and RF2 pins while in this mode.

The polarity of the comparator outputs can be changed using the C2INV and C1INV bits (CMCON<4:5>).

- Note 1: When reading the Port register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input according to the Schmitt Trigger input specification.
  - 2: Analog levels on any pin defined as a digital input may cause the input buffer to consume more current than is specified.




FIGURE 21-3: COMPARATOR OUTPUT BLOCK DIAGRAM

### 21.6 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<7:6>, to determine the actual change that occurred. The CMIF bit (PIR registers) is the comparator interrupt flag. The CMIF bit must be reset by clearing '0'. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

The CMIE bit (PIE registers) and the PEIE bit (INTCON register) must be set to enable the interrupt. In addition, the GIE bit must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

Note: If a change in the CMCON register (C1OUT or C2OUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR registers) interrupt flag may not get set.

The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of CMCON will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition and allow flag bit CMIF to be cleared.

## 21.7 Comparator Operation During Sleep

When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode when enabled. While the comparator is powered up, higher Sleep currents than shown in the power-down current specification will occur. Each operational comparator will consume additional current, as shown in the comparator specifications. To minimize power consumption while in Sleep mode, turn off the comparators, CM<2:0> = 111, before entering Sleep. If the device wakes up from Sleep, the contents of the CMCON register are not affected.

### 21.8 Effects of a Reset

A device Reset forces the CMCON register to its Reset state, causing the comparator module to be in the comparator Reset mode, CM<2:0>=000. This ensures that all potential inputs are analog inputs. Device current is minimized when analog inputs are present at Reset time. The comparators will be powered down during the Reset interval.

## 21.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 21-4. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up condition may occur. A maximum source impedance of  $10\ k\Omega$  is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.

FIGURE 21-4: COMPARATOR ANALOG INPUT MODEL




TABLE 21-1: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

| Name   | Bit 7        | Bit 6         | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR | Value on<br>all other<br>Resets |
|--------|--------------|---------------|--------|--------|--------|--------|--------|--------|-----------------|---------------------------------|
| CMCON  | C2OUT        | C10UT         | C2INV  | C1INV  | CIS    | CM2    | CM1    | CM0    | 0000 0000       | 0000 0000                       |
| CVRCON | CVREN        | CVROE         | CVRR   | CVRSS  | CVR3   | CVR2   | CVR1   | CVR0   | 0000 0000       | 0000 0000                       |
| INTCON | GIE/<br>GIEH | PEIE/<br>GIEL | TMR0IE | INT0IE | RBIE   | TMR0IF | INT0IF | RBIF   | 0000 000x       | 0000 000u                       |
| PIR2   | _            | CMIF          | _      | EEIF   | BCLIF  | LVDIF  | TMR3IF | CCP2IF | -0-0 0000       | -0-0 0000                       |
| PIE2   | _            | CMIE          | _      | EEIE   | BCLIE  | LVDIE  | TMR3IE | CCP2IE | -0-0 0000       | -0-0 0000                       |
| IPR2   | _            | CMIP          | _      | EEIP   | BCLIP  | LVDIP  | TMR3IP | CCP2IP | -1-1 1111       | -1-1 1111                       |
| PORTF  | RF7          | RF6           | RF5    | RF4    | RF3    | RF2    | RF1    | RF0    | x000 0000       | u000 0000                       |
| LATF   | LATF7        | LATF6         | LATF5  | LATF4  | LATF3  | LATF2  | LATF1  | LATF0  | xxxx xxxx       | uuuu uuuu                       |
| TRISF  | TRISF7       | TRISF6        | TRISF5 | TRISF4 | TRISF3 | TRISF2 | TRISF1 | TRISF0 | 1111 1111       | 1111 1111                       |

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'.

Shaded cells are unused by the comparator module.

# 22.0 COMPARATOR VOLTAGE REFERENCE MODULE

The comparator voltage reference is a 16-tap resistor ladder network that provides a selectable voltage reference. The resistor ladder is segmented to provide two ranges of CVREF values and has a power-down function to conserve power when the reference is not being used. The CVRCON register controls the operation of the reference as shown in Register 22-1. The block diagram is given in Figure 22-1.

The comparator reference supply voltage can come from either VDD and VSS, or the external VREF+ and VREF+ that are multiplexed with RA3 and RA2. The comparator reference supply voltage is controlled by the CVRSS bit.

## 22.1 Configuring the Comparator Voltage Reference

The comparator voltage reference can output 16 distinct voltage levels for each range. The equations used to calculate the output of the comparator voltage reference are as follows:

If CVRR = 1:

CVREF = (CVR<3:0>/24) x CVRSRC

If CVRR = 0:

CVREF=(CVRSRC x 1/4)+(CVR<3:0>/32)xCVRSRC

The settling time of the comparator voltage reference must be considered when changing the CVREF output (Section 27.0 "Electrical Characteristics").

### REGISTER 22-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER

| R/W-0 | R/W-0                | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-------|----------------------|-------|-------|-------|-------|-------|-------|
| CVREN | CVROE <sup>(1)</sup> | CVRR  | CVRSS | CVR3  | CVR2  | CVR1  | CVR0  |
| bit 7 |                      |       |       |       |       |       | bit 0 |

bit 7 CVREN: Comparator Voltage Reference Enable bit

1 = CVREF circuit powered on

0 = CVREF circuit powered down

bit 6 **CVROE**: Comparator VREF Output Enable bit<sup>(1)</sup>

1 = CVREF voltage level is also output on the RF5/AN10/CVREF pin

0 = CVREF voltage is disconnected from the RF5/AN10/CVREF pin

**Note 1:** If enabled for output, RF5 must also be configured as an input by setting TRISF<5> to '1'.

bit 5 CVRR: Comparator VREF Range Selection bit

1 = 0.00 CVRSRC to 0.667 CVRSRC, with CVRSRC/24 step size (low range)

0 = 0.25 CVRSRC to 0.75 CVRSRC, with CVRSRC/32 step size (high range)

bit 4 CVRSS: Comparator VREF Source Selection bit

1 = Comparator reference source, CVRSRC = VREF+ - VREF-

0 = Comparator reference source, CVRSRC = AVDD - AVSS

bit 3-0 **CVR3:CVR0:** Comparator VREF Value Selection bits  $(0 \le VR3:VR0 \le 15)$ 

When CVRR = 1:

CVREF = (CVR<3:0>/ 24) • (CVRSRC)

When CVRR = 0:


CVREF = 1/4 • (CVRSRC) + (CVR3:CVR0/32) • (CVRSRC)

| _ | .e | ч | ┖ | <br>u |  |
|---|----|---|---|-------|--|

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### FIGURE 22-1: COMPARATOR VOLTAGE REFERENCE BLOCK DIAGRAM



### 22.2 Voltage Reference Accuracy/Error

The full range of voltage reference cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 22-1) keep CVREF from approaching the reference source rails. The voltage reference is derived from the reference source; therefore, the CVREF output changes with fluctuations in that source. The tested absolute accuracy of the voltage reference can be found in **Section 27.0** "Electrical Characteristics".

### 22.3 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the CVRCON register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

### 22.4 Effects of a Reset


A device Reset disables the voltage reference by clearing bit CVREN (CVRCON<7>). This Reset also disconnects the reference from the RA2 pin by clearing bit CVROE (CVRCON<6>) and selects the high-voltage range by clearing bit CVRR (CVRCON<5>). The VRSS value select bits, CVRCON<3:0>, are also cleared.

### 22.5 Connection Considerations

The voltage reference module operates independently of the comparator module. The output of the reference generator may be connected to the RF5 pin if the TRISF<5> bit is set and the CVROE bit is set. Enabling the voltage reference output onto the RF5 pin configured as a digital input will increase current consumption. Connecting RF5 as a digital output with VRSS enabled will also increase current consumption.

The RF5 pin can be used as a simple D/A output with limited drive capability. Due to the limited current drive capability, a buffer must be used on the voltage reference output for external connections to VREF. Figure 22-2 shows an example buffering technique.

### FIGURE 22-2: COMPARATOR VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE



### TABLE 22-1: REGISTERS ASSOCIATED WITH COMPARATOR VOLTAGE REFERENCE

| Name   | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Value on<br>POR | Value on<br>all other<br>Resets |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------------|---------------------------------|
| CVRCON | CVREN  | CVROE  | CVRR   | CVRSS  | CVR3   | CVR2   | CVR1   | CVR0   | 0000 0000       | 0000 0000                       |
| CMCON  | C2OUT  | C1OUT  | C2INV  | C1INV  | CIS    | CM2    | CM1    | CM0    | 0000 0000       | 0000 0000                       |
| TRISF  | TRISF7 | TRISF6 | TRISF5 | TRISF4 | TRISF3 | TRISF2 | TRISF1 | TRISF0 | 1111 1111       | 1111 1111                       |

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used with the comparator voltage reference.

NOTES:

### 23.0 LOW-VOLTAGE DETECT


In many applications, the ability to determine if the device voltage (VDD) is below a specified voltage level is a desirable feature. A window of operation for the application can be created, where the application software can do "housekeeping tasks" before the device voltage exits the valid operating range. This can be done using the Low-Voltage Detect module.

This module is a software programmable circuitry, where a device voltage trip point can be specified. When the voltage of the device becomes lower then the specified point, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to that interrupt source.

The Low-Voltage Detect circuitry is completely under software control. This allows the circuitry to be "turned off" by the software which minimizes the current consumption for the device.

Figure 23-1 shows a possible application voltage curve (typically for batteries). Over time, the device voltage decreases. When the device voltage equals voltage VA, the LVD logic generates an interrupt. This occurs at time TA. The application software then has the time, until the device voltage is no longer in valid operating range, to shutdown the system. Voltage point VB is the minimum valid operating voltage specification. This occurs at time TB. The difference TB – TA is the total time for shutdown.






The block diagram for the LVD module is shown in Figure 23-2. A comparator uses an internally generated reference voltage as the set point. When the selected tap output of the device voltage crosses the set point (is lower than), the LVDIF bit is set.

Each node in the resistor divider represents a "trip point" voltage. The "trip point" voltage is the minimum supply voltage level at which the device can operate before the LVD module asserts an interrupt. When the


supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the 1.2V internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal setting the LVDIF bit. This voltage is software programmable to any one of 16 values (see Figure 23-2). The trip point is selected by programming the LVDL3:LVDL0 bits (LVDCON<3:0>).

FIGURE 23-2: LOW-VOLTAGE DETECT (LVD) BLOCK DIAGRAM



The LVD module has an additional feature that allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits LVDL3:LVDL0 are set to '1111'. In this state, the comparator input is multiplexed from the external input pin, LVDIN (Figure 23-3). This gives users flexibility because it allows them to configure the Low-Voltage Detect interrupt to occur at any voltage in the valid operating range.

FIGURE 23-3: LOW-VOLTAGE DETECT (LVD) WITH EXTERNAL INPUT BLOCK DIAGRAM



## 23.1 Control Register

The Low-Voltage Detect Control register (Register 23-1) controls the operation of the Low-Voltage Detect circuitry.

#### REGISTER 23-1: LVDCON: LOW-VOLTAGE DETECT CONTROL REGISTER

| U-0   | U-0 | R-0   | R/W-0 | R/W-0 | R/W-1 | R/W-0 | R/W-1 |
|-------|-----|-------|-------|-------|-------|-------|-------|
| _     | _   | IRVST | LVDEN | LVDL3 | LVDL2 | LVDL1 | LVDL0 |
| bit 7 |     |       |       |       |       |       | bit 0 |

bit 7-6 Unimplemented: Read as '0'

bit 5 IRVST: Internal Reference Voltage Stable Flag bit

- 1 = Indicates that the Low-Voltage Detect logic will generate the interrupt flag at the specified voltage range
- 0 = Indicates that the Low-Voltage Detect logic will not generate the interrupt flag at the specified voltage range and the LVD interrupt should not be enabled
- bit 4 LVDEN: Low-Voltage Detect Power Enable bit
  - 1 = Enables LVD, powers up LVD circuit
  - 0 = Disables LVD, powers down LVD circuit
- bit 3-0 LVDL3:LVDL0: Low-Voltage Detection Limit bits
  - 1111 = External analog input is used (input comes from the LVDIN pin)
  - 1110 = 4.45V-4.83V
  - 1101 = 4.16V-4.5V
  - 1100 = 3.96V-4.3V
  - 1011 = 3.76V 3.92V
  - 1010 = 3.57V-3.87V
  - 1001 = 3.47V-3.75V
  - 1000 = 3.27V-3.55V
  - 0111 = 2.98V-3.22V0110 = 2.77V-3.01V
  - 0101 = 2.67V-2.89V
  - 0100 = 2.48V-2.68V
  - 0011 = 2.37V-2.57V
  - 0010 = 2.18V-2.36V
  - 0001 = 1.98V-2.14V
  - 0000 = Reserved

**Note:** LVDL3:LVDL0 modes, which result in a trip point below the valid operating voltage of the device, are not tested.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | l bit, read as '0' |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

### 23.2 Operation

Depending on the power source for the device voltage, the voltage normally decreases relatively slowly. This means that the LVD module does not need to be constantly operating. To decrease the current requirements, the LVD circuitry only needs to be enabled for short periods where the voltage is checked. After doing the check, the LVD module may be disabled.


Each time that the LVD module is enabled, the circuitry requires some time to stabilize. After the circuitry has stabilized, all status flags may be cleared. The module will then indicate the proper state of the system.

The following steps are needed to set up the LVD module:

- Write the value to the LVDL3:LVDL0 bits (LVDCON register) which selects the desired LVD trip point.
- Ensure that LVD interrupts are disabled (the LVDIE bit is cleared or the GIE bit is cleared).
- 3. Enable the LVD module (set the LVDEN bit in the LVDCON register).
- 4. Wait for the LVD module to stabilize (the IRVST bit to become set).
- Clear the LVD interrupt flag, which may have falsely become set, until the LVD module has stabilized (clear the LVDIF bit).
- Enable the LVD interrupt (set the LVDIE and the GIE bits).

Figure 23-4 shows typical waveforms that the LVD module may be used to detect.

FIGURE 23-4: LOW-VOLTAGE DETECT WAVEFORMS



### 23.2.1 REFERENCE VOLTAGE SET POINT

The internal reference voltage of the LVD module may be used by other internal circuitry (the Programmable Brown-out Reset). If these circuits are disabled (lower current consumption), the reference voltage circuit requires a time to become stable before a low-voltage condition can be reliably detected. This time is invariant of system clock speed. This start-up time is specified in electrical specification parameter 36. The low-voltage interrupt flag will not be enabled until a stable reference voltage is reached. Refer to the waveform in Figure 23-4.

### 23.2.2 CURRENT CONSUMPTION

When the module is enabled, the LVD comparator and voltage divider are enabled and will consume static current. The voltage divider can be tapped from multiple places in the resistor array. Total current consumption, when enabled, is specified in electrical specification parameter D022B.

### 23.3 Operation During Sleep

When enabled, the LVD circuitry continues to operate during Sleep. If the device voltage crosses the trip point, the LVDIF bit will be set and the device will wake-up from Sleep. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

#### 23.4 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the LVD module to be turned off.

NOTES:

### 24.0 SPECIAL FEATURES OF THE CPU

There are several features intended to maximize system reliability, minimize cost through elimination of external components, provide power-saving operating modes and offer code protection. These are:

- · Oscillator Selection
- Reset
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Reset (BOR)
- Interrupts
- · Watchdog Timer (WDT)
- Sleep
- · Code Protection
- ID Locations
- · In-Circuit Serial Programming

All PIC18F6525/6621/8525/8621 devices have a Watchdog Timer which is permanently enabled via the configuration bits, or software controlled. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT) which provides a fixed delay on power-up only, designed to keep the part in Reset while the power supply stabilizes. With these two timers on-chip, most applications need no external Reset circuitry.

Sleep mode is designed to offer a very low current power-down mode. The user can wake-up from Sleep through external Reset, Watchdog Timer wake-up, or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost, while the LP crystal option saves power. A set of configuration bits is used to select various options.

## 24.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1'), to select various device configurations. These bits are mapped, starting at program memory location 300000h.

The user will note that address 300000h is beyond the user program memory space. In fact, it belongs to the configuration memory space (300000h through 3FFFFFh) which can only be accessed using table reads and table writes.

Programming the Configuration registers is done in a manner similar to programming the Flash memory. The EECON1 register WR bit starts a self-timed write to the Configuration register. In normal operation mode, a TBLWT instruction, with the TBLPTR pointed to the Configuration register, sets up the address and the data for the Configuration register write. Setting the WR bit starts a long write to the Configuration register. The Configuration registers are written a byte at a time. To write or erase a configuration cell, a TBLWT instruction can write a '1' or a '0' into the cell.

TABLE 24-1: CONFIGURATION BITS AND DEVICE IDS

| File                   | Name     | Bit 7 | Bit 6 | Bit 5  | Bit 4  | Bit 3                | Bit 2  | Bit 1                 | Bit 0  | Default/<br>Unprogrammed<br>Value |
|------------------------|----------|-------|-------|--------|--------|----------------------|--------|-----------------------|--------|-----------------------------------|
| 300001h                | CONFIG1H | _     | _     | OSCSEN | _      | FOSC3                | FOSC2  | FOSC1                 | FOSC0  | 1- 1111                           |
| 300002h                | CONFIG2L | _     | _     | _      | _      | BORV1                | BORV0  | BOR                   | PWRTEN | 1111                              |
| 300003h                | CONFIG2H | _     | _     | _      | WDTPS3 | WDTPS2               | WDTPS1 | WDTPS0                | WDTEN  | 1 1111                            |
| 300004h <sup>(1)</sup> | CONFIG3L | WAIT  | _     | _      | _      | _                    | _      | PM1                   | PM0    | 111                               |
| 300005h                | CONFIG3H | MCLRE | _     | -      | _      | 1                    |        | ECCPMX <sup>(1)</sup> | CCP2MX | 111                               |
| 300006h                | CONFIG4L | DEBUG | _     | -      | _      | _                    | LVP    | -                     | STVREN | 11-1                              |
| 300008h                | CONFIG5L | _     | _     | _      | _      | CP3 <sup>(2)</sup>   | CP2    | CP1                   | CP0    | 1111                              |
| 300009h                | CONFIG5H | CPD   | СРВ   | _      | _      | _                    | _      | _                     | _      | 11                                |
| 30000Ah                | CONFIG6L |       | _     | -      | _      | WRT3 <sup>(2)</sup>  | WRT2   | WRT1                  | WRT0   | 1111                              |
| 30000Bh                | CONFIG6H | WRTD  | WRTB  | WRTC   | _      |                      |        | I                     | _      | 111                               |
| 30000Ch                | CONFIG7L | _     | _     | _      | _      | EBTR3 <sup>(2)</sup> | EBTR2  | EBTR1                 | EBTR0  | 1111                              |
| 30000Dh                | CONFIG7H | -     | EBTRB |        | _      | _                    | _      |                       | _      | -1                                |
| 3FFFFEh                | DEVID1   | DEV2  | DEV1  | DEV0   | REV4   | REV3                 | REV2   | REV1                  | REV0   | (Note 3)                          |
| 3FFFFFh                | DEVID2   | DEV10 | DEV9  | DEV8   | DEV7   | DEV6                 | DEV5   | DEV4                  | DEV3   | 0000 1010                         |

**Legend:** x = unknown, u = unchanged, - = unimplemented. Shaded cells are unimplemented, read as '0'.

Note 1: Unimplemented in PIC18F6525/6621 devices; maintain this bit set.

- 2: Unimplemented in PIC18FX525 devices; maintain this bit set.
- 3: See Register 24-13 for DEVID1 values.

### REGISTER 24-1: CONFIG1H: CONFIGURATION REGISTER 1 HIGH (BYTE ADDRESS 300001h)

| U-0   | U-0 | R/P-1  | U-0 | R/P-1 | R/P-1 | R/P-1 | R/P-1 |
|-------|-----|--------|-----|-------|-------|-------|-------|
| _     | _   | OSCSEN | _   | FOSC3 | FOSC2 | FOSC1 | FOSC0 |
| bit 7 |     |        |     |       |       |       | bit 0 |

bit 7-6 Unimplemented: Read as '0'

bit 5 OSCSEN: Oscillator System Clock Switch Enable bit

- 1 = Oscillator system clock switch option is disabled (main oscillator is source)
- 0 = Timer1 oscillator system clock switch option is enabled (oscillator switching is enabled)
- bit 4 Unimplemented: Read as '0'
- bit 3-0 FOSC3:FOSC0: Oscillator Selection bits
  - 1111 = RC oscillator with OSC2 configured as RA6
  - 1110 = HS oscillator with SW enabled 4x PLL
  - 1101 = EC oscillator with OSC2 configured as RA6 and SW enabled 4x PLL
  - 1100 = EC oscillator with OSC2 configured as RA6 and HW enabled 4x PLL
  - 1011 = Reserved; do not use
  - 1010 = Reserved; do not use
  - 1001 = Reserved; do not use
  - 1000 = Reserved; do not use
  - 0111 = RC oscillator with OSC2 configured as RA6
  - 0110 = HS oscillator with HW enabled 4x PLL
  - 0101 = EC oscillator with OSC2 configured as RA6
  - 0100 = EC oscillator with OSC2 configured as divide by 4 clock output
  - 0011 = RC oscillator with OSC2 configured as divide by 4 clock output
  - 0010 = HS oscillator
  - 0001 = XT oscillator
  - 0000 = LP oscillator

#### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

-n = Value when device is unprogrammed u = Unchanged from programmed state

### REGISTER 24-2: CONFIG2L: CONFIGURATION REGISTER 2 LOW (BYTE ADDRESS 300002h)

| U-0   | U-0 | U-0 | U-0 | R/P-1 | R/P-1 | R/P-1 | R/P-1  |
|-------|-----|-----|-----|-------|-------|-------|--------|
| _     | _   | _   | _   | BORV1 | BORV0 | BOR   | PWRTEN |
| bit 7 |     |     |     |       |       |       | bit 0  |

bit 7-4 Unimplemented: Read as '0'

bit 3-2 BORV1:BORV0: Brown-out Reset Voltage bits

11 = VBOR set to 2.0V

10 = VBOR set to 2.7V

01 = VBOR set to 4.2V

00 = VBOR set to 4.5V

bit 1 BOR: Brown-out Reset Enable bit

1 = Brown-out Reset enabled

0 = Brown-out Reset disabled

bit 0 **PWRTEN:** Power-up Timer Enable bit

1 = PWRT disabled

0 = PWRT enabled

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-3: CONFIG2H: CONFIGURATION REGISTER 2 HIGH (BYTE ADDRESS 300003h)

| U-0   | U-0 | U-0 | R/P-1  | R/P-1  | R/P-1  | R/P-1  | R/P-1 |
|-------|-----|-----|--------|--------|--------|--------|-------|
| _     | _   | _   | WDTPS3 | WDTPS2 | WDTPS1 | WDTPS0 | WDTEN |
| bit 7 |     |     |        |        |        |        | bit 0 |

bit 7-5 Unimplemented: Read as '0'

bit 4-1 WDTPS2:WDTPS0: Watchdog Timer Postscaler Select bits

1111 = 1:32768

1110 = 1:16384

1101 = 1:8192

1100 = 1:4096

1011 = 1:2048

1010 = 1:1024

1001 = 1:512

1000 = 1:256

0111 = 1:128

0110 = 1:64

0101 = 1:32

0100 = 1:16

0011 = 1:80010 = 1:4

0001 = 1:2

0000 = 1:1

bit 0 WDTEN: Watchdog Timer Enable bit

1 = WDT enabled

0 = WDT disabled (control is placed on the SWDTEN bit)

### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read \ as '0'$   $-n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

## REGISTER 24-4: CONFIG3L: CONFIGURATION REGISTER 3 LOW (BYTE ADDRESS 300004h)<sup>(1)</sup>

| R/P-1 | U-0 | U-0 | U-0 | U-0 | U-0 | R/P-1 | R/P-1 |
|-------|-----|-----|-----|-----|-----|-------|-------|
| WAIT  | _   | _   | _   | _   | _   | PM1   | PM0   |
| bit 7 |     |     |     |     |     |       | bit 0 |

#### bit 7 WAIT: External Bus Data Wait Enable bit

- 1 = Wait selections unavailable for table reads and table writes
- 0 = Wait selections for table reads and table writes are determined by WAIT1:WAIT0 bits (MEMCOM<5:4>)

### bit 6-2 Unimplemented: Read as '0'

### bit 1-0 PM1:PM0: Processor Mode Select bits

- 11 = Microcontroller mode
- 10 = Microprocessor mode
- 01 = Microprocessor with Boot Block mode
- 00 = Extended Microcontroller mode

Note 1: This register is unimplemented for PIC18F6525/6621 devices; maintain these bits set.

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-5: CONFIG3H: CONFIGURATION REGISTER 3 HIGH (BYTE ADDRESS 300005h)

| R/P-1                | U-0 | U-0 | U-0 | U-0 | U-0 | R/P-1                 | R/P-1  |
|----------------------|-----|-----|-----|-----|-----|-----------------------|--------|
| MCLRE <sup>(1)</sup> | _   | _   | _   | _   | _   | ECCPMX <sup>(2)</sup> | CCP2MX |
| bit 7                |     |     |     |     |     |                       | bit 0  |

## bit 7 MCLRE: MCLR Enable bit(1)

- $1 = \overline{MCLR}$  pin enabled, RG5 input pin disabled
- 0 = RG5 input enabled,  $\overline{MCLR}$  disabled

### bit 6-2 Unimplemented: Read as '0'

### bit 1 **ECCPMX:** ECCP Mux bit<sup>(2)</sup>

- 1 = ECCP1 (P1B/P1C) and ECCP3 (P3B/P3C) PWM outputs are multiplexed with RE6 through RE3
- 0 = ECCP1 (P1B/P1C) and ECCP3 (P3B/P3C) PWM outputs are multiplexed with RH7 through RH4

#### bit 0 CCP2MX: ECCP2 Mux bit

#### In Microcontroller mode:

- 1 = ECCP2 input/output is multiplexed with RC1
- 0 = ECCP2 input/output is multiplexed with RE7

# In Microprocessor, Microprocessor with Boot Block and Extended Microcontroller modes (PIC18F8525/8621 devices only):

- 1 = ECCP2 input/output is multiplexed with RC1
- 0 = ECCP2 input/output is multiplexed with RB3
  - **Note 1:** If MCLR is disabled, either disable Low-Voltage ICSP or hold RB5/KBI1/PGM low to ensure proper entry into ICSP mode.
    - 2: This register is unimplemented for PIC18F6525/6621 devices; maintain these bits set.

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

### REGISTER 24-6: CONFIG4L: CONFIGURATION REGISTER 4 LOW (BYTE ADDRESS 300006h)

| R/P-1 | U-0 | U-0 | U-0 | U-0 | R/P-1 | U-0 | R/P-1  |
|-------|-----|-----|-----|-----|-------|-----|--------|
| DEBUG | _   | _   | _   | _   | LVP   | _   | STVREN |
| bit 7 |     |     |     |     |       |     | bit 0  |

bit 7 DEBUG: Background Debugger Enable bit

1 = Background debugger disabled. RB6 and RB7 configured as general purpose I/O pins.

0 = Background debugger enabled. RB6 and RB7 are dedicated to in-circuit debug.

bit 6-3 Unimplemented: Read as '0'

bit 2 LVP: Low-Voltage ICSP Enable bit

1 = Low-Voltage ICSP enabled

0 = Low-Voltage ICSP disabled

bit 1 Unimplemented: Read as '0'

bit 0 STVREN: Stack Full/Underflow Reset Enable bit

1 = Stack full/underflow will cause Reset

0 = Stack full/underflow will not cause Reset

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

### REGISTER 24-7: CONFIG5L: CONFIGURATION REGISTER 5 LOW (BYTE ADDRESS 300008h)

| U-0   | U-0 | U-0 | U-0 | R/C-1              | R/C-1 | R/C-1 | R/C-1 |
|-------|-----|-----|-----|--------------------|-------|-------|-------|
| _     | _   | _   | _   | CP3 <sup>(1)</sup> | CP2   | CP1   | CP0   |
| bit 7 |     |     |     |                    |       |       | bit 0 |

bit 7-4 Unimplemented: Read as '0'

bit 3 CP3: Code Protection bit<sup>(1)</sup>

1 = Block 3 (00C000-00FFFFh) not code-protected

0 = Block 3 (00C000-00FFFFh) code-protected

Note 1: Unimplemented in PIC18FX525 devices; maintain this bit set.

bit 2 CP2: Code Protection bit

1 = Block 2 (008000-00BFFFh) not code-protected

0 = Block 2 (008000-00BFFFh) code-protected

bit 1 CP1: Code Protection bit

1 = Block 1 (004000-007FFFh) not code-protected

0 = Block 1 (004000-007FFFh) code-protected

bit 0 CP0: Code Protection bit

1 = Block 0 (000800-003FFFh) not code-protected

0 = Block 0 (000800-003FFFh) code-protected

### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$  $-n = Value \ when \ device is \ unprogrammed$  $<math>u = Unchanged \ from \ programmed \ state$ 

#### **REGISTER 24-8:** CONFIG5H: CONFIGURATION REGISTER 5 HIGH (BYTE ADDRESS 300009h)

| R/C-1 | R/C-1 | U-0 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| CPD   | CPB   | _   | _   | _   | _   | _   |       |
| bit 7 |       |     |     |     |     |     | bit 0 |

bit 0

bit 7 CPD: Data EEPROM Code Protection bit

1 = Data EEPROM not code-protected

0 = Data EEPROM code-protected

CPB: Boot Block Code Protection bit bit 6

1 = Boot block (000000-0007FFh) not code-protected

0 = Boot block (000000-0007FFh) code-protected

bit 5-0 Unimplemented: Read as '0'

### Legend:

C = Clearable bit R = Readable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

#### REGISTER 24-9: CONFIG6L: CONFIGURATION REGISTER 6 LOW (BYTE ADDRESS 30000Ah)

| U-0   | U-0 | U-0 | U-0 | R/C-1               | R/C-1 | R/C-1 | R/C-1 |
|-------|-----|-----|-----|---------------------|-------|-------|-------|
| _     | _   | _   | _   | WRT3 <sup>(1)</sup> | WRT2  | WRT1  | WRT0  |
| bit 7 |     |     |     |                     |       |       | bit 0 |

Unimplemented: Read as '0' bit 7-4

bit 3 WRT3: Write Protection bit<sup>(1)</sup>

1 = Block 3 (00C000-00FFFFh) not write-protected

0 = Block 3 (00C000-00FFFFh) write-protected

Note 1: Unimplemented in PIC18FX525 devices; maintain this bit set.

bit 2 WRT2: Write Protection bit

1 = Block 2 (008000-00BFFFh) not write-protected

0 = Block 2 (008000-00BFFFh) write-protected

bit 1 WRT1: Write Protection bit

1 = Block 1 (004000-007FFFh) not write-protected

0 = Block 1 (004000-007FFFh) write-protected

bit 0 WR0: Write Protection bit

1 = Block 0 (000800-003FFFh) not write-protected

0 = Block 0 (000800-003FFFh) write-protected

#### Leaend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

### REGISTER 24-10: CONFIG6H: CONFIGURATION REGISTER 6 HIGH (BYTE ADDRESS 30000Bh)

| R/C-1 | R/C-1 | R/C-1 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|-------|-----|-----|-----|-----|-------|
| WRTD  | WRTB  | WRTC  | _   | _   | _   | _   |       |
| bit 7 |       |       |     |     |     |     | bit 0 |

bit 7 WRTD: Data EEPROM Write Protection bit

1 = Data EEPROM not write-protected

0 = Data EEPROM write-protected

bit 6 WRTB: Boot Block Write Protection bit

1 = Boot block (000000-0007FFh) not write-protected

0 = Boot block (000000-0007FFh) write-protected

bit 5 WRTC: Configuration Register Write Protection bit

1 = Configuration registers (300000-3000FFh) not write-protected

0 = Configuration registers (300000-3000FFh) write-protected

bit 4-0 Unimplemented: Read as '0'

### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-11: CONFIG7L: CONFIGURATION REGISTER 7 LOW (BYTE ADDRESS 30000Ch)

| h:4 7 |     |     |     | 251110               | LDTINL |       | LD1110 |
|-------|-----|-----|-----|----------------------|--------|-------|--------|
| _     | _   | _   | _   | EBTR3 <sup>(1)</sup> | EBTR2  | EBTR1 | EBTR0  |
| U-0   | U-0 | U-0 | U-0 | R/C-1                | R/C-1  | R/C-1 | R/C-1  |

bit 7 bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 **EBTR3:** Table Read Protection bit<sup>(1)</sup>

1 = Block 3 (00C000-00FFFFh) not protected from table reads executed in other blocks

0 = Block 3 (00C000-00FFFFh) protected from table reads executed in other blocks

Note 1: Unimplemented in PIC18FX525 devices; maintain this bit set.

bit 2 EBTR2: Table Read Protection bit

1 = Block 2 (008000-00BFFFh) not protected from table reads executed in other blocks

0 = Block 2 (008000-00BFFFh) protected from table reads executed in other blocks

bit 1 EBTR1: Table Read Protection bit

1 = Block 1 (004000-007FFFh) not protected from table reads executed in other blocks

0 = Block 1 (004000-007FFFh) protected from table reads executed in other blocks

bit 0 **EBTR0**: Table Read Protection bit

1 = Block 0 (000800-003FFFh) not protected from table reads executed in other blocks

0 = Block 0 (000800-003FFFh) protected from table reads executed in other blocks

### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$  $-n = Value \ when \ device is unprogrammed <math>u = Unchanged \ from \ programmed \ state$ 

### REGISTER 24-12: CONFIG7H: CONFIGURATION REGISTER 7 HIGH (BYTE ADDRESS 30000Dh)

| U-0   | R/C-1 | U-0 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| _     | EBTRB | _   | _   | _   | _   | _   | _     |
| bit 7 |       |     |     |     |     |     | hit 0 |

bit 7 Unimplemented: Read as '0'

bit 6 EBTRB: Boot Block Table Read Protection bit

1 = Boot block (000000-0007FFh) not protected from table reads executed in other blocks

0 = Boot block (000000-0007FFh) protected from table reads executed in other blocks

bit 5-0 Unimplemented: Read as '0'

### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$   $u = Unchanged \ from \ programmed \ state$ 

# REGISTER 24-13: DEVID1: DEVICE ID REGISTER 1 FOR PIC18F6525/6621/8525/8621 DEVICES (ADDRESS 3FFFFEh)

| R     | R    | R    | R    | R    | R    | R    | R     |
|-------|------|------|------|------|------|------|-------|
| DEV2  | DEV1 | DEV0 | REV4 | REV3 | REV2 | REV1 | REV0  |
| bit 7 |      |      |      |      |      |      | bit 0 |

#### bit 7-5 **DEV2:DEV0:** Device ID bits

100 = PIC18F8621

101 = PIC18F6621

110 = PIC18F8525

111 = PIC18F6525

#### bit 4-0 REV4:REV0: Revision ID bits

These bits are used to indicate the device revision.

### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$  $-n = Value \ when device is unprogrammed <math>u = Unchanged \ from \ programmed \ state$ 

# REGISTER 24-14: DEVID2: DEVICE ID REGISTER 2 FOR PIC18F6525/6621/8525/8621 DEVICES (ADDRESS 3FFFFFh)

| R-0   | R-0  | R-0  | R-0  | R-1  | R-0  | R-1  | R-0   |
|-------|------|------|------|------|------|------|-------|
| DEV10 | DEV9 | DEV8 | DEV7 | DEV6 | DEV5 | DEV4 | DEV3  |
| bit 7 |      |      |      |      |      |      | bit 0 |

### bit 7-0 **DEV10:DEV3:** Device ID bits

These bits are used with the DEV2:DEV0 bits in the Device ID Register 1 to identify the part number.

0000 1010 = PIC18F6525/6621/8525/8621

### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$   $-n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

## 24.2 Watchdog Timer (WDT)

The Watchdog Timer is a free running on-chip RC oscillator which does not require any external components. This RC oscillator is separate from the RC oscillator of the OSC1/CLKI pin. That means that the WDT will run even if the clock on the OSC1/CLKI and OSC2/CLKO/RA6 pins of the device has been stopped, for example, by execution of a SLEEP instruction.

During normal operation, a WDT time-out generates a device Reset (Watchdog Timer Reset). If the device is in Sleep mode, a WDT time-out causes the device to wake-up and continue with normal operation (Watchdog Timer wake-up). The TO bit in the RCON register will be cleared upon a WDT time-out.

The Watchdog Timer is enabled or disabled by a device configuration bit, WDTEN (CONFIG2H<0>). If WDTEN is set, software execution may not disable this function. When WDTEN is cleared, the SWDTEN bit enables or disables the operation of the WDT.

The WDT time-out period values may be found in the Electrical Specifications section under parameter 31. Values for the WDT postscaler may be assigned using the configuration bits.

- Note 1: The CLRWDT and SLEEP instructions clear the WDT and the postscaler if assigned to the WDT and prevent it from timing out and generating a device Reset condition.
  - 2: When a CLRWDT instruction is executed and the postscaler is assigned to the WDT, the postscaler count will be cleared but the postscaler assignment is not changed.

#### 24.2.1 CONTROL REGISTER

Register 24-15 shows the WDTCON register. This is a readable and writable register which contains a control bit that allows software to override the WDT enable configuration bit only when the configuration bit has disabled the WDT.

#### REGISTER 24-15: WDTCON: WATCHDOG TIMER CONTROL REGISTER

| U-0   | U-0 | U-0 | U-0 | U-0 | U-0 | U-0 | R/W-0  |
|-------|-----|-----|-----|-----|-----|-----|--------|
| _     | _   | _   | _   | _   | _   | _   | SWDTEN |
| bit 7 |     |     |     |     |     |     | bit 0  |

bit 7-1 Unimplemented: Read as '0'

bit 0 **SWDTEN:** Software Controlled Watchdog Timer Enable bit

1 = Watchdog Timer is on

0 = Watchdog Timer is turned off (if CONFIG2H < 0 > = 0)

| Legend:           |                  |   |
|-------------------|------------------|---|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0'        |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared $x = Bit$ is unknown |

### 24.2.2 WDT POSTSCALER

The WDT has a postscaler that can extend the WDT Reset period. The postscaler is selected at the time of the device programming by the value written to the CONFIG2H Configuration register.

FIGURE 24-1: WATCHDOG TIMER BLOCK DIAGRAM




TABLE 24-2: SUMMARY OF REGISTERS ASSOCIATED WITH THE WATCHDOG TIMER

| Name     | Bit 7 | Bit 6 | Bit 5 | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  |
|----------|-------|-------|-------|--------|--------|--------|--------|--------|
| CONFIG2H | _     | _     | _     | WDTPS3 | WDTPS2 | WDTPS2 | WDTPS0 | WDTEN  |
| RCON     | IPEN  | _     | _     | RI     | TO     | PD     | POR    | BOR    |
| WDTCON   | _     |       |       | _      | _      | _      | _      | SWDTEN |

Legend: Shaded cells are not used by the Watchdog Timer.

## 24.3 Power-Down Mode (Sleep)

Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared but keeps running, the  $\overline{PD}$  bit (RCON<3>) is cleared, the  $\overline{TO}$  (RCON<4>) bit is set and the oscillator driver is turned off. The I/O ports maintain the status they had before the SLEEP instruction was executed (driving high, low or high-impedance).

For lowest current consumption in this mode, place all I/O pins at either VDD or Vss, ensure no external circuitry is drawing current from the I/O pin, power-down the A/D and disable external clocks. Pull all I/O pins that are high-impedance inputs, high or low externally, to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on-chip pull-ups on PORTB should be considered.

The MCLR pin must be at a logic high level (VIHMC).

### 24.3.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on  $\overline{MCLR}$  pin.
- Watchdog Timer wake-up (if WDT was enabled).
- Interrupt from INTx pin, RB port change or a peripheral interrupt.

The following peripheral interrupts can wake the device from Sleep:

- PSP read or write.
- 2. TMR1 interrupt. Timer1 must be operating as an asynchronous counter.
- TMR3 interrupt. Timer3 must be operating as an asynchronous counter.
- 4. CCP Capture mode interrupt (Capture will not occur).
- MSSP (Start/Stop) bit detect interrupt.
- MSSP transmit or receive in Slave mode (SPI/I<sup>2</sup>C).
- 7. USART RXx or TXx (Synchronous Slave mode).
- 8. A/D conversion (when A/D clock source is RC).
- 9. EEPROM write operation complete.
- 10. LVD interrupt.

Other peripherals cannot generate interrupts since during Sleep, no on-chip clocks are present.

External MCLR Reset will cause a device Reset. All other events are considered a continuation of program execution and will cause a "wake-up". The TO and PD bits in the RCON register can be used to determine the cause of the device Reset. The PD bit, which is set on power-up, is cleared when Sleep is invoked. The TO bit is cleared if a WDT time-out occurred (and caused wake-up).

When the SLEEP instruction is being executed, the next instruction (PC + 2) is prefetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address. In cases where the execution of the instruction following Sleep is not desirable, the user should have a NOP after the SLEEP instruction.

### 24.3.2 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If an interrupt condition (interrupt flag bit and interrupt enable bits are set) occurs **before** the execution of a SLEEP instruction, the SLEEP instruction will complete as a NOP. Therefore, the WDT and WDT postscaler will not be cleared, the TO bit will not be set and PD bits will not be cleared.
- If the interrupt condition occurs during or after
  the execution of a SLEEP instruction, the device
  will immediately wake-up from Sleep. The SLEEP
  instruction will be completely executed before the
  wake-up. Therefore, the WDT and WDT
  postscaler will be cleared, the TO bit will be set
  and the PD bit will be cleared.

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.

To ensure that the WDT is cleared, a CLRWDT instruction should be executed before a SLEEP instruction.

FIGURE 24-2: WAKE-UP FROM SLEEP THROUGH INTERRUPT<sup>(1,2)</sup>



# 24.4 Program Verification and Code Protection

The overall structure of the code protection on the PIC18 Flash devices differs significantly from other PICmicro devices.

The user program memory is divided on binary boundaries into four blocks of 16 Kbytes each. The first block is further divided into a boot block of 2048 bytes and a second block (Block 0) of 14 Kbytes.

Each of the blocks has three code protection bits associated with them. They are:

- Code-Protect bit (CPn)
- Write-Protect bit (WRTn)
- External Block Table Read bit (EBTRn)

Figure 24-3 shows the program memory organization for 48 and 64-Kbyte devices and the specific code protection bit associated with each block. The actual locations of the bits are summarized in Table 24-3.

FIGURE 24-3: CODE-PROTECTED PROGRAM MEMORY FOR PIC18F6525/6621/8525/8621 DEVICES

| MEMORY SIZI               | E/DEVICE                  |                    | Block Code Protection |  |
|---------------------------|---------------------------|--------------------|-----------------------|--|
| 48 Kbytes<br>(PIC18FX525) | 64 Kbytes<br>(PIC18FX621) | Address<br>Range   | Controlled By:        |  |
| Boot Block                | Boot Block                | 000000h<br>0007FFh | CPB, WRTB, EBTRB      |  |
| Block 0                   | Block 0                   | 000800h<br>003FFFh | CP0, WRT0, EBTR0      |  |
| Block 1                   | Block 1                   | 004000h<br>007FFFh | CP1, WRT1, EBTR1      |  |
| Block 2                   | Block 2                   | 008000h<br>00BFFFh | CP2, WRT2, EBTR2      |  |
| Unimplemented, read '0'   | Block 3                   | 00C000h<br>00FFFFh | CP3, WRT3, EBTR3      |  |

TABLE 24-3: SUMMARY OF REGISTERS ASSOCIATED WITH CODE PROTECTION

| File    | Name     | Bit 7 | Bit 6 | Bit 5 | Bit 4 | Bit 3                | Bit 2 | Bit 1 | Bit 0 |
|---------|----------|-------|-------|-------|-------|----------------------|-------|-------|-------|
| 300008h | CONFIG5L | _     | _     | _     | _     | CP3 <sup>(1)</sup>   | CP2   | CP1   | CP0   |
| 300009h | CONFIG5H | CPD   | СРВ   | _     | _     | _                    | _     | _     | _     |
| 30000Ah | CONFIG6L | _     | _     | _     | _     | WRT3 <sup>(1)</sup>  | WRT2  | WRT1  | WRT0  |
| 30000Bh | CONFIG6H | WRTD  | WRTB  | WRTC  | _     | _                    | _     | _     | _     |
| 30000Ch | CONFIG7L | _     | _     | _     | _     | EBTR3 <sup>(1)</sup> | EBTR2 | EBTR1 | EBTR0 |
| 30000Dh | CONFIG7H | _     | EBTRB | _     | _     | _                    | _     | _     |       |

Legend: Shaded cells are unimplemented.

Note 1: Unimplemented in PIC18FX525 devices.

# 24.4.1 PROGRAM MEMORY CODE PROTECTION

The user memory may be read to or written from any location using the table read and table write instructions. The Device ID register may be read with table reads. The Configuration registers may be read and written with the table read and table write instructions.

In user mode, the CPn bits have no direct effect. CPn bits inhibit external reads and writes. A block of user memory may be protected from table writes if the WRTn configuration bit is '0'. The EBTRn bits control table reads. For a block of user memory with the EBTRn bit set to '0', a table read instruction that executes from within that block is allowed to read. A

table read instruction that executes from a location outside of that block is not allowed to read and will result in reading '0's. Figures 24-4 through 24-6 illustrate table write and table read protection.

Code protection bits may only be written to a '0' from a '1' state. It is not possible to write a '1' to a bit in the '0' state. Code protection bits are only set to '1' by a full chip erase or block erase function. The full chip erase and block erase functions can only be initiated via ICSP or an external programmer.

FIGURE 24-4: TABLE WRITE (WRTn) DISALLOWED





FIGURE 24-5: EXTERNAL BLOCK TABLE READ (EBTRn) DISALLOWED






FIGURE 24-6: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED

# 24.4.2 DATA EEPROM CODE PROTECTION

The entire data EEPROM is protected from external reads and writes by two bits: CPD and WRTD. CPD inhibits external reads and writes of data EEPROM. WRTD inhibits external writes to data EEPROM. The CPU can continue to read data EEPROM regardless of the protection bit settings.

# 24.4.3 CONFIGURATION REGISTER PROTECTION

The Configuration registers can be write-protected. The WRTC bit controls protection of the Configuration registers. In user mode, the WRTC bit is readable only. WRTC can only be written via ICSP or an external programmer.

#### 24.5 ID Locations

Eight memory locations (200000h-200007h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are accessible during normal execution through the TBLRD and TBLWT instructions, or during program/verify. The ID locations can be read when the device is code-protected.

# 24.6 In-Circuit Serial Programming™ (ICSP™)

PIC18F6525/6621/8525/8621 microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

## 24.7 In-Circuit Debugger

When the DEBUG bit in Configuration register, CONFIG4L, is programmed to a '0', the in-circuit debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB® IDE. When the microcontroller has this feature enabled, some of the resources are not available for general use. Table 24-4 shows which features are consumed by the background debugger.

TABLE 24-4: DEBUGGER RESOURCES

| I/O pins       | RB6, RB7  |
|----------------|-----------|
| Stack          | 2 levels  |
| Program Memory | 512 bytes |
| Data Memory    | 10 bytes  |

To use the in-circuit debugger function of the microcontroller, the design must implement In-Circuit Serial Programming connections to  $\overline{\text{MCLR}}/\text{VPP}$ , VDD, GND, RB7 and RB6. This will interface to the in-circuit debugger module available from Microchip or one of the third party development tool companies.

## 24.8 Low-Voltage ICSP Programming

The LVP bit in Configuration register, CONFIG4L, enables Low-Voltage ICSP programming. This mode allows the microcontroller to be programmed via ICSP using a VDD source in the operating voltage range. This only means that VPP does not have to be brought to VIHH, but can instead be left at the normal operating voltage. In this mode, the RB5/KBI1/PGM pin is dedicated to the programming function and ceases to be a general purpose I/O pin. During programming, VDD is applied to the MCLR/VPP pin. To enter Programming mode, VDD must be applied to the RB5/KBI1/PGM pin provided the LVP bit is set. The LVP bit defaults to a '1' from the factory.

- Note 1: The High-Voltage Programming mode is always available, regardless of the state of the LVP bit, by applying VIHH to the MCLR pin.
  - 2: While in Low-Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin and should be held low during normal operation.
  - 3: When using Low-Voltage ICSP Programming (LVP) and the pull-ups on PORTB are enabled, bit 5 in the TRISB register must be cleared to disable the pull-up on RB5 and ensure the proper operation of the device.
  - **4:** If the device Master Clear is disabled, verify that either of the following is done to ensure proper entry into ICSP mode:
    - a.) disable Low-Voltage Programming (CONFIG4L<2> = 0); or
    - b.) make certain that RB5/KBI1/PGM is held low during entry into ICSP.

If Low-Voltage Programming mode is not used, the LVP bit can be programmed to a '0' and RB5/KBI1/PGM becomes a digital I/O pin. However, the LVP bit may only be programmed when programming is entered with VIHH on  $\overline{\text{MCLR}}/\text{VPP}$ .

It should be noted that once the LVP bit is programmed to '0', only the High-Voltage Programming mode is available and only High-Voltage Programming mode can be used to program the device.

When using Low-Voltage ICSP, the part must be supplied 4.5V to 5.5V if a bulk erase will be executed. This includes reprogramming of the code-protect bits from an on-state to off-state. For all other cases of Low-Voltage ICSP, the part may be programmed at the normal operating voltage. This means unique user IDs or user code can be reprogrammed or added.

### 25.0 INSTRUCTION SET SUMMARY

The PIC18 instruction set adds many enhancements to the previous PICmicro® instruction sets, while maintaining an easy migration from these PICmicro instruction sets.

Most instructions are a single program memory word (16 bits), but there are three instructions that require two program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- · Byte-oriented operations
- · Bit-oriented operations
- · Literal operations
- · Control operations

The PIC18 instruction set summary in Table 25-2 lists **byte-oriented**, **bit-oriented**, **literal** and **control** operations. Table 25-1 shows the opcode field descriptions.

Most byte-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction.

The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All bit-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The **literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the call or return instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for three double-word instructions. These three instructions were made double-word instructions so that all the required information is available in these 32 bits. In the second word, the 4 MSbs are '1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle unless a conditional test is true, or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 25-1 shows the general formats that the instructions can have.

All examples use the format 'nnh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

The Instruction Set Summary, shown in Table 25-2, lists the instructions recognized by the Microchip MPASM™ Assembler.

**Section 25.1 "Instruction Set"** provides a description of each instruction.

## TABLE 25-1: OPCODE FIELD DESCRIPTIONS

| Field           | Description  |
|-----------------|--|
| a               | RAM access bit  a = 0: RAM location in Access RAM (BSR register is ignored)  a = 1: RAM bank is specified by BSR register                                    |
| bbb             | Bit address within an 8-bit file register (0 to 7).  |
| BSR             | Bank Select Register. Used to select the current RAM bank.   |
| d               | Destination select bit   |
|                 | d = 0: store result in WREG<br>d = 1: store result in file register f  |
| dest            | Destination either the WREG register or the specified register file location.  |
| f               | 8-bit register file address (0x00 to 0xFF).  |
| fs              | 12-bit register file address (0x000 to 0xFFF). This is the source address.   |
| fd              | 12-bit register file address (0x000 to 0xFFF). This is the destination address.  |
| k               | Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value).  |
| label           | Label name.  |
| mm              | The mode of the TBLPTR register for the table read and table write instructions.  Only used with table read and table write instructions:                    |
| *               | No change to register (such as TBLPTR with table reads and writes)   |
| *+              | Post-Increment register (such as TBLPTR with table reads and writes)   |
| *-              | Post-Decrement register (such as TBLPTR with table reads and writes)   |
| +*              | Pre-Increment register (such as TBLPTR with table reads and writes)  |
| n               | The relative address (2's complement number) for relative branch instructions, or the direct address for call/branch and return instructions.                |
| PRODH           | Product of Multiply High Byte.   |
| PRODL           | Product of Multiply Low Byte.  |
| S               | Fast Call/Return mode select bit  s = 0: do not update into/from shadow registers  s = 1: certain registers loaded into/from shadow registers (Fast mode)    |
| u               | Unused or unchanged.   |
| WREG            | Working register (accumulator).  |
| х               | Don't care ('0' or '1')  The assembler will generate code with x = 0. It is the recommended form of use for compatibility with all Microchip software tools. |
| TBLPTR          | 21-bit Table Pointer (points to a Program Memory location).  |
| TABLAT          | 8-bit Table Latch.   |
| TOS             | Top-of-Stack.  |
| PC              | Program Counter.   |
| PCL             | Program Counter Low Byte.  |
| PCH             | Program Counter High Byte.   |
| PCLATH          | Program Counter High Byte Latch.   |
| PCLATU          | Program Counter Upper Byte Latch.  |
| GIE             | Global Interrupt Enable bit.   |
| WDT             | Watchdog Timer.  |
| TO              | Time-out bit.  |
| PD              | Power-down bit.  |
| C, DC, Z, OV, N | ALU Status bits: Carry, Digit Carry, Zero, Overflow, Negative.   |
| [ ]             | Optional.  |
| ( )             | Contents.  |
| $\rightarrow$   | Assigned to.   |
| < >             | Register bit field.  |
| €               | In the set of.   |
| italics         | User defined term (font is courier).   |

### FIGURE 25-1: GENERAL FORMAT FOR INSTRUCTIONS

#### Byte-oriented file register operations **Example Instruction** 10 OPCODE f (FILE #) ADDWF MYREG, W, B d а d = 0 for result destination to be WREG register d = 1 for result destination to be file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Byte to Byte move operations (2-word) 12 11 OPCODE f (Source FILE #) MOVFF MYREG1, MYREG2 15 12 11 0 f (Destination FILE #) 1111 f = 12-bit file register address Bit-oriented file register operations OPCODE b (BIT #) a f (FILE #) BSF MYREG, bit, B b = 3-bit position of bit in file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Literal operations 15 0 **OPCODE** k (literal) MOVLW 0x7F k = 8-bit immediate value **Control** operations CALL, GOTO and Branch operations 15 0 OPCODE n<7:0> (literal) GOTO Label 15 12 11 0 1111 n<19:8> (literal) n = 20-bit immediate value 15 CALL MYFUNC **OPCODE** n<7:0> (literal) 15 12 11 0 n<19:8> (literal) S = Fast bit 11 10 OPCODE BRA MYFUNC n<10:0> (literal) 15 8 7 OPCODE n<7:0> (literal) BC MYFUNC

TABLE 25-2: PIC18FXXXX INSTRUCTION SET

| Mnemo     | nic,       | Description                              | Cycles     | 16-Bit Instruction Word |      |      | Status  | Notes           |            |
|-----------|------------|--|------------|-------------------------|------|------|---------|-----------------|------------|
| Operai    | nds        | Description                              | Cycles     | MSb                     |      |      | LSb     | Affected        | Notes      |
| BYTE-ORIE | ENTED F    | FILE REGISTER OPERATIONS                 |            |                         |      |      |         |                 |            |
| ADDWF     | f, d, a    | Add WREG and f                           | 1          | 0010                    | 01da | ffff | ffff    | C, DC, Z, OV, N | 1, 2       |
| ADDWFC    | f, d, a    | Add WREG and Carry bit to f              | 1          | 0010                    | 00da | ffff | ffff    | C, DC, Z, OV, N | 1, 2       |
| ANDWF     | f, d, a    | AND WREG with f                          | 1          | 0001                    | 01da | ffff | ffff    | Z, N            | 1,2        |
| CLRF      | f, a       | Clear f                                  | 1          | 0110                    | 101a | ffff | ffff    | Z               | 2          |
| COMF      | f, d, a    | Complement f                             | 1          | 0001                    | 11da | ffff | ffff    | Z, N            | 1, 2       |
| CPFSEQ    | f, a       | Compare f with WREG, skip =              | 1 (2 or 3) | 0110                    | 001a | ffff | ffff    | None            | 4          |
| CPFSGT    | f, a       | Compare f with WREG, skip >              | 1 (2 or 3) | 0110                    | 010a | ffff | ffff    | None            | 4          |
| CPFSLT    | f, a       | Compare f with WREG, skip <              | 1 (2 or 3) | 0110                    | 000a | ffff | ffff    | None            | 1, 2       |
| DECF      | f, d, a    | Decrement f                              | 1          | 0000                    | 01da | ffff | ffff    | C, DC, Z, OV, N | 1, 2, 3, 4 |
| DECFSZ    | f, d, a    | Decrement f, Skip if 0                   | 1 (2 or 3) | 0010                    | 11da | ffff | ffff    | None            | 1, 2, 3, 4 |
| DCFSNZ    | f, d, a    | Decrement f, Skip if Not 0               | 1 (2 or 3) | 0100                    | 11da | ffff | ffff    | None            | 1, 2       |
| INCF      | f, d, a    | Increment f                              | 1          | 0010                    | 10da | ffff | ffff    | C, DC, Z, OV, N | 1, 2, 3, 4 |
| INCFSZ    | f, d, a    | Increment f, Skip if 0                   | 1 (2 or 3) | 0011                    | 11da | ffff | ffff    | None            | 4          |
| INFSNZ    | f, d, a    | Increment f, Skip if Not 0               | 1 (2 or 3) | 0100                    | 10da | ffff | ffff    | None            | 1, 2       |
| IORWF     | f, d, a    | Inclusive OR WREG with f                 | 1 '        | 0001                    | 00da | ffff | ffff    | Z, N            | 1, 2       |
| MOVF      | f, d, a    | Move f                                   | 1          | 0101                    | 00da | ffff | ffff    | Z, N            | 1          |
| MOVFF     | $f_s, f_d$ | Move f <sub>s</sub> (source) to 1st word | 2          | 1100                    | ffff | ffff | ffff    | None            |            |
|           | ٠ ٠        | f <sub>d</sub> (destination) 2nd word    |            | 1111                    | ffff | ffff | ffff    |                 |            |
| MOVWF     | f, a       | Move WREG to f                           | 1          | 0110                    | 111a | ffff | ffff    | None            |            |
| MULWF     | f, a       | Multiply WREG with f                     | 1          | 0000                    | 001a | ffff | ffff    | None            |            |
| NEGF      | f, a       | Negate f                                 | 1          | 0110                    | 110a | ffff | ffff    | C, DC, Z, OV, N | 1, 2       |
| RLCF      | f, d, a    | Rotate Left f through Carry              | 1          | 0011                    | 01da | ffff | ffff    | C, Z, N         |            |
| RLNCF     | f, d, a    | Rotate Left f (No Carry)                 | 1          | 0100                    | 01da | ffff | ffff    | Z, N            | 1, 2       |
| RRCF      | f, d, a    | Rotate Right f through Carry             | 1          | 0011                    | 00da | ffff | ffff    | C, Z, N         |            |
| RRNCF     | f, d, a    | Rotate Right f (No Carry)                | 1          | 0100                    | 00da | ffff | ffff    | Z, N            |            |
| SETF      | f, a       | Set f                                    | 1          | 0110                    | 100a | ffff | ffff    | None            |            |
| SUBFWB    | f, d, a    | Subtract f from WREG with                | 1          | 0101                    | 01da | ffff | ffff    | C, DC, Z, OV, N | 1, 2       |
| SUBWF     | fdo        | borrow Subtract WREG from f              | 1          | 0101                    | 112- |      | <b></b> | C DC 7 OV N     |            |
|           | f, d, a    |  | 1          |                         | 11da | ffff |         | C, DC, Z, OV, N | 1 0        |
| SUBWFB    | f, d, a    | Subtract WREG from f with                | 1          | 0101                    | 10da | ffff | ffff    | C, DC, Z, OV, N | 1, ∠       |
| CWADE     | f d a      | borrow                                   | 4          | 0011                    | 107- |      |         | None            | 4          |
| SWAPF     | f, d, a    | Swap nibbles in f                        | 1 (2 or 2) |                         | 10da | ffff | ffff    | None            | 4          |
| TSTFSZ    | f, a       | Test f, skip if 0                        | 1 (2 or 3) | 0110                    | 011a | ffff | ffff    | None            | 1, 2       |
| XORWF     | f, d, a    | Exclusive OR WREG with f                 | 1          | 0001                    | 10da | ffff | ffff    | Z, N            |            |
|           |            | E REGISTER OPERATIONS                    | 1          |                         |      |      |         | T               |            |
| BCF       | f, b, a    | Bit Clear f                              | 1          |                         | bbba | ffff | ffff    | None            | 1, 2       |
| BSF       | f, b, a    | Bit Set f                                | 1          |                         | bbba | ffff | ffff    | None            | 1, 2       |
| BTFSC     | f, b, a    | Bit Test f, Skip if Clear                | 1 (2 or 3) |                         | bbba | ffff |         | None            | 3, 4       |
| BTFSS     | f, b, a    | Bit Test f, Skip if Set                  | 1 (2 or 3) | 1010                    |      | ffff | ffff    | None            | 3, 4       |
| BTG       | f, b, a    | Bit Toggle f                             | 1          | 0111                    | bbba | ffff | ffff    | None            | 1, 2       |

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as an input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.
  - **3:** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 25-2: PIC18FXXXX INSTRUCTION SET (CONTINUED)

| Mnemonic, |       | Description                    | Cycles | 16-Bit Instruction Word |      |      | Status | Notes                  |       |
|-----------|-------|--------------------------------|--------|-------------------------|------|------|--------|------------------------|-------|
| Opera     | nds   | Description                    | Cycles | MSb                     |      |      | LSb    | Affected               | Notes |
| CONTROL   | OPERA | TIONS                          |        |                         |      |      |        |                        |       |
| ВС        | n     | Branch if Carry                | 1 (2)  | 1110                    | 0010 | nnnn | nnnn   | None                   |       |
| BN        | n     | Branch if Negative             | 1 (2)  | 1110                    | 0110 | nnnn | nnnn   | None                   |       |
| BNC       | n     | Branch if Not Carry            | 1 (2)  | 1110                    | 0011 | nnnn | nnnn   | None                   |       |
| BNN       | n     | Branch if Not Negative         | 1 (2)  | 1110                    | 0111 | nnnn | nnnn   | None                   |       |
| BNOV      | n     | Branch if Not Overflow         | 1 (2)  | 1110                    | 0101 | nnnn | nnnn   | None                   |       |
| BNZ       | n     | Branch if Not Zero             | 2      | 1110                    | 0001 | nnnn | nnnn   | None                   |       |
| BOV       | n     | Branch if Overflow             | 1 (2)  | 1110                    | 0100 | nnnn | nnnn   | None                   |       |
| BRA       | n     | Branch Unconditionally         | 1 (2)  | 1101                    | 0nnn | nnnn | nnnn   | None                   |       |
| BZ        | n     | Branch if Zero                 | 1 (2)  | 1110                    | 0000 | nnnn | nnnn   | None                   |       |
| CALL      | n, s  | Call subroutine 1st word       | 2      | 1110                    | 110s | kkkk | kkkk   | None                   |       |
|           |       | 2nd word                       |        | 1111                    | kkkk | kkkk | kkkk   |                        |       |
| CLRWDT    | _     | Clear Watchdog Timer           | 1      | 0000                    | 0000 | 0000 | 0100   | TO, PD                 |       |
| DAW       | _     | Decimal Adjust WREG            | 1      | 0000                    | 0000 | 0000 | 0111   | С                      |       |
| GOTO      | n     | Go to address 1st word         | 2      | 1110                    | 1111 | kkkk | kkkk   | None                   |       |
|           |       | 2nd word                       |        | 1111                    | kkkk | kkkk | kkkk   |                        |       |
| NOP       | _     | No Operation                   | 1      | 0000                    | 0000 | 0000 | 0000   |                        |       |
| NOP       | _     | No Operation                   | 1      | 1111                    | xxxx | xxxx | xxxx   | None                   | 4     |
| POP       | _     | Pop top of return stack (TOS)  | 1      | 0000                    | 0000 | 0000 | 0110   | None                   |       |
| PUSH      | _     | Push top of return stack (TOS) | 1      | 0000                    | 0000 | 0000 | 0101   | None                   |       |
| RCALL     | n     | Relative Call                  | 2      | 1101                    | 1nnn | nnnn | nnnn   |                        |       |
| RESET     |       | Software device Reset          | 1      | 0000                    | 0000 | 1111 |        | All                    |       |
| RETFIE    | S     | Return from interrupt enable   | 2      | 0000                    | 0000 | 0001 | 000s   | GIE/GIEH,<br>PEIE/GIEL |       |
| RETLW     | k     | Return with literal in WREG    | 2      | 0000                    | 1100 | kkkk | kkkk   | None                   |       |
| RETURN    | S     | Return from Subroutine         | 2      | 0000                    | 0000 | 0001 | 001s   | None                   |       |
| SLEEP     | _     | Go into Standby mode           | 1      | 0000                    | 0000 | 0000 | 0011   | TO, PD                 |       |

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as an input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.
  - 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - **5:** If the table write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 25-2: PIC18FXXXX INSTRUCTION SET (CONTINUED)

| Mnemonic, |                        | Description                     | Cycles | 16-Bit Instruction Word |      |      |      | Status          | Notes |
|-----------|------------------------|---------------------------------|--------|-------------------------|------|------|------|-----------------|-------|
| Oper      | ands                   | Description                     | Cycles | MSb                     |      |      | LSb  | Affected        | Notes |
| LITERAL   | OPERATI                | ONS                             |        |                         |      |      |      |                 |       |
| ADDLW     | k                      | Add literal and WREG            | 1      | 0000                    | 1111 | kkkk | kkkk | C, DC, Z, OV, N |       |
| ANDLW     | k                      | AND literal with WREG           | 1      | 0000                    | 1011 | kkkk | kkkk | Z, N            |       |
| IORLW     | k                      | Inclusive OR literal with WREG  | 1      | 0000                    | 1001 | kkkk | kkkk | Z, N            |       |
| LFSR      | f, k                   | Move literal (12-bit) 2nd word  | 2      | 1110                    | 1110 | OOff | kkkk | None            |       |
|           |                        | to FSRx 1st word                |        | 1111                    | 0000 | kkkk | kkkk |                 |       |
| MOVLB     | k                      | Move literal to BSR<3:0>        | 1      | 0000                    | 0001 | 0000 | kkkk | None            |       |
| MOVLW     | k                      | Move literal to WREG            | 1      | 0000                    | 1110 | kkkk | kkkk | None            |       |
| MULLW     | k                      | Multiply literal with WREG      | 1      | 0000                    | 1101 | kkkk | kkkk | None            |       |
| RETLW     | k                      | Return with literal in WREG     | 2      | 0000                    | 1100 | kkkk |      | None            |       |
| SUBLW     | k                      | Subtract WREG from literal      | 1      | 0000                    | 1000 | kkkk | kkkk | C, DC, Z, OV, N |       |
| XORLW     | k                      | Exclusive OR literal with WREG  | 1      | 0000                    | 1010 | kkkk | kkkk | Z, N            |       |
| DATA ME   | $MORY \leftrightarrow$ | PROGRAM MEMORY OPERATION        | ONS    |                         |      |      |      |                 |       |
| TBLRD*    |                        | Table Read                      | 2      | 0000                    | 0000 | 0000 | 1000 | None            |       |
| TBLRD*+   |                        | Table Read with post-increment  |        | 0000                    | 0000 | 0000 | 1001 | None            |       |
| TBLRD*-   |                        | Table Read with post-decrement  |        | 0000                    | 0000 | 0000 | 1010 | None            |       |
| TBLRD+*   |                        | Table Read with pre-increment   |        | 0000                    | 0000 | 0000 | 1011 | None            |       |
| TBLWT*    |                        | Table Write                     | 2 (5)  | 0000                    | 0000 | 0000 | 1100 | None            |       |
| TBLWT*+   |                        | Table Write with post-increment |        | 0000                    | 0000 | 0000 | 1101 | None            |       |
| TBLWT*-   |                        | Table Write with post-decrement |        | 0000                    | 0000 | 0000 | 1110 | None            |       |
| TBLWT+*   |                        | Table Write with pre-increment  |        | 0000                    | 0000 | 0000 | 1111 | None            |       |

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as an input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.
  - 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

## 25.1 Instruction Set

| ADD   | LW             | Add Lite              | al to W   |            |  |  |  |  |
|-------|----------------|-----------------------|---|------------|--|--|--|--|
| Synta | ax:            | [ label ] Al          | [ label ] ADDLW k   |            |  |  |  |  |
| Oper  | ands:          | $0 \le k \le 255$     | ;   |            |  |  |  |  |
| Oper  | ation:         | (W) + k $\rightarrow$ | $(W) + k \rightarrow W$   |            |  |  |  |  |
| Statu | s Affected:    | N, OV, C, I           | N, OV, C, DC, Z   |            |  |  |  |  |
| Enco  | ding:          | 0000                  | 1111 kk   | kk kkkk    |  |  |  |  |
| Desc  | ription:       |                       | The contents of W are added to the 8-bit literal 'k' and the result is placed in W. |            |  |  |  |  |
| Word  | ls:            | 1                     |   |            |  |  |  |  |
| Cycle | es:            | 1                     |   |            |  |  |  |  |
| QC    | ycle Activity: |                       |   |            |  |  |  |  |
|       | Q1             | Q2                    | Q3  | Q4         |  |  |  |  |
|       | Decode         | Read                  | Process   | Write to W |  |  |  |  |

Example: ADDLW 0x15

literal 'k'

Data

Before Instruction W = 0x10After Instruction W = 0x25

| ADDWF             | DDWF Add W to f   |                                       |      |                       |  |  |  |
|-------------------|---|---------------------------------------|------|-----------------------|--|--|--|
| Syntax:           | [ label ] AD  | [ label ] ADDWF f [,d [,a] f [,d [,a] |      |                       |  |  |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |                                       |      |                       |  |  |  |
| Operation:        | $(W) + (f) \rightarrow$   | dest                                  |      |                       |  |  |  |
| Status Affected:  | N, OV, C, D   | C, Z                                  |      |                       |  |  |  |
| Encoding:         | 0010  | 01da                                  | ffff | ffff                  |  |  |  |
| деясприон.        | Description: Add W to register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access B will be selected. If 'a' is '1', the BS used. |                                       |      |                       |  |  |  |
| Words:            | 1   |                                       |      |                       |  |  |  |
| Cycles:           | 1   |                                       |      |                       |  |  |  |
| Q Cycle Activity: |   |                                       |      |                       |  |  |  |
| Q1                | Q2  | Q3                                    | 3    | Q4                    |  |  |  |
| Decode            | Read<br>register 'f'  | Proce<br>Data                         | -    | /rite to<br>stination |  |  |  |

Example: ADDWF REG, 0, 0

Before Instruction

W = 0x17 REG = 0xC2

After Instruction

W = 0xD9 REG = 0xC2

| ADDWFC            | Add W and Carry bit to f   |      |            |          |  |  |  |
|-------------------|--|------|------------|----------|--|--|--|
| Syntax:           | [ label ] ADI  | OWFC | f [,d [,a] |          |  |  |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |      |            |          |  |  |  |
| Operation:        | $(W) + (f) + (C) \rightarrow dest$   |      |            |          |  |  |  |
| Status Affected:  | N, OV, C, DC, Z  |      |            |          |  |  |  |
| Encoding:         | 0010   | 00da | ffff       | ffff     |  |  |  |
| Description:      | Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'. If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR will not be overridden. |      |            |          |  |  |  |
| Words:            | 1  |      |            |          |  |  |  |
| Cycles:           | 1  |      |            |          |  |  |  |
| Q Cycle Activity: |  |      |            |          |  |  |  |
| •                 |  |      |            | <u> </u> |  |  |  |

|   | Q1     | Q2           | Q3      | Q4          |
|---|--------|--------------|---------|-------------|
|   | Decode | Read         | Process | Write to    |
| L |        | register 'f' | Data    | destination |

Example: ADDWFC REG, 0, 1

| ANDLW             | AND Lite          | AND Literal with W          |      |                         |  |  |  |
|-------------------|-------------------|-----------------------------|------|-------------------------|--|--|--|
| Syntax:           | [label] AN        | IDLW I                      | <    |                         |  |  |  |
| Operands:         | $0 \le k \le 255$ |                             |      |                         |  |  |  |
| Operation:        | (W) .AND.         | (W) .AND. $k \rightarrow W$ |      |                         |  |  |  |
| Status Affected:  | N, Z              |                             |      |                         |  |  |  |
| Encoding:         | 0000              | 1011                        | kkkk | kkkk                    |  |  |  |
| Description:      |                   |                             |      | ed with the placed in W |  |  |  |
| Words:            | 1                 |                             |      |                         |  |  |  |
| Cycles:           | 1                 |                             |      |                         |  |  |  |
| Q Cycle Activity: |                   |                             |      |                         |  |  |  |
| Q1                | Q2                | Q3                          |      | Q4                      |  |  |  |
| Decode            | Read literal      | Proce                       | ss   | Write to W              |  |  |  |
|                   | 'k'               | Data                        | ì    |                         |  |  |  |

Example: ANDLW 0x5F

Before Instruction

W = 0xA3

After Instruction

W = 0x03

| ANDWF            | AND W with f   |  |  |  |  |
|------------------|--|--|--|--|--|
| Syntax:          | [ label ] ANDWF f [,d [,a]   |  |  |  |  |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |  |  |  |
| Operation:       | (W) .AND. (f) $\rightarrow$ dest   |  |  |  |  |
| Status Affected: | N, Z   |  |  |  |  |
| Encoding:        | 0001 01da ffff ffff  |  |  |  |  |
| Description:     | The contents of W are ANDed with register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'd' (default). If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR will not be overridden (default). |  |  |  |  |

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example: ANDWF REG, 0, 0

Before Instruction

 $\begin{array}{rcl} W & = & 0x17 \\ REG & = & 0xC2 \\ After Instruction \end{array}$ 

W = 0x02 REG = 0xC2

| ВС               | Branch if Carry   |      |      |      |  |  |
|------------------|---|------|------|------|--|--|
| Syntax:          | [ label ] BC n  |      |      |      |  |  |
| Operands:        | -128 ≤ n ≤ 127  |      |      |      |  |  |
| Operation:       | if Carry bit is '1' $(PC) + 2 + 2n \rightarrow PC$  |      |      |      |  |  |
| Status Affected: | None  |      |      |      |  |  |
| Encoding:        | 1110  | 0010 | nnnn | nnnn |  |  |
| Description:     | If the Carry bit is '1', then the program will branch.  The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction. |      |      |      |  |  |
| Words:           | 1   |      |      |      |  |  |

Q Cycle Activity: If Jump:

Cycles:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | ʻn'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BC 5

1(2)

Before Instruction

PC = address (HERE)

After Instruction

If Carry = 1;

PC = address (HERE + 12)

If Carry = 0;

PC = address (HERE + 2)

| BCF              | Bit Clear   | f    |      |      |
|------------------|---|------|------|------|
| Syntax:          | [ label ] BCF f,b[,a]   |      |      |      |
| Operands:        | $0 \le f \le 255$<br>$0 \le b \le 7$<br>$a \in [0,1]$   |      |      |      |
| Operation:       | $0 \rightarrow f < b >$   |      |      |      |
| Status Affected: | None  |      |      |      |
| Encoding:        | 1001  | bbba | ffff | ffff |
| Description:     | Bit 'b' in register 'f' is cleared. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |      |      |      |
| Words:           | 1   |      |      |      |
|                  |   |      |      |      |

Cycles:

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: FLAG\_REG, 7, 0 BCF

Before Instruction

FLAG\_REG 0xC7

After Instruction

 $\mathsf{FLAG}\_\mathsf{REG}$ 0x47

| BN                                   | Branch i  | f Negati   | ve   |                     |
|--------------------------------------|---|--|--|---------------------|
| Syntax:                              | [label] B   | N n  |  |                     |
| Operands:                            | -128 ≤ n ≤ 127  |  |  |                     |
| Operation:                           | if Negative bit is '1' $(PC) + 2 + 2n \rightarrow PC$                 |  |  |                     |
| Status Affected:                     | None  |  |  |                     |
| Encoding:                            | 1110  | 0110   | nnnn   | nnnn                |
| Description:                         | program w<br>The 2's co<br>added to the<br>incremental<br>instruction | vill branch<br>implementhe PC. Sired to fetch<br>the the the the the the the the the the | t number 'ince the PC<br>in the next<br>address wastruction is | 2n' is<br>will have |
| Words:                               | 1   |  |  |                     |
| Cycles:  Q Cycle Activity:  If Jump: | 1(2)  |  |  |                     |

Q1 Q2 Q3 Q4 Read literal Process Write to PC Decode 'n' Data No No No No

operation If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

operation

operation

Example: HERE Jump

operation

Before Instruction

PC address (HERE)

After Instruction

If Negative PC

address (Jump)

If Negative

PC address (HERE + 2)

BNC Branch if Not Carry

Syntax: [label] BNC n Operands:  $-128 \le n \le 127$ Operation: if Carry bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0011 nnnn nnnn

Description: If the Carry bit is '0', then the program

will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1
Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BNC Jump

Before Instruction

PC = address (HERE)

After Instruction

If Carry = 0;

PC = address (Jump)

If Carry = 1;

PC = address (HERE + 2)

BNN Branch if Not Negative

Syntax: [label] BNN n

Operands:  $-128 \le n \le 127$ Operation: if Negative bit is '0'

Status Affected: None

Encoding: 1110 0111 nnnn nnnn

 $(PC) + 2 + 2n \rightarrow PC$ 

Description: If the Negative bit is '0', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to feet the pour

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1
Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | ʻn'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BNN Jump

Before Instruction

PC = address (HERE)

After Instruction

If Negative = 0;

PC = address (Jump)

If Negative = 1;

PC = address (HERE + 2)

| BNOV | Branch i | f N | ot C | Overflow |
|------|----------|-----|------|----------|
|------|----------|-----|------|----------|

Syntax: [label] BNOV n Operands:  $-128 \le n \le 127$ Operation: if Overflow bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0101 nnnn nnnn

Description: If the Overflow bit is '0', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1
Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3              | Q4          |
|-----------|--------------|-----------------|-------------|
| Decode    | Read literal | Process<br>Data | Write to PC |
| No        | No           | No              | No          |
| operation | operation    | operation       | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BNOV Jump

Before Instruction

PC = address (HERE)

After Instruction

If Overflow = 0

PC = address (Jump)

If Overflow = 1;

PC = address (HERE + 2)

BNZ Branch if Not Zero

Syntax: [label] BNZ n Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0001 nnnn nnnn

Description: If the Zero bit is '0', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

operation

operation

two-cycle instruction.

Words: 1
Cycles: 1(2)

operation

Q Cycle Activity: If Jump:

 Q1
 Q2
 Q3
 Q4

 Decode
 Read literal 'n'
 Process Data
 Write to PC

 No
 No
 No
 No

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BNZ Jump

operation

Before Instruction

PC = address (HERE)

After Instruction

If Zero = 0;

PC = address (Jump)

If Zero = 1;

PC = address (HERE + 2)

**BRA Unconditional Branch** 

Syntax: [label] BRA n Operands:  $\text{-}1024 \leq n \leq 1023$ Operation:  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1101 0nnn nnnn nnnn

Description: Add the 2's complement number '2n' to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a

two-cycle instruction.

Words: 2 Cycles:

Q Cycle Activity:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | ʻn'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

Example: HERE BRA Jump

Before Instruction

PC address (HERE)

After Instruction

PC address (Jump) **BSF** Bit Set f

Syntax: [label] BSF f,b[,a]

Operands:  $0 \le f \le 255$  $0 \le b \le 7$ 

 $a \in [0,1]$ 

Operation:  $1 \rightarrow f < b >$ Status Affected: None

Encoding: 1000 bbba ffff ffff Bit 'b' in register 'f' is set. If 'a' is '0', Description:

Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR

value.

Words: 1 Cycles:

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: BSF FLAG REG, 7, 1

Before Instruction

FLAG\_REG 0x0A

1

After Instruction

FLAG\_REG A8x0

| BTFSC  | Bit Test Fi   | le, Skip if Cl                                | ear   | BTFSS       |   | Bit Test Fi  | le, Skip if Se  | t   |
|--|---|---|---|-------------|---|--|---|---|
| Syntax:  | [ label ] BTF   | SC f,b[,a]                                    |   | Syntax:     |   | [label] BTF  | SS f,b[,a]  |   |
| Operands:  | $0 \le f \le 255$<br>$0 \le b \le 7$<br>$a \in [0,1]$   |   |   | Operands    | s:  | $0 \le f \le 255$<br>$0 \le b < 7$<br>$a \in [0,1]$  |   |   |
| Operation:   | skip if (f <b>)</b>   | ) = 0   |   | Operation   | n:  | skip if (f <b>)</b>  | = 1   |   |
| Status Affected:   | None  |   |   | Status Af   | fected:   | None   |   |   |
| Encoding:  | 1011  | bbba ff                                       | ff ffff   | Encoding    | <b>j</b> :  | 1010   | bbba ff:  | ff ffff   |
| Description:   | instruction is<br>If bit 'b' is '0<br>fetched duri<br>execution is<br>executed ins<br>instruction. I<br>will be select<br>value. If 'a' = | ', then the nexting the current discarded and | instruction<br>instruction<br>la NOP is<br>his a two-cycle<br>Access Bank<br>the BSR<br>ank will be | Description | on:   | instruction is<br>If bit 'b' is '1'<br>fetched during<br>execution, is<br>executed instruction. I<br>will be select<br>value. If 'a' = | gister 'f' is '1', to so skipped.  ', then the next not the current is so discarded and stead, making the f'a' is '0', the A ted, overriding = 1, then the baper the BSR va | instruction nstruction I a NOP is nis a two-cycle access Bank the BSR ink will be |
| Words:   | 1   |   |   | Words:      |   | 1  |   |   |
| Cycles:  |   | ycles if skip an<br>a 2-word instru           |   | Cycles:     |   |  | cycles if skip an<br>a 2-word instru  |   |
| Q Cycle Activity:  |   |   |   | Q Cycle     | Activity:   |  |   |   |
| Q1   | Q2  | Q3  | Q4  |             | Q1  | Q2   | Q3  | Q4  |
| Decode   | Read register 'f'   | Process<br>Data                               | No operation  |             | Decode  | Read register 'f'  | Process<br>Data   | No operation  |
| If skip:   |   |   |   | If skip:    |   |  |   |   |
| Q1   | Q2  | Q3  | Q4  |             | Q1  | Q2   | Q3  | Q4  |
| No operation   | No operation  | No operation                                  | No operation  | 01          | No<br>peration  | No operation   | No operation  | No operation  |
| <u> </u>   | ved by 2-word ins   |   | operation   |             |   | by 2-word ins  |   | operation   |
| Q1   | Q2  | Q3  | Q4  | •           | Q1  | Q2   | Q3  | Q4  |
| No operation   | No operation  | No operation                                  | No operation  | ot          | No<br>peration  | No operation   | No operation  | No<br>operation   |
| No operation   | No operation  | No operation                                  | No operation  | Oţ          | No<br>peration  | No operation   | No<br>operation   | No<br>operation   |
| Example:   | HERE B'<br>FALSE :<br>TRUE :  |   | G, 1, 0   | Example:    | i   | HERE B'<br>FALSE :<br>TRUE :   | TFSS FLAG   | , 1, 0  |
| Before Instru<br>PC<br>After Instruc<br>If FLAC<br>PC<br>If FLAC<br>PC | = add<br>etion<br>G<1> = 0;<br>= add<br>G<1> = 1;   | dress (HERE) dress (TRUE)                     | )   |             | ore Instruct<br>PC<br>or Instructio<br>If FLAG<<br>PC<br>If FLAG<<br>PC | = add<br>n<br>1> = 0;<br>= add<br>1> = 1;  | dress (HERE) dress (FALSE) dress (TRUE)   |   |

BTG Bit Toggle f

Syntax: [ label ] BTG f,b[,a]

Operands:  $0 \le f \le 255 \\ 0 \le b < 7 \\ a \in [0,1]$ 

Operation:  $(\overline{f < b >}) \rightarrow f < b >$ 

Status Affected: None

Encoding: 0111 bbba ffff ffff

Description: Bit 'b' in data memory location 'f' is inverted. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If

'a' = 1, then the bank will be selected as per the BSR value (default).

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: BTG PORTC, 4, 0

Before Instruction:

PORTC = 0111 0101 [0x75]

After Instruction:

PORTC = 0110 0101 [0x65]

| BOV              | Branch if Overflow  |        |      |
|------------------|---|--------|------|
| Syntax:          | [ <i>label</i> ] BOV r                                    | 1      |      |
| Operands:        | $\text{-}128 \leq n \leq 127$                             |        |      |
| Operation:       | if Overflow bit is '1' $(PC) + 2 + 2n \rightarrow PC$     |        |      |
| Status Affected: | None  |        |      |
| Encoding:        | 1110 010  | 0 nnnn | nnnn |
| Description:     | If the Overflow bit is '1', then the program will branch. |        |      |

The 2's complement number '2n' is added to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BOV Jump

Before Instruction

PC = address (HERE)

After Instruction

If Overflow = 1;

PC = address (Jump)

If Overflow = 0;

PC = address (HERE + 2)

| D.7 | Duamah it Zana |
|-----|----------------|
| BZ  | Branch if Zero |

Syntax: [label] BZ n Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0000 nnnn nnnn

Description: If the Zero bit is '1', then the program

will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1
Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BZ Jump

Before Instruction

PC = address (HERE)

After Instruction

If Zero = 1;

PC = address (Jump)

If Zero = 0;

PC = address (HERE + 2)

CALL Subroutine Call

Syntax: [ label ] CALL k [,s]

Operands:  $0 \le k \le 1048575$ 

 $s \in [0,1]$ 

Operation: (PC) + 4  $\rightarrow$  TOS;

 $k \rightarrow PC < 20:1 >$  if s = 1

 $(W) \rightarrow WS;$ 

 $(STATUS) \rightarrow STATUSS;$ 

 $(BSR) \rightarrow BSRS$ 

Status Affected: None

Encoding: 1st word (k<7:0>) 2nd word(k<19:8>)

| 1110 | 110s                | k <sub>7</sub> kkk | kkkk <sub>0</sub> |
|------|---------------------|--------------------|-------------------|
| 1111 | k <sub>19</sub> kkk | kkkk               | kkkk <sub>8</sub> |

Description:

Subroutine call of entire 2-Mbyte memory range. First, return address (PC + 4) is pushed onto the return stack. If 's' = 1, the W, STATUS and BSR registers are also pushed into their respective shadow registers, WS, STATUSS and BSRS. If 's' = 0, no update occurs (default). Then, the 20-bit value 'k' is loaded into PC<20:1>. CALL is a two-cycle instruction.

Words: 2 Cycles: 2

Q Cycle Activity:

|   | Q1        | Q2           | Q3         | Q4           |
|---|-----------|--------------|------------|--------------|
| ĺ | Decode    | Read literal | Push PC to | Read literal |
|   |           | 'k'<7:0>,    | stack      | 'k'<19:8>,   |
|   |           |              |            | Write to PC  |
| ĺ | No        | No           | No         | No           |
|   | operation | operation    | operation  | operation    |

Example: HERE CALL THERE, 1

Before Instruction

PC = address (HERE)

After Instruction

PC = address (THERE)
TOS = address (HERE + 4)

WS = W BSRS = BSR STATUSS= STATUS

| CLRF              | Clear f  |          |      |      |  |
|-------------------|--|----------|------|------|--|
| Syntax:           | [ label ] CL   | RF f [,a | 1]   |      |  |
| Operands:         | $0 \le f \le 255$<br>$a \in [0,1]$   |          |      |      |  |
| Operation:        | $000h \rightarrow f;$ $1 \rightarrow Z$  |          |      |      |  |
| Status Affected:  | Z  |          |      |      |  |
| Encoding:         | 0110   | 101a     | ffff | ffff |  |
| Description:      | Clears the contents of the specified register. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |          |      |      |  |
| Words:            | 1  |          |      |      |  |
| Cycles:           | 1  |          |      |      |  |
| Q Cycle Activity: |  |          |      |      |  |

| Q1     | Q2           | Q3      | Q4           |  |
|--------|--------------|---------|--------------|--|
| Decode | Read         | Process | Write        |  |
|        | register 'f' | Data    | register 'f' |  |
|        |              |         |              |  |

Example: CLRF FLAG\_REG, 1

Before Instruction

 $FLAG_REG = 0x5A$ 

After Instruction

 $FLAG_REG = 0x00$ 

| CLR               | WDT         | Clear Wa  | tchdog           | Time    | r    |               |  |  |
|-------------------|-------------|---|------------------|---------|------|---------------|--|--|
| Synta             | ax:         | [label] C   | [ label ] CLRWDT |         |      |               |  |  |
| Oper              | ands:       | None  | None             |         |      |               |  |  |
| Oper              | ation:      | 000h → WDT;<br>000h → WDT postscaler;<br>1 → $\overline{10}$ ;<br>1 → $\overline{PD}$ |                  |         |      |               |  |  |
| Statu             | s Affected: | $\overline{TO}, \overline{PD}$  | TO, PD           |         |      |               |  |  |
| Encoding:         |             | 0000  | 0000             | 000     | 0    | 0100          |  |  |
| Desc              | ription:    | CLRWDT ins<br>Watchdog<br>postscaler<br>and PD, are                                   | Timer. It a      | also re | sets |               |  |  |
| Word              | ls:         | 1   |                  |         |      |               |  |  |
| Cycles:           |             | 1   | 1                |         |      |               |  |  |
| Q Cycle Activity: |             |   |                  |         |      |               |  |  |
|                   | Q1          | Q2  | Q3               | 3       |      | Q4            |  |  |
|                   | Decode      | No operation  | Proce<br>Data    |         | ор   | No<br>eration |  |  |

CLRWDT

Example:

| COMF   | Complen  | Complement f  |         |    |                   |  |
|--|--|---------------|---------|----|-------------------|--|
| Syntax:  | [label] C  | OMF f         | [,d [,a | 1] |                   |  |
| Operands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  | d ∈ [0,1]     |         |    |                   |  |
| Operation:                                       | $(\overline{f}) \rightarrow de$  | st            |         |    |                   |  |
| Status Affected:                                 | N, Z   |               |         |    |                   |  |
| Encoding:  | 0001   | 11da          | fff     | f  | ffff              |  |
| Description:                                     | The contents of register 'f' are complemented. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |               |         |    |                   |  |
| Words:   | 1  |               |         |    |                   |  |
| Cycles:  | 1  |               |         |    |                   |  |
| Q Cycle Activity:                                |  |               |         |    |                   |  |
| Q1   | Q2   | Q3            | 3       |    | Q4                |  |
| Decode   | Read register 'f'  | Proce<br>Data |         |    | rite to stination |  |
| Example:   | COMF   | REG,          | 0, 0    |    |                   |  |
| Before Instruc<br>REG<br>After Instructio<br>REG | = 0x13<br>on<br>= 0x13   |               |         |    |                   |  |
| W  | = 0xEC   |               |         |    |                   |  |

| CPF     | SEQ                        | Compare  | Compare f with W, Skip if f = W   |            |               |  |  |
|---------|----------------------------|--|---|------------|---------------|--|--|
| Synta   | ax:                        | [label] C  | [label] CPFSEQ f[,a]  |            |               |  |  |
| Oper    | ands:                      | $0 \le f \le 255$<br>a $\in [0,1]$   |   |            |               |  |  |
| Oper    | ation:                     |  | (f) – (W);<br>skip if (f) = (W)<br>(unsigned comparison)  |            |               |  |  |
| Statu   | s Affected:                | None   |   |            |               |  |  |
| Enco    | ding:                      | 0110   | 001a  | ffff       | ffff          |  |  |
| Desc    | ription:                   | location 'f' performing If 'f' = W, th discarded a instead, ma instruction. will be sele value. If 'a' | Compares the contents of data memory location 'f' to the contents of W by performing an unsigned subtraction. If 'f' = W, then the fetched instruction is discarded and a NOP is executed instead, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |            |               |  |  |
| Word    | ls:                        | 1  | 1   |            |               |  |  |
| Cycles: |                            |  | -   | kip and fo |               |  |  |
| Q C     | ycle Activity:             |  |   |            |               |  |  |
|         | Q1                         | Q2   | Q3  |            | Q4            |  |  |
|         | Decode                     | Read<br>register 'f'   | Proce<br>Data   |            | No<br>eration |  |  |
| lf sk   | ip:                        |  |   |            |               |  |  |
|         | Q1                         | Q2   | Q3  | <u> </u>   | Q4            |  |  |
|         | No                         | No   | No  |            | No            |  |  |
|         | operation                  | operation  | operat  |            | eration       |  |  |
| If sk   | ip and followed            | •  |   |            |               |  |  |
| ı       | Q1                         | Q2   | Q3  | 1          | Q4            |  |  |
|         | No                         | No   | No  |            | No            |  |  |
|         | operation                  | operation  | operat  | ion op     | eration       |  |  |
|         | No                         | No<br>operation  | No  | ion on     | No            |  |  |
|         | operation                  | operation  | operat  | ion   op   | eration       |  |  |
| Exam    | nple:                      | HERE<br>NEQUAL<br>EQUAL  | CPFSEQ<br>:   | REG, 0     |               |  |  |
|         | Before Instruc             |  |   |            |               |  |  |
|         | PC Address = HERE<br>W = ? |  |   |            |               |  |  |

| CPFSGT Compare f with W, Skip if f > W |   | GT Compare f with W, Skip if f > W CPFSLT   |  | SLT   | Compare f with W, Skip if f < W    |  |                               | f <b>f &lt; W</b> |               |
|--|---|---|--|---|------------------------------------|--|-------------------------------|-------------------|---------------|
| Syntax:                                | [label] C   | PFSGT f[,a]   |  | Synta   | ix:                                | [label] C  | PFSLT f[,a                    | a]                |               |
| Operands:                              | $0 \le f \le 255$<br>$a \in [0,1]$  |   | Opera  | ands:   | $0 \le f \le 255$<br>$a \in [0,1]$ |  |                               |                   |               |
| Operation:                             | ation: $(f) - (W)$ ; Operation $(f) - (W)$ ; $(f) > (W)$ (unsigned comparison)                                      |   | ation:   | (f) – (W);<br>skip if (f) <<br>(unsigned  | (W)<br>comparison)                 |  |                               |                   |               |
| Status Affected:                       | None  |   |  | Status  | s Affected:                        | None   |                               |                   |               |
| Encoding:                              | 0110  | 010a ff   | ff ffff  | Enco  | ding:                              | 0110   | 000a f                        | fff               | ffff          |
| Description:                           | location 'f' is performing If the contect contents of instruction executed ir two-cycle in Access Barroverriding to | to the contents an unsigned so the sof 'f' are grand WREG, then is discarded and the stead, making astruction. If 'ank will be selected to the BSR value. | subtraction. reater than the the fetched and a NOP is this a 'is '0', the cted, If 'a' = 1, then | Description:  Compares the contents of data location 'f' to the contents of W performing an unsigned subtra If the contents of 'f' are less that contents of W, then the fetched instruction is discarded and a N executed instead, making this atwo-cycle instruction. If 'a' is 'o' Access Bank will be selected. If the BSR will not be overridden |                                    | V by action. an the d NOP is a ', the If 'a' is '1', |                               |                   |               |
|  | the bank w<br>BSR value   | ill be selected   | as per the   | Word  | s:                                 | 1  |                               |                   |               |
| Words:                                 | 1   | (dorddir).  |  | Cycle   | s:                                 | 1(2)   |                               |                   |               |
| Cycles:                                | 1(2)<br><b>Note:</b> 3 (  | cycles if skip a  |  | Q C <sub>)</sub>  | cle Activity:                      |  | cycles if skip<br>a 2-word in |                   |               |
|  | by  | a 2-word instr  | uction.  | _   | Q1                                 | Q2   | Q3                            |                   | Q4            |
| Q Cycle Activity:<br>Q1                | Q2  | Q3  | Q4   |   | Decode                             | Read register 'f'                                    | Process<br>Data               | on                | No<br>eration |
| Decode                                 | Read register 'f'   | Process<br>Data   | No operation   | lf ski  | p:<br>Q1                           | Q2   | Q3                            | T OP              | Q4            |
| If skip:                               |   |   |  | ſ   | No                                 | No.  | No.                           |                   | No.           |
| Q1                                     | Q2  | Q3  | Q4   |   | operation                          | operation  | operation                     | ор                | eration       |
| No                                     | No  | No  | No   | lf ski  | p and followe                      | d by 2-word in                                       | struction:                    |                   |               |
| operation                              | operation   | operation   | operation  |   | Q1                                 | Q2   | Q3                            |                   | Q4            |
| If skip and followe                    | •   |   |  |   | No                                 | No   | No                            |                   | No            |
| Q1                                     | Q2  | Q3  | Q4   |   | operation                          | operation  | operation                     | ор                | eration       |
| No                                     | No  | No  | No   |   | No                                 | No   | No                            |                   | No            |
| operation                              | operation   | operation   | operation  | l   | operation                          | operation  | operation                     | ор                | eration       |
| No<br>operation                        | No<br>operation   | No<br>operation   | No<br>operation  | <u>Exam</u>   | ple:                               |  | CPFSLT RE                     | G, 1              |               |
| Example:                               | HERE<br>NGREATER<br>GREATER   | CPFSGT RE   | EG, 0  | 1   | Before Instruc                     | NLESS<br>LESS<br>etion                               | :                             |                   |               |

Before Instruction
PC =
W =

After Instruction

If REG PC If REG PC GREATER

Address (HERE) ?

Address (GREATER) W;
Address (NGREATER)

Address (HERE)

Address (LESS) W;

Address (NLESS)

After Instruction

If REG PC If REG PC

| DAV               | V           | Decimal A                     | Adjust W Re  | gister                         |  |  |
|-------------------|-------------|-------------------------------|--|--------------------------------|--|--|
| Synta             | ax:         | [label] Di                    | [ label ] DAW  |                                |  |  |
| Oper              | ands:       | None                          |  |                                |  |  |
| Oper              | ation:      | (W<3:0>) +<br>else            | If [W<3:0> > 9] or [DC = 1] then (W<3:0>) + 6 $\rightarrow$ W<3:0>; else (W<3:0>) $\rightarrow$ W<3:0> |                                |  |  |
|                   |             | -                             | > 9] or [C = 1]<br>$6 \to W < 7:4 >$ ;<br>$0 \to W < 7:4 >$  | then                           |  |  |
| Statu             | s Affected: | С                             |  |                                |  |  |
| Enco              | ding:       | 0000                          | 0000 000   | 00 0111                        |  |  |
| Description:      |             | resulting fro<br>variables (e | is the eight-bit<br>om the earlier a<br>each in packed<br>es a correct pa                              | addition of two<br>BCD format) |  |  |
| Word              | ls:         | 1                             | 1  |                                |  |  |
| Cycles:           |             | 1                             |  |                                |  |  |
| Q Cycle Activity: |             |                               |  |                                |  |  |
|                   | Q1          | Q2                            | Q3   | Q4                             |  |  |
|                   | Decode      | Read register W               | Process<br>Data  | Write<br>W                     |  |  |

| Example 1:        | DA   | AM.  |
|-------------------|------|------|
| Before Instruc    | tion |      |
| W                 | =    | 0xA5 |
| С                 | =    | 0    |
| DC                | =    | 0    |
| After Instruction | on   |      |
| W                 | =    | 0x05 |
| С                 | =    | 1    |
| DC                | =    | 0    |
| Example 2:        |      |      |
| Before Instruc    | tion |      |
| W                 | =    | 0xCE |
| С                 | =    | 0    |
| DC                | =    | 0    |
| After Instruction | on   |      |
| W                 | =    | 0x34 |
| С                 | =    | 1    |
| DC                | =    | 0    |

| DEC   | F              | Decremen  | Decrement f   |   |   |  |  |
|-------|----------------|---|---|---|---|--|--|
| Synta | ax:            | [label] Di  | ECF f[,d  | l [,a]  |   |  |  |
| Oper  | ands:          | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   | d ∈ [0,1]   |   |   |  |  |
| Oper  | ation:         | $(f) - 1 \rightarrow de$  | est   |   |   |  |  |
| Statu | s Affected:    | C, DC, N, C   | OV, Z   |   |   |  |  |
| Enco  | ding:          | 0000  | 01da  | ffff  | ffff  |  |  |
| 2000  | ription:       | Decrement<br>result is sto<br>result is sto<br>(default). If<br>will be sele-<br>value. If 'a'<br>selected as | red in W. red back 'a' is '0', t cted, over = 1, then | If 'd' is '1 in registe the Accestriding the the bank | ', the<br>or 'f'<br>os Bank<br>e BSR<br>will be |  |  |
| Word  | ds:            | 1   |   |   |   |  |  |
| Cycle | es:            | 1   |   |   |   |  |  |
| QC    | ycle Activity: |   |   |   |   |  |  |
| Q1    |                | Q2  | Q3  |   | Q4  |  |  |
|       | Decode         | Read register 'f'   | Proces<br>Data  |   | Vrite to stination                              |  |  |
| Exan  | nple:          | DECF (  | CNT, 1  | ., 0  |   |  |  |

| DEC    | FSZ Decrement f, Skip if 0              |  | DCFSNZ   |   | Decrement f, Skip if Not 0  |  |  |                                    |                |
|--------|---|--|--|---|---|--|--|------------------------------------|----------------|
| Synta  | ax:                                     | [label] DE   | CFSZ f[,d[   | ,a]]  | Synt  | ax:  | [label] D  | CFSNZ f[,d                         | [,a]           |
| Oper   | ands:                                   | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |   | Operands:   |  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |                                    |                |
| Oper   | ation:                                  | (f) $-1 \rightarrow de$ skip if result   | •  |   | Ope   | ration:  | (f) $-1 \rightarrow d$ skip if resu  | •                                  |                |
| Statu  | s Affected:                             | None   |  |   | Statu   | us Affected:                                   | None   |                                    |                |
| Enco   | ding:                                   | 0010   | 11da fff   | f ffff  | Enco  | oding:   | 0100   | 11da ff                            | ff ffff        |
| Desc   | ription:                                | decremented placed in William placed back of the result which is alread a NOP in it a two-cycle Access Barriding the B | ts of register 'f ed. If 'd' is '0', '/. If 'd' is '1', th k in register 'f' is '0', the nex eady fetched i s executed ins le instruction. nk will be select SR value. If 'a e selected as p ult). | the result is the result is the result is (default). It instruction is discarded stead, making If 'a' is '0', the oted, over- | Description:  The contents of register 'f' a decremented. If 'd' is '0', the placed in W. If 'd' is '1', the placed back in register 'f' (a lf the result is '0', the next is which is already fetched is and a NOP is executed instati a two-cycle instruction. If Access Bank will be selecter riding the BSR value. If 'a' = bank will be selected as pevalue (default). |  | the result is ne result is (default). It instruction is discarded stead, making If 'a' is '0', the cted, over- |                                    |                |
| Word   | ls:                                     | 1  |  |   | Word  | ds:  | 1  |                                    |                |
| Cycle  | es:                                     | 1(2)   |  |   | Cycl  | es:  | 1(2)   |                                    |                |
| •      |   | <b>Note:</b> 3 cycles if skip and followed by a 2-word instruction.  |  |   |   |  |  | cycles if skip a<br>a 2-word instr |                |
| Q C    | ycle Activity:                          | 00   | 00   | 0.4   | QC  | cycle Activity:                                | 00   | 00                                 | 0.4            |
|        | Q1<br>Decode                            | Q2<br>Read   | Q3<br>Process  | Q4<br>Write to  |   | Q1<br>Decode                                   | Q2<br>Read   | Q3<br>Process                      | Q4<br>Write to |
|        | Decode                                  | register 'f'   | Data   | destination   |   | Decode   | register 'f'   | Data                               | destination    |
| If sk  | ip:                                     | -  |  |   | If sk   | kip:   | -  |                                    |                |
|        | Q1                                      | Q2   | Q3   | Q4  |   | Q1   | Q2   | Q3                                 | Q4             |
|        | No                                      | No   | No   | No  |   | No   | No   | No                                 | No             |
| lf ale | operation                               | operation  | operation  | operation   | If all  | operation                                      | operation  | operation                          | operation      |
| II SK  | ip and followe<br>Q1                    | d by 2-word in:<br>Q2  | Q3   | Q4  | II Sr   | kip and followe<br>Q1                          | Q2   | Q3                                 | Q4             |
|        | No                                      | No   | No   | No No   |   | No   | No   | No                                 | No             |
|        | operation                               | operation  | operation  | operation   |   | operation                                      | operation  | operation                          | operation      |
|        | No                                      | No   | No   | No  |   | No   | No   | No                                 | No             |
|        | operation                               | operation  | operation  | operation   |   | operation                                      | operation  | operation                          | operation      |
| Exan   | nple:                                   | HERE<br>CONTINUE   | DECFSZ<br>GOTO   | CNT, 1, 1<br>LOOP   | Exar  | mple:  | ZERO   | DCFSNZ TEN<br>:                    | MP, 1, 0       |
|        | Before Instruction PC After Instruction | = Address  | S (HERE)   |   |   | Before Instruction TEMP After Instruction TEMP | = ?<br>on  | EMD 1                              |                |
|        | If CNT<br>PC<br>If CNT<br>PC            | <b>≠</b> 0;  | CONTINUE (HERE + 2   |   |   | IF TEMP PC If TEMP PC                          | = 0;<br>= Ac<br>≠ 0;   | ddress (ZERO                       |                |

range. The 20-bit value 'k' is loaded into

PC<20:1>. GOTO is always a

| GOTO  | Unconditional Branch   |        |  |  |  |
|---|--|--------|--|--|--|
| Syntax:   | [ label ]  | GOTO k |  |  |  |
| Operands:   | $0 \le k \le 10^4$   | 48575  |  |  |  |
| Operation:  | $k \rightarrow PC < 20:1 >$  |        |  |  |  |
| Status Affected:                                    | None   |        |  |  |  |
| Encoding:<br>1st word (k<7:0>)<br>2nd word(k<19:8>) | 1110 1111 k <sub>7</sub> kkk kkkk <sub>0</sub> 1111 k <sub>19</sub> kkk kkkk kkkk <sub>8</sub> |        |  |  |  |
| Description:  | GOTO allows an unconditional branch anywhere within entire 2-Mbyte memory                      |        |  |  |  |

two-cycle instruction.

Words: 2

Cycles: 2

Q Cycle Activity:

| Q1           | Q2                     | Q2 Q3           |   |
|--------------|------------------------|-----------------|---|
| Decode       | Read literal 'k'<7:0>, | No<br>operation | Read literal<br>'k'<19:8>,<br>Write to PC |
| No operation | No operation           | No operation    | No operation                              |

Example: GOTO THERE

After Instruction

PC = Address (THERE)

| INC          | INCF Increment f |  |  |  |  |  |
|--------------|------------------|--|--|--|--|--|
| Synta        | ax:              | [label] IN   | [ label ] INCF f [,d [,a]  |  |  |  |
| Oper         | ands:            | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |  |  |  |
| Oper         | ation:           | (f) + 1 $\rightarrow$ de   | est  |  |  |  |
| Statu        | s Affected:      | C, DC, N, C  | OV, Z  |  |  |  |
| Enco         | oding:           | 0010   | 10da   | ffff   | ffff   |  |
| Description: |                  | The conten incremente placed in W placed bacl is '0', the A overriding t the bank wi BSR value | d. If 'd' is<br>/. If 'd' is<br>k in regis<br>ccess Ba<br>he BSR v | s '0', the re '1', the re ster 'f' (def. ank will be value. If 'a ected as p | esult is<br>sult is<br>ault). If 'a'<br>selected,<br>' = 1, then |  |
| Word         | ds:              | 1  |  |  |  |  |
| Cycles:      |                  | 1  |  |  |  |  |
| QC           | ycle Activity:   |  |  |  |  |  |
|              | Q1               | Q2   | Q3   | 3  | Q4   |  |
|              | Decode           | Read register 'f'  | Proce<br>Data  |  | Vrite to stination   |  |

Example: INCF CNT, 1, 0 Before Instruction CNT Z C 0xFF 0 DC ? After Instruction CNT 0x00 Z C = 1 DC

| INC   | SZ                           | Increment f, Skip if 0  |  | INF   | SNZ         | Increment f, Skip if Not 0                  |  |   |   |
|---|------------------------------|---|--|---|-------------|---|--|---|---|
| Synta   | ax:                          | [ label ] IN  | NCFSZ f[,d   | [,a]  | Synt        | ax:   | [ label ] IN   | NFSNZ f[,d  | [,a]  |
| Operands: $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$ |                              | Оре   | rands:   | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |             |   |  |   |   |
| Oper  | ation:                       | (f) + 1 $\rightarrow$ deskip if result  | -  |   | Ope         | ration:                                     | (f) + 1 $\rightarrow$ description (f) skip if results  |   |   |
| Statu   | s Affected:                  | None  |  |   | Statu       | us Affected:                                | None   |   |   |
| Enco  | ding:                        | 0011  | 11da ff:   | ff ffff   | Enco        | oding:                                      | 0100   | 10da ff   | ff ffff   |
| Desc  | ription:                     | incremente placed in W placed bacl If the result which is alr and a NOP if a two-cyc Access Barriding the B | le instruction.<br>nk will be select<br>SR value. If 'a<br>e selected as p | he result is the result is (default). It instruction s discarded stead, making If 'a' is '0', the cted, over- ' = 1, then the | Desc        | cription:                                   | incremente placed in W placed back If the result which is alr and a NOP it a two-cyc Access Bar riding the B | le instruction.<br>nk will be seled<br>SR value. If 'a<br>e selected as p | he result is ne result is (default). t instruction s discarded stead, making If 'a' is '0', the cted, over- ' = 1, then the |
| Word  | s:                           | 1   | - ',   |   | Word        | ds:   | 1  | - ,   |   |
| Cycle   |                              | 1(2)  |  |   | Cycle       | es.   | 1(2)   |   |   |
| Cyolo   |                              | Note: 3 cy  | rcles if skip an<br>a 2-word instru  |   | Oyo.        | <b>.</b>                                    | Note: 3 c  | ycles if skip a<br>a 2-word instr   |   |
| Q C   | ycle Activity:               |   |  |   | QC          | cycle Activity:                             |  |   |   |
|   | Q1                           | Q2  | Q3   | Q4  |             | Q1  | Q2   | Q3  | Q4  |
|   | Decode                       | Read register 'f'   | Process<br>Data  | Write to destination  |             | Decode                                      | Read register 'f'  | Process<br>Data   | Write to destination  |
| If sk   | ip:                          |   |  |   | If sk       | kip:  |  |   |   |
| ı   | Q1                           | Q2  | Q3   | Q4  |             | Q1  | Q2   | Q3  | Q4  |
|   | No                           | No  | No   | No  |             | No  | No   | No  | No  |
|   | operation                    | operation   | operation  | operation   |             | operation                                   | operation  | operation   | operation   |
| It sk   | •                            | d by 2-word in  |  | 0.4   | lt sk       | If skip and followed by 2-word instruction: |  |   | 0.4   |
|   | Q1                           | Q2  | Q3   | Q4  |             | Q1  | Q2   | Q3  | Q4  |
|   | No operation                 | No  | No operation   | No operation  |             | No operation                                | No operation   | No operation  | No operation  |
|   | No                           | operation<br>No   | No   | No  |             | No  | No   | No  | No  |
|   | operation                    | operation   | operation  | operation   |             | operation                                   | operation  | operation   | operation   |
| Exam  | ·                            | HERE :  |  | TT, 1, 0  | <u>Exar</u> | mple:                                       |  | INFSNZ REC  |   |
| Before Instruction  |                              |   | Before Instruc   | ction   |             |   |  |   |   |
| PC = Address (HERE)   |                              |   | PC   | = Address   | s (HERE)    |   |  |   |   |
|   | After Instruction CNT If CNT | on<br>= CNT + '<br>= 0;   | 1  |   |             | After Instruction<br>REG<br>If REG          | on<br>= REG +<br>≠ 0;  | 1   |   |
|   | PC<br>15 CNIT                |   | (ZERO)   |   |             | PC<br># DEC                                 |  | S (NZERO)   |   |
|   | If CNT<br>PC                 | ≠ 0;<br>= Address   | S (NZERO)  |   |             | If REG<br>PC                                | = 0;<br>= Address  | s (ZERO)  |   |

| IORI              | LW          | Inclusive           | OR Lite           | eral w | ith W                        |  |  |
|-------------------|-------------|---------------------|-------------------|--------|------------------------------|--|--|
| Synta             | ax:         | [ label ] I         | ORLW k            | (      |                              |  |  |
| Oper              | ands:       | $0 \le k \le 25$    | $0 \le k \le 255$ |        |                              |  |  |
| Oper              | ation:      | (W) .OR. k          | $x \to W$         |        |                              |  |  |
| Statu             | s Affected: | N, Z                |                   |        |                              |  |  |
| Enco              | ding:       | 0000                | 1001              | kkk    | k kkkk                       |  |  |
| Description:      |             |                     |                   |        | ed with the<br>ult is placed |  |  |
| Word              | ls:         | 1                   | 1                 |        |                              |  |  |
| Cycle             | es:         | 1                   | 1                 |        |                              |  |  |
| Q Cycle Activity: |             |                     |                   |        |                              |  |  |
|                   | Q1          | Q2                  | Q3                | 3      | Q4                           |  |  |
|                   | Decode      | Read<br>literal 'k' | Proce<br>Data     |        | Write to W                   |  |  |

Example: IORLW 0x35

 $\begin{array}{rcl} \text{Before Instruction} & & & \\ W & = & 0x9A \\ \text{After Instruction} & & & \\ W & = & 0xBF \end{array}$ 

| IOR               | WF     | Inclusive  | OR W   | with f  |  |  |  |
|-------------------|--------|--|--|---|--|--|--|
| Synta             | ax:    | [ label ]  | ORWF   | f [,d [,a]  |  |  |  |
| Oper              | ands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |   |  |  |  |
| Oper              | ation: | (W) .OR. (f  | $) \rightarrow dest$                                   |   |  |  |  |
| Status Affected:  |        | N, Z   |  |   |  |  |  |
| Encoding:         |        | 0001   | 00da   | ffff  | ffff   |  |  |
| Description:      |        | Inclusive O  '0', the result is the result is (default). If will be sele value. If 'a' selected as | ult is places placed I 'a' is '0', cted, ove = 1, ther | ed in W. I<br>back in reg<br>the Acces<br>erriding the<br>in the bank | f 'd' is '1',<br>gister 'f'<br>ss Bank<br>e BSR<br>will be |  |  |
| Word              | ls:    | 1  |  |   |  |  |  |
| Cycles:           |        | 1  | 1  |   |  |  |  |
| Q Cycle Activity: |        |  |  |   |  |  |  |
|                   | Q1     | Q2   | Q3   | 3   | Q4   |  |  |
|                   | Decode | Read register 'f'  | Proce<br>Data  |   | Vrite to stination   |  |  |

Example: IORWF RESULT, 0, 1

Before Instruction

RESULT = 0x13 W = 0x91

After Instruction

RESULT = 0x13 W = 0x93

| LFSR             | Load FSR  |  |  |  |
|------------------|---|--|--|--|
| Syntax:          | [ label ] LFSR f,k  |  |  |  |
| Operands:        | $0 \le f \le 2$<br>$0 \le k \le 4095$   |  |  |  |
| Operation:       | $k \to FSRf$  |  |  |  |
| Status Affected: | None  |  |  |  |
| Encoding:        | 1110 1110 00ff k <sub>11</sub> kkk<br>1111 0000 k <sub>7</sub> kkk kkkk           |  |  |  |
| Description:     | The 12-bit literal 'k' is loaded into the file select register pointed to by 'f'. |  |  |  |

Words: 2 Cycles: 2

Q Cycle Activity:

|     | Q1   | Q2           | Q3      | Q4            |
|-----|------|--------------|---------|---------------|
| Dec | code | Read literal | Process | Write         |
|     |      | 'k' MSB      | Data    | literal 'k'   |
|     |      |              |         | MSB to        |
|     |      |              |         | FSRfH         |
| Dec | code | Read literal | Process | Write literal |
|     |      | 'k' LSB      | Data    | 'k' to FSRfL  |

Example: LFSR 2, 0x3AB

After Instruction

FSR2H = 0x03FSR2L = 0xAB

| MOVF              | Move f   |        |          |      |  |
|-------------------|--|--------|----------|------|--|
| Syntax:           | [ label ]  | MOVF f | [,d [,a] |      |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |        |          |      |  |
| Operation:        | $f \to \text{dest}$  |        |          |      |  |
| Status Affected:  | N, Z   |        |          |      |  |
| Encoding:         | 0101   | 00da   | ffff     | ffff |  |
| Description:      | The contents of register 'f' are moved to a destination dependent upon the status of 'd'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). Location 'f' can be anywhere in the 256-byte bank. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |        |          |      |  |
| Words:            | 1  |        |          |      |  |
| Cycles:           | 1  |        |          |      |  |
| Q Cycle Activity: |  |        |          |      |  |
| Q1                | Q2   | Q3     | 3        | Q4   |  |

Example: MOVF REG, 0, 0

Read

register 'f'

Process

Data

Write W

Before Instruction

Decode

REG = 0x22 W = 0xFF

After Instruction

REG = 0x22 W = 0x22

MOVFF Move f to f

Syntax: [ label ] MOVFF f<sub>s</sub>,f<sub>d</sub>

Operands:  $0 \le f_{\text{S}} \le 4095 \\ 0 \le f_{\text{d}} \le 4095$ 

Operation:  $(f_s) \rightarrow f_d$ 

Status Affected: None

Encoding: 1st word (source) 2nd word (destin.) 1100 ffff ffff ffff<sub>s</sub>
1111 ffff ffff ffff<sub>d</sub>

Description: The contents of source register  $f_s$  are

moved to destination register ' $f_d$ '. Location of source ' $f_s$ ' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination ' $f_d$ ' can also be anywhere from 000h to

FFFh.

Either source or destination can be W

(a useful special situation). MOVFF is particularly useful for

transferring a data memory location to a peripheral register (such as the transmit

buffer or an I/O port).

The MOVFF instruction cannot use the PCL, TOSU, TOSH or TOSL as the

destination register.

Words: 2 Cycles: 2 (3)

Q Cycle Activity:

| Q1     | Q2                                  | Q3              | Q4                              |
|--------|-------------------------------------|-----------------|---------------------------------|
| Decode | Read<br>register 'f'<br>(src)       | Process<br>Data | No<br>operation                 |
| Decode | No<br>operation<br>No dummy<br>read | No<br>operation | Write<br>register 'f'<br>(dest) |

Example: MOVFF REG1, REG2

Before Instruction

 $\begin{array}{rcl}
\mathsf{REG1} & = & 0x33 \\
\mathsf{REG2} & = & 0x11
\end{array}$ 

After Instruction

 $\begin{array}{rcl} \mathsf{REG1} & = & \mathsf{0x33} \\ \mathsf{REG2} & = & \mathsf{0x33} \end{array}$ 

MOVLB Move Literal to Low Nibble in BSR

Syntax: [label] MOVLB k

 $\begin{tabular}{lll} Operands: & 0 \le k \le 255 \\ Operation: & k \to BSR \\ Status \ Affected: & None \\ \end{tabular}$ 

Encoding: 0000 0001 kkkk kkkk

Description: The 8-bit literal 'k' is loaded into the

Bank Select Register (BSR).

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4             |
|--------|--------------|---------|----------------|
| Decode | Read literal | Process | Write          |
|        | 'k'          | Data    | literal 'k' to |
|        |              |         | BSR            |

Example: MOVLB 5

Before Instruction

BSR register = 0x02

After Instruction

BSR register = 0x05

| MΟ\               | /LW      | Move Lit            | eral to V                                   | V   |    |          |
|-------------------|----------|---------------------|---|-----|----|----------|
| Synta             | ax:      | [ label ]           | MOVLW                                       | k   |    |          |
| Oper              | ands:    | $0 \leq k \leq 255$ |   |     |    |          |
| Operation:        |          | $k\toW$             |   |     |    |          |
| Status Affected:  |          | None                |   |     |    |          |
| Enco              | ding:    | 0000                | 1110  | kkk | ck | kkkk     |
| Desc              | ription: | The eight-          | The eight-bit literal 'k' is loaded into W. |     |    |          |
| Word              | ls:      | 1                   |   |     |    |          |
| Cycle             | es:      | 1                   |   |     |    |          |
| Q Cycle Activity: |          |                     |   |     |    |          |
|                   | Q1       | Q2                  | Q   | 3   |    | Q4       |
|                   | Decode   | Read<br>literal 'k' | Proce<br>Data                               |     | Wr | ite to W |

Example: MOVLW 0x5A

After Instruction W = 0x5A

| MΟ\          | /WF            | Move W t  | o f                                      |                                  |   |  |
|--------------|----------------|---|--|----------------------------------|---|--|
| Synta        | ax:            | [label] N   | 10VWF                                    | f [,a]                           |   |  |
| Oper         | ands:          | $0 \le f \le 255$<br>$a \in [0,1]$  |  |                                  |   |  |
| Oper         | ation:         | $(W) \to f$   |  |                                  |   |  |
| Statu        | s Affected:    | None  |  |                                  |   |  |
| Enco         | ding:          | 0110  | 111a                                     | ffff                             | fffff                                   |  |
| Description: |                | Location 'f'<br>256-byte ba<br>Bank will be<br>BSR value<br>be selected<br>(default). | ank. If 'a'<br>e selecte<br>. If 'a' = 1 | is '0', t<br>d, over<br>, then t | he Access<br>riding the<br>he bank will |  |
| Word         | ls:            | 1   | 1  |                                  |   |  |
| Cycle        | es:            | 1   | 1  |                                  |   |  |
| QC           | ycle Activity: |   |  |                                  |   |  |
|              | Q1             | Q2  | Q3                                       | 1                                | Q4                                      |  |
|              | Decode         | Read register 'f'   | Proce<br>Data                            |                                  | Write register 'f'                      |  |

Example: MOVWF REG, 0

Before Instruction

 $\begin{array}{ccc} W & = & 0x4F \\ REG & = & 0xFF \end{array}$ 

After Instruction

W = 0x4F REG = 0x4F

# MULLW Multiply Literal with W Syntax: [label] MULLW k Operands: $0 \le k \le 255$ Operation: (W) x k $\rightarrow$ PRODH:PRODL Status Affected: None Encoding: 0000 1101 kkkk kkkk Description: An unsigned multiplication is carried

Description:

An unsigned multiplication is carried out between the contents of W and the 8-bit literal 'k'. The 16-bit result is placed in PRODH:PRODL register pair. PRODH contains the high byte. W is unchanged.

None of the Status flags are affected. Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2                  | Q3              | Q4                                    |
|--------|---------------------|-----------------|---------------------------------------|
| Decode | Read<br>literal 'k' | Process<br>Data | Write<br>registers<br>PRODH:<br>PRODL |

Example: MULLW 0xC4

Before Instruction

W = 0xE2 PRODH = ? PRODL = ?

After Instruction

W = 0xE2PRODH = 0xAD PRODL = 0x08

| MULWF            | Multiply W with f   |  |  |  |  |
|------------------|---|--|--|--|--|
| Syntax:          | [ label ] MULWF f [,a]  |  |  |  |  |
| Operands:        | $0 \le f \le 255$<br>$a \in [0,1]$  |  |  |  |  |
| Operation:       | (W) $x (f) \rightarrow PRODH:PRODL$   |  |  |  |  |
| Status Affected: | None  |  |  |  |  |
| Encoding:        | 0000 001a ffff ffff   |  |  |  |  |
|                  | An unsigned multiplication is carried out between the contents of W and the register file location 'f'. The 16-bit result is stored in the PRODH:PRODL register pair. PRODH contains the high byte.  Both W and 'f' are unchanged.  None of the Status flags are affected.  Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). |  |  |  |  |
| Words:           | 1   |  |  |  |  |

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read         | Process | Write     |
|        | register 'f' | Data    | registers |
|        |              |         | PRODH:    |
|        |              |         | PRODL     |

Example: MULWF REG, 1

Before Instruction

W = 0xC4 REG = 0xB5 PRODH = ? PRODL = ?

After Instruction

W = 0xC4 REG = 0xB5 PRODH = 0x8A PRODL = 0x94

| NEGF              | Negate f  |  |  |  |
|-------------------|---|--|--|--|
| Syntax:           | [ label ] NEGF f [,a]   |  |  |  |
| Operands:         | $0 \le f \le 255$<br>$a \in [0,1]$  |  |  |  |
| Operation:        | $(\overline{f}) + 1 \rightarrow f$  |  |  |  |
| Status Affected:  | N, OV, C, DC, Z   |  |  |  |
| Encoding:         | 0110 110a ffff ffff   |  |  |  |
| Description:      | Location 'f' is negated using 2's complement. The result is placed in the data memory location 'f'. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value. |  |  |  |
| Words:            | 1   |  |  |  |
| Cycles:           | 1   |  |  |  |
| Q Cycle Activity: |   |  |  |  |

Q3

Process

Data

Q4

Write

register 'f'

Example: NEGF REG, 1

Before Instruction

Q1

Decode

REG =  $0011 \ 1010 \ [0x3A]$ 

Q2

Read

register 'f'

After Instruction

REG = 1100 0110 [0xC6]

| NOF   | •              | No Operation |        |     |     |         |
|-------|----------------|--------------|--------|-----|-----|---------|
| Synta | ax:            | [ label ]    | NOP    |     |     |         |
| Oper  | ands:          | None         |        |     |     |         |
| Oper  | ation:         | No operati   | on     |     |     |         |
| Statu | s Affected:    | None         |        |     |     |         |
| Enco  | ding:          | 0000         | 0000   | 000 | 0 0 | 0000    |
|       |                | 1111         | xxxx   | XXX | XΣ  | xxxx    |
| Desc  | ription:       | No operati   | on.    |     |     |         |
| Word  | ls:            | 1            |        |     |     |         |
| Cycle | es:            | 1            |        |     |     |         |
| QC    | ycle Activity: |              |        |     |     |         |
|       | Q1             | Q2           | Q3     | 3   |     | Q4      |
|       | Decode         | No           | No     |     |     | No      |
|       |                | operation    | operat | ion | ор  | eration |

Example:

None.

| POP        | Pop Top of Return Stack        |  |  |
|------------|--------------------------------|--|--|
| Syntax:    | [ label ] POP                  |  |  |
| Operands:  | None                           |  |  |
| Operation: | $(TOS) \rightarrow bit bucket$ |  |  |

Status Affected: None Encoding: 0000 0000 0000 0110

Description: The TOS value is pulled off the return stack and is discarded. The TOS value then becomes the previous value that was pushed onto the return stack. This instruction is provided to enable the user to properly manage the return

Words: 1 Cycles:

Q Cycle Activity:

| Q1     | Q2        | Q3      | Q4        |
|--------|-----------|---------|-----------|
| Decode | No        | POP TOS | No        |
|        | operation | value   | operation |

stack to incorporate a software stack.

Example: POP GOTO NEW

Before Instruction

TOS 0031A2h Stack (1 level down)= 014332h

After Instruction

TOS 014332h PC NEW

| PUSH   | ł             | Push Top of Return Stack   |      |     |   |      |
|--------|---------------|--|------|-----|---|------|
| Syntax | <b>(</b> :    | [label] P  | USH  |     |   |      |
| Opera  | nds:          | None   |      |     |   |      |
| Opera  | tion:         | (PC + 2) →   | TOS  |     |   |      |
| Status | Affected:     | None   |      |     |   |      |
| Encod  | ing:          | 0000   | 0000 | 000 | 0 | 0101 |
| Descri | риоп.         | The PC + 2 is pushed onto the top of the return stack. The previous TOS value is pushed down on the stack. This instruction allows implementing a software stack by modifying TOS and then pushing it onto the return stack. |      |     |   |      |
| Words  | :             | 1  |      |     |   |      |
| Cycles | s:            | 1  |      |     |   |      |
| Q Cyc  | cle Activity: |  |      |     |   |      |
| _      | Q1            | Q2   | Q3   |     |   | Q4   |
|        | Decode        | PUSH   | No   |     |   | No   |

Example: PUSH

Before Instruction

TOS 00345Ah PC 000124h

PC + 2 onto

return stack

operation

operation

After Instruction

000126h PC TOS 000126h Stack (1 level down)= 00345Ah

| RCALL            | Relative Call   |  |  |  |
|------------------|---|--|--|--|
| Syntax:          | [ label ] RCALL n   |  |  |  |
| Operands:        | $-1024 \le n \le 1023$  |  |  |  |
| Operation:       | $ (PC) + 2 \rightarrow TOS;  (PC) + 2 + 2n \rightarrow PC $                   |  |  |  |
| Status Affected: | None  |  |  |  |
| Encoding:        | 1101 1nnn nnnn nnnn   |  |  |  |
| Description:     | Subroutine call with a jump up to 1K from the current location. First, return |  |  |  |

from the current location. First, return address (PC + 2) is pushed onto the stack. Then, add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a

two-cycle instruction.

Words: 1 Cycles: 2

Q Cycle Activity:

|   | Q1        | Q2               | Q3              | Q4          |
|---|-----------|------------------|-----------------|-------------|
|   | Decode    | Read literal 'n' | Process<br>Data | Write to PC |
|   |           | Push PC to stack |                 |             |
| Ī | No        | No               | No              | No          |
|   | operation | operation        | operation       | operation   |

Example: HERE RCALL Jump

Before Instruction

PC = Address (HERE)

After Instruction

PC = Address (Jump)
TOS = Address (HERE + 2)

| RESET             | Reset  |       |      |      |
|-------------------|--|-------|------|------|
| Syntax:           | [ label ]  | RESET |      |      |
| Operands:         | None   |       |      |      |
| Operation:        | Reset all registers and flags that are affected by a MCLR Reset.     |       |      |      |
| Status Affected:  | All  |       |      |      |
| Encoding:         | 0000   | 0000  | 1111 | 1111 |
| Description:      | This instruction provides a way to execute a MCLR Reset in software. |       |      | •    |
| Words:            | 1  |       |      |      |
| Cycles:           | 1  |       |      |      |
| Q Cycle Activity: |  |       |      |      |
| Q1                | Q2   | Q3    | 3    | Q4   |

Example: RESET

After Instruction

Decode

Registers = Reset Value Flags\* = Reset Value

Start

Reset

No

operation

No

operation

#### RETFIE Return from Interrupt

Operands:  $s \in [0,1]$ 

Syntax:

Operation:  $(TOS) \rightarrow PC;$ 

 $1 \to \mathsf{GIE}/\mathsf{GIEH} \text{ or } \mathsf{PEIE}/\mathsf{GIEL}$ 

 $\begin{tabular}{l} \mbox{if s = 1} \\ \mbox{(WS)} \rightarrow \mbox{W}; \\ \end{tabular}$ 

 $(STATUSS) \rightarrow STATUS;$  $(BSRS) \rightarrow BSR;$ 

[label] RETFIE [s]

PCLATU, PCLATH are unchanged

Status Affected: GIE/GIEH, PEIE/GIEL.

Encoding: 0000 0000 0001 000s

Description: Return from interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into

the PC. Interrupts are enabled by setting either the high or low priority global interrupt enable bit. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers, W, STATUS and BSR. If 's' = 0, no update of these registers occurs (default).

Words: 1 Cycles: 2

Q Cycle Activity:

| Q1        | Q2        | Q3        | Q4          |
|-----------|-----------|-----------|-------------|
| Decode    | No        | No        | Pop PC      |
|           | operation | operation | from stack  |
|           |           |           | Set GIEH or |
|           |           |           | GIEL        |
| No        | No        | No        | No          |
| operation | operation | operation | operation   |

Example: RETFIE 1

After Interrupt

PC = TOS W = WS BSR = BSRS STATUS = STATUSS

GIE/GIEH, PEIE/GIEL = 1

#### RETLW Return Literal to W

Syntax: [ label ] RETLW k

Operands:  $0 \le k \le 255$ 

Operation:  $k \rightarrow W$ ; (TOS)  $\rightarrow$  PC;

PCLATU, PCLATH are unchanged

Status Affected: None

Encoding: 0000 1100 kkkk kkkk

W is loaded with the eight-bit literal 'k'.
The program counter is loaded from the top of the stack (the return address).
The high address latch (PCLATH)

remains unchanged.

Words: 1
Cycles: 2

Q Cycle Activity:

Description:

| Q1        | Q2          | Q3        | Q4          |
|-----------|-------------|-----------|-------------|
| Decode    | Read        | Process   | Pop PC      |
|           | literal 'k' | Data      | from stack, |
|           |             |           | Write to W  |
| No        | No          | No        | No          |
| operation | operation   | operation | operation   |

#### Example:

```
CALL TABLE ; W contains table ; offset value ; W now has ; table value
```

: TABLE

ADDWF PCL ; W = offset RETLW k0 ; Begin table

RETLW k1 ;

:

RETLW kn ; End of table

Before Instruction

W = 0x07

After Instruction

W = value of kn

| RETURN            | Return from Subroutine  |        |      |      |
|-------------------|---|--------|------|------|
| Syntax:           | [ label ]   | RETURN | [s]  |      |
| Operands:         | s ∈ [0,1]   |        |      |      |
| Operation:        | $\begin{split} &(TOS) \to PC;\\ &if \ s = 1\\ &(WS) \to W;\\ &(STATUSS) \to STATUS;\\ &(BSRS) \to BSR;\\ &PCLATU, \ PCLATH \ are \ unchanged \end{split}$   |        |      |      |
| Status Affected:  | None  |        |      |      |
| Encoding:         | 0000  | 0000   | 0001 | 001s |
| Description:      | Return from subroutine. The stack is popped and the top of the stack (TOS) is loaded into the program counter. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers, W, STATUS and BSR. If 's' = 0, no update of these registers occurs (default). |        |      |      |
| Words:            | 1   |        |      |      |
| Cycles:           | 2   |        |      |      |
| Q Cycle Activity: |   |        |      |      |

| Q1        | Q2        | Q3        | Q4         |
|-----------|-----------|-----------|------------|
| Decode    | No        | Process   | Pop PC     |
|           | operation | Data      | from stack |
| No        | No        | No        | No         |
| operation | operation | operation | operation  |

Example: RETURN

After Interrupt PC = TOS


| RLC   | F              | Rotate L   | Rotate Left f through Carry   |   |  |  |
|-------|----------------|--|---|---|--|--|
| Synta | ax:            | [ label ]  | RLCF  | f [,d [,a]  |  |  |
| Oper  | ands:          | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  | 5   |   |  |  |
| Oper  | ration:        | $(f<7>) \rightarrow 0$   | $(f) \rightarrow dest;$<br>$(f<7>) \rightarrow C;$<br>$(C) \rightarrow dest<0>$         |   |  |  |
| Statu | ıs Affected:   | C, N, Z  |   |   |  |  |
| Enco  | oding:         | 0011   | 01da  | ffff  | ffff   |  |
|       |                | one bit to t  If 'd' is '0', is '1', the r  'f' (default) will be sele value. If 'a selected a | the result<br>esult is sto<br>I. If 'a' is 'o<br>ected, ove<br>' = 1, ther<br>s per the | is placed bred back o', the Accertiding the nake the bank | in W. If 'd'<br>in register<br>cess Bank<br>e BSR<br>will be |  |
| Word  | ds:            | 1  |   |   |  |  |
| Cycle | es:            | 1  |   |   |  |  |
| QC    | ycle Activity: |  |   |   |  |  |
|       | Q1             | Q2   | Q3  |   | Q4   |  |
|       | Decode         | Read register 'f'  | Proces<br>Data  | -   | rite to<br>tination  |  |
|       |                |  |   |   |  |  |

Example: RLCF REG, 0, 0 Before Instruction REG = 1110 0110 After Instruction REG = W = C = 1110 0110

1100 1100

| RLNCF                    | Rotate L   | Rotate Left f (No Carry)  |  |   |
|--------------------------|--|---|--|---|
| Syntax:                  | [ label ]  | RLNCF   | f [,d [,a]   |   |
| Operands:                | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  | 5   |  |   |
| Operation:               | $ (f < n >) \rightarrow 0 $ $ (f < 7 >) \rightarrow 0 $  | dest <n +="" 1:<br="">dest&lt;0&gt;</n>   | >;   |   |
| Status Affected:         | N, Z   |   |  |   |
| Encoding:                | 0100   | 01da  | ffff   | ffff  |
| Description:             | one bit to to placed in No stored back is '0', the According then the both to the place of the p | nts of regis the left. If 'c W. If 'd' is ' k in registe Access Bar the BSR v ank will be alue (defau | d' is '0', th<br>1', the reser 'f' (defank will be<br>ralue. If 'a<br>selected | e result is<br>sult is<br>ault). If 'a'<br>selected,<br>' is '1', |
| Words:                   | 1  |   |  |   |
| Cycles:                  | 1  |   |  |   |
| Q Cycle Activity:        |  |   |  |   |
| Q1                       | Q2   | Q3  |  | Q4  |
| Decode                   | Read<br>register 'f'   | Process<br>Data   |  | rite to<br>tination   |
| Example:  Before Instruc | RLNCF  | REG,  | 1, 0   |   |
| REG                      | = 1010 1   | 1011  |  |   |

0101 0111



After Instruction

REG

| RRNCF            | Rotate Right f (No Carry)   |  |  |  |
|------------------|---|--|--|--|
| Syntax:          | [ label ] RRNCF f [,d [,a]  |  |  |  |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  |  |  |
| Operation:       | $(f) \rightarrow dest;$<br>$(f<0>) \rightarrow dest<7>$   |  |  |  |
| Status Affected: | N, Z  |  |  |  |
| Encoding:        | 0100 00da ffff ffff   |  |  |  |
| Description:     | The contents of register 'f' are rotated one bit to the right. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is |  |  |  |

placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).



Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example 1: RRNCF REG, 1, 0

Before Instruction

REG 1101 0111

After Instruction

REG 1110 1011

Example 2: RRNCF REG, 0, 0

Before Instruction

W REG

1101 0111

After Instruction

W REG 1110 1011 1101 0111

| SETF              | Set f  |  |                                       |                               |
|-------------------|--|--|---------------------------------------|-------------------------------|
| Syntax:           | [ label ] SE   | ETF f[,a                                     | ι]                                    |                               |
| Operands:         | $0 \le f \le 255$ $a \in [0,1]$  | 5  |                                       |                               |
| Operation:        | $FFh \to f$  |  |                                       |                               |
| Status Affected:  | None   |  |                                       |                               |
| Encoding:         | 0110   | 100a   | ffff                                  | ffff                          |
| Description:      | The conte<br>are set to<br>Bank will be<br>BSR value<br>be selecte<br>(default). | FFh. If 'a'<br>be selecte<br>e. If 'a' is 'a | is '0', the ded, overriding, then the | Access<br>ng the<br>bank will |
| Words:            | 1  |  |                                       |                               |
| Cycles:           | 1  |  |                                       |                               |
| Q Cycle Activity: |  |  |                                       |                               |

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: SETF REG,1

Before Instruction

REG 0x5A

After Instruction

REG 0xFF

| SLE   | EP             | Enter Sleep Mode  |                 |      |                |  |
|-------|----------------|---|-----------------|------|----------------|--|
| Synta | ax:            | [ label ]   | [ label ] SLEEP |      |                |  |
| Oper  | ands:          | None  | None            |      |                |  |
| Oper  | ation:         | $\begin{array}{l} \text{O0h} \rightarrow \text{WDT}; \\ \text{0} \rightarrow \underline{\text{WDT}} \text{ postscaler}; \\ \text{1} \rightarrow \overline{\text{TO}}; \\ \text{0} \rightarrow \overline{\text{PD}} \end{array}$ |                 |      |                |  |
| Statu | s Affected:    | TO, PD  |                 |      |                |  |
| Enco  | ding:          | 0000  | 0000            | 0000 | 0011           |  |
| Desc  | ription:       | The Power-Down status bit (PD) is cleared. The Time-out status bit (TO) is set. Watchdog Timer and its postscaler are cleared. The processor is put into Sleep mode with the oscillator stopped.                                |                 |      |                |  |
| Word  | ls:            | 1   |                 |      |                |  |
| Cycle | es:            | 1   |                 |      |                |  |
| Q C   | ycle Activity: |   |                 |      |                |  |
|       | Q1             | Q2  | Q3              |      | Q4             |  |
|       | Decode         | No<br>operation   | Proces<br>Data  | ss   | Go to<br>Sleep |  |

 $\begin{array}{lll} \underline{\text{Example:}} & & \text{SLEEP} \\ & \underline{\text{Before Instruction}} \\ & \underline{\overline{\text{TO}}} & = & ? \\ & \underline{\text{PD}} & = & ? \\ & \\ & \underline{\text{After Instruction}} \\ & \underline{\overline{\text{TO}}} & = & 1 \uparrow \\ & \underline{\text{PD}} & = & 0 \\ \end{array}$ 

† If WDT causes wake-up, this bit is cleared.

| SUBFWB   | Subtrac   | t f from W w  | ith Borrow   |
|--|---|---|--|
| Syntax:  | [ label ]   | SUBFWB f[   | ,d [,a]  |
| Operands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   | 5   |  |
| Operation:   | (W) - (f) -   | $\overline{(C)} \rightarrow dest$   |  |
| Status Affected:   | N, OV, C,   | DC, Z   |  |
| Encoding:  | 0101  | 01da ff   | ff ffff  |
| Description:   | (borrow) f<br>method).<br>in W. If 'd'<br>register 'f'<br>Access Ba<br>riding the<br>the bank v | egister 'f' and C<br>rom W (2's con<br>f 'd' is '0', the r<br>is '1', the resu<br>(default). If 'a'<br>ank will be sele<br>BSR value. If 'a<br>vill be selected<br>e (default). | nplement<br>esult is stored<br>It is stored in<br>is '0', the<br>octed, over-<br>a' is '1', then |
| Words:   | 1   |   |  |
| Cycles:  | 1   |   |  |
| Q Cycle Activity:  |   |   |  |
| Q1   | Q2  | Q3  | Q4   |
| Decode   | Read register 'f'   | Process<br>Data   | Write to destination   |
| Example 1:   | SUBFWB  | REG, 1, 0   | )  |
| Before Instruc<br>REG<br>W<br>C<br>After Instructic<br>REG | = 3<br>= 2<br>= 1   |   |  |
| W  | = 2   |   |  |
| C<br>Z   | = 0<br>= 0  |   |  |
| N  | = 1 ; re  | esult is negative   | е  |
| Example 2:   | SUBFWB  | REG, 0, 0   | )  |
| Before Instruc   |   |   |  |
| REG<br>W   | = 2<br>= 5  |   |  |
| C  | = 1   |   |  |
| After Instructio   | on<br>= 2   |   |  |
| W  | = 3   |   |  |
| C<br>Z   | = 1<br>= 0  |   |  |
| N  | -   | sult is positive  | •  |
| Example 3:   | SUBFWB  | REG, 1, 0   | )  |
| Before Instruc   | tion  |   |  |
| REG  | = 1   |   |  |
| W<br>C   | = 2<br>= 0  |   |  |
| After Instruction  | -   |   |  |
| REG  | = 0   |   |  |
| W<br>C   | = 2<br>= 1  |   |  |
| Z  | = 1 ; re  | sult is zero  |  |
| N  | = 0   |   |  |

| SUBLW                       | Subtract W from Literal                  | SUBWF                  | Subtract W from f  |        |
|-----------------------------|--|------------------------|--|--------|
| Syntax:                     | [ label ] SUBLW k                        | Syntax:                | [ label ] SUBWF f [,d [,a]   |        |
| Operands:                   | $0 \le k \le 255$                        | Operands:              | $0 \le f \le 255$  |        |
| Operation:                  | $k - (W) \rightarrow W$                  |                        | d ∈ [0,1]  |        |
| Status Affected:            | N, OV, C, DC, Z                          |                        | a ∈ [0,1]  |        |
| Encoding:                   | 0000 1000 kkkk kkkk                      | Operation:             | $(f) - (W) \rightarrow dest$   |        |
| Description:                | W is subtracted from the eight-bit       | Status Affected:       | N, OV, C, DC, Z  |        |
| 2 000                       | literal 'k'. The result is placed in W.  | Encoding:              |  | Efff   |
| Words:                      | 1  | Description:           | Subtract W from register 'f' (2's complement method). If 'd' is '0                                 |        |
| Cycles:                     | 1  |                        | result is stored in W. If 'd' is '1',  |        |
| Q Cycle Activity:           |  |                        | result is stored back in register  | 'f'    |
| Q1                          | Q2 Q3 Q4                                 |                        | (default). If 'a' is '0', the Access   |        |
| Decode                      | Read Process Write to W literal 'k' Data |                        | will be selected, overriding the value. If 'a' is '1', then the bank selected as per the BSR value |        |
| Example 1:                  | SUBLW 0x02                               |                        | (default).   |        |
| Before Instruct             | ion                                      | Words:                 | 1  |        |
| W<br>C                      | = 1<br>= ?                               | Cycles:                | 1  |        |
| After Instructio            |  | Q Cycle Activity:      |  |        |
| W                           | = 1                                      | Q1                     | Q2 Q3 C  | Q4     |
| C<br>Z                      | = 1 ; result is positive<br>= 0          | Decode                 |  | e to   |
| N                           | = 0                                      |                        | register 'f' Data destir   | nation |
| Example 2:                  | SUBLW 0x02                               | Example 1:             | SUBWF REG, 1, 0  |        |
| Before Instruct             | ion                                      | Before Instru          |  |        |
| W                           | = 2                                      | REG<br>W               | = 3<br>= 2   |        |
| C<br>After Instructio       | = ?<br>n                                 | С                      | = ?  |        |
| W W                         | = 0                                      | After Instructi<br>REG | on<br>= 1  |        |
| C                           | = 1 ; result is zero                     | W                      | = 1 = 2  |        |
| Z<br>N                      | = 1<br>= 0                               | С                      | = 1 ; result is positive   |        |
|                             |  | Z<br>N                 | = 0<br>= 0   |        |
| Example 3:  Before Instruct | SUBLW 0x02                               | Example 2:             | SUBWF REG, 0, 0  |        |
| W Delote instruct           | = 3                                      | Before Instruc         | , ,  |        |
| С                           | = ?                                      | REG                    | = 2  |        |
| After Instructio            |  | W                      | = 2  |        |
| W                           | = FF ; (2's complement)                  | C                      | = ?  |        |
| C<br>Z                      | = 0 ; result is negative<br>= 0          | After Instructi<br>REG | on<br>= 2  |        |
| N                           | = 1                                      | W                      | = 0  |        |
|                             |  | C                      | = 1 ; result is zero   |        |
|                             |  | Z<br>N                 | = 1<br>= 0   |        |
|                             |  | Example 3:             | SUBWF REG, 1, 0  |        |
|                             |  | Before Instruc         |  |        |
|                             |  | REG                    | ction = 1  |        |
|                             |  | W                      | = 2  |        |
|                             |  | C<br>After Instructi   | = ?  |        |

After Instruction

REG W C Z N FFh ;(2's complement)
2
0 ; result is negative
0

| SUBWFB                             | Subtract \   | W from f witl  | n Borrow       |  |
|------------------------------------|--|--|----------------|--|
| Syntax:                            | [label] S  | UBWFB f [,d  | [,a]           |  |
| Operands:                          | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |                |  |
| Operation:                         | (f) - (W) - (  | $f(f) - (W) - (\overline{C}) \rightarrow dest$   |                |  |
| Status Affected:                   | N, OV, C, D  | C, Z   |                |  |
| Encoding:                          | 0101   | 10da fff   | f ffff         |  |
| Description:                       | from registe<br>If 'd' is '0', th<br>'1', the resul<br>(default). If 'd<br>be selected,<br>'a' is '1', the | Subtract W and the Carry flag (borrow) from register 'f' (2's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default). |                |  |
| Words:                             | 1  |  |                |  |
| Cycles:                            | 1  |  |                |  |
| Q Cycle Activity:                  | _  |  | _              |  |
| Q1<br>Decode                       | Q2<br>Read   | Q3<br>Process  | Q4<br>Write to |  |
| Decode                             | register 'f'   | Data   | destination    |  |
| Example 1:                         | SUBWFB   | REG, 1, 0  |                |  |
| Before Instruc<br>REG<br>W<br>C    | = 0x19<br>= 0x0D<br>= 1  | (0001 100<br>(0000 110   | -              |  |
| After Instruction REG W C Z N      | = 0x0C<br>= 0x0D<br>= 1<br>= 0<br>= 0  | (0000 101<br>(0000 110<br>; result is po   | )1)            |  |
| Example 2:                         | SUBWFB   | REG, 0, 0  |                |  |
| Before Instruc                     | tion   |  |                |  |
| REG<br>W<br>C<br>After Instruction | = 0x1B<br>= 0x1A<br>= 0  | (0001 101<br>(0001 101   |                |  |
| REG<br>W<br>C                      | = 0x1B<br>= 0x00<br>= 1  | (0001 101  | .1)            |  |
| Ž<br>N                             | = 1<br>= 0   | ; result is ze   | ero            |  |
| Example 3:                         | SUBWFB   | REG, 1, 0  |                |  |
| Before Instruc<br>REG<br>W<br>C    | = 0x03<br>= 0x0E<br>= 1  | (0000 001<br>(0000 110   |                |  |
| After Instruction                  | on<br>= 0xF5   | (1111 010  | 00)            |  |
| W<br>C<br>Z<br>N                   | = 0x0E<br>= 0  | ; [2's comp]<br>(0000 110  |                |  |
| Z                                  | = 0<br>= 1   | ; result is ne   | agative        |  |

| SWAPF             | Swap f   |  |  |  |
|-------------------|--|--|--|--|
| Syntax:           | [label] S  | SWAPF  | f [,d [,a]   |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |  |  |
| Operation:        | ,  | $(f<3:0>) \rightarrow dest<7:4>;$<br>$(f<7:4>) \rightarrow dest<3:0>$    |  |  |
| Status Affected:  | None   |  |  |  |
| Encoding:         | 0011   | 10da   | ffff   | ffff   |
| Description:      | The upper of the upper of the exchange of the excess overriding the excess the excess over the | anged. If<br>W. If 'd'<br>gister 'f'<br>Bank wil<br>he BSR<br>nk will be | 'd' is '0', is '1', the (default). If be selected selected | the result<br>result is<br>If 'a' is '0',<br>sted,<br>a' is '1', |
| Words:            | 1  |  |  |  |
| Cycles:           | 1  |  |  |  |
| Q Cycle Activity: |  |  |  |  |
| Q1                | Q2   | Q3   |  | Q4   |
| Decode            | Read register 'f'  | Proce<br>Data  |  | Vrite to stination   |

| Example:          | SW | APF  | REG, | 1, | 0 |
|-------------------|----|------|------|----|---|
| Before Instructi  | on |      |      |    |   |
| REG               | =  | 0x53 |      |    |   |
| After Instruction | 1  |      |      |    |   |
| REG               | =  | 0x35 |      |    |   |

**Table Read TBLRD** 

Svntax: [ label ] TBLRD ( \*; \*+; \*-; +\*)

Operands: None Operation: if TBLRD\*

(Prog Mem (TBLPTR)) → TABLAT; TBLPTR – No Change

if TBLRD\*+

 $(Prog Mem (TBLPTR)) \rightarrow TABLAT;$ 

(TBĽPTR) + 1 → TBĽPTR

if TBLRD\*-

(Prog Mem (TBLPTR))  $\rightarrow$  TABLAT; (TBLPTR)  $-1 \rightarrow$  TBLPTR

if TBLRD+\*

(TBLPTR) + 1  $\rightarrow$  TBLPTR;

(Prog Mem (TBLPTR)) → TABLAT

Status Affected: None

Encoding:

| 0000 | 0000 | 0000 | 10nn |     |
|------|------|------|------|-----|
|      |      |      | nn=0 | *   |
|      |      |      | =1   | *+  |
|      |      |      | =2   | * - |
|      |      |      | =3   | +*  |

Description:

This instruction is used to read the contents of Program Memory (P.M.). To address the program memory, a pointer called Table Pointer (TBLPTR) is used. The TBLPTR (a 21-bit pointer) points to

each byte in the program memory. TBLPTR has a 2-Mbyte address range.

TBLPTR[0] = 0: Least Significant Byte of Program Memory Word

TBLPTR[0] = 1: Most Significant Byte of Program Memory Word

The TBLRD instruction can modify the value of TBLPTR as follows:

· no change

post-increment

post-decrement

pre-increment

Words: Cycles: 2

Q Cycle Activity:

| Q1        | Q2            | Q3        | Q4           |
|-----------|---------------|-----------|--------------|
| Decode    | No            | No        | No           |
|           | operation     | operation | operation    |
| No        | No operation  | No        | No operation |
| operation | (Read Program | operation | (Write       |
|           | Memory)       |           | TABLAT)      |

**TBLRD Table Read (Continued)** 

Example 1: TBLRD \*+ ;

Before Instruction

TABLAT TBLPTR 0x55 0x00A356 MEMORY(0x00A356) 0x34

After Instruction

**TABLAT** 0x34 **TBLPTR** 0x00A357

Example 2: TBLRD +\*;

Before Instruction

**TABLAT** 0xAA TBLPTR 0x01A357 = MEMORY(0x01A357) MEMORY(0x01A358) 0x12 = 0x34 =

After Instruction

TABLAT 0x34TBLPTR 0x01A358

| TBLWT   | Table Write  |  |   | TBLWT  | Table   | Write (Cor                          | ntinued)                                    |                    |
|---|--|--|---|--|---|-------------------------------------|---|--------------------|
| Syntax:   | [ label ] TBLWT ( '  | *; *+; *-; +*  | )   | Words:   | 1   |                                     |   |                    |
| Operands:   | None   |  |   | Cycles:  | 2   |                                     |   |                    |
| Operation:  | if TBLWT*<br>(TABLAT) → Holding<br>TBLPTR – No Chan  |  |   | Q Cycle  | Activity:<br>Q1   | Q2                                  | Q3  |                    |
|   | if TBLWT*+ (TABLAT) $\rightarrow$ Holding (TBLPTR) + 1 $\rightarrow$ TB  |  |   |  | Decode  | No<br>operation                     | No<br>operation                             | O                  |
|   | if TBLWT*-<br>$(TABLAT) \rightarrow Holding$<br>$(TBLPTR) - 1 \rightarrow TB$<br>if TBLWT+*<br>$(TBLPTR) + 1 \rightarrow TB$<br>$(TABLAT) \rightarrow Holding$   | ĹPTŘ<br>LPTR;  |   |  | No<br>operation   | No<br>operation<br>(Read<br>TABLAT) | No<br>operation                             | 0)<br>(1<br>H<br>R |
| Status Affected:  | None   |  |   | Example  | <u>1:</u>   | TBLWT *+                            | -;  |                    |
| Encoding:   | 0000 0000  | 0000   | 11nn<br>nn=0 *<br>=1 *+<br>=2 *-<br>=3 +*   |  | TABLAT TBLPTR HOLDING I (0x00A356) T Instructions                       | REGISTER                            | = 0x55<br>= 0x00A3<br>= 0xFF<br>completion) | 356                |
| Description:  | to determine which of<br>the TABLAT is writter   | s instruction uses the 3 LSBs of TBLPTR<br>letermine which of the 8 holding registers<br>TABLAT is written to. The holding |   |  | TABLAT<br>TBLPTR<br>HOLDING I<br>(0x00A356)                             | REGISTER                            | = 0x55<br>= 0x00A3<br>= 0x55                | 357                |
|   | registers are used to of Program Memory  |  |   | Example  | <u>2:</u>   | TBLWT +*                            | ;   |                    |
|   | Section 5.0 "Flash Program Memory" for additional details on programming Flash memory.)  The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2-MByte address range. The LSB of |  | Memory" for ing Flash points to bry. TBLPTR | Befo   | ore Instruction TABLAT TBLPTR HOLDING I (0x01389A) HOLDING I (0x01389B) | REGISTER                            | = 0x34<br>= 0x0138<br>= 0xFF<br>= 0xFF      | 39A                |
| the TBLPTR selects which byte of the program memory location to access.  TBLPTR[0] = 0: Least Significant Byte of Program Memory Word |  | e of the<br>ccess.<br>cant Byte of   | Afte  | r Instruction<br>TABLAT<br>TBLPTR<br>HOLDING I | (table write o  | ompletion)<br>= 0x34<br>= 0x0138    | 39B   |                    |
|   | TBLPTR[0] = 1: Me<br>Pr<br>The TBLWT instructi   | ogram Me   | mory Word                                   |  | (0x01389A)<br>HOLDING I<br>(0x01389B)                                   | REGISTER                            | = 0xFF<br>= 0x34                            |                    |
|   | value of TBLPTR as   | follows:   |   |  |   |                                     |   |                    |
|   | <ul><li>no change</li><li>post-increment</li></ul>   |  |   |  |   |                                     |   |                    |

post-decrement pre-increment

Q4 No

No operation

(Write to Holding Register)

TSTFSZ Test f, Skip if 0

Syntax: [ label ] TSTFSZ f [,a]

Operands:  $0 \le f \le 255 \\ a \in [0,1]$ 

Operation: skip if f = 0

Status Affected: None

Encoding: 0110 011a fffff ffff

Description: If 'f' = 0, the next instruction, fetched during the current instruction execution is discarded and a NOP is executed, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1',

then the bank will be selected as per

the BSR value (default).

Words: 1
Cycles: 1(2)

Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read         | Process | No        |
|        | register 'f' | Data    | operation |

If skip:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No        | No        | No        |
| operation | operation | operation | operation |

If skip and followed by 2-word instruction:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No        | No        | No        |
| operation | operation | operation | operation |
| No        | No        | No        | No        |
| operation | operation | operation | operation |

Example: HERE TSTFSZ CNT, 1

NZERO : ZERO :

Before Instruction

PC = Address (HERE)

After Instruction

If CNT = 0x00,

PC = Address (ZERO)
If CNT \( \neq 0x00, \)

PC = Address (NZERO)

XORLW Exclusive OR Literal with W

Syntax: [ label ] XORLW k

Operands:  $0 \le k \le 255$ Operation: (W) .XOR.  $k \to W$ 

Status Affected: N, Z

Encoding: 0000 1010 kkkk kkkk

Description: The contents of W are XORed with

the 8-bit literal 'k'. The result is placed

in W.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2          | Q3      | Q4       |  |
|--------|-------------|---------|----------|--|
| Decode | Read        | Process | Write to |  |
|        | literal 'k' | Data    | W        |  |

Example: XORLW 0xAF

Before Instruction W = 0xB5

After Instruction W = 0x1A

Syntax: [ label ] XORWF f [,d [,a]

Operands:  $0 \leq f \leq 255 \\ d \in [0,1]$ 

 $a \in [0,1]$ 

Operation: (W) .XOR. (f)  $\rightarrow$  dest

Status Affected: N, Z

Encoding: 0001 10da ffff ffff

Description: Exclusive OR the contents of W with register 'f'. If 'd' is '0', the result is stored

in W. If 'd' is '1', the result is stored back in the register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per

the BSR value (default).

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example: XORWF REG, 1, 0

Before Instruction

 $\begin{array}{ccc} \mathsf{REG} & = & \mathsf{0xAF} \\ \mathsf{W} & = & \mathsf{0xB5} \end{array}$ 

After Instruction

REG = 0x1A W = 0xB5

#### 26.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM™ Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB C30 C Compiler
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
  - MPLAB dsPIC30 Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB ICE 4000 In-Circuit Emulator
- In-Circuit Debugger
  - MPLAB ICD 2
- Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Development Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration Boards
  - PICDEM™ 1 Demonstration Board
  - PICDEM.net™ Demonstration Board
  - PICDEM 2 Plus Demonstration Board
  - PICDEM 3 Demonstration Board
  - PICDEM 4 Demonstration Board
  - PICDEM 17 Demonstration Board
  - PICDEM 18R Demonstration Board
  - PICDEM LIN Demonstration Board
  - PICDEM USB Demonstration Board
- Evaluation Kits
  - KEELOQ® Evaluation and Programming Tools
  - PICDEM MSC
  - microID® Developer Kits
  - CAN
  - PowerSmart® Developer Kits
  - Analog

#### 26.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit micro-controller market. The MPLAB IDE is a Windows® based application that contains:

- · An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor with color coded context
- A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- · Mouse over variable inspection
- · Extensive on-line help

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - source files (assembly or C)
  - mixed assembly and C
  - machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increasing flexibility and power.

#### 26.2 MPASM Assembler

The MPASM assembler is a full-featured, universal macro assembler for all PICmicro MCUs.

The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM assembler features include:

- · Integration into MPLAB IDE projects
- User defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

## 26.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI C compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

#### 26.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB object librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

#### 26.5 MPLAB C30 C Compiler

The MPLAB C30 C compiler is a full-featured, ANSI compliant, optimizing compiler that translates standard ANSI C programs into dsPIC30F assembly language source. The compiler also supports many command line options and language extensions to take full advantage of the dsPIC30F device hardware capabilities and afford fine control of the compiler code generator.

MPLAB C30 is distributed with a complete ANSI C standard library. All library functions have been validated and conform to the ANSI C library standard. The library includes functions for string manipulation, dynamic memory allocation, data conversion, time-keeping and math functions (trigonometric, exponential and hyperbolic). The compiler provides symbolic information for high-level source debugging with the MPLAB IDE.

#### 26.6 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 compiler uses the assembler to produce it's object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- · Support for the entire dsPIC30F instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- · Flexible macro language
- MPLAB IDE compatibility

#### 26.7 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any pin. The execution can be performed in Single-Step, Execute Until Break or Trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and MPLAB C18 C Compilers, as well as the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent, economical software development tool.

#### 26.8 MPLAB SIM30 Software Simulator

The MPLAB SIM30 software simulator allows code development in a PC hosted environment by simulating the dsPIC30F series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any of the pins.

The MPLAB SIM30 simulator fully supports symbolic debugging using the MPLAB C30 C Compiler and MPLAB ASM30 assembler. The simulator runs in either a Command Line mode for automated tasks, or from MPLAB IDE. This high-speed simulator is designed to debug, analyze and optimize time intensive DSP routines.

## 26.9 MPLAB ICE 2000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 2000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers. Software control of the MPLAB ICE 2000 in-circuit emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE 2000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft® Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 26.10 MPLAB ICE 4000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 4000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for highend PICmicro microcontrollers. Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICD 4000 is a premium emulator system, providing the features of MPLAB ICE 2000, but with increased emulation memory and high-speed performance for dsPIC30F and PIC18XXXX devices. Its advanced emulator features include complex triggering and timing, up to 2 Mb of emulation memory and the ability to view variables in real-time.

The MPLAB ICE 4000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

#### 26.11 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PICmicro MCUs and can be used to develop for these and other PICmicro microcontrollers. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming™ (ICSP™) protocol, offers cost effective in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single-stepping and watching variables, CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real-time. MPLAB ICD 2 also serves as a development programmer for selected PICmicro devices.

## 26.12 PRO MATE II Universal Device Programmer

The PRO MATE II is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features an LCD display for instructions and error messages and a modular detachable socket assembly to support various package types. In Stand-Alone mode, the PRO MATE II device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode.

#### 26.13 MPLAB PM3 Device Programmer

The MPLAB PM3 is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode. MPLAB PM3 connects to the host PC via an RS-232 or USB cable. MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

## 26.14 PICSTART Plus Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus development programmer supports most PICmicro devices up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

#### 26.15 PICDEM 1 PICmicro Demonstration Board

The PICDEM 1 demonstration board demonstrates the capabilities of the PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The sample microcontrollers provided with the PICDEM 1 demonstration board can be programmed with a PRO MATE II device programmer or a PICSTART Plus development programmer. The PICDEM 1 demonstration board can be connected to the MPLAB ICE in-circuit emulator for testing. A prototype area extends the circuitry for additional application components. Features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs.

#### 26.16 PICDEM.net Internet/Ethernet Demonstration Board

The PICDEM.net demonstration board is an Internet/ Ethernet demonstration board using the PIC18F452 microcontroller and TCP/IP firmware. The board supports any 40-pin DIP device that conforms to the standard pinout used by the PIC16F877 or PIC18C452. This kit features a user friendly TCP/IP stack, web server with HTML, a 24L256 Serial EEPROM for Xmodem download to web pages into Serial EEPROM, ICSP/MPLAB ICD 2 interface connector, an Ethernet interface, RS-232 interface and a 16 x 2 LCD display. Also included is the book and CD-ROM "TCP/IP Lean, Web Servers for Embedded Systems," by Jeremy Bentham

#### 26.17 PICDEM 2 Plus Demonstration Board

The PICDEM 2 Plus demonstration board supports many 18, 28 and 40-pin microcontrollers, including PIC16F87X and PIC18FXX2 devices. All the necessary hardware and software is included to run the demonstration programs. The sample microcontrollers provided with the PICDEM 2 demonstration board can be programmed with a PRO MATE II device programmer, PICSTART Plus development programmer, or MPLAB ICD 2 with a Universal Programmer Adapter. The MPLAB ICD 2 and MPLAB ICE in-circuit emulators may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area extends the circuitry for additional application components. Some of the features include an RS-232 interface, a 2 x 16 LCD display, a piezo speaker, an on-board temperature sensor, four LEDs and sample PIC18F452 and PIC16F877 Flash microcontrollers.

#### 26.18 PICDEM 3 PIC16C92X Demonstration Board

The PICDEM 3 demonstration board supports the PIC16C923 and PIC16C924 in the PLCC package. All the necessary hardware and software is included to run the demonstration programs.

### 26.19 PICDEM 4 8/14/18-Pin Demonstration Board

The PICDEM 4 can be used to demonstrate the capabilities of the 8, 14 and 18-pin PIC16XXXX and PIC18XXXX MCUs, including the PIC16F818/819, PIC16F87/88, PIC16F62XA and the PIC18F1320 family of microcontrollers. PICDEM 4 is intended to showcase the many features of these low pin count parts, including LIN and Motor Control using ECCP. Special provisions are made for low-power operation with the supercapacitor circuit and jumpers allow onboard hardware to be disabled to eliminate current draw in this mode. Included on the demo board are provisions for Crystal, RC or Canned Oscillator modes, a five volt regulator for use with a nine volt wall adapter or battery, DB-9 RS-232 interface, ICD connector for programming via ICSP and development with MPLAB ICD 2, 2 x 16 liquid crystal display, PCB footprints for H-Bridge motor driver, LIN transceiver and EEPROM. Also included are: header for expansion, eight LEDs, four potentiometers, three push buttons and a prototyping area. Included with the kit is a PIC16F627A and a PIC18F1320. Tutorial firmware is included along with the User's Guide.

#### 26.20 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. A programmed sample is included. The PRO MATE II device programmer, or the PICSTART Plus development programmer, can be used to reprogram the device for user tailored application development. The PICDEM 17 demonstration board supports program download and execution from external on-board Flash memory. A generous prototype area is available for user hardware expansion.

#### 26.21 PICDEM 18R PIC18C601/801 Demonstration Board

The PICDEM 18R demonstration board serves to assist development of the PIC18C601/801 family of Microchip microcontrollers. It provides hardware implementation of both 8-bit Multiplexed/Demultiplexed and 16-bit Memory modes. The board includes 2 Mb external Flash memory and 128 Kb SRAM memory, as well as serial EEPROM, allowing access to the wide range of memory types supported by the PIC18C601/801.

#### 26.22 PICDEM LIN PIC16C43X Demonstration Board

The powerful LIN hardware and software kit includes a series of boards and three PICmicro microcontrollers. The small footprint PIC16C432 and PIC16C433 are used as slaves in the LIN communication and feature on-board LIN transceivers. A PIC16F874 Flash microcontroller serves as the master. All three microcontrollers are programmed with firmware to provide LIN bus communication.

#### 26.23 PICkit<sup>™</sup> 1 Flash Starter Kit

A complete "development system in a box", the PICkit™ Flash Starter Kit includes a convenient multi-section board for programming, evaluation and development of 8/14-pin Flash PIC® microcontrollers. Powered via USB, the board operates under a simple Windows GUI. The PICkit 1 Starter Kit includes the User's Guide (on CD ROM), PICkit 1 tutorial software and code for various applications. Also included are MPLAB® IDE (Integrated Development Environment) software, software and hardware "Tips 'n Tricks for 8-pin Flash PIC® Microcontrollers" Handbook and a USB interface cable. Supports all current 8/14-pin Flash PIC microcontrollers, as well as many future planned devices.

#### 26.24 PICDEM USB PIC16C7X5 Demonstration Board

The PICDEM USB Demonstration Board shows off the capabilities of the PIC16C745 and PIC16C765 USB microcontrollers. This board provides the basis for future USB products.

## 26.25 Evaluation and Programming Tools

In addition to the PICDEM series of circuits, Microchip has a line of evaluation kits and demonstration software for these products.

- KEELOQ evaluation and programming tools for Microchip's HCS Secure Data Products
- CAN developers kit for automotive network applications
- Analog design boards and filter design software
- PowerSmart battery charging evaluation/ calibration kits
- IrDA® development kit
- microID development and rfLab<sup>TM</sup> development software
- SEEVAL® designer kit for memory evaluation and endurance calculations
- PICDEM MSC demo boards for Switching mode power supply, high-power IR driver, delta sigma ADC and flow rate sensor

Check the Microchip web page and the latest Product Selector Guide for the complete list of demonstration and evaluation kits.

NOTES:

#### 27.0 ELECTRICAL CHARACTERISTICS

#### Absolute Maximum Ratings(†)

| Ambient temperature under bias                                    | 40°C to +125°C       |
|---|----------------------|
| Storage temperature   | 65°C to +150°C       |
| Voltage on any pin with respect to Vss (except VDD, MCLR and RA4) | 0.3V to (VDD + 0.3V) |
| Voltage on VDD with respect to Vss                                | 0.3V to +5.5V        |
| Voltage on MCLR with respect to Vss (Note 2)                      | 0V to +13.25V        |
| Voltage on RA4 with respect to Vss                                | 0V to +8.5V          |
| Total power dissipation (Note 1)                                  | 1.0W                 |
| Maximum current out of Vss pin                                    | 300 mA               |
| Maximum current into VDD pin                                      | 250 mA               |
| Input clamp current, IiK (VI < 0 or VI > VDD)                     | ±20 mA               |
| Output clamp current, lok (Vo < 0 or Vo > VDD)                    | ±20 mA               |
| Maximum output current sunk by any I/O pin                        | 25 mA                |
| Maximum output current sourced by any I/O pin                     | 25 mA                |
| Maximum current sunk by all ports                                 | 200 mA               |
| Maximum current sourced by all ports                              | 200 mA               |

- **Note 1:** Power dissipation is calculated as follows: Pdis = VDD x {IDD  $\Sigma$  IOH} +  $\Sigma$  {(VDD VOH) x IOH} +  $\Sigma$ (VOL x IOL)
  - 2: Voltage spikes below Vss at the MCLR/VPP pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100Ω should be used when applying a "low" level to the MCLR/VPP pin, rather than pulling this pin directly to Vss.

† NOTICE: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.







FIGURE 27-2: PIC18LF6X2X/8X2X VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)



#### 27.1 DC Characteristics: Supply Voltage

PIC18F6X2X/8X2X (Industrial, Extended) PIC18LF6X2X/8X2X (Industrial)

| PIC18LF6<br>(Indus | X2X/8X2X<br>trial)         |  |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial   |      |      |  |  |  |  |  |
|--------------------|----------------------------|--|------|---|------|------|--|--|--|--|--|
| PIC18F6X<br>(Indus | (2X/8X2X<br>strial, Extend | ded)   |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |      |      |  |  |  |  |  |
| Param<br>No.       | Symbol                     | Characteristic   | Min  | Min Typ Max Units Conditions  |      |      |  |  |  |  |  |
| D001               | VDD                        | Supply Voltage   |      |   |      |      |  |  |  |  |  |
|                    |                            | PIC18LF6X2X/8X2X   | 2.0  | _   | 5.5  | V    |  |  |  |  |  |
|                    |                            | PIC18F6X2X/8X2X  | 4.2  | _   | 5.5  | V    |  |  |  |  |  |
| D001A              | AVDD                       | Analog Supply Voltage  | -0.3 | _   | +0.3 | V    |  |  |  |  |  |
| D002               | VDR                        | RAM Data Retention<br>Voltage <sup>(1)</sup>                     | 1.5  | _   | _    | V    |  |  |  |  |  |
| D003               | VPOR                       | VDD Start Voltage<br>to ensure internal<br>Power-on Reset signal | _    | _   | 0.7  | V    | See Section 3.1 "Power-on Reset (POR)" for details |  |  |  |  |
| D004               | SVDD                       | VDD Rise Rate<br>to ensure internal<br>Power-on Reset signal     | 0.05 | _   | _    | V/ms | See Section 3.1 "Power-on Reset (POR)" for details |  |  |  |  |
| D005               | VBOR                       | Brown-out Reset Voltage  |      |   |      |      |  |  |  |  |  |
|                    |                            | BORV1:BORV0 = 11   | 1.96 | _   | 2.18 | V    |  |  |  |  |  |
|                    |                            | BORV1:BORV0 = 10   | 2.64 |   | 2.92 | V    |  |  |  |  |  |
|                    |                            | BORV1:BORV0 = 01   | 4.11 | _   | 4.55 | V    |  |  |  |  |  |
|                    |                            | BORV1:BORV0 = 00   | 4.41 | _   | 4.87 | V    |  |  |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: This is the limit to which VDD can be lowered in Sleep mode or during a device Reset without losing RAM data.

# 27.2 DC Characteristics: Power-Down and Supply Current PIC18F6X2X/8X2X (Industrial, Extended)

PIC18LF6X2X/8X2X (Industrial)

| PIC18LF      | 6X2X/8X2X<br>strial)                    |     | •   | rating Co            | onditions (unless otherwise stated $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for indust          | •                           |  |  |  |
|--------------|---|-----|-----|----------------------|--|-----------------------------|--|--|--|
|              | X2X/8X2X<br>strial, Extended)           |     | •   | rating Co<br>erature | onditions (unless otherwise stated -40°C $\leq$ TA $\leq$ +85°C for indust -40°C $\leq$ TA $\leq$ +125°C for exter | rial                        |  |  |  |
| Param<br>No. | Device                                  | Тур | Max | Units                | Conditions   |                             |  |  |  |
|              | Power-Down Current (IPD) <sup>(1)</sup> |     |     |                      |  |                             |  |  |  |
|              | PIC18LF6X2X/8X2X                        | 0.2 | 1   | μΑ                   | -40°C  | .,                          |  |  |  |
|              |   | 0.2 | 1   | μΑ                   | +25°C  | VDD = 2.0V,<br>(Sleep mode) |  |  |  |
|              |   | 5.0 | 10  | μΑ                   | +85°C  | (Gloop meda)                |  |  |  |
|              | PIC18LF6X2X/8X2X                        | 0.4 | 1   | μΑ                   | -40°C  | .,                          |  |  |  |
|              |   | 0.4 | 1   | μΑ                   | +25°C  | VDD = 3.0V,<br>(Sleep mode) |  |  |  |
|              |   |     | 18  | μΑ                   | +85°C  | (Gloop meda)                |  |  |  |
|              | All devices                             | 0.7 | 2   | μΑ                   | -40°C  | \/ 5 0\/                    |  |  |  |
|              |   | 0.7 | 2   | μΑ                   | +25°C  | VDD = 5.0V,<br>(Sleep mode) |  |  |  |
|              |   | 15  | 32  | μΑ                   | +85°C  | (Siespillods)               |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- **4:** The band gap reference is a shared resource used by both BOR and LVD modules. Enabling both modules will consume less than the specified sum current of the modules.

# 27.2 DC Characteristics: Power-Down and Supply Current PIC18F6X2X/8X2X (Industrial, Extended) PIC18LF6X2X/8X2X (Industrial) (Continued)

|              | 6X2X/8X2X<br>strial)                  |     | rd Oper              |       |           | ss otherwise stated)<br>Ā ≤ +85°C for industri                       |                                |  |
|--------------|---------------------------------------|-----|----------------------|-------|-----------|--|--------------------------------|--|
|              | X2X/8X2X<br>strial, Extended)         |     | ird Oper<br>ing temp |       | -40°C ≤ T | ss otherwise stated)  ¬A ≤ +85°C for industri ¬A ≤ +125°C for extend | al                             |  |
| Param<br>No. | Device                                | Тур | Max                  | Units |           | Condition  | ons                            |  |
|              | Supply Current (IDD) <sup>(2,3)</sup> |     |                      |       |           |  |                                |  |
| D010         | PIC18LF6X2X/8X2X                      | 300 | 500                  | μΑ    | -40°C     |  |                                |  |
|              |                                       | 300 | 500                  | μА    | +25°C     | VDD = 2.0V   |                                |  |
|              |                                       | 850 | 1000                 | μА    | +85°C     |  |                                |  |
|              | PIC18LF6X2X/8X2X                      | 500 | 900                  | μΑ    | -40°C     |  | F                              |  |
|              |                                       | 500 | 900                  | μА    | +25°C     | VDD = 3.0V   | Fosc = 1 MHz,<br>EC oscillator |  |
|              |                                       | 1   | 1.5                  | mA    | +85°C     |  |                                |  |
|              | All devices                           | 1   | 2                    | mA    | -40°C     |  |                                |  |
|              |                                       | 1   | 2                    | mA    | +25°C     | VDD = 5.0V   |                                |  |
|              |                                       | 1.3 | 3                    | mA    | +85°C     |  |                                |  |
|              | PIC18LF6X2X/8X2X                      | 1   | 2                    | mA    | -40°C     |  |                                |  |
|              |                                       | 1   | 2                    | mA    | +25°C     | VDD = 2.0V   |                                |  |
|              |                                       | 1.5 | 2.5                  | mA    | +85°C     |  |                                |  |
|              | PIC18LF6X2X/8X2X                      | 1.5 | 2                    | mA    | -40°C     |  | Face (MIL)                     |  |
|              |                                       | 1.5 | 2                    | mA    | +25°C     | VDD = 3.0V   | Fosc = 4 MHz,<br>EC oscillator |  |
|              |                                       | 2   | 2.5                  | mA    | +85°C     |  | LO oddinator                   |  |
|              | All devices                           | 3   | 5                    | mA    | -40°C     |  |                                |  |
|              |                                       | 3   | 5                    | mA    | +25°C     | VDD = 5.0V   |                                |  |
|              |                                       | 4   | 6                    | mA    | +85°C     |  |                                |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in  $k\Omega$ .
- 4: The band gap reference is a shared resource used by both BOR and LVD modules. Enabling both modules will consume less than the specified sum current of the modules.

#### 27.2 DC Characteristics: Power-Down and Supply Current

PIC18F6X2X/8X2X (Industrial, Extended)
PIC18LF6X2X/8X2X (Industrial) (Continued)

|              | 6X2X/8X2X<br>strial)                  |     | rd Oper            |       |            | s otherwise stated<br>\( \leq +85°C \) for indust                                    |                 |  |  |  |  |
|--------------|---------------------------------------|-----|--------------------|-------|------------|--|-----------------|--|--|--|--|
|              | X2X/8X2X<br>strial, Extended)         |     | rd Oper<br>ng temp |       | -40°C ≤ TA | s otherwise stated $A \le +85^{\circ}$ C for indust $A \le +125^{\circ}$ C for exter | rial            |  |  |  |  |
| Param<br>No. | Device                                | Тур | Max                | Units |            | Condit   | ions            |  |  |  |  |
|              | Supply Current (IDD) <sup>(2,3)</sup> |     |                    |       |            |  |                 |  |  |  |  |
|              | PIC18F6X2X/8X2X                       | 13  | 27                 | mA    | -40°C      |  |                 |  |  |  |  |
|              |                                       | 15  | 27                 | mA    | +25°C      | VDD = 4.2V   |                 |  |  |  |  |
|              |                                       | 19  | 29                 | mA    | +85°C      |  | Fosc = 25 MHz,  |  |  |  |  |
|              | PIC18F6X2X/8X2X                       | 17  | 31                 | mA    | -40°C      |  | EC oscillator   |  |  |  |  |
|              |                                       | 21  | 31                 | mA    | +25°C      | VDD = 5.0V   |                 |  |  |  |  |
|              |                                       | 23  | 34                 | mA    | +85°C      |  |                 |  |  |  |  |
|              | PIC18F6X2X/8X2X                       | 20  | 34                 | mA    | -40°C      |  |                 |  |  |  |  |
|              |                                       | 24  | 34                 | mA    | +25°C      | VDD = 4.2V   | Fosc = 40 MHz,  |  |  |  |  |
|              |                                       | 29  | 44                 | mA    | +85°C      |  |                 |  |  |  |  |
|              | PIC18F6X2X/8X2X                       | 28  | 46                 | mA    | -40°C      |  | EC oscillator   |  |  |  |  |
|              |                                       | 33  | 46                 | mA    | +25°C      | VDD = 5.0V   |                 |  |  |  |  |
|              |                                       | 40  | 51                 | mA    | +85°C      |  |                 |  |  |  |  |
| D014         | PIC18LF6X2X/8X2X                      | 27  | 45                 | μΑ    | -10°C      |  |                 |  |  |  |  |
|              |                                       | 30  | 50                 | μΑ    | +25°C      | VDD = 2.0V   |                 |  |  |  |  |
|              |                                       | 32  | 54                 | μΑ    | +70°C      |  |                 |  |  |  |  |
|              | PIC18LF6X2X/8X2X                      | 33  | 55                 | μΑ    | -10°C      | _  | Fosc = 32 kHz,  |  |  |  |  |
|              |                                       | 36  | 60                 | μΑ    | +25°C      | VDD = 3.0V   | Timer1 as clock |  |  |  |  |
|              |                                       | 39  | 65                 | μΑ    | +70°C      |  |                 |  |  |  |  |
|              | All devices                           | 75  | 125                | μΑ    | -10°C      | _  |                 |  |  |  |  |
|              |                                       | 90  | 150                | μΑ    | +25°C      | VDD = 5.0V   |                 |  |  |  |  |
|              |                                       | 113 | 188                | μΑ    | +70°C      |  |                 |  |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

 $\underline{\mathsf{OSC1}} = \mathsf{external} \; \mathsf{square} \; \mathsf{wave}, \; \mathsf{from} \; \mathsf{rail}\text{-}\mathsf{to}\text{-}\mathsf{rail}; \; \mathsf{all} \; \mathsf{I/O} \; \mathsf{pins} \; \mathsf{tri}\text{-}\mathsf{stated}, \; \mathsf{pulled} \; \mathsf{to} \; \mathsf{VDD};$ 

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- **4:** The band gap reference is a shared resource used by both BOR and LVD modules. Enabling both modules will consume less than the specified sum current of the modules.

# 27.2 DC Characteristics: Power-Down and Supply Current PIC18F6X2X/8X2X (Industrial, Extended) PIC18LF6X2X/8X2X (Industrial) (Continued)

| PIC18LF6<br>(Indus | 6X2X/8X2X<br>strial)              |           | rd Oper<br>ng temp |          |                 | s otherwise stated<br>≤ +85°C for indust                        |                        |  |  |
|--------------------|-----------------------------------|-----------|--------------------|----------|-----------------|---|------------------------|--|--|
|                    | X2X/8X2X<br>strial, Extended)     |           | rd Oper<br>ng temp |          | -40°C ≤ TA      | s otherwise stated<br>≤ +85°C for indust<br>≤ +125°C for extent | rial                   |  |  |
| Param<br>No.       | Device                            | Тур       | Max                | Units    |                 | Condit  | ions                   |  |  |
|                    | Module Differential Currer        | nts (∆lw  | DT, ∆lBO           | R, ∆ILVD | , ΔIOSCB, ΔIAD) |   |                        |  |  |
| D022               | Watchdog Timer                    | <1        | 2.0                | μΑ       | -40°C           |   |                        |  |  |
| $(\Delta I WDT)$   |                                   | <1        | 2                  | μΑ       | +25°C           |   | VDD = 2.0V             |  |  |
|                    |                                   | 5         | 20                 | μΑ       | +85°C           |   |                        |  |  |
|                    |                                   | 3         | 10                 | μА       | -40°C           |   |                        |  |  |
|                    |                                   | 3         | 20                 | μА       | +25°C           |   | VDD = 3.0V             |  |  |
|                    |                                   | 10        | 35                 | μА       | +85°C           |   |                        |  |  |
|                    |                                   | 12        | 25                 | μА       | -40°C           |   |                        |  |  |
|                    |                                   | 15        | 35                 | μΑ       | +25°C           |   | VDD = 5.0V             |  |  |
|                    |                                   | 20        | 50                 | μΑ       | +85°C           |   |                        |  |  |
| D022A              | Brown-out Reset <sup>(4)</sup>    | 55        | 115                | μΑ       | -40°C to +85°C  | VDD = 3.0V  |                        |  |  |
| (∆lbor)            |                                   | 105       | 175                | μΑ       | -40°C to +85°C  |   | VDD = 5.0V             |  |  |
| D022B              | Low-Voltage Detect <sup>(4)</sup> | 45        | 125                | μΑ       | -40°C to +85°C  |   | VDD = 2.0V             |  |  |
| (∆ILVD)            |                                   | 45        | 150                | μΑ       | -40°C to +85°C  |   | VDD = 3.0V             |  |  |
|                    |                                   | 45        | 225                | μΑ       | -40°C to +85°C  |   | VDD = 5.0V             |  |  |
| D025               | Timer1 Oscillator                 | 20        | 27                 | μΑ       | -10°C           |   |                        |  |  |
| (∆loscb)           |                                   | 20        | 30                 | μΑ       | +25°C           | VDD = 2.0V  | 32 kHz on Timer1       |  |  |
|                    |                                   | 25        | 35                 | μΑ       | +70°C           |   |                        |  |  |
|                    |                                   | 22        | 60                 | μΑ       | -10°C           |   |                        |  |  |
|                    |                                   | 22        | 65                 | μΑ       | +25°C           | VDD = 3.0V  | 32 kHz on Timer1       |  |  |
|                    |                                   | 25        | 75                 | μΑ       | +70°C           |   |                        |  |  |
|                    |                                   | 30        | 75                 | μΑ       | -10°C           |   |                        |  |  |
|                    |                                   | 30        | 85                 | μА       | +25°C           | VDD = 5.0V  | 32 kHz on Timer1       |  |  |
|                    |                                   | 35        | 100                | μΑ       | +70°C           |   |                        |  |  |
| D026               | A/D Converter                     | <1        | 2                  | μА       | +25°C           | VDD = 2.0V  |                        |  |  |
| $(\Delta I A D)$   |                                   | <1        | 2                  | μА       | +25°C           | VDD = 3.0V  | A/D on, not converting |  |  |
|                    |                                   | <1        | 2                  | μА       | +25°C           | VDD = 5.0V  |                        |  |  |
| _eaend:            | Shading of rows is to assi        | ct in roa | dahility           | •        |                 |   |                        |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

 $\frac{\mathsf{OSC1}}{\mathsf{MCLR}} = \mathsf{external}$  square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;  $\frac{\mathsf{MCLR}}{\mathsf{MCLR}} = \mathsf{VDD}$ ; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: The band gap reference is a shared resource used by both BOR and LVD modules. Enabling both modules will consume less than the specified sum current of the modules.

# 27.3 DC Characteristics: PIC18F6X2X/8X2X (Industrial, Extended) PIC18LF6X2X/8X2X (Industrial)

| DC CHA       | ARACTER | ISTICS                                 |                 | erature -40°C | $\leq$ TA $\leq$ | nless otherwise stated)<br>+85°C for industrial<br>+125°C for extended |
|--------------|---------|--|-----------------|---------------|------------------|--|
| Param<br>No. | Symbol  | Characteristic                         | Min             | Max           | Units            | Conditions   |
|              | VIL     | Input Low Voltage                      |                 |               |                  |  |
|              |         | I/O ports:                             |                 |               |                  |  |
| D030         |         | with TTL buffer                        | Vss             | 0.15 VDD      | V                | VDD < 4.5V   |
| D030A        |         |  | _               | 0.8           | V                | $4.5V \le VDD \le 5.5V$  |
| D031         |         | with Schmitt Trigger buffer            | Vss             | 0.2 VDD       | V                |  |
|              |         | RC3 and RC4                            | Vss             | 0.3 VDD       | V                |  |
| D032         |         | MCLR                                   | Vss             | 0.2 VDD       | V                |  |
| D033         |         | OSC1                                   | Vss             | 0.3 VDD       | V                | HS, HS+PLL modes   |
| D033A        |         | OSC1                                   | Vss             | 0.2 VDD       | V                | RC, EC modes   |
| D033B        |         | OSC1                                   | Vss             | 0.3           | V                | XT, LP modes   |
| D034         |         | T1OSI                                  | Vss             | 0.3           | V                |  |
|              | VIH     | Input High Voltage                     |                 |               |                  |  |
|              |         | I/O ports:                             |                 |               |                  |  |
| D040         |         | with TTL buffer                        | 0.25 VDD + 0.8V | VDD           | V                | VDD < 4.5V   |
| D040A        |         |  | 2.0             | VDD           | V                | $4.5V \le VDD \le 5.5V$  |
| D041         |         | with Schmitt Trigger buffer            | 0.8 VDD         | VDD           | V                |  |
|              |         | RC3 and RC4                            | 0.7 Vdd         | VDD           | V                |  |
| D042         |         | MCLR, OSC1 (EC mode)                   | 0.8 VDD         | VDD           | V                |  |
| D043         |         | OSC1                                   | 0.7 VDD         | VDD           | V                | HS, HS+PLL modes   |
| D043A        |         | OSC1                                   | 0.8 VDD         | VDD           | V                | EC mode  |
| D043B        |         | OSC1                                   | 0.9 VDD         | VDD           | V                | RC mode <sup>(1)</sup>   |
| D043C        |         | OSC1                                   | 1.6             | VDD           | V                | XT, LP modes   |
| D044         |         | T13CKI                                 | 1.6             | VDD           | V                |  |
|              | lı∟     | Input Leakage Current <sup>(2,3)</sup> |                 |               |                  |  |
| D060         |         | I/O ports                              | _               | ±1            | μА               | Vss ≤ VPIN ≤ VDD,<br>Pin at high-impedance                             |
| D061         |         | MCLR                                   | _               | ±5            | μΑ               | VSS ≤ VPIN ≤ VDD   |
| D063         |         | OSC1                                   | _               | ±5            | μΑ               | VSS ≤ VPIN ≤ VDD   |
|              | IPU     | Weak Pull-up Current                   |                 |               |                  |  |
| D070         | IPURB   | PORTB weak pull-up current             | 50              | 400           | μΑ               | VDD = 5V, VPIN = VSS   |

- **Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro<sup>®</sup> device be driven with an external clock while in RC mode.
  - 2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
  - 3: Negative current is defined as current sourced by the pin.
  - 4: Parameter is characterized but not tested.

# 27.3 DC Characteristics: PIC18F6X2X/8X2X (Industrial, Extended) PIC18LF6X2X/8X2X (Industrial) (Continued)

| DC CHA              | RACTER            | RISTICS                                 | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |     |       |   |  |  |
|---------------------|-------------------|---|--|-----|-------|---|--|--|
| Param<br>No.        | Symbol            | Characteristic                          | Min  | Max | Units | Conditions  |  |  |
|                     | Vol               | Output Low Voltage                      |  |     |       |   |  |  |
| D080                |                   | I/O ports                               | _  | 0.6 | V     | IOL = $8.5 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+85^{\circ}\text{C}$  |  |  |
| D080A               |                   |   | _  | 0.6 | V     | IOL = $7.0 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+125^{\circ}\text{C}$ |  |  |
| D083                |                   | OSC2/CLKO<br>(RC mode)                  | _  | 0.6 | V     | IOL = $1.6 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+85^{\circ}\text{C}$  |  |  |
| D083A               |                   |   | _  | 0.6 | V     | IOL = $1.2 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+125^{\circ}\text{C}$ |  |  |
|                     | Vон               | Output High Voltage <sup>(3)</sup>      |  |     |       |   |  |  |
| D090                |                   | I/O ports                               | VDD - 0.7  | _   | V     | IOH = $-3.0$ mA, VDD = $4.5$ V, $-40$ °C to $+85$ °C  |  |  |
| D090A               |                   |   | VDD - 0.7  | _   | V     | IOH = $-2.5$ mA, VDD = $4.5$ V, $-40$ °C to $+125$ °C   |  |  |
| D092                |                   | OSC2/CLKO<br>(RC mode)                  | VDD - 0.7  | _   | V     | IOH = $-1.3$ mA, VDD = $4.5$ V, $-40$ °C to $+85$ °C  |  |  |
| D092A               |                   |   | VDD - 0.7  | _   | V     | IOH = $-1.0$ mA, VDD = $4.5$ V, $-40$ °C to $+125$ °C   |  |  |
| D150                | Vod               | Open-Drain High Voltage                 | _  | 8.5 | V     | RA4 pin   |  |  |
|                     |                   | Capacitive Loading Specs on Output Pins |  |     |       |   |  |  |
| D100 <sup>(4)</sup> | Cosc <sub>2</sub> | OSC2 pin                                | _  | 15  | pF    | In XT, HS and LP modes when external clock is used to drive OSC1                                |  |  |
| D101                | Сю                | All I/O pins and OSC2<br>(in RC mode)   | _  | 50  | pF    | To meet the AC Timing Specifications  |  |  |
| D102                | Св                | SCL, SDA                                | _  | 400 | pF    | In I <sup>2</sup> C™ mode   |  |  |

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro<sup>®</sup> device be driven with an external clock while in RC mode.

- 2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
- 3: Negative current is defined as current sourced by the pin.
- 4: Parameter is characterized but not tested.

#### **TABLE 27-1: COMPARATOR SPECIFICATIONS**

| Operatin     | Operating Conditions: 3.0V < VDD < 5.5V, -40°C < TA < +125°C (unless otherwise stated) |  |     |      |            |          |                                     |  |  |  |
|--------------|--|--|-----|------|------------|----------|-------------------------------------|--|--|--|
| Param<br>No. | Sym  | Characteristics                        | Min | Тур  | Max        | Units    | Comments                            |  |  |  |
| D300         | VIOFF  | Input Offset Voltage                   |     | ±5.0 | ±10        | mV       |                                     |  |  |  |
| D301         | VICM   | Input Common Mode Voltage              | 0   | _    | VDD - 1.5  | V        |                                     |  |  |  |
| D302         | CMRR   | Common Mode Rejection Ratio            | 55  | _    | _          | dB       |                                     |  |  |  |
| 300<br>300A  | TRESP  | Response Time <sup>(1)</sup>           | _   | 150  | 400<br>600 | ns<br>ns | PIC18F6X2X/8X2X<br>PIC18LF6X2X/8X2X |  |  |  |
| 301          | TMC2OV   | Comparator Mode Change to Output Valid | _   | _    | 10         | μs       |                                     |  |  |  |

Note 1: Response time measured with one comparator input at (VDD – 1.5)/2 while the other input transitions from Vss to VDD.

#### TABLE 27-2: VOLTAGE REFERENCE SPECIFICATIONS

| Operating   | Operating Conditions: 3.0V < VDD < 5.5V, -40°C < TA < +125°C (unless otherwise stated) |                              |        |     |        |       |          |  |  |  |
|-------------|--|------------------------------|--------|-----|--------|-------|----------|--|--|--|
| Spec<br>No. | Sym  | Characteristics              | Min    | Тур | Max    | Units | Comments |  |  |  |
| D310        | VRES   | Resolution                   | VDD/24 |     | VDD/32 | LSb   |          |  |  |  |
| D311        | VRAA   | Absolute Accuracy            | _      | _   | 1/2    | LSb   |          |  |  |  |
| D312        | VRUR   | Unit Resistor Value (R)      | _      | 2k  | _      | Ω     |          |  |  |  |
| 310         | TSET   | Settling Time <sup>(1)</sup> | _      | _   | 10     | μs    |          |  |  |  |

**Note 1:** Settling time measured while VRR = 1 and VR<3:0> transitions from 0000 to 1111.

FIGURE 27-3: LOW-VOLTAGE DETECT CHARACTERISTICS




TABLE 27-3: LOW-VOLTAGE DETECT CHARACTERISTICS

| LOW-V        | LOW-VOLTAGE DETECT CHARACTERISTICS |                    |               |      |      | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |       |            |  |  |
|--------------|------------------------------------|--------------------|---------------|------|------|--|-------|------------|--|--|
| Param<br>No. | Symbol                             | Characteris        | stic          | Min  | Тур† | Max  | Units | Conditions |  |  |
| D420         | VLVD                               | LVD Voltage on VDD | LVV = 0000    | _    | _    | _  | V     |            |  |  |
|              | transition high-to-low             | LVV = 0001         | 1.96          | 2.06 | 2.16 | V  |       |            |  |  |
|              |                                    | LVV = 0010         | 2.16          | 2.27 | 2.38 | V  |       |            |  |  |
|              |                                    | LVV = 0011         | 2.35          | 2.47 | 2.59 | V  |       |            |  |  |
|              |                                    | LVV = 0100         | 2.46          | 2.58 | 2.71 | V  |       |            |  |  |
|              |                                    |                    | LVV = 0101    | 2.64 | 2.78 | 2.92   | V     |            |  |  |
|              |                                    |                    | LVV = 0110    | 2.75 | 2.89 | 3.03   | V     |            |  |  |
|              |                                    |                    | LVV = 0111    | 2.95 | 3.10 | 3.26   | V     |            |  |  |
|              |                                    |                    | LVV = 1000    | 3.24 | 3.41 | 3.58   | V     |            |  |  |
|              |                                    |                    | LVV = 1001    | 3.43 | 3.61 | 3.79   | V     |            |  |  |
|              |                                    |                    | LVV = 1010    | 3.53 | 3.72 | 3.91   | V     |            |  |  |
|              |                                    |                    | LVV = 1011    | 3.72 | 3.92 | 4.12   | V     |            |  |  |
|              |                                    |                    | LVV = 1100    | 3.92 | 4.13 | 4.33   | V     |            |  |  |
|              |                                    |                    | LVV = 1101    | 4.11 | 4.33 | 4.55   | V     |            |  |  |
|              |                                    |                    | LVV = 1110    | 4.41 | 4.64 | 4.87   | V     |            |  |  |
| D423         | VBG                                | Band Gap Reference | /oltage Value |      | 1.22 | _  | V     |            |  |  |

 $<sup>\</sup>dagger$  Production tested at TAMB = 25°C. Specifications over temp. limits ensured by characterization.

TABLE 27-4: MEMORY PROGRAMMING REQUIREMENTS

| DC Cha       | ıracteris | stics  |             |             | ature -40° | $C \leq TA$ | unless otherwise stated)<br>≤ +85°C for industrial<br>≤ +125°C for extended |
|--------------|-----------|--|-------------|-------------|------------|-------------|---|
| Param<br>No. | Sym       | Characteristic   | Min         | Тур†        | Max        | Units       | Conditions  |
|              |           | Internal Program Memory<br>Programming Specifications            |             |             |            |             |   |
| D110         | VPP       | Voltage on MCLR/VPP pin  | 9.00        | _           | 13.25      | V           | (Note 2)  |
| D112         | IPP       | Current into MCLR/VPP pin  | _           | _           | 300        | μΑ          |   |
| D113         | IDDP      | Supply Current during<br>Programming                             | _           | _           | 1.0        | mA          |   |
|              |           | Data EEPROM Memory   |             |             |            |             |   |
| D120         | ED        | Byte Endurance   | 100K<br>10K | 1M<br>100K  | _          | E/W<br>E/W  | -40°C to +85°C<br>-40°C to +125°C   |
| D121         | VDRW      | VDD for Read/Write   | VMIN        | _           | 5.5        | V           | Using EECON to read/write VMIN = Minimum operating voltage                  |
| D122         | TDEW      | Erase/Write Cycle Time   | _           | 4           | _          | ms          |   |
| D123         | TRETD     | Characteristic Retention   | 40          | _           | _          | Year        | Provided no other specifications are violated                               |
| D124         | TREF      | Number of Total Erase/Write Cycles before Refresh <sup>(1)</sup> | 1M<br>100K  | 10M<br>1M   | _<br>_     | E/W<br>E/W  | -40°C to +85°C<br>-40°C to +125°C   |
|              |           | Program Flash Memory   |             |             |            |             |   |
| D130         | ЕР        | Cell Endurance   | 10K<br>1K   | 100K<br>10K | _<br>_     | E/W<br>E/W  | -40°C to +85°C<br>-40°C to +125°C   |
| D131         | VPR       | VDD for Read   | VMIN        | _           | 5.5        | V           | VMIN = Minimum operating voltage  |
| D132         | VIE       | VDD for Block Erase  | 4.5         | _           | 5.5        | V           | Using ICSP™ port  |
| D132A        | Viw       | VDD for Externally Timed Erase or Write                          | 4.5         | _           | 5.5        | V           | Using ICSP port   |
| D132B        | VPEW      | VDD for Self-Timed Write and Row Erase                           | VMIN        | _           | 5.5        | V           | VMIN = Minimum operating voltage  |
| D133         | TIE       | ICSP Block Erase Cycle Time                                      | _           | 4           | _          | ms          | VDD > 4.5V  |
| D133A        | Tıw       | ICSP Erase or Write Cycle Time (externally timed)                | 1           | _           | _          | ms          | VDD > 4.5V  |
| D133A        | Tıw       | Self-Timed Write Cycle Time                                      | _           | 2           | _          | ms          |   |
| D134         | TRETD     | Characteristic Retention   | 40          | _           | _          | Year        | Provided no other specifications are violated                               |

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Refer to Section 7.8 "Using the Data EEPROM" for a more detailed discussion on data EEPROM endurance.

<sup>2:</sup> Required only if Low-Voltage Programming is disabled.

#### 27.4 AC (Timing) Characteristics

#### 27.4.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created following one of the following formats:

| 1. TppS2pp               | oS .                             | 3. Tcc:st | (I <sup>2</sup> C specifications only) |
|--------------------------|----------------------------------|-----------|--|
| 2. TppS                  |                                  | 4. Ts     | (I <sup>2</sup> C specifications only) |
| Т                        |                                  |           |  |
| F                        | Frequency                        | Т         | Time                                   |
| Lowercase                | letters (pp) and their meanings: |           |  |
| рр                       |                                  |           |  |
| СС                       | CCP1                             | osc       | OSC1                                   |
| ck                       | CLKO                             | rd        | RD                                     |
| cs                       | <del>CS</del>                    | rw        | RD or WR                               |
| di                       | SDI                              | sc        | SCK                                    |
| do                       | SDO                              | SS        | SS                                     |
| dt                       | Data in                          | tO        | TOCKI                                  |
| io                       | I/O port                         | t1        | T1CKI                                  |
| mc                       | MCLR                             | wr        | WR                                     |
| Uppercase                | letters and their meanings:      |           |  |
| S                        |                                  |           |  |
| F                        | Fall                             | Р         | Period                                 |
| Н                        | High                             | R         | Rise                                   |
| 1                        | Invalid (High-impedance)         | V         | Valid                                  |
| L                        | Low                              | Z         | High-impedance                         |
| I <sup>2</sup> C only    |                                  |           |  |
| AA                       | output access                    | High      | High                                   |
| BUF                      | Bus free                         | Low       | Low                                    |
| TCC:ST (I <sup>2</sup> C | specifications only)             |           |  |
| CC                       |                                  |           |  |
| HD                       | Hold                             | SU        | Setup                                  |
| ST                       |                                  |           |  |
| DAT                      | DATA input hold                  | STO       | Stop condition                         |
| STA                      | Start condition                  |           |  |

#### 27.4.2 TIMING CONDITIONS

**AC CHARACTERISTICS** 

The temperature and voltages specified in Table 27-5 apply to all timing specifications, unless otherwise noted. Figure 27-4 specifies the load conditions for the timing specifications.

#### TABLE 27-5: TEMPERATURE AND VOLTAGE SPECIFICATIONS - AC

Standard Operating Conditions (unless otherwise stated) Operating temperature  $-40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C}$  for industrial


-40°C ≤ TA ≤ +125°C for extended

Operating voltage VDD range as described in DC spec Section 27.1 and

Section 27.3.

LF parts operate for industrial temperatures only.

#### FIGURE 27-4: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



#### 27.4.3 TIMING DIAGRAMS AND SPECIFICATIONS

FIGURE 27-5: EXTERNAL CLOCK TIMING (ALL MODES EXCEPT PLL)




TABLE 27-6: EXTERNAL CLOCK TIMING REQUIREMENTS

| Param.<br>No. | Symbol        | Characteristic                            | Min       | Max       | Units | Conditions  |
|---------------|---------------|---|-----------|-----------|-------|---|
| 1A            | Fosc          | External CLKI Frequency <sup>(1)</sup>    | DC        | 25        | MHz   | EC, ECIO <sup>(2)</sup> (-40°C to +85°C)                  |
|               |               |   | DC        | 40        | MHz   | EC, ECIO  |
|               |               |   | DC        | 25        | MHz   | EC, ECIO (+85°C to +125°C)                                |
|               |               | Oscillator Frequency <sup>(1)</sup>       | DC        | 4         | MHz   | RC oscillator   |
|               |               |   | 0.1       | 4         | MHz   | XT oscillator   |
|               |               |   | 4         | 25        | MHz   | HS oscillator   |
|               |               |   | 4         | 10        | MHz   | HS + PLL oscillator                                       |
|               |               |   | 4         | 6.25      | MHz   | HS + PLL oscillator <sup>(2)</sup>                        |
|               |               |   | 5         | 33        | kHz   | LP Oscillator mode  |
| 1             | Tosc          | External CLKI Period <sup>(1)</sup>       | 25        | _         | ns    | EC, ECIO  |
|               |               |   | 40        | _         | ns    | EC, ECIO <sup>(2)</sup>                                   |
|               |               |   | 40        | _         | ns    | EC, ECIO (+85°C to +125°C)                                |
|               |               | Oscillator Period <sup>(1)</sup>          | 250       | _         | ns    | RC oscillator   |
|               |               |   | 250       | 10,000    | ns    | XT oscillator   |
|               |               |   | 40        | 250       | ns    | HS oscillator   |
|               |               |   | 100       | 250       | ns    | HS + PLL oscillator<br>HS + PLL oscillator <sup>(2)</sup> |
|               |               |   | 160<br>30 | 250       | ns    | LP oscillator   |
| 2             | Tcy           | Instruction Cycle Time <sup>(1)</sup>     | 100       | 200       | μs    | Tcy = 4/Fosc  |
| 3             |               | ·   |           |           | ns    | XT oscillator   |
| ٥             | TosL,<br>TosH | External Clock in (OSC1) High or Low Time | 30        | _         | ns    |   |
|               | . 55. 1       |   | 2.5<br>10 | _         | μs    | LP oscillator HS oscillator                               |
| 4             | TooP          | External Clock in (OSC1)                  | 10        | 20        | ns    |   |
| 4             | TosR,<br>TosF | Rise or Fall Time                         | _         | 20        | ns    | XT oscillator   |
|               |               | Taco or rain rinno                        |           | 50<br>7.5 | ns    | LP oscillator   |
|               |               |   | _         | 7.5       | ns    | HS oscillator   |

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period for all configurations except PLL. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "max." cycle time limit is "DC" (no clock) for all devices.

2: PIC18F6525/6621/8525/8621 devices using external memory interface.

TABLE 27-7: PLL CLOCK TIMING SPECIFICATIONS (VDD = 4.2 TO 5.5V)

| Param. No. | Sym                             | Characteristic                | Min | Typ† | Max | Units | Conditions |
|------------|---------------------------------|-------------------------------|-----|------|-----|-------|------------|
|            | Fosc Oscillator Frequency Range |                               | 4   | _    | 10  | MHz   | HS mode    |
|            | Fsys                            | On-Chip Vco System Frequency  |     | _    | 40  | MHz   | HS mode    |
|            | t <sub>rc</sub>                 | PLL Start-up Time (Lock Time) | _   | _    | 2   | ms    |            |
|            | ΔCLK CLKO Stability (Jitter)    |                               | -2  | _    | +2  | %     |            |

<sup>†</sup> Data in "Typ" column is at 5V, 25°C, unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 27-6: CLKO AND I/O TIMING




TABLE 27-8: CLKO AND I/O TIMING REQUIREMENTS

| Param<br>No. | Symbol   | Characteris                      | stic             | Min           | Тур          | Max | Units    | Conditions |
|--------------|----------|----------------------------------|------------------|---------------|--------------|-----|----------|------------|
| 10           | TosH2ckL | OSC1 ↑ to CLKO ↓                 |                  | _             | 75           | 200 | ns       | (Note 1)   |
| 11           | TosH2ckH | OSC1 ↑ to CLKO ↑                 |                  | _             | 75           | 200 | ns       | (Note 1)   |
| 12           | TckR     | CLKO Rise Time                   | _                | 35            | 100          | ns  | (Note 1) |            |
| 13           | TckF     | CLKO Fall Time                   | _                | 35            | 100          | ns  | (Note 1) |            |
| 14           | TckL2ioV | CLKO ↓ to Port Out Valid         | _                | _             | 0.5 Tcy + 20 | ns  | (Note 1) |            |
| 15           | TioV2ckH | Port In Valid before CLKO ↑      |                  | 0.25 Tcy + 25 | _            | _   | ns       | (Note 1)   |
| 16           | TckH2ioI | Port In Hold after CLKO ↑        |                  | 0             | _            | _   | ns       | (Note 1)   |
| 17           | TosH2ioV | OSC1 ↑ (Q1 cycle) to Port O      | _                | 50            | 150          | ns  |          |            |
| 18           | TosH2iol | OSC1 ↑ (Q2 cycle) to Port        | PIC18F6X2X/8X2X  | 100           | _            | _   | ns       |            |
| 18A          |          | Input Invalid (I/O in hold time) | PIC18LF6X2X/8X2X | 200           | _            | _   | ns       |            |
| 19           | TioV2osH | Port Input Valid to OSC1 ↑ (I/C  | in setup time)   | 0             | _            | _   | ns       |            |
| 20           | TioR     | Port Output Rise Time            | PIC18F6X2X/8X2X  | _             | 10           | 25  | ns       |            |
| 20A          |          |                                  | PIC18LF6X2X/8X2X | _             | _            | 60  | ns       |            |
| 21           | TioF     | Port Output Fall Time            | PIC18F6X2X/8X2X  | _             | 10           | 25  | ns       |            |
| 21A          |          |                                  | PIC18LF6X2X/8X2X | _             | _            | 60  | ns       |            |
| 22†          | TINP     | INT pin High or Low Time         |                  | TCY           | _            | _   | ns       |            |
| 23†          | TRBP     | RB7:RB4 Change INT High o        | TCY              | _             | _            | ns  |          |            |
| 24†          | TRCP     | RC7:RC4 Change INT High of       | or Low Time      | 20            |              |     | ns       |            |

<sup>†</sup> These parameters are asynchronous events not related to any internal clock edges.

Note 1: Measurements are taken in RC mode, where CLKO output is 4 x Tosc.





TABLE 27-9: PROGRAM MEMORY READ TIMING REQUIREMENTS

| Param.<br>No | Symbol   | Characteristics   | Min            | Тур       | Max            | Units |
|--------------|----------|---|----------------|-----------|----------------|-------|
| 150          | TadV2alL | Address Out Valid to ALE ↓ (address setup time)                           | 0.25 Tcy - 10  | _         | _              | ns    |
| 151          | TalL2adl | ALE ↓ to Address Out Invalid (address hold time)                          | 5              | _         | _              | ns    |
| 155          | TalL2oeL | ALE ↓ to OE ↓   | 10             | 0.125 Tcy | _              | ns    |
| 160          | TadZ2oeL | AD high-Z to $\overline{OE} \downarrow$ (bus release to $\overline{OE}$ ) | 0              | _         | _              | ns    |
| 161          | ToeH2adD | OE ↑ to AD Driven   | 0.125 Tcy - 5  | _         | _              | ns    |
| 162          | TadV2oeH | LS Data Valid before OE ↑ (data setup time)                               | 20             | _         | _              | ns    |
| 163          | ToeH2adl | OE ↑ to Data In Invalid (data hold time)                                  | 0              |           | _              | ns    |
| 164          | TalH2alL | ALE Pulse Width   | _              | 0.25 Tcy  | _              | ns    |
| 165          | ToeL2oeH | OE Pulse Width  | 0.5 Tcy - 5    | 0.5 Tcy   | _              | ns    |
| 166          | TalH2alH | ALE ↑ to ALE ↑ (cycle time)   | 40 ns          | Tcy       | _              | ns    |
| 167          | Tacc     | Address Valid to Data Valid   | 0.75 Tcy - 25  | _         | _              | ns    |
| 168          | Toe      | OE ↓ to Data Valid  |                | _         | 0.5 Tcy - 25   | ns    |
| 169          | TalL2oeH | ALE ↓ to <del>OE</del> ↑  | 0.625 Tcy - 10 | _         | 0.625 Tcy + 10 | ns    |
| 171          | TalH2csL | Chip Enable Active to ALE $\downarrow$                                    | _              | _         | 10             | ns    |
| 171A         | TubL2oeH | AD Valid to Chip Enable Active  | 0.25 Tcy - 20  | _         | _              | ns    |

FIGURE 27-8: PROGRAM MEMORY WRITE TIMING DIAGRAM



**TABLE 27-10: PROGRAM MEMORY WRITE TIMING REQUIREMENTS** 

| Param.<br>No | Symbol   | Characteristics   | Min           | Тур     | Max | Units |
|--------------|----------|---|---------------|---------|-----|-------|
| 150          | TadV2alL | Address Out Valid to ALE ↓ (address setup time)         | 0.25 Tcy - 10 | _       | _   | ns    |
| 151          | TalL2adl | ALE ↓ to Address Out Invalid (address hold time)        | 5             | _       | _   | ns    |
| 153          | TwrH2adl | WRn ↑ to Data Out Invalid (data hold time)              | 5             | _       | _   | ns    |
| 154          | TwrL     | WRn Pulse Width   | 0.5 Tcy - 5   | 0.5 Tcy | _   | ns    |
| 156          | TadV2wrH | Data Valid before WRn ↑ (data setup time)               | 0.5 Tcy - 10  | _       | _   | ns    |
| 157          | TbsV2wrL | Byte Select Valid before WRn ↓ (byte select setup time) | 0.25 TcY      | _       | _   | ns    |
| 157A         | TwrH2bsI | WRn ↑ to Byte Select Invalid (byte select hold time)    | 0.125 Tcy - 5 | _       | _   | ns    |
| 166          | TalH2alH | ALE ↑ to ALE ↑ (cycle time)                             | _             | Tcy     | _   | ns    |
| 171          | TalH2csL | Chip Enable Active to ALE ↓                             | _             | _       | 10  | ns    |
| 171A         | TubL2oeH | AD Valid to Chip Enable Active                          | 0.25 Tcy - 20 | _       | _   | ns    |

FIGURE 27-9: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 27-10: BROWN-OUT RESET TIMING




TABLE 27-11: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET REQUIREMENTS

| Param.<br>No. | Symbol | Characteristic   | Min       | Тур | Max       | Units | Conditions            |
|---------------|--------|--|-----------|-----|-----------|-------|-----------------------|
| 30            | TmcL   | MCLR Pulse Width (low)                                   | 2         | _   | _         | μs    |                       |
| 31            | TWDT   | Watchdog Timer Time-out Period (no postscaler)           | 7         | 18  | 33        | ms    |                       |
| 32            | Tost   | Oscillation Start-up Timer Period                        | 1024 Tosc | _   | 1024 Tosc | _     | Tosc = OSC1 period    |
| 33            | TPWRT  | Power-up Timer Period                                    | 28        | 72  | 132       | ms    |                       |
| 34            | Tioz   | I/O High-impedance from MCLR Low or Watchdog Timer Reset | _         | 2   | _         | μs    |                       |
| 35            | TBOR   | Brown-out Reset Pulse Width                              | 200       | _   | _         | μs    | VDD ≤ BVDD (see D005) |
| 36            | TIRVST | Time for Internal Reference<br>Voltage to become stable  | _         | 20  | 50        | μs    |                       |
| 37            | TLVD   | Low-Voltage Detect Pulse Width                           | 200       | _   | _         | μs    | VDD ≤ VLVD            |

FIGURE 27-11: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS




TABLE 27-12: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

| Param.<br>No. | Symbol    |                           | Characteri         | stic                         | Min  | Max    | Units | Conditions                               |
|---------------|-----------|---------------------------|--------------------|------------------------------|--|--------|-------|--|
| 40            | Tt0H      | T0CKI High                | Pulse Width        | No prescaler                 | 0.5 Tcy + 20                                 | _      | ns    |  |
|               |           |                           |                    | With prescaler               | 10   | _      | ns    |  |
| 41            | Tt0L      | T0CKI Low I               | Pulse Width        | No prescaler                 | 0.5 Tcy + 20                                 | _      | ns    |  |
|               |           |                           |                    | With prescaler               | 10   | _      | ns    |  |
| 42            | Tt0P      | T0CKI Perio               | d                  | No prescaler                 | Tcy + 10                                     | _      | ns    |  |
|               |           | -                         |                    | With prescaler               | Greater of:<br>20 ns or <u>TCY + 40</u><br>N | _      | ns    | N = prescale<br>value<br>(1, 2, 4,, 256) |
| 45            | Tt1H      | T13CKI                    | Synchronous, r     | no prescaler                 | 0.5 Tcy + 20                                 | _      | ns    |  |
|               |           | High Time                 | Synchronous,       | PIC18F6X2X/8X2X              | 10   | _      | ns    |  |
|               |           |                           | with prescaler     | PIC18LF6X2X/8X2X             | 25   | _      | ns    |  |
|               |           |                           | Asynchronous       | PIC18F6X2X/8X2X              | 30   | _      | ns    |  |
|               |           |                           |                    | PIC18LF6X2X/8X2X             | 50   | _      | ns    |  |
| 46            | Tt1L      | T13CKI<br>Low Time        | Synchronous, r     | no prescaler                 | 0.5 Tcy + 5                                  | _      | ns    |  |
|               |           |                           | Synchronous,       | PIC18F6X2X/8X2X              | 10   | _      | ns    |  |
|               |           |                           | with prescaler     | PIC18LF6X2X/8X2X             | 25   | _      | ns    |  |
|               |           |                           | Asynchronous       | PIC18F6X2X/8X2X              | 30   | _      | ns    |  |
|               |           |                           |                    | PIC18LF6X2X/8X2X             | TBD  | TBD    | ns    |  |
| 47            | Tt1P      | T13CKI<br>Input Period    | Synchronous        |                              | Greater of:<br>20 ns or <u>TCY + 40</u><br>N | _      | ns    | N = prescale<br>value (1, 2, 4, 8)       |
|               |           |                           | Asynchronous       |                              | 60   | _      | ns    |  |
|               | Ft1       | T13CKI Osc                | illator Input Fred | Ilator Input Frequency Range |  | 50     | kHz   |  |
| 48            | Tcke2tmrl | Delay from E<br>Increment | external T13CKI    | Clock Edge to Timer          | 2 Tosc                                       | 7 Tosc |       |  |

**Legend:** TBD = To Be Determined

FIGURE 27-12: CAPTURE/COMPARE/PWM TIMINGS (ALL ECCP/CCP MODULES)




TABLE 27-13: CAPTURE/COMPARE/PWM REQUIREMENTS (ALL ECCP/CCP MODULES)

| Param.<br>No. | Symbol | Characteri             |                  | istic            | Min             | Max | Units | Conditions                        |
|---------------|--------|------------------------|------------------|------------------|-----------------|-----|-------|-----------------------------------|
| 50            | TccL   |                        |                  | er               | 0.5 Tcy + 20    | _   | ns    |                                   |
|               |        | Low Time               | With             | PIC18F6X2X/8X2X  | 10              | _   | ns    |                                   |
|               |        | prescaler              | PIC18LF6X2X/8X2X | 20               | _               | ns  |       |                                   |
| 51            | TccH   | CCPx Input No prescale |                  | er               | 0.5 Tcy + 20    | _   | ns    |                                   |
|               | H      | High Time              | With             | PIC18F6X2X/8X2X  | 10              | _   | ns    |                                   |
|               |        |                        | prescaler        | PIC18LF6X2X/8X2X | 20              | _   | ns    |                                   |
| 52            | TccP   | CCPx Input Per         | iod              |                  | 3 Tcy + 40<br>N | _   | ns    | N = prescale<br>value (1,4 or 16) |
| 53            | TccR   | CCPx Output Ri         | se Time          | PIC18F6X2X/8X2X  | _               | 25  | ns    |                                   |
|               |        |                        |                  | PIC18LF6X2X/8X2X | _               | 45  | ns    |                                   |
| 54            | TccF   | CCPx Output Fall Time  |                  | PIC18F6X2X/8X2X  | _               | 25  | ns    |                                   |
|               |        |                        |                  | PIC18LF6X2X/8X2X | _               | 45  | ns    |                                   |

FIGURE 27-13: PARALLEL SLAVE PORT TIMING (PIC18F8525/8621)




TABLE 27-14: PARALLEL SLAVE PORT REQUIREMENTS (PIC18F8525/8621)

| Param.<br>No. | Symbol   | Characteristic                                 |                    | Min      | Max      | Units    | Conditions           |
|---------------|----------|--|--------------------|----------|----------|----------|----------------------|
| 62            | TdtV2wrH | Data In Valid before WR ↑ or CS ↑ (setup time) |                    | 20<br>25 | _        | ns<br>ns | Extended Temp. range |
| 63            | TwrH2dtl | WR ↑ or CS ↑ to Data–in                        | PIC18F6X2X/8X2X    | 20       | _        | ns       |                      |
|               |          | Invalid (hold time)                            | PIC18LF6X2X/8X2X   | 35       | _        | ns       |                      |
| 64            | TrdL2dtV | RD ↓ and CS ↓ to Data–o                        | ut Valid           | _        | 80<br>90 | ns<br>ns | Extended Temp. range |
| 65            | TrdH2dtl | RD ↑ or CS ↓ to Data–out Invalid               |                    | 10       | 30       | ns       | 7 7 7 7 7            |
| 66            | TibfINH  | Inhibit of the IBF Flag bit bWR ↑ or CS ↑      | peing cleared from | _        | 3 Tcy    |          |                      |




FIGURE 27-14: EXAMPLE SPI™ MASTER MODE TIMING (CKE = 0)

TABLE 27-15: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 0)

| Param.<br>No. | Symbol                | Characteri                               | stic             | Min           | Max | Units    | Conditions |
|---------------|-----------------------|--|------------------|---------------|-----|----------|------------|
| 70            | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Inpu              | t                | Tcy           | _   | ns       |            |
| 71            | TscH                  | SCK Input High Time                      | Continuous       | 1.25 Tcy + 30 | _   | ns       |            |
| 71A           |                       | (Slave mode)                             | Single Byte      | 40            | _   | ns       | (Note 1)   |
| 72            | TscL                  | SCK Input Low Time                       | Continuous       | 1.25 Tcy + 30 | _   | ns       |            |
| 72A           |                       | (Slave mode)                             | Single Byte      | 40            | _   | ns       | (Note 1)   |
| 73            | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input             | 100              | _             | ns  |          |            |
| 73A           | Тв2в                  | Last Clock Edge of Byte 1 to t<br>Byte 2 | 1.5 Tcy + 40     |               | ns  | (Note 2) |            |
| 74            | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to           | SCK Edge         | 100           | _   | ns       |            |
| 75            | TdoR                  | SDO Data Output Rise Time                | PIC18F6X2X/8X2X  | _             | 25  | ns       |            |
|               |                       |  | PIC18LF6X2X/8X2X | _             | 45  | ns       |            |
| 76            | TdoF                  | SDO Data Output Fall Time                |                  | _             | 25  | ns       |            |
| 78            | TscR                  | SCK Output Rise Time                     | PIC18F6X2X/8X2X  | _             | 25  | ns       |            |
|               |                       | (Master mode)                            | PIC18LF6X2X/8X2X | _             | 45  | ns       | ]          |
| 79            | TscF                  | SCK Output Fall Time (Master mode)       |                  | _             | 25  | ns       |            |
| 80            | TscH2doV,             | SDO Data Output Valid after              | PIC18F6X2X/8X2X  | _             | 50  | ns       |            |
|               | TscL2doV              | SCK Edge                                 | PIC18LF6X2X/8X2X | _             | 100 | ns       | ]          |

FIGURE 27-15: EXAMPLE SPI™ MASTER MODE TIMING (CKE = 1)




TABLE 27-16: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 1)

| Param.<br>No. | Symbol                | Characteri                               | stic             | Min           | Max | Units    | Conditions |
|---------------|-----------------------|--|------------------|---------------|-----|----------|------------|
| 71            | TscH                  | SCK Input High Time                      | Continuous       | 1.25 Tcy + 30 |     | ns       |            |
| 71A           |                       | (Slave mode)                             | Single Byte      | 40            | _   | ns       | (Note 1)   |
| 72            | TscL                  | SCK Input Low Time                       | Continuous       | 1.25 Tcy + 30 | _   | ns       |            |
| 72A           |                       | (Slave mode)                             | Single Byte      | 40            | _   | ns       | (Note 1)   |
| 73            | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input             | 100              | _             | ns  |          |            |
| 73A           | Тв2в                  | Last Clock Edge of Byte 1 to t<br>Byte 2 | 1.5 Tcy + 40     | _             | ns  | (Note 2) |            |
| 74            | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to SCK Edge  |                  | 100           | _   | ns       |            |
| 75            | TdoR                  | SDO Data Output Rise Time                | PIC18F6X2X/8X2X  | _             | 25  | ns       |            |
|               |                       |  | PIC18LF6X2X/8X2X |               | 45  | ns       |            |
| 76            | TdoF                  | SDO Data Output Fall Time                |                  | _             | 25  | ns       |            |
| 78            | TscR                  | SCK Output Rise Time                     | PIC18F6X2X/8X2X  | _             | 25  | ns       |            |
|               |                       | (Master mode)                            | PIC18LF6X2X/8X2X |               | 45  | ns       |            |
| 79            | TscF                  | SCK Output Fall Time (Maste              | r mode)          | _             | 25  | ns       |            |
| 80            | TscH2doV,             | SDO Data Output Valid after              | PIC18F6X2X/8X2X  | _             | 50  | ns       |            |
|               | TscL2doV              | SCK Edge                                 | PIC18LF6X2X/8X2X |               | 100 | ns       |            |
| 81            | TdoV2scH,<br>TdoV2scL | SDO Data Output Setup to So              | CK Edge          | Tcy           |     | ns       |            |




FIGURE 27-16: **EXAMPLE SPI™ SLAVE MODE TIMING (CKE = 0)** 

TABLE 27-17: EXAMPLE SPI™ MODE REQUIREMENTS (SLAVE MODE TIMING, CKE = 0)

| Param.<br>No. | Symbol                | Characteristic                             |   | Min           | Max | Units    | Conditions |
|---------------|-----------------------|--|---|---------------|-----|----------|------------|
| 70            | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Input               | Tcy                                     | _             | ns  |          |            |
| 71            | TscH                  | SCK Input High Time                        |   |               | _   | ns       |            |
| 71A           |                       | (Slave mode)                               | Single Byte                             | 40            | _   | ns       | (Note 1)   |
| 72            | TscL                  | SCK Input Low Time                         | Continuous                              | 1.25 Tcy + 30 | _   | ns       |            |
| 72A           |                       | (Slave mode)                               | Single Byte                             | 40            | _   | ns       | (Note 1)   |
| 73            | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input to SCK E      | 100                                     | _             | ns  |          |            |
| 73A           | Тв2в                  | Last Clock Edge of Byte 1 to the First Clo | 1.5 Tcy + 40                            | _             | ns  | (Note 2) |            |
| 74            | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to SCK Ed      | Hold Time of SDI Data Input to SCK Edge |               |     | ns       |            |
| 75            | TdoR                  | SDO Data Output Rise Time                  | PIC18F6X2X/8X2X                         | _             | 25  | ns       |            |
|               |                       |  | PIC18F6X2X/8X2X                         |               | 45  | ns       |            |
| 76            | TdoF                  | SDO Data Output Fall Time                  |   | _             | 25  | ns       |            |
| 77            | TssH2doZ              | SS ↑ to SDO Output High-impedance          |   | 10            | 50  | ns       |            |
| 78            | TscR                  | SCK Output Rise Time (Master mode)         | PIC18F6X2X/8X2X                         | _             | 25  | ns       |            |
|               |                       |  | PIC18F6X2X/8X2X                         |               | 45  | ns       |            |
| 79            | TscF                  | SCK Output Fall Time (Master mode)         |   | _             | 25  | ns       |            |
| 80            | TscH2doV,             | SDO Data Output Valid after SCK            | PIC18F6X2X/8X2X                         | _             | 50  | ns       |            |
|               | TscL2doV              | Edge                                       | PIC18F6X2X/8X2X                         |               | 100 | ns       |            |
| 83            | TscH2ssH,<br>TscL2ssH | SS ↑ after SCK Edge                        |   | 1.5 Tcy + 40  | _   | ns       |            |

FIGURE 27-17: EXAMPLE SPI™ SLAVE MODE TIMING (CKE = 1)




TABLE 27-18: EXAMPLE SPI™ SLAVE MODE REQUIREMENTS (CKE = 1)

| Param<br>No. | Symbol                | Characterist                         | ic                      | Min           | Max | Units | Conditions |
|--------------|-----------------------|--------------------------------------|-------------------------|---------------|-----|-------|------------|
| 70           | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Input         | Tcy                     |               | ns  |       |            |
| 71           | TscH                  | SCK Input High Time                  | Continuous              | 1.25 Tcy + 30 | 1   | ns    |            |
| 71A          |                       | (Slave mode)                         | Single Byte             | 40            | -   | ns    | (Note 1)   |
| 72           | TscL                  | SCK Input Low Time                   | Continuous              | 1.25 Tcy + 30 |     | ns    |            |
| 72A          |                       | (Slave mode)                         | Single Byte             | 40            | _   | ns    | (Note 1)   |
| 73A          | Тв2в                  | Last Clock Edge of Byte 1 to the Fir | st Clock Edge of Byte 2 | 1.5 Tcy + 40  | _   | ns    | (Note 2)   |
| 74           | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to SO    | 100                     | _             | ns  |       |            |
| 75           | TdoR                  | SDO Data Output Rise Time            | PIC18F6X2X/8X2X         | _             | 25  | ns    |            |
|              |                       |                                      | PIC18LF6X2X/8X2X        |               | 45  | ns    |            |
| 76           | TdoF                  | SDO Data Output Fall Time            |                         | _             | 25  | ns    |            |
| 77           | TssH2doZ              | SS ↑ to SDO Output High-impeda       | ince                    | 10            | 50  | ns    |            |
| 78           | TscR                  | SCK Output Rise Time                 | PIC18F6X2X/8X2X         | _             | 25  | ns    |            |
|              |                       | (Master mode)                        | PIC18LF6X2X/8X2X        | _             | 45  | ns    |            |
| 79           | TscF                  | SCK Output Fall Time (Master mo      | ode)                    | _             | 25  | ns    |            |
| 80           | TscH2doV,             | SDO Data Output Valid after SCK      | PIC18F6X2X/8X2X         | _             | 50  | ns    |            |
|              | TscL2doV              | Edge                                 | PIC18LF6X2X/8X2X        | _             | 100 | ns    |            |
| 82           | TssL2doV              | SDO Data Output Valid after          | PIC18F6X2X/8X2X         | _             | 50  | ns    |            |
|              |                       | SS ↓ Edge                            | PIC18LF6X2X/8X2X        | _             | 100 | ns    |            |
| 83           | TscH2ssH,<br>TscL2ssH | SS ↑ after SCK Edge                  |                         | 1.5 Tcy + 40  | _   | ns    |            |

FIGURE 27-18: I<sup>2</sup>C™ BUS START/STOP BITS TIMING




TABLE 27-19: I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS (SLAVE MODE)

| Param.<br>No. | Symbol  | Characte        | ristic       | Min  | Max | Units | Conditions                   |  |
|---------------|---------|-----------------|--------------|------|-----|-------|------------------------------|--|
| 90            | Tsu:sta | Start Condition | 100 kHz mode | 4700 | _   | ns    | Only relevant for Repeated   |  |
|               |         | Setup Time      | 400 kHz mode | 600  | _   |       | Start condition              |  |
| 91            | THD:STA | Start Condition | 100 kHz mode | 4000 | _   | ns    | After this period, the first |  |
|               |         | Hold Time       | 400 kHz mode | 600  | _   |       | clock pulse is generated     |  |
| 92            | Tsu:sto | Stop Condition  | 100 kHz mode | 4700 | _   | ns    |                              |  |
|               |         | Setup Time      | 400 kHz mode | 600  | _   |       |                              |  |
| 93            | THD:STO | Stop Condition  | 100 kHz mode | 4000 | _   | ns    |                              |  |
|               |         | Hold Time       | 400 kHz mode | 600  | _   |       |                              |  |

FIGURE 27-19: I<sup>2</sup>C™ BUS DATA TIMING




TABLE 27-20: I<sup>2</sup>C™ BUS DATA REQUIREMENTS (SLAVE MODE)

| Param.<br>No. | Symbol  | Charact             | eristic      | Min         | Max  | Units | Conditions  |
|---------------|---------|---------------------|--------------|-------------|------|-------|---|
| 100           | THIGH   | Clock High Time     | 100 kHz mode | 4.0         | 1    | μѕ    | PIC18F6X2X/8X2X must operate at a minimum of 1.5 MHz      |
|               |         |                     | 400 kHz mode | 0.6         |      | μѕ    | PIC18F6X2X/8X2X must operate at a minimum of 10 MHz       |
|               |         |                     | MSSP module  | 1.5 TcY     | l    |       |   |
| 101           | TLOW    | Clock Low Time      | 100 kHz mode | 4.7         |      | μs    | PIC18F6X2X/8X2X must operate at a minimum of 1.5 MHz      |
|               |         |                     | 400 kHz mode | 1.3         | 1    | μs    | PIC18F6X2X/8X2X must<br>operate at a minimum of<br>10 MHz |
|               |         |                     | MSSP module  | 1.5 TcY     | I    |       |   |
| 102           | TR      | SDA and SCL Rise    | 100 kHz mode | _           | 1000 | ns    |   |
|               |         | Time                | 400 kHz mode | 20 + 0.1 Св | 300  | ns    | CB is specified to be from 10 to 400 pF                   |
| 103           | TF      | SDA and SCL Fall    | 100 kHz mode | _           | 300  | ns    |   |
|               |         | Time                | 400 kHz mode | 20 + 0.1 CB | 300  | ns    | CB is specified to be from 10 to 400 pF                   |
| 90            | TSU:STA | Start Condition     | 100 kHz mode | 4.7         | _    | μs    | Only relevant for Repeated                                |
|               |         | Setup Time          | 400 kHz mode | 0.6         |      | μs    | Start condition   |
| 91            | THD:STA | Start Condition     | 100 kHz mode | 4.0         | _    | μs    | After this period, the first                              |
|               |         | Hold Time           | 400 kHz mode | 0.6         | _    | μs    | clock pulse is generated                                  |
| 106           | THD:DAT | Data Input Hold     | 100 kHz mode | 0           | _    | ns    |   |
|               |         | Time                | 400 kHz mode | 0           | 0.9  | μs    |   |
| 107           | TSU:DAT | Data Input Setup    | 100 kHz mode | 250         | _    | ns    | (Note 2)  |
|               |         | Time                | 400 kHz mode | 100         | _    | ns    |   |
| 92            | Tsu:sto | Stop Condition      | 100 kHz mode | 4.7         | _    | μs    |   |
|               |         | Setup Time          | 400 kHz mode | 0.6         | _    | μs    |   |
| 109           | TAA     | Output Valid from   | 100 kHz mode | _           | 3500 | ns    | (Note 1)  |
|               |         | Clock               | 400 kHz mode | _           | _    | ns    |   |
| 110           | TBUF    | Bus Free Time       | 100 kHz mode | 4.7         | _    | μs    | Time the bus must be free                                 |
|               |         |                     | 400 kHz mode | 1.3         | _    | μs    | before a new transmission can start                       |
| D102          | Св      | Bus Capacitive Load | ding         | _           | 400  | pF    |   |

- **Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.
  - 2: A Fast mode I<sup>2</sup>C™ bus device can be used in a Standard mode I<sup>2</sup>C bus system but the requirement TSU:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line.
    - TR max. + Tsu:DAT = 1000 + 250 = 1250 ns (according to the Standard mode  $I^2C$  bus specification) before the SCL line is released.

FIGURE 27-20: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS TIMING WAVEFORMS




TABLE 27-21: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS

| Param.<br>No. | Symbol  | Characte                          | ristic                    | Min              | Max | Units | Conditions  |  |
|---------------|---------|-----------------------------------|---------------------------|------------------|-----|-------|---|--|
| 90            | Tsu:sta | Start Condition                   | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    | Only relevant for                                     |  |
|               |         | Setup Time                        | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       | Repeated Start  |  |
|               |         |                                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       | condition   |  |
| 91            | THD:STA | Start Condition<br>Hold Time      | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    | After this period, the first clock pulse is generated |  |
|               |         |                                   | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       |   |  |
|               |         |                                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       |   |  |
| 92            | Tsu:sto | Stop Condition                    | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    |   |  |
|               |         | Setup Time                        | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       |   |  |
|               |         |                                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       |   |  |
| 93            | THD:STO | D:STO Stop Condition<br>Hold Time | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    |   |  |
|               |         |                                   | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       |   |  |
|               |         |                                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       |   |  |

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2\text{C}$  pins.

FIGURE 27-21: MASTER SSP I<sup>2</sup>C™ BUS DATA TIMING




TABLE 27-22: MASTER SSP I<sup>2</sup>C™ BUS DATA REQUIREMENTS


| Param.<br>No. | Symbol  | Charac            | teristic                  | Min              | Max  | Units | Conditions                   |
|---------------|---------|-------------------|---------------------------|------------------|------|-------|------------------------------|
| 100           | THIGH   | Clock High Time   | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         |                   | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                              |
| 101           | TLOW    | Clock Low Time    | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         |                   | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                              |
| 102           | Tr      | SDA and SCL       | 100 kHz mode              | _                | 1000 | ns    | CB is specified to be from   |
|               |         | Rise Time         | 400 kHz mode              | 20 + 0.1 CB      | 300  | ns    | 10 to 400 pF                 |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | _                | 300  | ns    |                              |
| 103           | TF      | SDA and SCL       | 100 kHz mode              | _                | 300  | ns    | CB is specified to be from   |
|               |         | Fall Time         | 400 kHz mode              | 20 + 0.1 CB      | 300  | ns    | 10 to 400 pF                 |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | _                | 100  | ns    |                              |
| 90            | Tsu:sta | Start Condition   | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | Only relevant for            |
|               |         | Setup Time        | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | Repeated Start               |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    | condition                    |
| 91            | THD:STA | Start Condition   | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | After this period, the first |
|               |         | Hold Time         | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | clock pulse is generated     |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                              |
| 106           | THD:DAT | Data Input        | 100 kHz mode              | 0                | _    | ns    |                              |
|               |         | Hold Time         | 400 kHz mode              | 0                | 0.9  | ms    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | TBD              | _    | ns    |                              |
| 107           | TSU:DAT | Data Input        | 100 kHz mode              | 250              | _    | ns    | (Note 2)                     |
|               |         | Setup Time        | 400 kHz mode              | 100              | _    | ns    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | TBD              | _    | ns    |                              |
| 92            | Tsu:sto | Stop Condition    | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         | Setup Time        | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                              |
| 109           | Таа     | Output Valid      | 100 kHz mode              | _                | 3500 | ns    |                              |
|               |         | from Clock        | 400 kHz mode              | _                | 1000 | ns    |                              |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | _                | _    | ns    |                              |
| 110           | TBUF    | Bus Free Time     | 100 kHz mode              | 4.7              | _    | ms    | Time the bus must be free    |
|               |         |                   | 400 kHz mode              | 1.3              | _    | ms    | before a new transmission    |
|               |         |                   | 1 MHz mode <sup>(1)</sup> | TBD              | _    | ms    | can start                    |
| D102          | Св      | Bus Capacitive Lo | oading                    |                  | 400  | pF    |                              |

**Legend:** TBD = To Be Determined

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.

2: A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system but parameter #107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line, parameter #102.+ parameter #107 = 1000 + 250 = 1250 ns (for 100 kHz mode), before the SCL line is released.

#### FIGURE 27-22: EUSART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



#### TABLE 27-23: EUSART SYNCHRONOUS TRANSMISSION REQUIREMENTS

| Param.<br>No. | Symbol   | Characteristic                    | Characteristic   |   |     | Units | Conditions |
|---------------|----------|-----------------------------------|------------------|---|-----|-------|------------|
| 120           | TckH2dtV | SYNC XMIT (Master and Slave)      |                  |   |     |       |            |
|               |          | Clock High to Data Out Valid      | PIC18F6X2X/8X2X  | _ | 40  | ns    |            |
|               |          |                                   | PIC18LF6X2X/8X2X |   | 100 | ns    |            |
| 121           | Tckrf    | Clock Out Rise Time and Fall Time | PIC18F6X2X/8X2X  | _ | 20  | ns    |            |
|               |          | (Master mode)                     | PIC18LF6X2X/8X2X | _ | 50  | ns    |            |
| 122           | Tdtrf    | Data Out Rise Time and Fall Time  | PIC18F6X2X/8X2X  | _ | 20  | ns    |            |
|               |          |                                   | PIC18LF6X2X/8X2X | _ | 50  | ns    |            |

#### FIGURE 27-23: EUSART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING




TABLE 27-24: EUSART SYNCHRONOUS RECEIVE REQUIREMENTS

| Param.<br>No. | Symbol   | Characteristic   | Min | Max | Units | Conditions |
|---------------|----------|--|-----|-----|-------|------------|
| 125           | TdtV2ckl | SYNC RCV (Master and Slave) Data Hold before CKx ↓ (DTx hold time) | 10  | _   | ns    |            |
| 126           | TckL2dtl | Data Hold after CKx ↓ (DTx hold time)                              | 15  | _   | ns    |            |

TABLE 27-25: A/D CONVERTER CHARACTERISTICS:PIC18F6X2X/8X2X (INDUSTRIAL, EXTENDED) PIC18LF6X2X/8X2X (INDUSTRIAL)

| Param<br>No. | Symbol | Char                               | acteristic       | Min         | Тур      | Max              | Units      | Conditions  |
|--------------|--------|------------------------------------|------------------|-------------|----------|------------------|------------|---|
| A01          | NR     | Resolution                         |                  | _<br>_      |          | 10<br>TBD        | bit<br>bit | VREF = VDD ≥ 3.0V<br>VREF = VDD < 3.0V                      |
| A03          | EIL    | Integral Linearity Error           |                  | _<br>_      | _        | <±1<br>TBD       | LSb<br>LSb | VREF = VDD ≥ 3.0V<br>VREF = VDD < 3.0V                      |
| A04          | EDL    | Differential Linearity Error       |                  | _<br>_      | _        | <±1<br>TBD       | LSb<br>LSb | VREF = VDD ≥ 3.0V<br>VREF = VDD < 3.0V                      |
| A05          | EFS    | Full Scale Error                   |                  | _<br>_      | _        | <±1<br>TBD       | LSb<br>LSb | VREF = VDD ≥ 3.0V<br>VREF = VDD < 3.0V                      |
| A06          | EOFF   | Offset Error                       |                  | _<br>_      | _        | <±1<br>TBD       | LSb<br>LSb | VREF = VDD ≥ 3.0V<br>VREF = VDD < 3.0V                      |
| A10          | _      | Monotonicity                       |                  | gu          | ıarantee | d <sup>(3)</sup> | _          | VSS ≤ VAIN ≤ VREF   |
| A20<br>A20A  | VREF   | Reference Volta<br>(VREFH – VREFL) |                  | 0V<br>3V    | _        |                  | V          | For 10-bit resolution                                       |
| A21          | VREFH  | Reference Voltag                   | ge High          | AVss        | _        | AVDD + 0.3V      | V          |   |
| A22          | VREFL  | Reference Voltag                   | ge Low           | AVss - 0.3V | -        | AVDD             | V          |   |
| A25          | VAIN   | Analog Input Vol                   | tage             | AVss - 0.3V |          | VREF + 0.3V      | V          |   |
| A30          | ZAIN   | Recommended I<br>Analog Voltage S  |                  | _           | _        | 10.0             | kΩ         |   |
| A40          | IAD    | A/D Conversion                     | PIC18F6X2X/8X2X  | _           | 180      | _                | μΑ         | Average current   |
|              |        | Current (VDD)                      | PIC18LF6X2X/8X2X | _           | 90       | _                | μА         | consumption when A/D is on (Note 1)                         |
| A50          | IREF   | VREF Input Curre                   | ent (Note 2)     |             | _<br>_   | 5<br>150         | μA<br>μA   | During VAIN acquisition.<br>During A/D conversion<br>cycle. |

**Legend:** TBD = To Be Determined

Note 1: When A/D is off, it will not consume any current other than minor leakage current. The power-down current spec includes any such leakage from the A/D module.


VREF current is from RA2/AN2/VREF- and RA3/AN3/VREF+ pins or AVDD and AVSs pins, whichever is selected as

reference input.

2:  $Vss \le Vain \le Vref$ 

3: The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.

FIGURE 27-24: A/D CONVERSION TIMING



#### **TABLE 27-26: A/D CONVERSION REQUIREMENTS**

| Param.<br>No. | Symbol | Charact   | eristic          | Min | Max               | Units | Conditions  |
|---------------|--------|---|------------------|-----|-------------------|-------|---|
| 130           | TAD    | A/D Clock Period  | PIC18F6X2X/8X2X  | 1.6 | 20 <sup>(5)</sup> | μs    | Tosc based, VREF ≥ 3.0V   |
|               |        |   | PIC18LF6X2X/8X2X | 3.0 | 20 <sup>(5)</sup> | μs    | Tosc based, VREF full range   |
|               |        |   | PIC18F6X2X/8X2X  | 2.0 | 6.0               | μs    | A/D RC mode   |
|               |        |   | PIC18LF6X2X/8X2X | 3.0 | 9.0               | μs    | A/D RC mode   |
| 131           | TCNV   | Conversion Time (not including acquisition time) (Note 1) |                  |     | 12                | TAD   |   |
| 132           | TACQ   | Acquisition Time (Note                                    | 3)               | 15  | _                 | μs    | -40°C ≤ Temp ≤ +125°C   |
|               |        |   |                  | 10  | —                 | μs    | 0°C ≤ Temp ≤ +125°C   |
| 135           | Tswc   | Switching Time from Co                                    | onvert → Sample  | _   | (Note 4)          |       |   |
| 136           | Тамр   | Amplifier Settling Time                                   | (Note 2)         | 1   | _                 | μs    | This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 5 mV @ 5.12V) from the last sampled voltage (as stated on CHOLD). |

- Note 1: ADRES register may be read on the following TcY cycle.
  - 2: See Section 20.0 "10-Bit Analog-to-Digital Converter (A/D) Module" for minimum conditions when input voltage has changed more than 1 LSb.
  - 3: The time for the holding capacitor to acquire the "New" input voltage when the voltage changes full scale after the conversion (AVDD to AVSS, or AVSS to AVDD). The source impedance (Rs) on the input channels is  $50\Omega$ .
  - 4: On the next Q4 cycle of the device clock.
  - 5: The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

NOTES:

#### 28.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

**Note:** The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range.

"Typical" represents the mean of the distribution at 25°C. "Maximum" or "minimum" represents (mean +  $3\sigma$ ) or (mean –  $3\sigma$ ) respectively, where  $\sigma$  is a standard deviation, over the whole temperature range.

FIGURE 28-1: TYPICAL IDD vs. FOSC OVER VDD (HS MODE)




FIGURE 28-2: MAXIMUM IDD vs. Fosc OVER VDD (HS MODE)





FIGURE 28-3: TYPICAL IDD vs. Fosc OVER VDD (HS/PLL MODE)









FIGURE 28-5: TYPICAL IDD vs. FOSC OVER VDD (XT MODE)









FIGURE 28-7: TYPICAL IDD vs. FOSC OVER VDD (LP MODE)









FIGURE 28-9: TYPICAL IDD vs. Fosc OVER VDD (EC MODE)








FIGURE 28-11: TYPICAL AND MAXIMUM IT10SC vs. VDD (TIMER1 AS SYSTEM CLOCK)





FIGURE 28-12: AVERAGE FOSC vs. VDD FOR VARIOUS Rs (RC MODE, C = 20 pF, TEMP = 25°C)








FIGURE 28-14: AVERAGE FOSC vs. VDD FOR VARIOUS Rs (RC MODE, C = 300 pF, TEMP = 25°C)




FIGURE 28-15: IPD vs. VDD (SLEEP MODE, ALL PERIPHERALS DISABLED)




FIGURE 28-16: TYPICAL AND MAXIMUM  $\triangle$ IBOR vs. VDD OVER TEMPERATURE, VBOR = 2.00-2.16V






FIGURE 28-17: IT10SC vs. VDD (SLEEP MODE, TIMER1 AND OSCILLATOR ENABLED)








FIGURE 28-19: TYPICAL, MINIMUM AND MAXIMUM WDT PERIOD vs. VDD




FIGURE 28-20: △ILVD vs. VDD OVER TEMPERATURE, VLVD = 4.5-4.78V




FIGURE 28-21: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 5V, -40°C TO +125°C)




FIGURE 28-22: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 3V, -40°C TO +125°C)




FIGURE 28-23: TYPICAL AND MAXIMUM Vol vs. lol (VDD = 5V, -40°C TO +125°C)




FIGURE 28-24: TYPICAL AND MAXIMUM Vol vs. Iol (VDD = 3V, -40°C TO +125°C)




FIGURE 28-25: MINIMUM AND MAXIMUM VIN vs. VDD (ST INPUT, -40°C TO +125°C)




FIGURE 28-26: MINIMUM AND MAXIMUM Vin vs. Vdd (TTL INPUT, -40°C TO +125°C)




FIGURE 28-27: MINIMUM AND MAXIMUM VIN vs. VDD (I<sup>2</sup>C INPUT, -40°C TO +125°C)






FIGURE 28-28: A/D NONLINEARITY vs. VREFH (VDD = VREFH, -40°C TO +125°C)








NOTES:

#### 29.0 PACKAGING INFORMATION

#### 29.1 **Package Marking Information**


64-Lead TQFP



Example



80-Lead TQFP



Example



Legend: XX...X Customer-specific information

> Year code (last digit of calendar year) Υ ΥY Year code (last 2 digits of calendar year) WW Week code (week of January 1 is week '01') NNN Alphanumeric traceability code

(e3) Pb-free JEDEC designator for Matte Tin (Sn)

This package is Pb-free. The Pb-free JEDEC designator (@3)


can be found on the outer packaging for this package.

Note: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

#### 29.2 Package Details

The following sections give the technical details of the packages.

#### 64-Lead Plastic Thin Quad Flatpack (PT) 10x10x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)



|                          | Units | INCHES |      |      | М     |       |       |
|--------------------------|-------|--------|------|------|-------|-------|-------|
| Dimension Lim            | its   | MIN    | NOM  | MAX  | MIN   | NOM   | MAX   |
| Number of Pins           | n     |        | 64   |      |       | 64    |       |
| Pitch                    | р     |        | .020 |      |       | 0.50  |       |
| Pins per Side            | n1    |        | 16   |      |       | 16    |       |
| Overall Height           | Α     | .039   | .043 | .047 | 1.00  | 1.10  | 1.20  |
| Molded Package Thickness | A2    | .037   | .039 | .041 | 0.95  | 1.00  | 1.05  |
| Standoff                 | A1    | .002   | .006 | .010 | 0.05  | 0.15  | 0.25  |
| Foot Length              | L     | .018   | .024 | .030 | 0.45  | 0.60  | 0.75  |
| Footprint (Reference)    | (F)   |        | .039 |      |       | 1.00  |       |
| Foot Angle               | ф     | 0      | 3.5  | 7    | 0     | 3.5   | 7     |
| Overall Width            | E     | .463   | .472 | .482 | 11.75 | 12.00 | 12.25 |
| Overall Length           | D     | .463   | .472 | .482 | 11.75 | 12.00 | 12.25 |
| Molded Package Width     | E1    | .390   | .394 | .398 | 9.90  | 10.00 | 10.10 |
| Molded Package Length    | D1    | .390   | .394 | .398 | 9.90  | 10.00 | 10.10 |
| Lead Thickness           | С     | .005   | .007 | .009 | 0.13  | 0.18  | 0.23  |
| Lead Width               | В     | .007   | .009 | .011 | 0.17  | 0.22  | 0.27  |
| Pin 1 Corner Chamfer     | CH    | .025   | .035 | .045 | 0.64  | 0.89  | 1.14  |
| Mold Draft Angle Top     | α     | 5      | 10   | 15   | 5     | 10    | 15    |
| Mold Draft Angle Bottom  | β     | 5      | 10   | 15   | 5     | 10    | 15    |


\*Controlling Parameter

Notes:

Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-026 Drawing No. C04-085

#### 80-Lead Plastic Thin Quad Flatpack (PT) 12x12x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)



|                          | Units  | INCHES |      |      | MILLIMETERS* |       |       |
|--------------------------|--------|--------|------|------|--------------|-------|-------|
| Dimension                | Limits | MIN    | NOM  | MAX  | MIN          | NOM   | MAX   |
| Number of Pins           | n      |        | 80   |      |              | 80    |       |
| Pitch                    | р      |        | .020 |      |              | 0.50  |       |
| Pins per Side            | n1     |        | 20   |      |              | 20    |       |
| Overall Height           | А      | .039   | .043 | .047 | 1.00         | 1.10  | 1.20  |
| Molded Package Thickness | A2     | .037   | .039 | .041 | 0.95         | 1.00  | 1.05  |
| Standoff                 | A1     | .002   | .004 | .006 | 0.05         | 0.10  | 0.15  |
| Foot Length              | L      | .018   | .024 | .030 | 0.45         | 0.60  | 0.75  |
| Footprint (Reference)    | (F)    |        | .039 |      |              | 1.00  |       |
| Foot Angle               | ф      | 0      | 3.5  | 7    | 0            | 3.5   | 7     |
| Overall Width            | E      | .541   | .551 | .561 | 13.75        | 14.00 | 14.25 |
| Overall Length           | D      | .541   | .551 | .561 | 13.75        | 14.00 | 14.25 |
| Molded Package Width     | E1     | .463   | .472 | .482 | 11.75        | 12.00 | 12.25 |
| Molded Package Length    | D1     | .463   | .472 | .482 | 11.75        | 12.00 | 12.25 |
| Lead Thickness           | С      | .004   | .006 | .008 | 0.09         | 0.15  | 0.20  |
| Lead Width               | В      | .007   | .009 | .011 | 0.17         | 0.22  | 0.27  |
| Pin 1 Corner Chamfer     | CH     | .025   | .035 | .045 | 0.64         | 0.89  | 1.14  |
| Mold Draft Angle Top     | α      | 5      | 10   | 15   | 5            | 10    | 15    |
| Mold Draft Angle Bottom  | β      | 5      | 10   | 15   | 5            | 10    | 15    |

<sup>\*</sup>Controlling Parameter

Notes:

Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010"  $(0.254 \, \text{mm})$  per side.

JEDEC Equivalent: MS-026 Drawing No. C04-092

NOTES:

#### **APPENDIX A: REVISION HISTORY**

#### Revision A (July 2003)

Original data sheet for PIC18F6525/6621/8525/8621 family.

#### **Revision B (August 2004)**

This revision includes updates to the Electrical Specifications in **Section 27.0**, the DC and AC Characteristics Graphs and Tables in **Section 28.0** have been added and includes minor corrections to the data sheet text.

#### **APPENDIX B: DEVICE**

**DIFFERENCES** 

The differences between the devices listed in this data sheet are shown in Table B-1.

TABLE B-1: DEVICE DIFFERENCES

| Feature                         | PIC18F6525                   | PIC18F6621                   | PIC18F8525                         | PIC18F8621                         |
|---------------------------------|------------------------------|------------------------------|------------------------------------|------------------------------------|
| On-chip Program Memory (Kbytes) | 48K                          | 64K                          | 48K                                | 64K                                |
| I/O Ports                       | Ports A, B, C, D,<br>E, F, G | Ports A, B, C, D,<br>E, F, G | Ports A, B, C, D,<br>E, F, G, H, J | Ports A, B, C, D,<br>E, F, G, H, J |
| A/D Channels                    | 12                           | 12                           | 16                                 | 16                                 |
| External Memory Interface       | No                           | No                           | Yes                                | Yes                                |
| Package Types                   | 64-pin TQFP                  | 64-pin TQFP                  | 80-pin TQFP                        | 80-pin TQFP                        |

# APPENDIX C: CONVERSION CONSIDERATIONS

This appendix discusses the considerations for converting from previous versions of a device to the ones listed in this data sheet. Typically, these changes are due to the differences in the process technology used. An example of this type of conversion is from a PIC17C756 to a PIC18F8720.

Not Applicable

# APPENDIX D: MIGRATION FROM MID-RANGE TO ENHANCED DEVICES

A detailed discussion of the differences between the mid-range MCU devices (i.e., PIC16CXXX) and the enhanced devices (i.e., PIC18FXXX) is provided in AN716, "Migrating Designs from PIC16C74A/74B to PIC18C442." The changes discussed, while device specific, are generally applicable to all mid-range to enhanced device migrations.

This Application Note is available as Literature Number DS00716.

APPENDIX E: MIGRATION FROM HIGH-END TO ENHANCED DEVICES

A detailed discussion of the migration pathway and differences between the high-end MCU devices (i.e., PIC17CXXX) and the enhanced devices (i.e., PIC18FXXXX) is provided in *AN726, "PIC17CXXX to PIC18CXXX Migration.*"

This Application Note is available as Literature Number DS00726.

NOTES:

#### **INDEX**

| A   |            | Block Diagrams                         |     |
|---|------------|--|-----|
| A/D   | 233        | 16-Bit Byte Select Mode                | 75  |
| Acquisition Requirements                                |            | 16-Bit Byte Write Mode                 | 73  |
| Acquisition Time  |            | 16-Bit Word Write Mode                 | 74  |
| ADCON0 Register   |            | A/D                                    | 236 |
| ADCONO Register   |            | Analog Input Model                     | 237 |
| ADCON1 Register   |            | Baud Rate Generator                    | 199 |
| ADCONZ Register   |            | Capture Mode Operation                 | 151 |
| ADRESL Register   |            | Comparator Analog Input Model          | 247 |
| Analog Port Pins  |            | Comparator I/O Operating Modes         | 244 |
| Analog Port Pins, Configuring                           |            | Comparator Output                      | 246 |
| Associated Register Summary                             |            | Comparator Voltage Reference           |     |
| ,   |            | Comparator Voltage Reference           |     |
| Automatic Acquisition Time Calculating Minimum Required | 239        | Output Buffer Example                  | 251 |
| · ·   | 220        | Compare Mode Operation                 |     |
| Acquisition Time  |            | Enhanced PWM                           | 161 |
| Configuring the Module                                  |            | EUSART Receive                         | 223 |
| Conversion Clock (TAD)                                  |            | EUSART Transmit                        | 221 |
|   |            | Low-Voltage Detect (LVD)               | 254 |
| Conversion TAD Cycles                                   |            | Low-Voltage Detect with External Input | 254 |
| Conversions  Converter Characteristics                  |            | MCLR/VPP/RG5 Pin                       |     |
|   |            | MSSP (I <sup>2</sup> C Master Mode)    |     |
| Converter Interrupt, Configuring                        |            | MSSP (I <sup>2</sup> C Mode)           |     |
| ECCP2 Special Event Trigger                             |            | MSSP (SPI Mode)                        |     |
| Equations   |            | On-Chip Reset Circuit                  |     |
| Minimum Charging Time                                   | 238        | PIC18F6525/6621                        |     |
| Selecting and Configuring                               | 000        | PIC18F8525/8621                        |     |
| Acquisition Time  |            | PLL                                    |     |
| Special Event Trigger (ECCP)                            | 160        | Port/LAT/TRIS Operation                |     |
| TAD vs. Device Operating                                | 000        | PORTC (Peripheral Output Override)     |     |
| Frequencies (table)                                     |            | PORTD and PORTE (Parallel Slave Port)  |     |
| Absolute Maximum Ratings                                |            | PORTD in I/O Port Mode                 |     |
| AC (Timing) Characteristics                             | 335        | PORTD in System Bus Mode               |     |
| Load Conditions for Device                              | 000        | PORTE in I/O Mode                      |     |
| Timing Specifications                                   |            | PORTE in System Bus Mode               |     |
| Parameter Symbology                                     | 335        | PORTG (Peripheral Output Override)     |     |
| Temperature and Voltage                                 | 000        | PORTJ in I/O Mode                      |     |
| Specifications  |            | PWM Operation (Simplified)             |     |
| Timing Conditions                                       |            | RA3:RA0 and RA5 Pins                   |     |
| ACKSTAT   |            | RA4/T0CKI Pin                          |     |
| ACKSTAT Status Flag                                     |            | RA6 Pin (Enabled as I/O)               |     |
| ADCONO Register   |            | RB2:RB0 Pins                           |     |
| GO/DONE Bit   |            | RB3 Pin                                |     |
| ADCON1 Register   |            | RB7:RB4 Pins                           | 106 |
| ADCON2 Register   |            | Reads from Flash Program Memory        | 65  |
| ADDLW   |            | RF1/AN6/C2OUT and RF2/AN7/C1OUT Pins   |     |
| ADDWF   | _          | RF6:RF3 and RF0 Pins                   |     |
| ADDWFC  |            | RF7 Pin                                |     |
| ADRESH Register23                                       | ,          | RH3:RH0 Pins in I/O Mode               |     |
| ADRESL Register   | 33, 236    | RH3:RH0 Pins in System Bus Mode        |     |
| Analog-to-Digital Converter. See A/D.                   | 000        | RH7:RH4 Pins in I/O Mode               |     |
| ANDLW   |            | RJ4:RJ0 Pins in System Bus Mode        |     |
| ANDWF   | 283        | RJ7:RJ6 Pins in System Bus Mode        |     |
| Assembler   | 0.47       | Single Comparator                      |     |
| MPASM Assembler   |            | Table Read Operation                   |     |
| Auto-Wake-up on Sync Break Character                    | 225        | Table Write Operation                  |     |
| В   |            | Table Writes to Flash Program Memory   |     |
|   | 100        | Timer0 in 16-Bit Mode                  |     |
| Baud Rate Generator                                     |            | Timer0 in 8-Bit Mode                   |     |
| BC  |            | Timer1                                 |     |
| BCF   |            | Timer1 (16-Bit Read/Write Mode)        |     |
| BF  | 203<br>203 | Timer2                                 |     |

| Timer3  | 144    | Initializing PORTE                     | 114 |
|---|--------|--|-----|
| Timer3 (16-Bit Read/Write Mode)               | 144    | Initializing PORTF                     | 117 |
| Timer4  | 148    | Initializing PORTG                     | 120 |
| Watchdog Timer                                | 268    | Initializing PORTH                     | 122 |
| BN  | 284    | Initializing PORTJ                     | 125 |
| BNC   | 285    | Loading the SSPBUF (SSPSR) Register    | 176 |
| BNN   | 285    | Reading a Flash Program Memory Word    | 65  |
| BNOV  | 286    | Saving STATUS, WREG and                |     |
| BNZ   | 286    | BSR Registers in RAM                   | 102 |
| BOR. See Brown-out Reset.                     |        | Writing to Flash Program Memory        |     |
| BOV   | 289    | Code Protection                        |     |
| BRA   |        | Associated Registers                   |     |
| Break Character (12-Bit) Transmit and Receive | -      | Configuration Register Protection      |     |
| BRG. See Baud Rate Generator.                 | 220    | Data EEPROM                            |     |
| Brown-out Reset (BOR)                         | 30 259 | Program Memory                         |     |
| BSF   |        | COMF                                   |     |
| BTFSC   |        | Comparator                             |     |
| BTFSS   |        | Analog Input Connection Considerations |     |
| BTG   |        | Associated Registers                   |     |
|   |        |  |     |
| BZ  | 290    | Configuration                          |     |
| C   |        | Effects of a Reset                     |     |
| C Compilers                                   |        | Interrupts                             |     |
|   | 240    | Operation                              |     |
| MPLAB C19                                     |        | Operation During Sleep                 |     |
| MPLAB C20                                     |        | Outputs                                |     |
| MPLAB C30                                     |        | Reference                              |     |
| CALL  |        | External Signal                        |     |
| Capture (CCP Module)                          |        | Internal Signal                        |     |
| Associated Registers                          |        | Response Time                          |     |
| CCP Pin Configuration                         |        | Comparator Specifications              |     |
| CCPR4H:CCPR4L Registers                       |        | Comparator Voltage Reference           | 249 |
| Software Interrupt                            |        | Accuracy and Error                     | 250 |
| Timer1/Timer3 Mode Selection                  |        | Associated Registers                   |     |
| Capture (ECCP Module)                         | 160    | Configuring                            | 249 |
| Capture/Compare/PWM (CCP)                     | 149    | Connection Considerations              | 250 |
| Capture Mode. See Capture.                    |        | Effects of a Reset                     | 250 |
| CCP Mode and Timer Resources                  | 150    | Operation During Sleep                 | 250 |
| CCPRxH Register                               | 150    | Compare (CCP Module)                   |     |
| CCPRxL Register                               | 150    | Associated Registers                   |     |
| Compare Mode. See Compare.                    |        | CCP Pin Configuration                  |     |
| Interconnect Configurations                   | 150    | CCPR1 Register                         |     |
| Module Configuration                          | 150    | Software Interrupt                     |     |
| PWM Mode. See PWM.                            |        | Special Event Trigger                  |     |
| Clocking Scheme/Instruction Cycle             | 44     | Timer1/Timer3 Mode Selection           |     |
| CLRF  |        | Compare (ECCP Module)                  |     |
| CLRWDT  |        | Special Event Trigger                  |     |
| Code Examples                                 |        | Configuration Bits                     |     |
| 16 x 16 Signed Multiply Routine               | 86     | Context Saving During Interrupts       |     |
| 16 x 16 Unsigned Multiply Routine             |        | Control Registers                      | 102 |
| 8 x 8 Signed Multiply Routine                 |        | <u> </u>                               | 60  |
| 8 x 8 Unsigned Multiply Routine               |        | EECON1 and EECON2                      |     |
|   |        | TABLAT (Table Latch) Register          |     |
| Changing Between Capture Prescalers           |        | TBLPTR (Table Pointer) Register        |     |
| Computed GOTO Using an Offset Value           |        | Conversion Considerations              |     |
| Data EEPROM Read                              |        | CPFSEQ                                 |     |
| Data EEPROM Refresh Routine                   |        | CPFSGT                                 |     |
| Data EEPROM Write                             |        | CPFSLT                                 | 293 |
| Erasing a Flash Program Memory Row            |        | D                                      |     |
| Fast Register Stack                           | 44     | В                                      |     |
| How to Clear RAM (Bank 1) Using               |        | Data EEPROM Memory                     |     |
| Indirect Addressing                           | 56     | Associated Registers                   |     |
| Implementing a Real-Time Clock Using a        |        | EEADR Register                         |     |
| Timer1 Interrupt Service                      |        | EEADRH Register                        | 79  |
| Initializing PORTA                            | 103    | EECON1 Register                        |     |
| Initializing PORTB                            |        | EECON2 Register                        | 79  |
| Initializing PORTC                            |        | Operation During Code-Protect          |     |
| Initializing PORTD                            |        | Protection Against Spurious Write      |     |
| <del>-</del>                                  |        | - ·                                    |     |

| Reading  | 81              |
|--|-----------------|
| Using  | 82              |
| Write Verify   | 82              |
|  | 81              |
| Data Memory  | 47              |
|  | sters47         |
|  | 8X2X Devices 48 |
| Special Function Regi  | sters 47        |
|  | 294             |
| DC and AC Characteristics  |                 |
|  | 357             |
|  | 330             |
|  | ply Current326  |
|  | 325             |
|  | 295             |
|  | 294             |
|  | 295             |
| Demonstration Boards   | 200             |
|  | 320             |
|  | 321             |
|  | 321             |
|  | 320             |
|  | 320             |
|  |                 |
|  | 321             |
|  | Ethernet321     |
|  |                 |
|  | 317             |
|  | 57              |
|  |                 |
|  |                 |
| Direct Addressing  | 55              |
| E  | 55              |
| _  | 55              |
| <b>E</b> ECCP  |                 |
| E<br>ECCP<br>Capture and Compare   | Modes160        |
| E<br>ECCP<br>Capture and Compare<br>Standard PWM Mode.   |                 |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar   | Modes160        |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Co Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Co Outputs and Configura Pin Configurations for Pin Configurations for   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Cal Enhanced PWM Mode. See  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter (  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ce Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata EUSART Asynchronous Mode  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ci Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ci Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata EUSART Asynchronous Mode 12-Bit Break Trar Associated Regis   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ci Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ci Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata EUSART Asynchronous Mode 12-Bit Break Tran Associated Regis Associated Regis  | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ca Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ci Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ci Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata EUSART Asynchronous Mode 12-Bit Break Tran Associated Regis Associated Regis Auto-Wake-up or Receiver                               | Modes           |
| EECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ca Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources   | Modes           |
| E ECCP Capture and Compare Standard PWM Mode. Electrical Characteristics Enhanced Capture/Compar and Program Memory Capture Mode. See Ci Outputs and Configura Pin Configurations for Pin Configurations for Pin Configurations for PWM Mode. See PWM Timer Resources Use with CCP4 and Ci Enhanced PWM Mode. See Enhanced Universal Synch Receiver Transmitter ( Errata EUSART Asynchronous Mode 12-Bit Break Tran Associated Regis Associated Regis Auto-Wake-up or Receiver Setting Up 9-Bit M Address De | Modes           |

| Baud Rate Generator (BRG)   |                |
|---|----------------|
| Associated Registers  | 217            |
| Auto-Baud Rate Detect   | 220            |
| Baud Rate Error, Calculating  | 217            |
| Baud Rates, Asynchronous Mo   | des 218        |
| High Baud Rate Select (BRGH   |                |
| Sampling  |                |
| Synchronous Master Mode   |                |
|   |                |
| Associated Registers, Receive   |                |
| Associated Registers, Transmi   |                |
| Reception   |                |
| Transmission  |                |
| Synchronous Slave Mode  | 231            |
| Associated Registers, Receive   | 232            |
| Associated Registers, Transmi   |                |
| Reception   |                |
| Transmission  |                |
| Evaluation and Programming Tools  |                |
|   |                |
| Extended Microcontroller Mode   |                |
| External Memory Interface   |                |
| 16-Bit Byte Select Mode   |                |
| 16-Bit Byte Write Mode  | 73             |
| 16-Bit Mode   | 73             |
| 16-Bit Mode Timing  | 76             |
| 16-Bit Word Write Mode  |                |
| PIC18F8X2X External Bus -   |                |
| I/O Port Functions  | 72             |
| Program Memory Modes and Extern   |                |
| Manage Later from   | lai            |
| Memory Interface  |                |
| F   |                |
|   |                |
|   |                |
|   |                |
| Associated Registers  | 69             |
| Flash Program Memory<br>Associated Registers<br>Control Registers   | 69             |
| Associated Registers Control Registers  | 69<br>62       |
| Associated Registers  Control Registers  Erase Sequence   | 69<br>62<br>66 |
| Associated Registers  Control Registers  Erase Sequence  Erasing  |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect   |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect  Reading  |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect  Reading  Table Pointer   |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect  Reading  Table Pointer  Boundaries Based on Operatio   |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Pointer Boundaries   |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect  Reading  Table Pointer  Boundaries Based on Operatio   |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Pointer Boundaries   |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Pointer Boundaries Table Reads and Table Writes Write Sequence   |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Pointer Boundaries Table Reads and Table Writes Write Sequence Writing To  |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Reads and Table Writes Write Sequence Writing To Protection Against Spurious W   |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operation Table Pointer Boundaries Table Reads and Table Writes Write Sequence Writing To Protection Against Spurious W Unexpected Termination                            |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Reads and Table Writes Write Sequence Writing To Protection Against Spurious W   |                |
| Associated Registers  Control Registers  Erase Sequence  Erasing  Operation During Code-Protect  Reading  Table Pointer  Boundaries Based on Operation  Table Pointer Boundaries  Table Reads and Table Writes  Write Sequence  Writing To  Protection Against Spurious W  Unexpected Termination  Write Verify |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operatio Table Pointer Boundaries Table Reads and Table Writes Write Sequence Writing To Protection Against Spurious W Unexpected Termination Write Verify                |                |
| Associated Registers  |                |
| Associated Registers  |                |
| Associated Registers Control Registers Erase Sequence Erasing Operation During Code-Protect Reading Table Pointer Boundaries Based on Operation Table Pointer Boundaries Table Reads and Table Writes Write Sequence Writing To Protection Against Spurious W Unexpected Termination Write Verify               |                |
| Associated Registers  |                |

| I   |      |
|---|------|
| I/O Ports                                   | .103 |
| I <sup>2</sup> C Mode                       |      |
| Associated Registers                        | 212  |
| General Call Address Support                |      |
| Master Mode                                 |      |
| Operation                                   | .198 |
| Master Mode Transmit Sequence               |      |
| Read/Write Bit Information (R/W Bit)186,    |      |
| Serial Clock (RC3/SCK/SCL)                  |      |
| ID Locations259,                            |      |
| INCF  |      |
| INCFSZ                                      |      |
| In-Circuit Debugger                         |      |
| Resources (table)                           |      |
| In-Circuit Serial Programming (ICSP)259,    |      |
| Indirect Addressing                         |      |
| INDF and FSR Registers                      |      |
| Operation                                   |      |
| Indirect Addressing Operation               |      |
| Indirect File Operand                       |      |
| INFSNZ                                      |      |
| Initialization Conditions for All Registers |      |
| Instruction Flow/Pipelining                 | 45   |
| Instruction Set                             |      |
| ADDLW                                       |      |
| ADDWF                                       | -    |
| ADDWFC                                      | -    |
| ANDLW                                       | -    |
| ANDWF                                       |      |
| BC  |      |
| BCF   |      |
| BN  |      |
| BNC   |      |
| BNN<br>BNOV                                 |      |
| BNZ   |      |
| BOV   |      |
| BRA   |      |
| BSF   |      |
| BTFSC                                       |      |
| BTFSS                                       |      |
| BTG   |      |
| BZ  |      |
| CALL  | 290  |
| CLRF  |      |
| CLRWDT                                      |      |
| COMF  | -    |
| CPFSEQ                                      |      |
| CPFSGT                                      |      |
| CPFSLT                                      |      |
| DAW   |      |
| DCFSNZ                                      | .295 |
| DECF  | .294 |
| DECFSZ                                      |      |
| Firmware Instructions                       |      |
| General Format                              | .277 |
| GOTO  | 296  |
| INCF  |      |
| INCFSZ                                      |      |
| INFSNZ                                      |      |
| IORLW                                       |      |
| IORWF                                       |      |
| LFSR  |      |

| MOVF   |  |
|--|--|
| MOVFF  |  |
| MOVLB  |  |
| MOVLW  |  |
| MOVWF  |  |
| MULLW  |  |
| MULWF  | . 302  |
| NEGF   |  |
| NOP  |  |
| Opcode Field Descriptions  | 276  |
| POP  |  |
| PUSH   | . 304  |
| RCALL  | . 305  |
| RESET  | . 305  |
| RETFIE   |  |
| RETLW  |  |
| RETURN   | . 307  |
| RLCF   |  |
| RLNCF  |  |
| RRCF   | . 308  |
| RRNCF  |  |
| SETF   |  |
| SLEEP  |  |
| SUBFWB   | 310  |
| SUBLW  | -  |
| SUBWF  |  |
| SUBWFB   |  |
| SWAPF  | -  |
| TBLRD  |  |
| TBLWT  |  |
| TSTFSZ   |  |
| XORLW  | 315  |
|  |  |
| XORWF  | 316  |
| XORWFSummary Table   | . 316<br>. 278   |
| XORWF  | . 316<br>. 278<br>es.  |
| XORWF  | . 316<br>. 278<br>es.  |
| XORWF  | . 316<br>. 278<br>es.<br>89  |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88  |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88  |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259   |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259<br>. 237  |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259<br>. 237<br>. 151   |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259<br>. 237<br>. 151<br>. 152  |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 106   |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 106<br>. 106  |
| XORWF  | . 316<br>. 278<br>es.<br>89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 106  |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP) Compare Complete (CCP) INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102   |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 102<br>. 102<br>. 102<br>. 102<br>. 133  |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow 135   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 133<br>. 137   |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match   | . 316<br>. 278<br>es 89<br>88<br>259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 133<br>. 137<br>. 142  |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0. TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match  | . 316<br>. 278<br>es 89<br>88<br>259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 103<br>. 133<br>. 137<br>. 142<br>. 160   |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO  | . 3166<br>. 278<br>es 89<br>88<br>259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 103<br>. 133<br>. 137<br>. 142<br>. 160<br>. 145                                |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO  | . 3166. 278 es 89 es 88 259 151 152 102 102 103 137 142 160 145 148 148  |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO  | . 3166<br>. 278<br>es 89<br>88<br>259<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 103<br>. 137<br>. 142<br>. 160<br>. 145<br>. 148<br>. 148                                |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4). PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match (PWM)  | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 103<br>. 137<br>. 142<br>. 160<br>. 145<br>. 148<br>. 147<br>87                         |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts. Control Registers   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 103<br>. 137<br>. 142<br>. 160<br>. 145<br>. 148<br>. 147<br>87                |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts Control Registers Enable Registers   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 103<br>. 137<br>. 142<br>. 160<br>. 145<br>. 148<br>. 147<br>87<br>89<br>95    |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0 Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0 TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts Control Registers Enable Registers Flag Registers  | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 103<br>. 137<br>. 142<br>. 148<br>. 147<br>87<br>89<br>95                      |
| XORWF Summary Table  INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources  A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INTO. Interrupt-on-Change (RB7:RB4). PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0. TMR0 Overflow. TMR1 Overflow. TMR2 to PR2 Match TMR2 to PR2 Match (PWM). TMR3 Overflow. 143, TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts.  Control Registers Enable Registers Flag Registers. Priority Registers.   | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 152<br>. 102<br>. 102<br>. 102<br>. 133<br>. 137<br>. 142<br>. 160<br>. 145<br>. 147<br>87<br>89<br>95<br>92<br>98 |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0. Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0. TMR0. TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match TMR2 to PR4 Match TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts. Control Registers Enable Registers Flag Registers Flag Registers Priority Registers Reset Control Registers.                                    | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 102<br>. 102<br>. 102<br>. 102<br>. 133<br>. 137<br>. 149<br>. 149<br>87<br>87<br>95<br>92<br>98                   |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0. Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0. TMR0. TMR0 Overflow TMR1 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match (PWM) TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts Control Registers Enable Registers Flag Registers Priority Registers Reset Control Registers. Reset Control Registers. IORLW | . 316<br>. 278<br>es 89<br>88<br>. 259<br>. 237<br>. 151<br>. 102<br>. 102<br>. 102<br>. 133<br>. 137<br>. 142<br>. 144<br>. 147<br>87<br>95<br>92<br>92<br>92<br>               |
| XORWF Summary Table INT Interrupt (RB3/INT3:RB0/INT0). See Interrupt Source INTCON Registers Inter-Integrated Circuit. See I <sup>2</sup> C. Interrupt Logic (diagram) Interrupt Sources A/D Conversion Complete Capture Complete (CCP). Compare Complete (CCP). INT0. Interrupt-on-Change (RB7:RB4) PORTB, Interrupt-on-Change RB3/INT3:RB0/INT0/FLT0 Pins, External. TMR0. TMR0. TMR0 Overflow TMR1 Overflow TMR2 to PR2 Match TMR2 to PR2 Match TMR2 to PR4 Match TMR3 Overflow TMR4 to PR4 Match TMR4 to PR4 Match TMR4 to PR4 Match (PWM) Interrupts. Control Registers Enable Registers Flag Registers Flag Registers Priority Registers Reset Control Registers.                                    | . 3166 . 278 es 88 es 89 259 151   |

| K  | Control Registers (general)            | 17             |
|--|--|----------------|
| Key Features                                     | Enabling SPI I/O                       |                |
| Easy Migration7                                  | I <sup>2</sup> C Mode                  |                |
| Expanded Memory7                                 | Acknowledge Sequence Timing            | 200            |
| External Memory Interface7                       | Baud Rate Generator                    | 199            |
| Other Special Features7                          | Bus Collision                          |                |
| ·  | During a Repeated                      |                |
| L  | Start Condition                        | 210            |
| LFSR   | Bus Collision During a Start Condition |                |
| Low-Voltage Detect                               | Bus Collision During a Stop Condition  | 21             |
| Characteristics                                  | Clock Arbitration                      | 200            |
| Converter Characteristics                        | Effect of a Reset                      |                |
| Effects of a Reset257                            | I <sup>2</sup> C Clock Rate w/BRG      | -              |
| Operation  | Master Mode                            |                |
| Current Consumption257                           | Reception                              |                |
| During Sleep                                     | Repeated Start Condition Timing        |                |
| Reference Voltage Set Point257                   | Start Condition Timing                 |                |
| Typical Application253                           | Transmission                           | 203            |
| Low-Voltage ICSP Programming                     | Multi-Master Communication, Bus        |                |
| LVD. See Low-Voltage Detect.                     | Collision and Arbitration              | -              |
|  | Multi-Master Mode                      |                |
| M  | Registers                              |                |
| Master SSP (MSSP) Module Overview173             | Sleep Operation                        |                |
| Master Synchronous Serial Port (MSSP). See MSSP. | Stop Condition Timing                  |                |
| Master Synchronous Serial Port. See MSSP         | Module Operation                       |                |
| Memory   | Operation                              |                |
| Mode Memory Access40                             | Slave Mode                             |                |
| Memory Maps for PIC18F6X2X/8X2X                  | Addressing                             |                |
| Program Memory Modes41                           | Reception                              |                |
| Memory Organization                              | Transmission                           |                |
| Data Memory47                                    | SPI Master Mode                        |                |
| Program Memory39                                 | SPI Mode                               |                |
| Modes39  | SPI Slave Mode                         |                |
| Memory Programming Requirements                  | SSPBUF                                 |                |
| Microcontroller Mode71                           | SSPSR TMR2 Output for Clock Shift      |                |
| Microprocessor Mode71                            | TMR4 Output for Clock Shift            |                |
| Microprocessor with Boot Block Mode71            | Typical Connection                     |                |
| Migration from High-End to                       | MSSP Module                            | 17             |
| Enhanced Devices                                 | SPI Master/Slave Connection            | 17             |
| Migration from Mid-Range to                      | MULLW                                  |                |
| Enhanced Devices                                 | MULWF                                  |                |
|  |  |                |
| MOVFF  | N                                      |                |
|  | NEGF                                   | 30:            |
| MOVLW  | NOP                                    |                |
| MPLAB ASM30 Assembler, Linker, Librarian318      | _                                      |                |
| MPLAB ICD 2 In-Circuit Debugger319               | 0                                      |                |
| MPLAB ICE 2000 High-Performance                  | Oscillator Configuration               | 2              |
| Universal In-Circuit Emulator                    | EC                                     | 2 <sup>-</sup> |
| MPLAB ICE 4000 High-Performance                  | ECIO                                   | 2 <sup>-</sup> |
| Universal In-Circuit Emulator                    | ECIO+PLL                               | 2 <sup>-</sup> |
| MPLAB Integrated Development                     | ECIO+SPLL                              | 2 <sup>-</sup> |
| Environment Software                             | HS                                     | 2 <sup>-</sup> |
| MPLAB PM3 Device Programmer                      | HS+PLL                                 | 2 <sup>-</sup> |
| MPLINK Object Linker/MPLIB Object Librarian318   | HS+SPLL                                |                |
| MSSP   | LP                                     |                |
| ACK Pulse  | RC                                     |                |
| Clock Stretching192                              | RCIO                                   |                |
| 10-Bit Slave Receive Mode (SEN = 1)192           | XT                                     |                |
| 10-Bit Slave Transmit Mode192                    | Oscillator Selection                   |                |
| 7-Bit Slave Receive Mode (SEN = 1)192            | Oscillator, Timer1                     | -              |
| 7-Bit Slave Transmit Mode192                     | Oscillator, Timer3                     |                |
| Clock Synchronization and the                    | Oscillator, WDT                        | 26             |
| CKP bit (SEN = 1)193                             |  |                |

| P                                    |          | RF3/AN8                               | 17  |
|--------------------------------------|----------|---------------------------------------|-----|
| Packaging                            | 272      | RF4/AN9                               | 17  |
| 8 8                                  |          | RF5/AN10/CVREF                        | 17  |
| Details                              |          | RF6/AN11                              | 17  |
| Marking                              |          | RF7/SS                                | 17  |
| Parallel Slave Port (PSP)            |          | RG0/ECCP3/P3A                         | 18  |
| Associated Registers                 |          | RG1/TX2/CK2                           |     |
| RE0/AD8/ <u>RD/</u> P2D Pin          |          | RG2/RX2/DT2                           |     |
| RE1/AD9/WR/P2C Pin                   |          | RG3/CCP4/P3D                          | _   |
| RE2/AD10/CS/P2B Pin                  |          | RG4/CCP5/P1D                          |     |
| Select (PSPMODE Bit)                 | 111, 128 |                                       |     |
| Phase Locked Loop (PLL)              | 23       | RH0/A16<br>RH1/A17                    | -   |
| PICkit 1 Flash Starter Kit           | 321      |                                       |     |
| PICSTART Plus Development Programmer | 320      | RH2/A18                               |     |
| PIE Registers                        | 95       | RH3/A19                               | -   |
| Pin Functions                        |          | RH4/AN12/P3C                          | _   |
| AVDD                                 | 20       | RH5/AN13/P3B                          |     |
| AVss                                 | _        | RH6/AN14/P1C                          |     |
| MCLR/VPP/RG5                         | -        | RH7/AN15/P1B                          | 19  |
| OSC1/CLKI                            |          | RJ0/ALE                               |     |
| OSC2/CLKO/RA6                        |          | RJ1/ <del>OE</del>                    | 20  |
| RAO/ANO                              |          | RJ2/WRL                               | 20  |
|                                      |          | RJ3/WRH                               | 20  |
| RA1/AN1                              |          | RJ4/BA0                               |     |
| RA2/AN2/VREF                         |          | RJ5/CE                                | _   |
| RA3/AN3/VREF+                        |          | RJ6/LB                                |     |
| RA4/T0CKI                            |          | RJ7/UB                                | _   |
| RA5/AN4/LVDIN                        |          | VDD                                   | _   |
| RA6                                  | 12       | Vss                                   |     |
| RB0/INT0/FLT0                        | 13       |                                       |     |
| RB1/INT1                             | 13       | Pinout I/O Descriptions               |     |
| RB2/INT2                             | 13       | PIR Registers                         |     |
| RB3/INT3/ECCP2/P2A                   | 13       | PLL Lock Time-out                     |     |
| RB4/KBI0                             | 13       | Pointer, FSR                          |     |
| RB5/KBI1/PGM                         | 13       | POP                                   | 304 |
| RB6/KBI2/PGC                         | 13       | POR. See Power-on Reset.              |     |
| RB7/KBI3/PGD                         |          | PORTA                                 |     |
| RC0/T10S0/T13CKI                     |          | Associated Registers                  |     |
| RC1/T1OSI/ECCP2/P2A                  |          | Functions                             | 105 |
| RC2/ECCP1/P1A                        |          | LATA Register                         | 103 |
| RC3/SCK/SCL                          |          | PORTA Register                        | 103 |
| RC4/SDI/SDA                          |          | TRISA Register                        | 103 |
| RC5/SDO                              |          | PORTB                                 |     |
| RC6/TX1/CK1                          |          | Associated Registers                  | 108 |
|                                      |          | Functions                             |     |
| RC7/RX1/DT1                          |          | LATB Register                         | 106 |
| RD0/AD0/PSP0                         |          | PORTB Register                        |     |
| RD1/AD1/PSP1                         |          | RB3/INT3:RB0/INT0/FLT0 Pins, External |     |
| RD2/AD2/PSP2                         |          | TRISB Register                        |     |
| RD3/AD3/PSP3                         |          | PORTC                                 |     |
| RD4/AD4/PSP4                         |          | Associated Registers                  | 110 |
| RD5/AD5/PSP5                         | 15       | Functions                             |     |
| RD6/AD6/PSP6                         | 15       |                                       |     |
| RD7/AD7/PSP7                         | 15       | LATC Register                         |     |
| RE0/AD8/RD/P2D                       | 16       | PORTC Register                        |     |
| RE1/AD9/WR/P2C                       |          | RC3/SCK/SCL Pin                       |     |
| RE2/AD10/CS/P2B                      | 16       | TRISC Register                        |     |
| RE3/AD11/P3C                         |          | PORTD                                 |     |
| RE4/AD12/P3B                         |          | Associated Registers                  |     |
| RE5/AD13/P1C                         | -        | Functions                             |     |
| RE6/AD14/P1B                         | -        | LATD Register                         |     |
| RE7/AD15/ECCP2/P2A                   |          | Parallel Slave Port (PSP) Function    | 111 |
| RF0/AN5                              |          | PORTD Register                        | 111 |
| RF1/AN6/C2OUT                        |          | TRISD Register                        | 111 |
| RF2/AN7/C1OUT                        |          |                                       |     |
| N 2/AN//01001                        | 17       |                                       |     |

| PORTE                                   |          | Program Verification                         | 270     |
|---|----------|--|---------|
| Analog Port Pins                        | 128      | Programming, Device Instructions             | 275     |
| Associated Registers                    | 116      | PSP. See Parallel Slave Port.                |         |
| Functions                               | 116      | Pulse-Width Modulation. See PWM (CCP Module) |         |
| LATE Register                           | 114      | and PWM (ECCP Module).                       |         |
| PORTE Register                          | 114      | PUSH   | 304     |
| PSP Mode Select (PSPMODE Bit)           | 111, 128 | PWM (CCP Module)                             | 154     |
| RE0/AD8/RD/P2D Pin                      | 128      | Associated Registers                         | 156     |
| RE1/AD9/WR/P2C Pin                      |          | CCPR4H:CCPR4L Registers                      | 154     |
| RE2/AD10/CS/P2B Pin                     | 128      | Duty Cycle                                   | 154     |
| TRISE Register                          |          | Example Frequencies/Resolutions              | 155     |
| PORTF                                   |          | Period                                       | 154     |
| Associated Registers                    | 119      | Setup for PWM Operation                      | 155     |
| Functions                               |          | TMR2 to PR2 Match1                           | 41, 154 |
| LATF Register                           | 117      | TMR4 to PR4 Match                            | 147     |
| PORTF Register                          | 117      | PWM (ECCP Module)                            | 160     |
| TRISF Register                          |          | Associated Registers                         |         |
| PORTG                                   |          | CCPR1H:CCPR1L Registers                      |         |
| Associated Registers                    | 121      | Direction Change in Full-Bridge              |         |
| Functions                               |          | Output Mode                                  | 166     |
| LATG Register                           |          | Duty Cycle                                   |         |
| PORTG Register                          |          | Effects of a Reset                           |         |
| TRISG Register                          |          | Enhanced PWM Auto-Shutdown                   |         |
| PORTH                                   |          | Example Frequencies/Resolutions              |         |
| Associated Registers                    | 124      | Full-Bridge Application Example              |         |
| Functions                               |          | Full-Bridge Mode                             |         |
| LATH Register                           |          | Half-Bridge Mode                             |         |
| PORTH Register                          |          | Half-Bridge Output Mode                      | 100     |
| TRISH Register                          |          | Applications Example                         | 164     |
| PORTJ                                   |          | Output Configurations                        |         |
| Associated Registers                    | 197      | Output Relationships (Active-High)           |         |
| Functions                               |          | Output Relationships (Active-Low)            |         |
|   |          | Period                                       |         |
| LATJ Register                           |          |  |         |
| PORTJ Register                          |          | Programmable Dead-Band Delay                 |         |
| TRISJ Register                          | 125      | Setup for PWM Operation                      |         |
| Postscaler, WDT                         | 400      | Start-up Considerations                      |         |
| Assignment (PSA Bit)                    |          | TMR2 to PR2 Match                            | 160     |
| Rate Select (T0PS2:T0PS0 Bits)          |          | Q  |         |
| Switching Between Timer0 and WDT        | 133      |  | F4 404  |
| Power-Down Mode. See Sleep.             |          | Q Clock1                                     | 54, 161 |
| Power-on Reset (POR)                    |          | R  |         |
| Oscillator Start-up Timer (OST)         |          | RAM. See Data Memory.                        |         |
| Power-up Timer (PWRT)                   |          | •  | 22      |
| Time-out Sequence                       | 30       | RC Oscillator                                |         |
| Prescaler                               |          | RCALL  |         |
| Timer2                                  |          | RCON Registers                               |         |
| Prescaler, Capture                      |          | Register File                                | 47      |
| Prescaler, Timer0                       |          | Registers                                    | 000     |
| Assignment (PSA Bit)                    |          | ADCON0 (A/D Control 0)                       |         |
| Rate Select (T0PS2:T0PS0 Bits)          |          | ADCON1 (A/D Control 1)                       |         |
| Switching Between Timer0 and WDT        |          | ADCON2 (A/D Control 2)                       |         |
| Prescaler, Timer2                       | 154      | BAUDCONx (Baud Rate Control)                 | 216     |
| PRO MATE II Universal Device Programmer | 319      | CCPxCON (Capture/Compare/PWM                 |         |
| Product Identification System           | 393      | Control - CCP4, CCP5)                        | 149     |
| Program Counter                         |          | CCPxCON (Capture/Compare/PWM Control -       |         |
| PCL, PCLATH and PCLATU Register         | 44       | ECCP1, ECCP2, ECCP3 Modules)                 |         |
| Program Memory                          |          | CMCON (Comparator Control)                   |         |
| Extended Microcontroller Mode           | 39       | CONFIG1H (Configuration 1 High)              |         |
| Instructions                            | 45       | CONFIG2H (Configuration 2 High)              |         |
| Two-Word                                | 46       | CONFIG2L (Configuration 2 Low)               |         |
| Interrupt Vector                        | 39       | CONFIG3H (Configuration 3 High)              | 262     |
| Map and Stack for PIC18FX525            |          | CONFIG3L (Configuration 3 Low)               | 41, 262 |
| Map and Stack for PIC18FX621            |          | CONFIG4L (Configuration 4 Low)               | 263     |
| Microcontroller Mode                    |          | CONFIG5H (Configuration 5 High)              |         |
| Microprocessor Mode                     |          | CONFIG5L (Configuration 5 Low)               | 263     |
| Microprocessor with Boot Block Mode     |          | CONFIG6H (Configuration 6 High)              |         |
| Reset Vector                            |          | CONFIG6L (Configuration 6 Low)               |         |
|   |          |  |         |

| CONFIG7H (Configuration 7 High)  |  |
|--|--|
| CONFIG7L (Configuration 7 Low)   | 265  |
| CVRCON (Comparator Voltage   |  |
| Reference Control)   | 249  |
| Device ID Register 2   |  |
| DEVID1 (Device ID Register 1)  |  |
| ECCPxAS (ECCP Auto-Shutdown Control)   |  |
| ECCPxDEL (PWM Configuration)   |  |
|  |  |
| EECON1 (Data EEPROM Control 1)   |  |
| INTCON (Interrupt Control)   |  |
| INTCON2 (Interrupt Control 2)  |  |
| INTCON3 (Interrupt Control 3)  | 91   |
| IPR1 (Peripheral Interrupt Priority 1)   | 98   |
| IPR2 (Peripheral Interrupt Priority 2)   |  |
| IPR3 (Peripheral Interrupt Priority 3)   |  |
| LVDCON (Low-Voltage Detect Control)  |  |
|  |  |
| MEMCON (Memory Control)  |  |
| OSCCON (Oscillator Control)  |  |
| PIE1 (Peripheral Interrupt Enable 1)   |  |
| PIE2 (Peripheral Interrupt Enable 2)   | 96   |
| PIE3 (Peripheral Interrupt Enable 3)   | 97   |
| PIR1 (Peripheral Interrupt   |  |
| Request (Flag) 1)  | 92   |
| PIR2 (Peripheral Interrupt   | 52   |
|  | 00   |
| Request (Flag) 2)  | 93   |
| PIR3 (Peripheral Interrupt   |  |
| Request (Flag) 3)  |  |
| PSPCON (Parallel Slave Port Control)   |  |
| RCON (Reset Control)   | 59, 101  |
| RCSTAx (Receive Status and Control)  | 215  |
| SSPCON1 (MSSP Control 1, I <sup>2</sup> C Mode)  |  |
| SSPCON1 (MSSP Control 1, SPI Mode)   | 175  |
| SSPCON1 (MSSP Control 2, I <sup>2</sup> C Mode)  | 175  |
|  |  |
|  |  |
| SSPSTAT (MSSP Status, I <sup>2</sup> C Mode)   |  |
| SSPSTAT (MSSP Status, Inc. Mode)SSPSTAT (MSSP Status, SPI Mode)  |  |
| SSPSTAT (MSSP Status, SPI Mode)STATUS  | 174<br>58  |
| SSPSTAT (MSSP Status, SPI Mode)STATUS  | 174<br>58  |
| SSPSTAT (MSSP Status, SPI Mode)STATUSSTKPTR (Stack Pointer)  | 174<br>58<br>43  |
| SSPSTAT (MSSP Status, SPI Mode)STATUSSTKPTR (Stack Pointer)Summary   | 174<br>58<br>43<br>51–54                                     |
| SSPSTAT (MSSP Status, SPI Mode)STATUSSTKPTR (Stack Pointer)SummarySummary  | 174<br>58<br>43<br>51–54                                     |
| SSPSTAT (MSSP Status, SPI Mode)  | 174<br>58<br>43<br>51–54<br>131                              |
| SSPSTAT (MSSP Status, SPI Mode)  | 174<br>58<br>51–54<br>131<br>135                             |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control)  | 174<br>58<br>51–54<br>131<br>135<br>141                      |
| SSPSTAT (MSSP Status, SPI Mode)  | 174<br>58<br>51–54<br>131<br>135<br>141                      |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control)  | 174<br>58<br>51–54<br>131<br>135<br>141<br>143               |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAx (Transmit Status and Control)   | 174<br>58<br>51–54<br>131<br>135<br>141<br>143<br>147        |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAx (Transmit Status and Control) WDTCON (Watchdog Timer Control)   | 174<br>58<br>51–54<br>131<br>145<br>143<br>147<br>147<br>214 |
| SSPSTAT (MSSP Status, SPI Mode)  |  |
| SSPSTAT (MSSP Status, SPI Mode)  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation)   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation)   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation)   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset   |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T3CON (Timer 2 Control) T4CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T3CON (Timer 2 Control) T4CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset.  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T3CON (Timer 2 Control) T4CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset.  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETFIE  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE RETLW RETURN  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE RETLW RETURN Return Address Stack and Associated Registers                         |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE RETLW RETURN  |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE RETLW RETURN Return Address Stack and Associated Registers                         |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset RETILW RETURN RETURN Return Address Stack and Associated Registers Revision History       |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer 3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control) RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETILW RETURN RETURN Return Address Stack and Associated Registers Revision History RLCF |  |
| SSPSTAT (MSSP Status, SPI Mode) STATUS STKPTR (Stack Pointer) Summary T0CON (Timer0 Control) T1CON (Timer 1 Control) T2CON (Timer 2 Control) T3CON (Timer3 Control) T4CON (Timer 4 Control) TXSTAX (Transmit Status and Control) WDTCON (Watchdog Timer Control)  RESET Reset MCLR Reset (normal operation) MCLR Reset (Sleep) Power-on Reset Programmable Brown-out Reset (BOR) RESET Instruction Stack Full Reset Stack Underflow Reset Watchdog Timer (WDT) Reset. RETIE RETLW RETURN Return Address Stack and Associated Registers                         |  |

| S   |     |
|---|-----|
| SCK   | 173 |
| SDI   | 173 |
| SDO   | 173 |
| Serial Clock, SCK                                 | 173 |
| Serial Data In (SDI)                              |     |
| Serial Data Out (SDO)                             |     |
| Serial Peripheral Interface. See SPI Mode.        |     |
| SETF  | 309 |
| Slave Select (SS)                                 |     |
| Slave Select Synchronization                      | 179 |
| SLEEP   |     |
| Sleep   |     |
| Software Simulator (MPLAB SIM)                    | 318 |
| Software Simulator (MPLAB SIM30)                  | 318 |
| Special Event Trigger. See Compare (ECCP Mode).   |     |
| Special Event Trigger. See Compare (ECCP Module). |     |
| Special Features of the CPU                       | 259 |
| Configuration Registers 260-                      |     |
| Special Function Registers                        |     |
| Map   |     |
| SPI Mode  |     |
| Associated Registers                              | 181 |
| Bus Mode Compatibility                            |     |
| Effects of a Reset                                |     |
| Master Mode                                       | 178 |
| Master/Slave Connection                           | 177 |
| Serial Clock                                      | 173 |
| Serial Data In                                    | 173 |
| Serial Data Out                                   | 173 |
| Slave Mode  |     |
| Slave Select                                      | 173 |
| Slave Select Synchronization                      | 179 |
| Sleep Operation                                   | 181 |
| SPI Clock   | 178 |
| <u>SS</u>   | 173 |
| SSPOV   | 203 |
| SSPOV Status Flag                                 | 203 |
| SSPSTAT Register                                  |     |
| R/W Bit186,                                       | 187 |
| Status Bits                                       |     |
| Significance and Initialization Condition         |     |
| for RCON Register                                 | 31  |
| SUBFWB  | 310 |
| SUBLW   |     |
| SUBWF   | 311 |
| SUBWFB  |     |
| SWAPF   | 312 |
| т   |     |
|   |     |
| T0CON Register                                    |     |
| PSA Bit   |     |
| TOCS Bit  |     |
| T0PS2:T0PS0 Bits                                  |     |
| TOSE Bit  |     |
| Table Pointer Operations (table)                  |     |
| TBLRD   |     |
| TBLWT   |     |
| Time-out in Various Situations                    | 31  |

| Timer0  | 131           | Bus Collision During a Stop                             |     |
|---|---------------|---|-----|
| 16-Bit Mode Timer Reads and Writes              | 133           | Condition (Case 1)                                      | 211 |
| Associated Registers                            | 133           | Bus Collision During a Stop                             |     |
| Clock Source Edge Select (T0SE Bit)             | 133           | Condition (Case 2)                                      | 211 |
| Clock Source Select (T0CS Bit)                  | 133           | Bus Collision During Start                              |     |
| Operation                                       | 133           | Condition (SDA Only)                                    | 208 |
| Overflow Interrupt                              | 133           | Bus Collision for Transmit and                          |     |
| Prescaler. See Prescaler, Timer0.               |               | Acknowledge   | 207 |
| Timer1  | 135           | Capture/Compare/PWM                                     |     |
| 16-Bit Read/Write Mode                          | 137           | (All ECCP/CCP Modules)                                  |     |
| Associated Registers                            | 139           | CLKO and I/O  | 338 |
| Operation                                       |               | Clock Synchronization                                   | 193 |
| Oscillator                                      | 135, 137      | Clock/Instruction Cycle                                 | 44  |
| Overflow Interrupt                              |               | EUSART Synchronous                                      |     |
| Special Event Trigger (ECCP)                    | 137, 160      | Receive (Master/Slave)                                  | 353 |
| TMR1H Register                                  |               | EUSART Synchronous                                      |     |
| TMR1L Register                                  | 135           | Transmission (Master/Slave)                             |     |
| Use as a Real-Time Clock                        |               | Example SPI Master Mode (CKE = 0)                       |     |
| Timer2  |               | Example SPI Master Mode (CKE = 1)                       |     |
| Associated Registers                            |               | Example SPI Slave Mode (CKE = 0)                        |     |
| MSSP Clock Shift                                |               | Example SPI Slave Mode (CKE = 1)                        |     |
| Operation                                       | 141           | External Clock (All Modes Except PLL)                   | 337 |
| Postscaler, See Postscaler, Timer2.             |               | External Memory Bus Timing for Sleep                    |     |
| PR2 Register                                    | 141, 154, 160 | (Microprocessor Mode)                                   | 77  |
| Prescaler. See Prescaler, Timer2.               |               | External Memory Bus Timing for TBLRD                    |     |
| TMR2 Register                                   |               | (Extended Microcontroller Mode)                         | 76  |
| TMR2 to PR2 Match Interrupt 141,                |               | External Memory Bus Timing for TBLRD                    | 70  |
| Timer3  |               | (Microprocessor Mode)                                   |     |
| Associated Registers                            |               | Full-Bridge PWM Output                                  |     |
| Operation                                       |               | Half-Bridge OutputI <sup>2</sup> C Bus Data             |     |
| Oscillator                                      |               |   |     |
| Overflow Interrupt Special Event Trigger (ECCP) |               | I <sup>2</sup> C Bus Start/Stop Bits                    | 348 |
| TMR3H Register                                  |               | (7 or 10-Bit Transmission)                              | 20/ |
| TMR3L Register                                  |               | I <sup>2</sup> C Master Mode (7-Bit Reception)          |     |
| Timer4  |               | I <sup>2</sup> C Master Mode (7-Bit Reception)          |     |
| Associated Registers                            |               | I <sup>2</sup> C Slave Mode (10-Bit Reception, SEN = 0) |     |
| MSSP Clock Shift                                |               | I <sup>2</sup> C Slave Mode (10-Bit Reception, SEN = 1) |     |
| Operation                                       |               | I <sup>2</sup> C Slave Mode (10-Bit Transmission)       |     |
| Postscaler. See Postscaler, Timer4.             |               | I <sup>2</sup> C Slave Mode (7-Bit Reception, SEN = 0)  |     |
| PR4 Register                                    | 147           | I <sup>2</sup> C Slave Mode (7-Bit Reception, SEN = 1)  |     |
| Prescaler. See Prescaler, Timer4.               |               | I <sup>2</sup> C Slave Mode (7-Bit Transmission)        | 189 |
| TMR4 Register                                   | 147           | Low-Voltage Detect                                      |     |
| TMR4 to PR4 Match Interrupt                     |               | Master SSP I <sup>2</sup> C Bus Data                    |     |
| Timing Diagrams                                 |               | Master SSP I <sup>2</sup> C Bus Start/Stop Bits         |     |
| A/D Conversion                                  | 355           | Parallel Slave Port (PSP)                               |     |
| Acknowledge Sequence                            |               | Parallel Slave Port (PSP) Read                          |     |
| Asynchronous Reception                          |               | Parallel Slave Port (PSP) Write                         |     |
| Asynchronous Transmission                       |               | Program Memory Read                                     |     |
| Asynchronous Transmission                       |               | Program Memory Write                                    |     |
| (Back to Back)                                  | 222           | PWM Auto-Shutdown (PRSEN = 0,                           |     |
| Automatic Baud Rate Calculation                 | 220           | Auto-Restart Disabled)                                  | 170 |
| Auto-Wake-up Bit (WUE) During                   |               | PWM Auto-Shutdown (PRSEN = 1,                           |     |
| Normal Operation                                | 225           | Auto-Restart Enabled)                                   | 170 |
| Auto-Wake-up Bit (WUE) During Sleep             | 225           | PWM Direction Change                                    | 167 |
| Baud Rate Generator with Clock Arbitration      | n 200         | PWM Direction Change at Near                            |     |
| BRG Reset Due to SDA Arbitration                |               | 100% Duty Cycle   |     |
| During Start Condition                          | 209           | PWM Output  |     |
| Brown-out Reset (BOR)                           | 341           | Repeated Start Condition                                | 202 |
| Bus Collision During a Repeated Start           |               | Reset, Watchdog Timer (WDT),                            |     |
| Condition (Case 1)                              | 210           | Oscillator Start-up Timer (OST)                         |     |
| Bus Collision During a Repeated Start           |               | and Power-up Timer (PWRT)                               |     |
| Condition (Case 2)                              | 210           | Send Break Character Sequence                           | 226 |
| Bus Collision During a Start                    |               | Slave Mode General Call Address Sequence                |     |
| Condition (SCL = 0)                             | 209           | (7 or 10-Bit Address Mode)                              | 196 |

| Slave Synchronization                        | 179 |
|--|-----|
| Slow Rise Time (MCLR Tied to VDD             |     |
| via 1 kΩ Resistor)                           |     |
| SPI Mode (Master Mode)                       | 178 |
| SPI Mode (Slave Mode with CKE = 0)           | 180 |
| SPI Mode (Slave Mode with CKE = 1)           | 180 |
| Stop Condition Receive or Transmit Mode      | 206 |
| Synchronous Reception                        |     |
| (Master Mode, SREN)                          |     |
| Synchronous Transmission                     |     |
| Synchronous Transmission (Through TXEN)      | 228 |
| Time-out Sequence on POR w/PLL Enabled       |     |
| (MCLR Tied to VDD via 1 k $\Omega$ Resistor) | 38  |
| Time-out Sequence on Power-up (MCLR          |     |
| Not Tied to VDD): Case 1                     | 37  |
| Time-out Sequence on Power-up (MCLR          |     |
| Not Tied to VDD): Case 2                     | 37  |
| Time-out Sequence on Power-up (MCLR          |     |
| Tied to VDD via 1 k $\Omega$ Resistor)       | 37  |
| Timer0 and Timer1 External Clock             | 342 |
| Timing for Transition Between Timer1 and     |     |
| OSC1 (EC with PLL Active, SCS1 = 1)          | 27  |
| Timing for Transition Between Timer1 and     |     |
| OSC1 (HS with PLL Active, SCS1 = 1)          | 27  |
| Transition Between Timer1 and                |     |
| OSC1 (HS, XT, LP)                            | 26  |
| Transition Between Timer1 and                |     |
| OSC1 (RC, EC)                                | 28  |
| Transition from OSC1 to Timer1 Oscillator    |     |
| Wake-up from Sleep via Interrupt             |     |
| Timing Specifications                        |     |
| A/D Conversion Requirements                  |     |
| Capture/Compare/PWM Requirements             |     |
| CLKO and I/O Requirements                    | 338 |
| EUSART Synchronous Receive                   |     |
| Requirements                                 | 353 |
| <b>EUSART Synchronous Transmission</b>       |     |
| Requirements                                 | 353 |
| Example SPI Mode Requirements                |     |
| (Master Mode, CKE = 0)                       | 345 |
| Example SPI Mode Requirements                |     |
| (Master Mode, CKE = 1)                       | 346 |
| Example SPI Mode Requirements                |     |
| (Slave Mode, CKE = 0)                        | 347 |
| Example SPI Slave Mode                       |     |
| Poquiromento (CKE – 1)                       | 2/0 |

| External Clock Requirements                         | 337   |
|---|-------|
| I <sup>2</sup> C Bus Data Requirements (Slave Mode) |       |
| I <sup>2</sup> C Bus Start/Stop Bits Requirements   |       |
| (Slave Mode)  | 349   |
| Master SSP I <sup>2</sup> C Bus Data Requirements   |       |
| Master SSP I <sup>2</sup> C Bus Start/Stop Bits     |       |
| Requirements  | 351   |
| Parallel Slave Port Requirements                    |       |
| PLL Clock   |       |
| Program Memory Read Requirements                    |       |
| Program Memory Write Requirements                   |       |
| Reset, Watchdog Timer, Oscillator                   |       |
| Start-up Timer, Power-up Timer                      |       |
| and Brown-out Reset Requirements                    | 341   |
| Timer0 and Timer1 External                          | •     |
| Clock Requirements                                  | 342   |
| TRISE Register                                      | 0     |
| PSPMODE Bit111                                      | 128   |
| TSTFSZ  |       |
| Two-Word Instructions                               | 010   |
| Example Cases                                       | 46    |
| TXSTAx Register                                     | 40    |
| BRGH Bit  | 217   |
| DICOTT DIL  | 217   |
| V   |       |
| Voltage Reference Specifications                    | . 332 |
|   | 002   |
| W   |       |
| Wake-up from Sleep                                  | , 269 |
| Using Interrupts                                    |       |
| Watchdog Timer (WDT)259                             |       |
| Associated Registers                                |       |
| Control Register                                    |       |
| Postscaler  |       |
| Programming Considerations                          |       |
| RC Oscillator                                       |       |
| Time-out Period                                     |       |
| WCOL  |       |
| WCOL Status Flag                                    |       |
| WWW, On-Line Support                                |       |
| ******, On-Line Support                             | 3     |
| X   |       |
| XORLW   | . 315 |
| XORWF   |       |
|   |       |

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com, click on Customer Change Notification and follow the registration instructions.

#### CUSTOMER SUPPORT

Users of Microchip products can receive assistance through several channels:

- Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- Technical Support
- · Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

### Technical support is available through the web site at: http://support.microchip.com

In addition, there is a Development Systems Information Line which lists the latest versions of Microchip's development systems software products. This line also provides information on how customers can receive currently available upgrade kits.

#### The Development Systems Information Line numbers are:

1-800-755-2345 - United States and most of Canada

1-480-792-7302 - Other International Locations

#### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

| 10:  | Technical Publications Manager              | Total Pages Sent                                  |
|------|---|---|
| RE:  | Reader Response                             |   |
| Fron | m: Name                                     |   |
|      | Company                                     |   |
|      | Address                                     |   |
|      | City / State / ZIP / Country                |   |
| ۸ ا  | Telephone: ()                               | FAX: ()   |
|      | plication (optional):                       |   |
| Wou  | uld you like a reply?YN                     |   |
| Devi | vice: PIC18F6525/6621/8525/8621 L           | iterature Number: DS39612B                        |
| Que  | estions:                                    |   |
| 1. \ | What are the best features of this docume   | ent?  |
|      |   |   |
| -    |   |   |
| 2.   | How does this document meet your hardy      | vare and software development needs?              |
| _    |   |   |
| _    |   |   |
| 3.   | Do you find the organization of this docum  | nent easy to follow? If not, why?                 |
| _    |   |   |
| _    |   |   |
| 4.   | What additions to the document do you th    | nink would enhance the structure and subject?     |
| _    |   |   |
| _    |   |   |
| 5. \ | What deletions from the document could I    | be made without affecting the overall usefulness? |
| -    |   |   |
| -    |   |   |
| 6. I | Is there any incorrect or misleading inform | nation (what and where)?                          |
| =    |   |   |
| -    |   |   |
| 7. l | How would you improve this document?        |   |
| -    |   |   |
| -    |   |   |

#### PIC18F6525/6621/8525/8621 PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

| PART NO.<br>Device   | − <u>X</u> <u>/XX</u><br>  Temperature Package<br>Range  | XXX<br> <br>  Pattern | Examples:  a) PIC18LF6621-I/PT 301 = Industrial temp., TQFP package, Extended VDD limits, QTP pattern #301. b) PIC18E8621-E/PT = Extended temp. |
|----------------------|--|-----------------------|---|
| Device               | PIC18F6525/6621/8525/8621 <sup>(1)</sup> ,<br>PIC18F6525/6621/8525/8621T <sup>(2)</sup> ;<br>VDD range 4.2V to 5.5V<br>PIC18LF6X2X/8X2X <sup>(1)</sup> ,<br>PIC18LF6X2X/8X2XT <sup>(2)</sup> ;<br>VDD range 2.0V to 5.5V |                       | b) PIC18F8621-E/PT = Extended temp., TQFP package, standard VDD limits.   |
| Temperature<br>Range | I = -40°C to +85°C (Industrial)<br>E = -40°C to +125°C (Extended)  |                       | Note 1: F = Standard Voltage Range  LF = Extended Voltage Range   |
| Package              | PT = TQFP (Thin Quad Flatpack)   |                       | 2: T = in tape and reel   |
| Pattern              | QTP, SQTP, Code or Special Requiren (blank otherwise)  | nents                 |   |



#### WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200

Fax: 480-792-7277 Technical Support:

http://support.microchip.com

Web Address: www.microchip.com

**Atlanta** 

Alpharetta, GA Tel: 770-640-0034 Fax: 770-640-0307

**Boston** 

Westford, MA Tel: 978-692-3848 Fax: 978-692-3821

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** 

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Kokomo

Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

San Jose

Mountain View, CA Tel: 650-215-1444 Fax: 650-961-0286

**Toronto** 

Mississauga, Ontario,

Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Australia - Sydney

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

China - Beijing

Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

China - Chengdu

Tel: 86-28-8676-6200 Fax: 86-28-8676-6599

China - Fuzhou

Tel: 86-591-8750-3506 Fax: 86-591-8750-3521

China - Hong Kong SAR

Tel: 852-2401-1200 Fax: 852-2401-3431

**China - Shanghai** Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

**China - Shenyang** Tel: 86-24-2334-2829

Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

China - Shenzhen

Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

China - Shunde

Tel: 86-757-2839-5507 Fax: 86-757-2839-5571

China - Qingdao

Tel: 86-532-502-7355 Fax: 86-532-502-7205

#### ASIA/PACIFIC

India - Bangalore

Tel: 91-80-2229-0061 Fax: 91-80-2229-0062

India - New Delhi

Tel: 91-11-5160-8631 Fax: 91-11-5160-8632

Japan - Kanagawa

Tel: 81-45-471- 6166 Fax: 81-45-471-6122

Korea - Seoul

Tel: 82-2-554-7200 Fax: 82-2-558-5932 or

82-2-558-5934

**Singapore** Tel: 65-6334-8870 Fax: 65-6334-8850

- · · · · ·

**Taiwan - Kaohsiung** Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan - Taipei

Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

Taiwan - Hsinchu

Tel: 886-3-572-9526 Fax: 886-3-572-6459

#### **EUROPE**

Austria - Weis

Tel: 43-7242-2244-399 Fax: 43-7242-2244-393 **Denmark - Ballerup** 

Tel: 45-4450-2828 Fax: 45-4485-2829

France - Massy

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Ismaning** 

Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen Tel: 31-416-690399

Fax: 31-416-690340 **England - Berkshire** Tel: 44-118-921-5869

Fax: 44-118-921-5820